



PUBLIC WORKS DEPARTMENT

Timothy J. LaPorte, P.E.

Public Works Director

400 West Gowe

Kent, WA 98032

Fax: 253-856-6500

PHONE: 253-856-5500

**CITY OF KENT
KING COUNTY, WASHINGTON**

**Green River Natural Resource Area (GRNRA)
South Stormwater Pump Station
Project Number: 17-3012**

**ADDENDUM No. 4
October 18, 2019**

**FROM: The Office of the City Engineer, Kent Washington
TO: All Plan Holders of the Project Specifications and Plans**

This addendum forms a part of the Contract documents and modifies the Project Proposal and Specifications and Contract Drawings in accordance with the following:

ALL CHANGES ARE REFLECTED IN RED

I – APPENDICES

Appendix 7 – Pump Station Structural, Architectural, HVAC, Electrical, and Instrumentation / Control Technical Specifications (CSI Format) – Section 09 90 04 - Painting

Page 6 - Subsection 3.04 Preparation of Surfaces

ADD the following new subsection to the end of this section:

- D. Gypsum Board Surface Preparation: Typically, new gypsum board surfaces need no special preparation before painting.**
 - 1. Surface Finish: Dry, free of dust, dirt, powdery residue, grease, oil, or any other contaminants.**

Page 10 – Subsection 3.07 Protective Coatings Systems and Application Schedule

ADD the following new subsection to the end of this section:

F. System No. 116 Gypsum Board and Plaster, Glossy Epoxy:

Surface Prep.	Paint Material	Min. Coats, Cover
In accordance with Paragraph Gypsum Board Surface Preparation	Manufacturer's Recommended Primer	1 coat, 350 SFPG
	Water Base Epoxy (Gloss)	1 coat, 250 SFPG

END OF ADDENDUM No. 4

Chad Bieren

Chad Bieren, P.E.
Deputy Director/City Engineer

10/18/19

Date