

**ADDENDUM NO. 2**  
**TO THE CONTRACT DOCUMENTS FOR**  
**City of Gig Harbor**  
**Replacement of Sanitary Sewer Lift Station #12 (CSSP-2005)**

Project Issued: 8/26/2021  
Addendum No. 2 Issued: 9/14/2021  
Original Bid Opening Date: 9/16/2021 10:00 A.M.  
***Bid Opening Date: To remain the same***

To: All Holders of Contract Documents

This addendum forms a part of the Contract Documents and modifies the original Plans and Specifications, for which proposals are still due on the date and time above.

Acknowledge receipt of this addendum on "Addenda Received" of the Bid Documents in the Contract Documents. Failure to do so might subject the bidder to disqualification.

This addendum shall clarify the Contract Documents as follows:

**ITEM NO.:** AD02-01  
**SECTION:** Drawing Sheet A-01  
**DESCRIPTION:** At Sheet A-01, add the following note to the Finish Schedule Notes: 5. Open web steel joists at roof framing to have rust-inhibiting shop primer conforming to SSPC Paint 15, *standard gray*. No finish paint required.

**ITEM NO.:** AD02-02  
**SECTION:** Specification 01 51 10  
**DESCRIPTION:** Add 2.01 H Bypass pumping system shall be sound attenuated and not exceed 66 dBa at 7m.

**ITEM NO.:** AD02-03  
**SECTION:** Specification 40 05 64  
**DESCRIPTION:** Replace 2.01 E Torque: shall not exceed "1,00 in lbf" with "1,200 in-lbf."

**CLARIFICATIONS AND ANSWERS TO CONTRACTOR'S QUESTIONS**

**ITEM NO.:** CL02-01  
**DESCRIPTION:** There was a bidder question about the lack of coating vendors willing to apply the 3M Scotchkote Liquid Phenolic 345 to fittings and pipe in the wet well.

*Response: The City may consider alternative coating options for fittings and piping, within the wet well, with the successful bidder after award and during the materials submittal process.*

**ITEM NO.:** CL02-02  
**DESCRIPTION:** There was a bidder question about allowable electrical conduit material for the building interior.

*Response: Specification 26 05 33 2.01.B states Galvanized Rigid Conduit (GRC) Rigid Metal Conduit (RMC) shall be used for all conduits except where the plans indicate different conduit type.*

**ADDENDUM NO. 2**  
**TO THE CONTRACT DOCUMENTS FOR**  
**City of Gig Harbor**  
**Replacement of Sanitary Sewer Lift Station #12 (CSSP-2005)**

Project Issued: 8/26/2021  
Addendum No. 2 Issued: 9/14/2021  
Original Bid Opening Date: 9/16/2021 10:00 A.M.  
***Bid Opening Date: To remain the same***

**ITEM NO.:** CL02-03  
**DESCRIPTION:** There was a bidder question asking for clarification about the concrete floor finish.

*Response: Sheet A-01 Finish Schedule Note 4 directs to Specification 09 62 00 Seamless Epoxy Flooring. The concrete floor shall be finished with a chemical-resistant, non-skid, epoxy resin per the specification.*

**CERTIFICATE OF ENGINEER**  
**Replacement of Sanitary Sewer Lift Station #12 (CSSP-2005)**

Addendum No. 2 of the Replacement of Sanitary Sewer Lift Station #12 (CSSP-2005) was prepared under the supervision and direction of the undersigned, whose seal, as a Professional Engineer, licensed to practice as such, is affixed below.

