

ADDENDUM NO. 1
TO THE CONTRACT DOCUMENTS
for the construction of
Salmon Creek Treatment Plant UV System Replacement Project

Date: April 10, 2026
Jacobs Project No. D3454455
DCWA Project No. 93-2023-0048

To All Plan holders and/or Prospective Bidders:

The following changes, additions, and/or deletions are hereby made a part of the Contract Documents for the construction of Salmon Creek Treatment Plant UV System Replacement Project, dated January 2026 as fully and completely as if the same were fully set forth therein:

A. VOLUME I, SPECIFICATIONS – NO CHANGES

B. VOLUME II, SPECIFICATIONS

1. Specification Section 07 41 13 METAL ROOF AND WALL PANELS
 - a. Paragraph 1.02 A 2. b. Delete in its entirety.
 - b. Paragraph 1.03 B 2. c. – Delete in its entirety and replace with “Review flashing details, roof drainage, roof penetrations and other construction and conditions that might affect metal roof panel installation.”
 - c. Paragraph 2.02 A 1. A. – Delete in its entirety and replace with “Factory-assembled preformed metal panels with manufacturer’s standard concealed fasteners, and gasketed seam system of double tongue and groove interlocking joint.”
 - d. Paragraph 2.02 A 1. b. – Delete in its entirety.
 - e. Paragraph 3.03 B. - Change title to “Metal Wall, and Canopy Roof Panels”
2. Specification Section 44 44 73 ULTRAVIOLET DISINFECTION EQUIPMENT FOR WASTEWATER
 - a. Paragraph 2.08 C - see table below for recommended anchors for both UV channels:

		SEISMIC		
		WEDGE TYPE		EPOXY TYPE
Equipment	Qty	STD Red Hat	Hilti-TZ2	Hilti-Threaded Rod
SW PDC	8	Ø 3/4" X 5.50" LG	N/A	Ø 3/4" X 9.63" LG
DW PDC	16	Ø 3/4" X 5.50" LG	N/A	Ø 3/4" X 9.63" LG
HSC	8	Ø 1/2" X 5.50" LG	N/A	Ø 1/2" X 6.50" LG
SCC WALL MNT	8	Ø 3/8" X 3.75" LG	N/A	Ø 3/8" X 5.13" LG
SCC FLOOR MNT	12	Ø 1/2" X 5.50" LG	N/A	Ø 1/2" X 6.50" LG
BANK FRAME/SUPT ASSY	144	Ø 3/8" X 3.75" LG	Ø 3/8" X 3.75" LG	N/A

- C. VOLUME III, GEOTECHNICAL DATA REPORT – NO CHANGES
- D. VOLUME IV, PLANS – NO CHANGES
- E. VOLUME V, PRE-SELECTED EQUIPMENT QUOTE AND SUBMITTALS
TROJAN TECHNOLOGIES / SECTION 44 44 73 – NO CHANGES

This Addendum does not change the date or time of when bids are due. All Bidders shall acknowledge receipt and acceptance of this Addendum No. 1 in the Bid Form. Bid Forms submitted without acknowledgment will be considered in nonconformance.

Clark Regional Wastewater District

Chris Stangl
Construction Manager

Appended hereto and part of Addendum No. 1 - none

Appended hereto and not part of Addendum No. 1:

- A. Pre-bid Meeting Agenda Minutes
- B. Pre-Bid Meeting Attendees Sign In Sheet

END OF ADDENDUM NO. 1

other permits by the contractor.

- Contract Payment & Performance Bond required. Copy included in front end of bid documents.
- Insurance requirements referenced in Supplementary Conditions section 00 73 00 – 6 and the supplementary conditions (SC 6.03).
- Federal Funds have been secured by the District for the project. Refer to specifications for additional monthly and/or weekly requirements.

6. Trojan Pre-selected equipment

- Owner has pre-selected Trojan for the new UV equipment (reference 44 44 73).
 - Price of the package is listed on the proposal form.
 - Awarded low & responsive bidder will enter into contract with Trojan per the proposal found in Volume V.
 - Product Data and Shop Drawing submittal for new equipment can be found in Volume 5.

7. Site Information

- Coordination will be required (shutdowns) as specified including notices.
- Coordination of work shall be made with District Construction Manager as specified.
- Several other projects will be taking place during this work, all projects have clearly identified lay-down areas.

8. Addendum – none at this time, one forthcoming.

- Will include resolution to insulated wall and roof panels bidder question received on 4-2-26

9. Questions

10. Site Tour

SCTP UV SYSTEM REPLACEMENT
 PROJECT #93-2023-0048
 APRIL 7, 2026 9:00AM PRE-BID MEETING
 SIGN-IN SHEET

Attendee Name	Company/Affiliation	Phone	Email
KEVIN JOLLY	DSL BUILDERS/GC	503-363-0202	KEVINJ@DSL-BUILDERS.COM
DAVE MCCANN	Prospect Const. Inc	253-293-9008	bids@prospectconst.com
JOE HALSTON	TAPANI inc	360-225-7996	bids@stellarj.com
Scott Parker	Stellar J	360-225-7996	bids@stellarj.com
DILLON R HAMBURG	API SCAFFOLD	973 36 6948	DILLON.RHAMBURG@APICONST.US
Chris White	Hammer Electric	360-522-2282	Chris.white@hammerelectric.com

SCTP UV SYSTEM REPLACEMENT
PROJECT #93-2023-0048
APRIL 7, 2026 9:00AM PRE-BID MEETING
SIGN-IN SHEET

Attendee Name	Company/Affiliation	Phone	Email
Loren Kysar	Rotschy Inc	360-334-3100	Estimator@Rotschyinc.com
Emma Hagedorn	NCE sub	360-921-9348	ed@nce.us

SCTP UV SYSTEM REPLACEMENT
PROJECT #93-2023-0048
APRIL 7, 2026 9:00AM PRE-BID MEETING
SIGN-IN SHEET

Attendee Name	Company/Affiliation	Phone	Email
DANIEL E MASSLE	ROTSCHLY INC	360-334-3100	ESTIMATOR@ROTSCHLYINC.COM

SIGN-IN SHEET
 APRIL 7, 2026 9:00AM PRE-BID MEETING
 PROJECT #93-2023-0048
 SCTP UV SYSTEM REPLACEMENT
 PAGE 7 OF 8