



April 13, 2026

**Addendum No. 1**

**ATTENTION: ALL BIDDERS**

Seven Mile Bridge – CRP 20-06

Bid Opening – April 20<sup>th</sup>, 2026 at 1:30pm

This addendum is hereby incorporated and made a part of the specifications. The Contractor shall acknowledge this addendum on the Bid Proposal signature sheet.

**1) Bid Proposal**

Pages 1 & 2 of the Bid Proposal documents are replaced with the following:

(Note: Due to revision to bid item #13)

**\*\*See Attached\*\***

**Walla Walla County**

  
\_\_\_\_\_  
Joel Dickerson, P.E., County Engineer

4/13/26  
\_\_\_\_\_  
Date

**BID PROPOSAL**  
**SEVEN MILE BRIDGE ON SEVEN MILE ROAD MP 2.30 TO MP 2.55**

CRP 20-06

THIS CERTIFIES THAT THE UNDERSIGNED HAS EXAMINED THE LOCATION OF THE PROPOSED PROJECT, AND THAT THE PLANS, SPECIFICATIONS AND CONTRACT GOVERNING THE WORK EMBRACED IN THIS IMPROVEMENT, AND THE METHOD BY WHICH PAYMENT WILL BE MADE FOR SAID WORK IS UNDERSTOOD. THE UNDERSIGNED HEREBY PROPOSES TO UNDERTAKE AND COMPLETE THE WORK EMBRACED IN THIS IMPROVEMENT, OR AS MUCH THEREOF AS CAN BE COMPLETED WITH THE MONEY AVAILABLE IN ACCORDANCE WITH THE SAID PLANS, SPECIFICATIONS AND CONTRACT, AND THE FOLLOWING SCHEDULE OF RATES AND PRICES.

(NOTE: UNIT PRICES FOR ALL ITEMS, ALL EXTENSIONS, AND TOTAL AMOUNT OF BID SHALL BE SHOWN. ALL ENTRIES MUST BE TYPED OR ENTERED IN INK)

**\*\*\*\*\* REVISED BID PROPOSAL 04/13/2026 \*\*\*\*\***

ITEM NO	DESCRIPTION	PLAN QUANTITY	UNITS	UNIT PRICE	TOTAL AMOUNT
<b>PREPARATION</b>					
1	MOBILIZATION	1.00	LS		
2	CLEARING AND GRUBBING	1.00	LS		
3	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	1.00	LS		
4	REMOVING EXISTING BRIDGE	1.00	LS		
<b>GRADING</b>					
5	UNSUITABLE FOUNDATION EXCAVATION INCL. HAUL	200.00	CY		
6	ROADWAY EXCAVATION INCL. HAUL	2360.00	CY		
7	CHANNEL EXCAVATION INCL. HAUL	3112.00	CY		
<b>DRAINAGE</b>					
8	FILTER BLANKET	372.00	CY		
9	ROCK FOR EROSION CONTROL AND SCOUR PROTECTION CLASS C	2330.00	CY		
10	HEAVY LOOSE RIPRAP	490.00	CY		
11	TEMPORARY STREAM DIVERSION	1.00	LS		
<b>STORM SEWER</b>					
12	CATCH BASIN TYPE 1L	4.00	EA		
13	SOLID WALL PVC STORM SEWER PIPE, 12-IN. DIAM.	82.00	LF		
<b>STRUCTURE</b>					
14	STRUCTURE EXCAVATION CLASS A INCL. HAUL	774.00	CY		
15	SHORING OR EXTRA EXCAVATION CLASS A	1.00	LS		
16	GRAVEL BACKFILL FOR WALL	156.00	CY		
17	STRUCTURAL FILL	250.00	CY		
18	FURNISHING ST. PILING	720.00	LF		
19	FURNISHING STEEL PILE TIP OR SHOE	20.00	EA		
20	DRIVING ST. PILE	20.00	EA		
21	ST. REINF. BAR FOR SUBSTRUCTURE	25800.00	LB		
22	CONC. CLASS 4000W FOR SEAL	48.00	CY		
23	CONC. CLASS 4000 FOR SUBSTRUCTURE	193.00	CY		
24	SUPERSTRUCTURE (SEVEN MILE BRIDGE)	1.00	LS		
25	TRAFFIC BARRIER	346.00	LF		
26	BRIDGE APPROACH SLAB	189.00	SY		
27	WATERPROOF MEMBRANE	800.00	SY		
28	CONTRACTOR DESIGNED BURIED STRUCTURE NO.1 (CONC. BOX)	1.00	LS		
29	6-IN DIAM. PVC SLEEVE	383.00	LF		
<b>SURFACING</b>					
30	CRUSHED SURFACING BASE COURSE	1440.00	CY		
<b>HOT MIX ASPHALT</b>					
31	HMA CL. 1/2-IN. PG 64H-28	584.00	TON		
32	HMA FOR APPROACH CL. 1/2-IN. PG 64H-28	30.00	TON		
33	JOB MIX COMPLIANCE PRICE ADJUSTMENT	1.00	DOL	\$ 1.00	\$ 1.00
34	COMPACTION PRICE ADJUSTMENT	1.00	DOL	\$ 1.00	\$ 1.00
<b>EROSION CONTROL AND PLANTING</b>					
35	HIGH VISIBILITY SILT FENCE	1600.00	LF		
36	EROSION CONTROL AND WATER POLLUTION PREVENTION	1.00	DOL	\$ 10,000.00	\$ 10,000.00

ITEM NO	DESCRIPTION	PLAN QUANTITY	UNITS	UNIT PRICE	TOTAL AMOUNT
<b>EROSION CONTROL AND PLANTING (CONTINUED)</b>					
37	SEEDING, FERTILIZING, AND MULCHING	0.70	ACRE		
38	ROOTED PLANTING	54.00	EA		
39	LIVE STAKE CUTTINGS	46.00	EA		
<b>TRAFFIC</b>					
40	EXTRUDED CURB	20.00	LF		
41	BEAM GUARDRAIL TYPE 31 TRANSITION SECTION TYPE 21	4.00	EA		
42	BEAM GUARDRAIL TYPE 31 NON-FLARED TERMINAL	4.00	EA		
43	PAINT LINE	2478.00	LF		
44	PROJECT TEMPORARY TRAFFIC CONTROL	1.00	LS		
<b>OTHER</b>					
45	STRUCTURE SURVEYING	1.00	LS		
46	ROADWAY SURVEYING	1.00	LS		
47	TRIMMING AND CLEANUP	1.00	LS		
48	SPCC PLAN	1.00	LS		
49	MINOR CHANGE	1.00	DOL	\$ 25,000.00	\$ 25,000.00

**TOTAL** \_\_\_\_\_

INFORMATIONAL  
COPY