SUMMARY OF QUANTITIES

5/4/2026

ITEM NO	TOTAL QUANTITY	SUB-TOTAL * SECTION I-07.2(1) OF STANDARD SPECS	SUB-TOTAL ** SECTION I-07.2(2) OF STANDARD SPECS	STD. ITEM NO.	UNIT	ITEM	GROUP 1 US 12 BRIDGE 12/12S	GROUP 2 REIMBURSE FOR THIRD PARTY DAMAGE
						1-PREPARATION		
1	LUMP SUM	LUMP SUM		0001	L.S.	MOBILIZATION	L.S.	
2	LUMP SUM	LUMP SUM		0061	L.S.	REMOVING PORTION OF EXISTING BRIDGE GRID DECK AND CURB	L.S.	
3				7800	EACH	DELETED ITEM		
						8-STRUCTURE		
4	496.00	496.00		4151	LB.	ST. REINF. BAR FOR CURB	496.00	
5	9.00	9.00		4202	C.Y.	CONC. CLASS 4000 FOR CURB	9.00	
6	5,176.00	5,176.00			S.F.	GRID DECK PANEL REPLACEMENT	5,176.00	
7	-1.00	-1.00		4219	DOL.	DEFICIENT STRENGTH CONC. PRICE ADJUSTMENT	-1.00	
8	LUMP SUM	LUMP SUM		4230	L.S.	STRUCTURAL CARBON STEEL	L.S.	
9	4.00	4.00			C.Y.	POLYESTER CONC. FOR STEEL GRID DECK	4.00	
10	LUMP SUM	LUMP SUM		4468	L.S.	CLEANING AND PAINTING BR. NO. 12/12S	L.S.	
11	LUMP SUM	LUMP SUM			L.S.	CONTAINMENT / PLATFORM SYSTEM	L.S.	
12	LUMP SUM	LUMP SUM		4469	L.S.	CONTAINMENT OF ABRASIVES	L.S.	
13	20,000.00	20,000.00		4470	DOL.	TESTING AND DISPOSAL OF CONTAINMENT WASTE	20,000.00	
14	LUMP SUM	LUMP SUM			L.S.	SPAN BALANCING	L.S.	
						18-TRAFFIC		
15	374.00	374.00		6780	L.F.	REMOVING AND RESETTING BEAM GUARDRAIL	374.00	
16	320.00	320.00		6895	L.F.	TEMPORARY PAVEMENT MARKING-SHORT DURATION	320.00	
17	6.00	6.00		6872	EACH	TEMPORARY MISC. PAVEMENT MARKINGS - SHORT DURATION	6.00	
18	77.00	77.00		6902	S.F.	SIGN COVERING	77.00	
19	LUMP SUM	LUMP SUM		6971	L.S.	PROJECT TEMPORARY TRAFFIC CONTROL	L.S.	
20	50,000.00	50,000.00		7572	DOL.	WORK ZONE SAFETY CONTINGENCY	50,000.00	
						19-OTHER ITEMS		
21	LUMP SUM	LUMP SUM		7004	L.S.	TYPE C PROGRESS SCHEDULE	L.S.	
22	50,000.00	50,000.00		7715	DOL.	FORCE ACCOUNT MISC. STEEL REPAIR BR. NO. 12/12S	50,000.00	
23	1,000.00	1,000.00		7480	DOL.	ROADSIDE CLEANUP	1,000.00	
24	5.00	5.00		7725	DOL.	REIMBURSEMENT FOR THIRD PARTY DAMAGE		5.00
25	1.00	1.00		7728	DOL.	MINOR CHANGE	1.00	
26	-1.00	-1.00		7732	DOL.	AGGREGATE COMPLIANCE PRICE ADJUSTMENT	-1.00	
27	LUMP SUM	LUMP SUM		7736	L.S.	SPCC PLAN	L.S.	
28	LUMP SUM	LUMP SUM		7570	L.S.	HEALTH AND SAFETY PLAN	L.S.	
29	1,000.00	1,000.00		7571	DOL.	FA-SITE CLEANUP OF BIO. AND PHYSICAL HAZARDS	1,000.00	

GROUP LEGEND

GROUP NUMBER	SR	CONTROL SECTION	TAX SCHEDULE	FUND PARTICIPANTS
1	012	140595	*	State Fund
2	012	140595	*	State Fund

2026-05-04	AD3-DELETED BI 3	A.A	REGION	STATE	FEDERAL AID PROJECT NO.		Washington State Department of Transportation	US 12 HERON ST BRIDGE GRID DECK REPLACEMENT
			10	WA				
			JOB NUMBER 25C516/4					
			CONTRACT NO XE3727					SUMMARY OF QUANTITIES
DATE	REVISION	BY						

SQ1

SHEET 2 OF 22 SHEETS