



Addendum No. 2

Bid No. 26012

DATE: Thursday, May 14, 2026
TO: All Plan and Specification Holders
FROM: Karen Chi, PE
PROJECT: Eastrail to NE Spring Blvd Trail Link

This addendum changes the original Invitation to Bid documents issued on April 23, 2026 for Invitation to Bid, Bid No. 26012, Eastrail to NE Spring Blvd Trail Link. This addendum shall be signed and submitted with the bid documents.

THE BID DOCUMENTS ARE MODIFIED AS FOLLOWS:

CONTRACT PROVISIONS

PROPOSAL/CONSTRUCTION CONTRACT

(F-21 TO F-25)

Bidders shall replace the pages of the Bid Proposal Tables, pages F-21 through F-25, with the attached revised pages. The summary of changes to the Bid Proposal table are as follows:

- Bid Item No. 31, "Drain Pipe 6 In. Diam.", is deleted.
- Quantity for Bid Item No. 32, "Underdrain Pipe 6 In. Diam.", is changed to 139 LF.
- Adjusted Bid Item Numbers from Bid Item No. 31 to Bid Item No. 101 as shown in the attached revised pages.

SPECIAL PROVISIONS

2-01 CLEARING, GRUBBING, AND ROADSIDE CLEANUP

Insert the following after line 17 on page 63 of the Special Provisions:

2-01.3(1) Clearing

Item number 7 of Section 2-01.3(1) is revised to read as follows:

7. Protect, by fencing and other means per the Contract BMPs, all trees or native growth shown on the Plans or directed by the Engineer to be protected from any damage caused by construction operations. An arborist shall be consulted if necessary per permit requirements.

Payment

Insert the following after line 2 on page 64 of the Special Provisions:

Section 2-01.5 is supplemented with the following:

The unit Contract price per lump sum for "Clearing and Grubbing" shall include the services of an arborist as needed.

6-14 Geosynthetic Retaining Walls

Payment

Lines 12 through 24 on page 83 of the Special Provisions are replaced by the following:

"Geosynthetic Wall with Concrete Fascia", per square foot.

All costs in connection with constructing the permanent geosynthetic retaining wall as specified and shown in the Plans including excavation, the haul and disposal of excavation, the shotcrete fascia with textured shotcrete surface as specified including all concrete, steel reinforcing bars, pre-molded joint filler, polyethylene bond breaker strip, joint sealant, PVC pipe for weep holes, exterior surface finish, acrylic exterior paint, and pigmented sealer and anti-graffiti coating (when specified); all costs associated with construction of shotcrete fascia panels and textured shotcrete surface, including working drawing submittals and qualification mockup panel; and the underdrain system, gravel backfill for drains, and all base course and gravel borrow used as fill for the excavation under the wall as shown on the Plans shall be included in the unit Contract price per square foot for "Geosynthetic Retaining Wall with Concrete Fascia", including furnishing and installing a temporary forming system.

CONTRACT PLANS

UTILITY PLAN AND DETAILS

(SHEET 9)

Replace Sheet 9 (Ref. No. UT02) with the attached sheets.

The following is a summary of the changes:

- Changed pipe type callout and added trash rack callout.

END OF ADDENDUM

Bidders must sign the Addendum in the space provided below and attach it to the bid Proposal.

Addendum No. 2 for Bid No. 26012, total of 8 pages, acknowledged by:

Signature

Firm Name

ITEM NO.	SECTION	ITEM	QUANTITY	UNIT	UNIT PRICE	TOTAL PRICE
19	2-02	Removing Chain Link Fence	290	LF		
20	2-03	Gravel Borrow Incl. Haul	14000	TON		
21	2-03	Roadway Excavation Incl. Haul	1	LS		
22	2-09	Structure Excavation Class B Incl. Haul	115	CY		
23	2-09	Shoring or Extra Excavation Class B	1000	SF		
24	4-04	Crushed Surfacing Base Course	475	TON		
25	5-04	HMA Cl. 1/2 In. PG 58H-22	240	TON		
26	6-06	Bridge Railing Type Bike/Pedestrian	508	LF		
27	6-06	Bridge Railing Type Chain Link Pipe Rail	83	LF		
28	6-11	Reinforced Concrete Wall	959	SF		
29	6-14	Gravel Borrow for Structural Earth Wall Incl. Haul	12000	TON		
30	6-14	Geosynthetic Wall with Concrete Fascia	10440	SF		
31	7-01	Underdrain Pipe 6 In. Diam.	139	LF		
32	7-01	Cleanout	3	EA		
33	7-02	Trash Rack	3	EA		
34	7-04	Ductile Iron Pipe Class 52, 8 In. Diam.	130	LF		
35	7-05	Catch Basin Type 1P	1	EA		
36	7-05	Adjust Catch Basin	3	EA		
37	8-01	ESC Lead	200	DAY		

ITEM NO.	SECTION	ITEM	QUANTITY	UNIT	UNIT PRICE	TOTAL PRICE
38	8-01	Inlet Protection	4	EA		
39	8-01	Stabilized Construction Entrance	85	SY		
40	8-01	High Visibility Fence	650	LF		
41	8-01	Erosion Control and Water Pollution Prevention	1	LS		
42	8-01	Passive or Active Treatment System Complete	1	LS		
43	8-01	Silt Fence	225	LF		
44	8-01	Turbidity and pH Monitoring	150	EA		
45	8-01	CSWPPP and ESC Plan	1	LS		
46	8-01	Erosion Control Blanket	2150	SY		
47	8-02	Topsoil Type A	100	CY		
48	8-02	Mulch	494	CY		
49	8-02	Fine Compost	961	CY		
50	8-02	PSIPE Thuja plicata, 5 Gal. Cont., 48" Ht. Min.	25	EA		
51	8-02	PSIPE Pseudotsuga menziesii, 5 Gal. Cont., 48" Ht. Min.	29	EA		
52	8-02	PSIPE Picea sitchensis, 5 Gal. Cont., 48" Ht. Min.	10	EA		
53	8-02	PSIPE Malus fusca, B&B, 6' Ht. Min.	18	EA		
54	8-02	PSIPE Rhamnus purshiana, B&B, 6' Ht. Min.	29	EA		
55	8-02	PSIPE Populus tremuloides, B&B, 6' Ht. Min.	38	EA		
56	8-02	PSIPE Prunus emarginata, 5 Gal. Cont., 6' Ht. Min.	7	EA		

ITEM NO.	SECTION	ITEM	QUANTITY	UNIT	UNIT PRICE	TOTAL PRICE
57	8-02	PSIPE Salix scouleriana, 2 Gal. Cont., 36" Ht. Min.	9	EA		
58	8-02	PSIPE Corylus cornuta, 5 Gal. Cont., 36"- 48" Ht. Min.	66	EA		
59	8-02	PSIPE Amelanchier alnifolia, 5 Gal. Cont., 36"- 48" Ht. Min.	67	EA		
60	8-02	PSIPE Acer circinatum, 5 Gal. Cont., 36"- 48" Ht. Min.	67	EA		
61	8-02	PSIPE Sambucus racemosa, 1 Gal. Cont., 8"-12" Ht. Min.	229	EA		
62	8-02	PSIPE Oemleria cerasiformus, 1 Gal. Cont., 8"-12" Ht. Min.	225	EA		
63	8-02	PSIPE Holidiscus discolor, 1 Gal. Cont., 8"-12" Ht. Min.	324	EA		
64	8-02	PSIPE Cornus sericea, 1 Gal. Cont., 8"-12" Ht. Min.	16	EA		
65	8-02	PSIPE Lonicera involucrata, 1 Gal. Cont., 8"-12" Ht. Min.	85	EA		
66	8-02	PSIPE Philadelphus lewisii, 1 Gal. Cont., 8"-12" Ht. Min.	324	EA		
67	8-02	PSIPE Symphoricaros albus, 1 Gal. Cont., 8"-12" Ht. Min.	42	EA		
68	8-02	PSIPE Rosa nutkana, 1 Gal. Cont., 8"-12" Ht. Min.	92	EA		
69	8-02	PSIPE Mahonia aquifolium, 1 Gal. Cont., 8"-12" Ht. Min.	72	EA		
70	8-02	PSIPE Polystichum munitum, 1 Gal. Cont., 8"-12" Ht. Min.	48	EA		
71	8-02	PSIPE Arctostaphylos uva-ursi, 1 Gal, Cont., 8"-12" Ht. Min.	1686	EA		
72	8-02	PSIPE Campanula rotundifolia, 1 Gal, Cont., 8"-12" Ht. Min.	35	EA		
73	8-02	PSIPE Lupinus polyphyllus, 1 Gal., Cont., 8"-12" Ht. Min.	814	EA		
74	8-02	PSIPE Tritelia hyacinthina, 1 Gal., Cont., 8"-12" Ht. Min.	106	EA		

ITEM NO.	SECTION	ITEM	QUANTITY	UNIT	UNIT PRICE	TOTAL PRICE
75	8-02	PSIPE Achillea millefolium, 1 Gal., Cont., 8"-12 Ht. Min.	387	EA		
76	8-02	PSIPE Cornus 'Starlight'/ Starlight Dogwood; 2" Cal., 10'-12' Ht.	3	EA		
77	8-02	PSIPE Liriope muscari 'Big Blue'/ Big Blue Lilyturf; 1 Gal., 6" Ht. Min.	115	EA		
78	8-02	PSIPE Geranium macrorrhizum 'Bevans Variety'/ Bigroot Geranium; 1 Gal., 6" Ht. Min.	106	EA		
79	8-02	PSIPE Pennisetum alopecuroides 'Hameln'/ Dwarf Fountain Grass; 1 Gal., 12" Ht. Min.	37	EA		
80	8-02	PSIPE Gaultheria shallon/ Salal; 1 Gal., 6" Ht. Min.	25	EA		
81	8-02	PSIPE Mahonia repens/ Creeping Oregon Grape; 1 Gal., 6" Ht. Min.	49	EA		
82	8-02	PSIPE Cornus sericea 'Kelseyii'/ Kelsey Dogwood; 1 Gal., 10" Ht. Min.	35	EA		
83	8-02	PSIPE Polystichum munitum/ Western Sword Fern; 1 Gal., 6" Ht. Min.	32	EA		
84	8-02	PSIPE Ceanothus gloriosus/ Point Reyes Ceanothus; 2 Gal., 6" Spread Min.	30	EA		
85	8-02	PSIPE Imperata cylindrica/ Japanese Blood Grass; 1 Gal., 6" Ht. Min.	47	EA		
86	8-02	PSIPE Ribes sanguineum 'King Edward VII'/ Red Flowering Currant; 5 Gal., 24" Ht. Min.	6	EA		
87	8-02	PSIPE Rosa 'Radrazz'/ Knock Out Rose; 2 Gal., 12" Ht. Min.	9	EA		

ITEM NO.	SECTION	ITEM	QUANTITY	UNIT	UNIT PRICE	TOTAL PRICE
88	8-02	PSIPE Carex pachystachya/ Thick-headed Sedge; 1 Gal., 6" Ht. Min.	27	EA		
89	8-02	Property Restoration	1	FA	\$25,000	\$25,000
90	8-02	Bench	2	EA		
91	8-03	Irrigation System	1	LS		
92	8-12	Coated Chain Link Fence Type 3	745	LF		
93	8-12	Coated End, Gate, Corner, Pullpost for Chain Link Fence	23	EACH		
94	8-14	Cement Conc. Sidewalk	48	SY		
95	8-14	Scored Cement Conc. Sidewalk	155	SY		
96	8-14	Cement Conc. Stairs	36	SY		
97	8-14	Stair Handrail	152	LF		
98	8-20	Illumination System Complete	1	LS		
99	8-21	Permanent Signing	1	LS		
100	8-22	Paint Line	815	LF		
101	8-30	Streambed Cobbles 8 In.	220	TON		

Schedule A Total