

**ADDENDUM 2  
TO THE CONTRACT PROVISIONS AND CONTRACT PLANS**

**FOR**

**NOB HILL WATER ASSOCIATION  
WESTBROOK RESERVOIRS IMPROVEMENTS**

**G&O #23873**

**ISSUED THIS DATE: WEDNESDAY, JUNE 10, 2026**

**BID SUBMITTAL: 2:00 P.M. (LOCAL TIME) ON  
WEDNESDAY, JUNE 17, 2026  
NOB HILL WATER ASSOCIATION  
6111 TIETON DRIVE  
YAKIMA, WASHINGTON 98908**



**Bidder shall acknowledge receipt of this Addendum on Page P-7 of the Proposal.**

---

TO PROSPECTIVE BIDDERS:

The attention of all prospective bidders on the above project is directed to the following additions and modifications to the Contract Provisions and Contract Plans.

**I. ADDITIONS, MODIFICATIONS, AND/OR DELETIONS TO THE  
TECHNICAL SPECIFICATIONS**

**ITEM 1:**

Page 15050-4, Specification Section 15050-2.3 A., PRESSURE PIPE

**REVISE** the first paragraph as shown below (added text is italicized, deleted text is shown as strike out):

“High Density Polyethylene (pipe) shall be butt welded PE 4710 pipe conforming to ASTM D3350 having a cell classification of PE 445574 or better. Pipe dimensions and workmanship shall conform to ASTM F714. HDPE pipe shall conform to AWWA C906 Standards and have a pressure rating of at least 200 psi (SDR11). HDPE pipe shall be class DIPS *or IPS.*”

**II. ADDITIONS, MODIFICATIONS, AND/OR DELETIONS TO THE CONTRACT PLANS**

**ITEM 1:**

**SHEET R1-2, ROOF DEMOLITION PLAN**

**ADD** the following note to the sheet:

- “1. CONSTRUCTION LOADS ON THE RESERVOIR ROOF SHALL NOT EXCEED 35 PSF. VEHICLES, MATERIAL STORAGE INCLUDING PILING OF DEBRIS, AND OTHER HEAVY LIVE LOADS ARE NOT PERMITTED ON THE ROOF SLAB.”

**ITEM 2:**

**SHEET R1-6, PROPOSED ROOF PLAN**

**ADD** the following note to the sheet:

- “4. CONSTRUCTION LOADS ON THE RESERVOIR ROOF SHALL NOT EXCEED 35 PSF. VEHICLES, MATERIAL STORAGE INCLUDING PILING OF DEBRIS, AND OTHER HEAVY LIVE LOADS ARE NOT PERMITTED ON THE ROOF SLAB.”

**ITEM 3:**

**SHEET R2-2, EXISTING ROOF AND DEMOLITION PLAN**

**ADD** the following to the end of the callout reading DEMOLISH 2-1/2"± CONC TOPPING SLAB:

- “CONSTRUCTION LOADS ON THE RESERVOIR ROOF SHALL BE LIMITED TO 35 PSF UNO. VEHICLES, MATERIAL STORAGE INCLUDING PILING OF DEBRIS, AND OTHER HEAVY LIVE LOADS ARE NOT PERMITTED ON THE ROOF SLAB.”

**ITEM 4:**

**SHEET R2-6, PROPOSED ROOF PLAN**

**ADD** the following note to the sheet:

- “11. CONSTRUCTION LOADS ON THE RESERVOIR ROOF, WITH THE EXCEPTION OF WET CONCRETE LOADS AS NOTED IN DETAIL 3 OF SHEET R2-8, SHALL NOT EXCEED 35 PSF. VEHICLES, MATERIAL STORAGE INCLUDING PILING OF DEBRIS, AND OTHER HEAVY LIVE LOADS ARE NOT PERMITTED ON THE ROOF SLAB.”