

Wallula Bridge on Wallula Avenue MP 0.00 To MP 0.20 | CRP 22-03

BIDDER'S Q&A 03 | July 09, 2026

Questions and Answers as of 07/09/2026:

1. A question has arisen regarding a conflict in the plans. On sheet 17, over CL Girder E, the note states that the grout pads are to be placed monolithically with the cap. Additionally, on sheet 28, the same grout pads are shown as constructed after cap placement.

Please advise which construction sequence is required.

The note on sheet 17 is correct. The notes on sheet 28 are also correct. It appears that the confusion comes from how the grout pad has a dashed line that appears to be below the top of the cap. That dashed line is not intended to show a construction joint. The grout pad is to be constructed monolithically with the cap, level longitudinally and along the abutment slope transversely.