



Oregon

Tina Kotek, Governor

Oregon Department of Transportation
Statewide Project Delivery Branch
Project Controls Office
555 13th St NE
Salem, OR 97301

BID REFERENCE DOCUMENT

DATE: October 14, 2026

Letter of Clarification No. 10

TO: PLAN HOLDERS

PREPARED BY: Steven Schultz Digitally signed by Steven Schultz
Date: 2026.10.14 09:34:53 -0700
Steven Schultz

FINAL ELECTRONIC DOCUMENT AVAILABLE UPON REQUEST

SUBJECT: OR22: Center St Bridge (Phase 1) Project
Willamina-Salem Highway
Marion & Polk Counties
Grading, Drainage, Structures, Paving, Signing, Illumination, And Roadside
Development
(Bids Closing October 27, 2026)

The following Bid Reference Documents have been added to eBIDS:

- Agency's Conceptual Temporary Fencing Layout

The following is the Agency's response to Bidders' questions/requests for clarification:

Question #1: Can temporary self-supported fencing be used in lieu of what's shown in BB18? Please provide more details as to where the fencing and gates are required and of the 21 day constraint listed in Section 00270?

Response #1: Section 00270 Temporary Fence: Despite the design for robust construction, as shown on Sheet BB18, the fence is "temporary" and to be removed after the project. Per 00270.00, the Work consists of constructing, maintaining, and removing temporary fences, gates, and gateways as shown or directed. It is intended to prevent the need to repeatedly and continuously clear work areas of personal property and hazardous debris. Even though the Agency has 21 Days for re-clearing hazards and personal property during which time contractors are not entitled to additional time or compensation, there is a cost to the Agency to clear the site again, which needs to be minimized. Temporary self-supported fencing is not expected to provide enough of a deterrent and will not be accepted in lieu of the fence detailed on Sheet

BB18. Regarding gates, 00270.80 specifies that gates will be paid center to center of the posts and paid for under the fence item.

Layout is dependent on the contractor's needs for shoring, work area and materials storage, access, etc. Although ODOT will direct the fence to be installed, it is expected that the Contractor and ODOT will work collaboratively to determine the best location for the fence, accesses, and gates. Also note that when someone enters a fenced and posted area, the legal timelines for cleanup of any personal property generated are shorter in duration, which will lead to areas being cleared more quickly.