CLARK COUNTY WASHINGTON
PUBLIC WORKS

PROPOSAL AND CONTRACT DOCUMENTS FOR

WHIPPLE, KNAPPS, CARSON BRIDGE BUNDLE

PROJECT NO. 0001799
COUNTY ROAD PROJECT NO. 320322
FEDERAL AID PROJECT NO. BHS-Z906(004)
FEDERAL CONTRACT NO. TA-7424

OCTOBER 2026

Approved For Construction: _____ 09/08/2026

Jeremiah D. Provenzola, P.E.
County Engineer


Date

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

WHIPPLE, KNAPPS, CARSON BRIDGE BUNDLE

Certification

The technical material and data contained in this document were prepared under the supervision and direction of the undersigned, whose seal, as a professional engineer licensed to practice as such, is affixed below.



9/04/2026



09/08/2026

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

CONTENTS

1. **NOTICE TO CONTRACTORS**
2. **BID FORMS**
   - Bidding Requirements Cover Sheet
   - Instructions And Information For Bidders
   - Non-Collusion Declaration
   - Local Agency Certification For Federal-Aid Contracts
   - Contractor Certification Wage Law Compliance
   - Bidder Questionnaire and Instructions
   - Chemical Hazard Communication Program
   - Proposal for Incorporating Recycled Materials into the Project
   - Proposal
   - Proposal Signature Page
3. **CONTRACT FORMS**
   - Contract
   - Contract Bond
4. **SPECIFICATIONS AND APPENDICES**
   - Table Of Contents
   - Special Provisions
5. **MISCELLANEOUS ITEMS**
   - Title VI Non-Discrimination Assurances
   - Required Contract Provisions Federal-Aid Construction Contracts
   - Prevailing Wage Rates

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Docusign Envelope ID: 85066612-2BFF-81FE-8059-6785CE514FF7

CLARK COUNTY WASHINGTON
PUBLIC WORKS

www.clark.wa.gov

1300 Franklin Street
PO Box 9810
Vancouver, WA 98666-9810
564.397.6118

NOTICE TO CONTRACTORS

Notice is hereby given that sealed bids will be received by Clark County, Washington until **1:50 P.M.** on October 6, **2026** for: **CRP 320322 / PRJ0001799, Whipple, Knapps, Carson Bridge Bundle.**

Sealed bids shall be delivered to the office of Clark County Purchasing, Public Service Center, 1300 Franklin Street, Suite 650, Vancouver, Washington 98660 (or P.O. Box 5000, Vancouver, WA 98666-5000). Bids delivered to locations other than as indicated above or received after the time indicated above will not be accepted. Bids will be publicly opened and read aloud at 2:00 P.M., or as soon thereafter as possible, on the same day in the Hearing Room of the Clark County Council, 6th Floor of the Public Service Center.

Description of work: This project includes strengthening three bridges with various bridge strengthening systems (cast-in-place concrete, fiber reinforced polymer), traffic control, and other related work.

Primary Bid Items: Construction Surveying, Traffic Control Supervisor, Flaggers, Other Traffic Control Labor, Br. Rehab. ___Bridge No. ___.

Bid documents can be viewed, downloaded, or purchased on the Builders Exchange of Washington (BXWA) website www.bxwa.com (Posted Projects, Public Works, Clark County and Projects Bidding). Bidders are encouraged to "Register as a Bidder" in order to receive automatic email notification of future addenda and to be placed on the Bidders List. Electronic and paper copies of bid documents are not available from Clark County.

It is the sole responsibility of the Bidder to obtain Addenda, if any. Such information may be obtained from the Builders Exchange of Washington (BXWA) web site, www.bxwa.com (Posted Projects, Public Works, Clark County and Projects Bidding). Clark County accepts no responsibility or liability and will provide no accommodation to bidders who fail to check for addenda and submit inadequate or incomplete bids.

Questions and requests for clarification must be submitted using the electronic "CRP Inquiry Submittal Form" located on the County website, https://clark.wa.gov/internal-services/public-works-roads-parks-clean-water-projects. Responses will be posted on the project's "Bid Inquiry Log".

All bids must be submitted on the forms provided in the bid documents. Bids must be submitted in a sealed envelope with the Bidder's company name, project title, project number, bid opening date, and "SEALED BID" clearly marked on the outside of the envelope. Bids submitted by FAX or email will not be accepted.

Each bid proposal must be accompanied by a bid deposit in the form of a certified check, cashier's check, or proposal bond in an amount of at least five percent (5%) of the total bid. Should the successful bidder fail to enter into a contract and furnish a satisfactory contract bond, the bid deposit shall be forfeited to Clark County.

For other formats, contact Clark County ADA Office / **Voice** 564.397.2322 **Relay** 711 800.833.6388 **Email** ADA@clark.wa.gov

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Docusign Envelope ID: 85066612-2BFF-81FE-8059-6785CE514FF7

Clark County, in accordance with the provisions of Title VI of the Civil Rights Act of 1964 (78 Stat. 252, 42 U.S.C. 2000d to 2000d-4) and the Regulations, hereby notifies all bidders that it will affirmatively ensure that any contract entered into pursuant to this advertisement, disadvantaged business enterprises will be afforded full and fair opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

For questions regarding Clark County Public Works' Title VI program, or for interpretation or translation services for non-English speakers, or otherwise making materials available in an alternate format, contact Clark County Public Works' Title VI Coordinator via email at CCPW-TitleVI@clark.wa.gov or phone 564-397-4944. Hearing/speech impaired may call the Washington Relay Center at 711.

TÍTULO VI

El condado de Clark, de acuerdo con las disposiciones del Título VI de la Ley de Derechos Civiles de 1964 y las Regulaciones, o Title VI of the Civil Rights Act of 1964 and the Regulations, (78 Stat.252, 42 USC 2000d a 2000d-4), por este medio notifica a todos los postores que se les asegura afirmativamente de que en cualquier contrato en conformidad con este anuncio, las empresas comerciales desfavorecidas tendrán la oportunidad plena y justa de presentar ofertas en respuesta a esta invitación y no serán discriminadas por motivos de raza, color u origen nacional en consideración para una concesión.

Si tiene preguntas sobre el programa Título VI de obras públicas del condado de Clark, o para servicios de interpretación o traducción para personas que no hablan inglés, o si tiene materiales disponibles en un formato alternativo, comuníquese con el coordinador del Título VI de obras públicas del condado de Clark por correo electrónico a CCPW-TitleVI@clark.wa.gov o teléfono 564-397-4944. Las personas con problemas de audición o del habla pueden llamar al Washington Relay Center al 711.

Раздел VI

В соответствии с нормами раздела VI Закона о гражданских правах 1964 г. (Civil Rights Act) (раздела 78 ст. 252 главы 42 Свода законов США, §§ 2000d — 2000d-4) и нормативными актами, округ Кларк настоящим уведомляет всех участников торгов о том, что он гарантирует, что в любом договоре, заключенном в соответствии с данным объявлением, предприятиям, находящимся в неблагоприятных условиях, предоставляются полные и равные возможности для подачи предложения в ответ на данное приглашение, и при рассмотрении вопроса о получении финансирования они не подвергаются дискриминации по признаку расовой принадлежности, цвета кожи или национального происхождения.

По вопросам, касающимся программы «Раздел VI» (Title VI) Управления общественных работ (Public Works) округа Кларк, а также по вопросам, касающимся устного или письменного перевода для лиц, не говорящих на английском языке, либо предоставления информационных материалов в альтернативном формате, обращайтесь к координатору программы «Раздел VI» Управления общественных работ округа Кларк по электронной почте CCPW-TitleVI@clark.wa.gov или по номеру 564-397-4944. Лица с нарушением слуха или речи могут позвонить в Вашингтонскую службу коммутируемых сообщений (Washington Relay Center) по номеру 711.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

The County reserves the right to waive informalities in the bidding, reject any or all bids, or cancel the bid if the best interests of Clark County are not served.

DATED this 22nd day of May, 2026

Priscilla Mason

Priscilla Mason, Purchasing Agent of Record

THE COLUMBIAN
DAILY JOURNAL OF COMMERCE:

PLEASE PUBLISH: Sept 16, Sept 23, Sept 30, 2026

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

BID FORMS

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

BIDDING REQUIREMENTS COVER SHEET

WHIPPLE, KNAPPS, CARSON BRIDGE BUNDLE
PROJECT NO. 0001799
CRP NO. 320322

PROPOSAL SUBMITTED BY:

_____

CONTRACTOR

_____

ADDRESS

_____

CITY, STATE, ZIP

_____

TELEPHONE

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

INSTRUCTIONS AND INFORMATION FOR BIDDERS

- Bids will be opened at the Councilors Hearing Room, 6th Floor of the Public Service Center, at the time and date specified in the Notice to Contractors.

- Bids shall be mailed or delivered to the office of Clark County Purchasing by the time and date specified in the Notice to Contractors. Bids received by FAX or email will not be accepted. Bids delivered to locations other than as indicated above or received after the designated time will not be accepted.

- Bids shall be placed in a sealed envelope, marked "Sealed Bid", which clearly states the name of the bidder, project number, project name, date of the bid opening, and appropriate wording to indicate definitely the nature of the contents.

- Bids are to be submitted on the forms provided in these bid documents.

- Proposal Bond forms are not provided in these bid documents. See Contract Specifications for Proposal Bond requirements.

- The Contractor, if awarded the Contract, shall register and enter into a Memorandum of Understanding (MOU) with the Department of Homeland Security E-Verify program before execution of the Contract. The Contractor shall ensure all Contractor employees and any sub-contractor(s) assigned to perform work under this Agreement are eligible to work in the United States. The Contractor shall provide verification of compliance. Failure by Contractor to comply with this subsection shall be considered a material breach.

- See Contract Specifications for additional information.

The following forms and information must be executed in full and submitted with the Bid:

- Non-Collusion Declaration
- Local Agency Certification For Federal-Aid Contracts
- Contractor Certification Wage Law Compliance
- Bidder Questionnaire(s)
- Chemical Hazard Communication Program
- Proposal for Incorporating Recycled Materials into the Project
- Proposal
- Proposal Signature Page
- Bid Deposit (Cashier's Check, Certified Check, Or Proposal Bond)

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Failure to return this Declaration as part of the bid proposal package will make the bid nonresponsive and ineligible for award.

NON-COLLUSION DECLARATION

I, by signing the proposal, hereby declare, under penalty of perjury under the laws of the United States that the following statements are true and correct:

1. That the undersigned person(s), firm, association or corporation has (have) not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of free competitive bidding in connection with the project for which this proposal is submitted.

2. **That by signing the signature page of this proposal, I am deemed to have signed and have agreed to the provisions of this declaration.**

NOTICE TO ALL BIDDERS

To report rigging activities call:

1-800-424-9071

The U.S. Department of Transportation (USDOT) operates the above toll-free "hotline" Monday through Friday, 8:00 a.m. to 5:00 p.m., eastern time. Anyone with knowledge of possible bid rigging, bidder collusion, or other fraudulent activities should use the "hotline" to report such activities.

The "hotline" is part of the USDOT's continuing effort to identify and investigate highway construction contract fraud and abuse and is operated under the direction of the USDOT Inspector General. All information will be treated confidentially and caller anonymity will be respected.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Local Agency Certification for Federal-Aid Contracts

The prospective participant certifies by signing and submitting this bid or proposal, to the best of his or her knowledge and belief, that:

(1) No Federal appropriated funds have been paid or will be paid, by or on behalf of the undersigned, to any person for influencing or attempting to influence an officer or employee of any Federal agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with the awarding of any Federal contract, the making of any Federal grant, the making of any Federal loan, the entering into of any cooperative agreement, and the extension, continuation, renewal, amendment, or modification of any Federal contract, grant, loan, or cooperative agreement.

(2) If any funds other than Federal appropriated funds have been paid or will be paid to any person for influencing or attempting to influence an officer or employee of any Federal agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with this Federal contract, grant, loan, or cooperative agreement, the undersigned shall complete and submit Standard Form-LLL, "Disclosure Form to Report Lobbying," in accordance with its instructions.

This certification is a material representation of the fact upon which reliance was placed when this transaction was made or entered into. Submission of this certification is a prerequisite for making or entering into this transaction imposed by Section 1352, Title 31, U.S. Code. Any person who fails to file the required certification shall be subject to a civil penalty of not less than $10,000 and not more than $100,000 for each failure.

The prospective participant also agrees by submitting his or her bid or proposal that he or she shall require that the language of this certification be included in all lower tier subcontracts, which exceed $100,000 and that all such subrecipients shall certify and disclose accordingly.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

CONTRACTOR CERTIFICATION WAGE LAW COMPLIANCE

The bidder hereby certifies that, within the three-year period immediately preceding the bid submittal date stated in the Notice to Contractors, the bidder is not a "willful" violator, as defined in RCW 49.48.082, of any provision of chapters 49.46, 49.48, or 49.52 RCW, as determined by a final and binding citation and notice of assessment issued by the Department of Labor and Industries or through a civil judgment entered by a court of limited or general jurisdiction.

I certify under penalty of perjury under the laws of the State of Washington that the foregoing is true and correct.

_____

Bidder Name (Name of Contractor/Bidder – Print full legal entity name of firm)

_____

Signature of Authorized Official*

_____

Printed Name (Print name of person making certification for firm)

_____

Title (Title of person signing certificate)

_____ _____

Date City & State (Print city and state where signed)

Bidder is a: (Check One)

Sole Proprietorship ☐ Partnership ☐ Joint Venture ☐ Corporation ☐

State of Incorporation, or if not a corporation, State where business entity was formed:

_____

If a co-partnership, give firm name under which business is transacted:

_____

** If a corporation, proposal must be executed in the corporate name by the president or vice-president (or any other corporate officer accompanied by evidence of authority to sign). If a co-partnership, proposal must be executed by a partner.*

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

BXWA

Washington State Department of Transportation

Bidder Questionnaire

Agency Name	Federal Aid Number
Prime Contractor Name	Contract Number
Contract Name	

Firm/Subcontractor Name	Address (incl. ZIP Code)	DBE Status	NAICS Codes	Scope of Work	Firm Age	Firm Gross Receipts

If you have additional Firms or Subcontractors that submitted Bids, please complete additional forms.
All bidders listed on any other forms, including the Subcontractor List, must appear on this form.

Prime Contractor Representative

Date

DOT Form 272-022 Revised 4/2026
• **Previous Versions Obsolete** •

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Form Instructions

The following information on each firm that submitted a bid is required as part of part of 49 CFR 26.11(c)(2):

Firm/Subcontractor Name: Enter the name of each firm or subcontractor who submitted a quote or a bid on the contract.

Address: Enter the main address of the firm/subcontractor. Include the ZIP code.

DBE Status: Enter the DBE status. *Options are DBE and Non-DBE.*

NAICS Codes: Enter the appropriate NAICS Codes for the work the bid was submitted for.

Scope of Work: Enter the scope of the work the bid was submitted for.

Firm Age: Enter the age of the firm.

Firm Gross Receipts: Enter the annual gross receipts. *Options are "Less than $1 million", "$1-$3 million", "$3-$6 million", "$6-$10 million", "$10-$20 million ", "$20-$30.72 million ", "Greater than $30.72 million ".*

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

CHEMICAL HAZARD COMMUNICATION PROGRAM

1. All county departments and contractors shall comply with Clark County's Chemical Hazard Communication Program. This program is in accordance with WAC 296-307 Part Y-1.

2. All contractors who will be working on Clark County premises must read Clark County's written Chemical Hazard Communication Program. **By signing the Proposal Signature Page, the Contractor acknowledges that they have read and will follow the directives of this section.**

3. Prior to work start-up, it is the responsibility of the Engineer to provide contractors working in their area information on the following:

    1) Hazardous chemicals to which they may be exposed while on the job site;
    2) Location of the MSDS file, which will be available to the contractor and its employees;
    3) Explanation of the labeling system and any precautionary measures or practices that need to be taken to protect their employees; and
    4) That at the completion of a job the Contractor must remove all hazardous substances that the Contractor has brought onto Clark County premises.

4. The Contractor must, before work begins, provide to the Engineer the following for any hazardous material:

    1) An inventory of the hazardous material the Contractor will be using;
    2) An MSDS for each of these materials;
    3) An explanation of the Contractor's labeling system; and
    4) Any precautionary measures which need to be taken to protect county employees.

5. It is the Engineer's responsibility to provide the information referred to in Section 4.4 of this form to all county employees who will be affected. This information must be given to the employees before the work begins. Posting of this information on the safety bulletin board will satisfy this requirement.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Proposal for Incorporating Recycled Materials into the Project

In compliance with RCW 70A.205.700, the Bidder shall propose below, the total percent of construction aggregate and concrete materials to be incorporated into the Project that are recycled materials. Calculated percentages must be within the amounts allowed in Section 9-03.21(1)E, Table on Maximum Allowable Percent (By Weight) of Recycled Material, of the Standard Specifications.

Proposed total percentage:_____percent.

Note: Use of recycled materials is highly encouraged within the limits shown above, but does not constitute a Bidder Preference, and will not affect the determination of award, unless two or more lowest responsive Bid totals are exactly equal, in which case proposed recycling percentages will be used as a tie-breaker, per the APWA GSP in Section 1-03.1 of the Special Provisions. Regardless, the Bidder's stated proposed percentages will become a goal the Contractor should do its best to accomplish. Bidders will be required to report on recycled materials actually incorporated into the Project, in accordance with the APWA GSP in Section 1-06.6 of the Special Provisions.

Bidder: _____

Signature of Authorized Official: _____

Date: _____

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

PROPOSAL

To the Clark County Council, Clark County Washington

The undersigned hereby certifies that he/she has examined the location of:

PROJECT NO. 0001799 / CRP NO. 320322

WHIPPLE, KNAPPS, CARSON BRIDGE BUNDLE

in Clark County and has read and thoroughly understands the plans, specifications, and contract governing the work embraced in this improvement, and the method by which payment will be made for said work, and hereby proposes to undertake and complete the work embraced in the improvement in accordance with the said plans, specifications, and contract, and at the following schedule of rates and prices.

NOTE:

- Unit prices for all items, all extensions, and total amount of bid shall be shown.
- All entries must be typed or written in ink. Show prices in legible figures (not words)

SCHEDULE A - WHIPPLE CREEK BRIDGE NO. 11

Include all applicable use and/or sales taxes in the individual Unit and Lump Sum prices.

ITEM NO.	SPEC. SECTION	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	TOTAL PRICE
1	2-01	MOBILIZATION	L.S.	1	LUMP SUM	
2	1-05.4	CONSTRUCTION SURVEYING	L.S.	1	LUMP SUM	
3	1-07.13	REIMBURSEMENT FOR THIRD PARTY DAMAGE	EST.	1	$5.00	$5.00
4	1-07.15	SPCC PLAN	L.S.	1	LUMP SUM	
5	2-04	TRAFFIC CONTROL SUPERVISOR	L.S.	1	LUMP SUM	
6	2-04	FLAGGERS	HR	200		
7	2-04	OTHER TRAFFIC CONTROL LABOR	HR	75		
8	2-04	OTHER TEMPORARY TRAFFIC CONTROL DEVICES	L.S.	1	LUMP SUM	
9	2-04	WORK ZONE SAFETY CONTINGENCY	EST.	1	$10,000.00	$10,000.00
10	3-01	ROADSIDE CLEANUP	EST.	1	$2,500.00	$2,500.00

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

ITEM NO.	SPEC. SECTION	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	TOTAL PRICE
11	6-02	BR. REHAB. - WHIPPLE CREEK BRIDGE NO. 11	L.S.	1	LUMP SUM	
12	8-01	EROSION CONTROL AND WATER POLLUTION PREVENTION	L.S.	1	LUMP SUM	
13	8-01	ESC LEAD	DAY	20		
14	8-01	HIGH VISIBILITY SILT FENCE	L.F.	60		
					SCHEDULE A TOTAL	

SCHEDULE B - KNAPPS STATION BRIDGE NO. 12

Include all applicable use and/or sales taxes in the individual Unit and Lump Sum prices.

ITEM NO.	SPEC. SECTION	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	TOTAL PRICE
15	2-01	MOBILIZATION	L.S.	1	LUMP SUM	
16	1-05.4	CONSTRUCTION SURVEYING	L.S.	1	LUMP SUM	
17	1-07.13	REIMBURSEMENT FOR THIRD PARTY DAMAGE	EST.	1	$5.00	$5.00
18	1-07.15	SPCC PLAN	L.S.	1	LUMP SUM	
19	2-04	TRAFFIC CONTROL SUPERVISOR	L.S.	1	LUMP SUM	
20	2-04	FLAGGERS	HR	200		
21	2-04	OTHER TRAFFIC CONTROL LABOR	HR	75		
22	2-04	OTHER TEMPORARY TRAFFIC CONTROL DEVICES	L.S.	1	LUMP SUM	
23	2-04	WORK ZONE SAFETY CONTINGENCY	EST.	1	$10,000.00	$10,000.00
24	3-01	ROADSIDE CLEANUP	EST.	1	$2,500.00	$2,500.00

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

ITEM NO.	SPEC. SECTION	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	TOTAL PRICE
25	6-02	BR. REHAB. - KNAPPS STATION BRIDGE NO. 12	L.S.	1	LUMP SUM	
26	8-01	EROSION CONTROL AND WATER POLLUTION PREVENTION	L.S.	1	LUMP SUM	
27	8-01	ESC LEAD	DAY	20		
28	8-01	HIGH VISIBILITY SILT FENCE	L.F.	120		
					SCHEDULE B TOTAL	

SCHEDULE C - CARSON BRIDGE NO. 63

Include all applicable use and/or sales taxes in the individual Unit and Lump Sum prices.

ITEM NO.	SPEC. SECTION	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	TOTAL PRICE
29	2-01	MOBILIZATION	L.S.	1	LUMP SUM	
30	1-05.4	CONSTRUCTION SURVEYING	L.S.	1	LUMP SUM	
31	1-07.13	REIMBURSEMENT FOR THIRD PARTY DAMAGE	EST.	1	$5.00	$5.00
32	1-07.15	SPCC PLAN	L.S.	1	LUMP SUM	
33	2-04	TRAFFIC CONTROL SUPERVISOR	L.S.	1	LUMP SUM	
34	2-04	FLAGGERS	HR	200		
35	2-04	OTHER TRAFFIC CONTROL LABOR	HR	75		
36	2-04	OTHER TEMPORARY TRAFFIC CONTROL DEVICES	L.S.	1	LUMP SUM	
37	2-04	WORK ZONE SAFETY CONTINGENCY	EST.	1	$10,000.00	$10,000.00
38	3-01	ROADSIDE CLEANUP	EST.	1	$2,500.00	$2,500.00

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

ITEM NO.	SPEC. SECTION	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	TOTAL PRICE
39	6-02	BR. REHAB. - CARSON BRIDGE NO. 63	L.S.	1	LUMP SUM	
40	8-01	EROSION CONTROL AND WATER POLLUTION PREVENTION	L.S.	1	LUMP SUM	
41	8-01	ESC LEAD	DAY	20		
42	8-01	HIGH VISIBILITY SILT FENCE	L.F.	60		
					SCHEDULE C TOTAL	

TOTAL BID (Sum of All Schedules)	

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

PROPOSAL SIGNATURE PAGE

The bidder is hereby advised that by signature of this proposal he/she is deemed to have acknowledged all requirements and signed all certificates contained herein.

A proposal guaranty in the amount of at least five percent (5%) of the total bid, based upon the approximate estimate of quantities at the above prices and in the form as indicated below, is attached hereto:

Cashier's Check ☐ Payable to Clark County Treasurer

Certified Check ☐ Payable to Clark County Treasurer

Proposal Bond ☐

Receipt is hereby acknowledged of Addenda (check appropriate box(es)):

None ☐ 1 ☐ 2 ☐ 3 ☐ 4 ☐ 5 ☐ 6 ☐ 7 ☐ 8 ☐

PROPOSAL MUST BE SIGNED

_____
(Signature of Authorized Official or Officials)

_____
(Printed Name of Authorized Official or Officials)

_____
(Company Name)

_____
(Address) (City, State, Zip)

_____ _____
(Telephone Number) (Email Address)

The following information is required per RCW 39.04.350:

_____ _____
(Washington State Contractor's License #) (WA State Contractor's License Expiration Date)

_____ _____
(State Unified Business Identifier #) (Industrial Insurance Coverage #)

_____ _____
(State Excise Tax Registration #) (Employment Security Department #)

Note:

1. *This proposal form is not transferable and any alteration of the firm's name entered hereon may be cause for considering the proposal irregular and subsequent rejection of the bid.*
2. *Refer to Section 1-02.6 of the Standard Specifications, re: "Preparation of Proposal".*

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

CONTRACT FORMS

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

1-10.4 Contract

CONTRACT

This agreement ("Agreement"), made and entered into on the day and year last below written, between CLARK COUNTY, STATE OF WASHINGTON, acting under and by virtue of Title 36 RCW, as amended, and Contractor_Name, hereinafter called the Contractor.

In consideration of the terms and conditions contained herein and attached and made a part of this Agreement, the parties hereto covenant and agree as follows:

1. The Contractor shall perform all work and furnish all tools, materials, labor, and equipment in order to fully and finally complete Project_Name CRPWO Project_CRP in accordance with the Contractor's PROPOSAL (the "Project").

2. The following documents: (i) the attached Plans and Specifications; (ii) the Standard Specifications for Road, Bridge, and Municipal Construction (M 41-10) published by the Washington State Department of Transportation as are in effect at the time of execution of this Agreement; (iii) any Special Provisions attached hereto; and (iv) any addenda attached hereto; are all, and each of them, incorporated herein by refence as though set forth in full at this point.

3. The Contractor shall fully and finally complete the Project and all of the work associated therewith in accordance with the bid price set forth in Contractor's PROPOSAL, a total amount of Low_Bid_Spelled (Low_Bid).

4. The Contractor shall perform any alterations in, or additions to, the work as may be required to fully and finally complete the Project, and shall perform any change order work, which may be ordered as provided in this Agreement.

5. The Contractor shall provide and bear the expense of all equipment, work and labor, of any sort whatsoever that may be required for the transfer of materials, to fully and finally and complete the Project, except such, if any, as are mentioned in the specifications to be furnished by Clark County.

INFORMATIONAL COPY

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

6. Clark County hereby agrees to pay for the Contractor's work on the Project according to the attached Specifications and the schedule of unit or itemized prices hereto attached, at the time and in the manner and upon the conditions provided for in this Agreement. Clark County further agrees to pay for any alterations in or additions to the work provided for in this Agreement that may be ordered under the terms of this Agreement and the attached Plans and Specifications.

7. The Contractor for itself, and for its' heirs, executors, administrators, successors, and assigns, does hereby agree to the full performance of all the covenants herein contained upon the part of the Contractor.

8. It is further provided that no liability shall attach to the County by reason of entering into this contract, except as expressly provided herein.

9. If any term or provision of this Agreement is held invalid or otherwise unenforceable, then such invalidity shall not affect the remaining terms and provisions of this Agreement, which shall be given effect to the maximum extent possible without the invalid term or provision. To this end, the terms and provisions of this Agreement are intended to be severable.

IN WITNESS WHEREOF, the Contractor has executed this instrument on the day and year last below written, and the Clark County Council has directed its County Manager to execute this instrument by and in the name of Clark County on the day and year last below written.

The above agreement made and entered into this ___ day of _____, year 2024.

CONTRACTOR

_____
By:
Its:

ATTEST:

CLARK COUNTY

_____
CLERK TO THE COUNCIL

_____
By: Kathleen Otto

INFORMATIONAL COPY

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Its: County Manager

Approved as to form only:

ANTHONY F. GOLIK
Prosecuting Attorney

_____

By: Kevin A. McDowell
Deputy Prosecuting Attorney

INFORMATIONAL COPY

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

1-10.5 Contract Bond

CONTRACT BOND

KNOW ALL MEN BY THESE PRESENTS, that Contractor_Name1 of Contractor_City, as Principal, and Surety, as Surety, are jointly and severally held and bound unto the County of Clark, State of Washington, in the penal sum of Low_Bid_Spelled1 (Low_Bid1), for the payment of which we jointly and severally bind ourselves, our heirs, executors, administrators, and assigns, and successors and assigns, firmly by these presents.

THE CONDITION of this bond is such that, WHEREAS, on the _____ day of _____, 2024, the said Contractor_Name2, Principal, herein, executed a certain contract with Clark County, by the terms, conditions and provisions of which contract the said Contractor_Name3 Principal, herein, agrees to furnish all material and do certain work, to-wit: That Contractor_Name4 will undertake and complete the construction of Project_Name4, CRPWO1 Project_CRP4, of Clark County, Washington, as per maps, plans and specifications made a part of said contract, which contract as so executed is hereunto attached, is now referred to and by reference is incorporated herein and made a part hereof as fully for all purposes as if here set forth at length.

NOW, THEREFORE, if the Principal herein shall faithfully and truly observe and comply with the terms, conditions and provisions of said contract in all respects, and shall well and truly and fully do and perform all matters and things by them undertaken to be performed under said contract, upon the terms proposed therein, and within the time prescribed therein, and until the same is accepted, and shall indemnify Clark County against any direct or indirect damages that shall be suffered or claimed, for injuries to persons or property during the performance of the work provided for in said contract, and shall pay all laborers, mechanics, subcontractors, materialmen, and all persons who shall supply such contractor or subcontractor with provisions and supplies for the carrying on of such work, and shall in all respects faithfully perform said contract according to law, then this obligation to be void, otherwise to remain in full force and effect.

WITNESS our hand this _____ day of _____, 2024.

INFORMATIONAL COPY

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

SURETY

PRINCIPAL

Address of Local Office and Agent of
Surety Company:

Approved as to form only:

ANTHONY F. GOLIK
Prosecuting Attorney

By: Kevin A. McDowell
Deputy Prosecuting Attorney

INFORMATIONAL COPY

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

BXWA

SPECIFICATIONS AND APPENDICES

WHIPPLE, KNAPPS, CARSON BRIDGE BUNDLE
PRJ NO. 0001799 / CRP NO. 320322

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

TABLE OF CONTENTS FOR THE SPECIAL PROVISIONS

SPECIAL PROVISIONS 1
Division 1 General Requirements 1
Description of Work 1
1-01 Definitions and Terms 1
1-01.3 Definitions 1
Dates 2
Additive 3
Alternate 3
Business Day 3
Contract Bond 3
Contract Documents 3
Contract Time 3
Notice of Award 3
Notice to Proceed 3
Traffic 3
1-02 Bid Procedures and Conditions 3
1-02.1 Prequalification of Bidders 3
1-02.1 Qualifications of Bidder 4
1-02.2 Plans and Specifications 4
1-02.4 Examination of Plans, Specifications, and Site of Work 4
1-02.4(1) General 4
1-02.5 Proposal Forms 5
1-02.6 Preparation of Proposal 5
Bidder Questionnaire 6
1-02.6(1) Recycled Materials Proposal 7
1-02.7 Bid Deposit 7
1-02.9 Delivery of Proposal 8
General 8
1-02.10 Withdrawing, Revising, or Supplementing Proposal 8
1-02.12 Public Opening of Proposals 9
1-02.13 Irregular Proposals 9
1-02.14 Disqualification of Bidders 10
1-03 Award and Execution of Contract 10
1-03.1 Consideration of Bids 10
1-03.1(1) Identical Bid Totals 11
1-03.3 Execution of Contract 11
1-03.4 Contract Bond 12
1-03.7 Judicial Review 12
1-04 Scope of the Work 13
1-04.2 Coordination of Contract Documents, Plans, Special Provisions, Specifications, and Addenda 13
1-04.3 Reference Information 13
Electronic Information 13
1-04.4 Changes 13
1-04.11 Final Cleanup 13
1-05 Control of Work 13
1-05.4 Conformity With And Deviations From Plans And Stakes 13
Construction Surveying 14
1-05.7 Nonconforming Work 16
1-05.7(1) Identification of Nonconforming Work 16
1-05.7(2) Reporting of Nonconforming Work 17
1-05.7(3) Remediation of Nonconforming Work 17
1-05.11 Final Inspection 17

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

1-05.11 Final Inspections and Operational Testing 18
1-05.13 Superintendents, Labor and Equipment of Contractor 19
1-05.15 Method of Serving Notices 19
1-05.16 Water and Power 20
1-06 Control of Material 20
Buy America Requirements 20
General Requirements 20
Definitions 21
Iron or Steel Product Requirements 22
Manufactured Products and Construction Material Requirements 23
1-06.1 Approval of Material Prior to Use 24
1-06.2 Acceptance of Materials 25
1-06.2(1) Samples and Tests for Acceptance 25
1-06.6 Recycled Materials 25
1-07 Legal Relations and Responsibilities to the Public 25
1-07.1 Laws to be Observed 25
Unmanned Aircraft Systems (UAS) 26
1-07.2 State Taxes 26
1-07.2 State Sales Tax 26
1-07.5 Environmental Regulations 27
Environmental Commitments 27
Payment 28
1-07.5(2) State Department of Fish and Wildlife 28
1-07.6 Permits and Licenses 28
1-07.7 Load Limits 29
1-07.8 High-Visibility Apparel 29
1-07.8(1) Traffic Control Personnel 29
1-07.9 Wages 29
1-07.9(1) General 29
1-07.9(5) Required Documents 30
1-07.11 Requirements For Nondiscrimination 30
1-07.11(1) Regulatory Authorities 38
1-07.11(2) Contractual Requirements 39
1-07.12 Federal Agency Inspection 39
Required Federal Aid Provisions 39
1-07.17 Utilities and Similar Facilities 39
1-07.18 Public Liability and Property Damage Insurance 40
1-07.18 Insurance 40
1-07.18(5)D Excess or Umbrella Liability 44
1-07.24 Rights of Way 44
1-08 Prosecution and Progress 45
Preconstruction Conference 45
Progress Meetings 46
1-08.1 Subcontracting 46
1-08.1(7) Payments to Subcontractors and Lower-Tier Subcontractors 46
1-08.1(8) Required Subcontract Clauses 47
1-08.1(9) Submittal of Executed Subcontracts 47
1-08.3 Progress Schedule 47
1-08.3(2) General Requirements 47
1-08.4 Prosecution of Work 47
1-08.4 Notice to Proceed and Prosecution of Work 48
Order of Work 48
1-08.5 Time for Completion 48
Work Restrictions 49
1-08.9 Liquidated Damages 49
1-09 Measurement and Payment 50

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

1-09.6 Force Account 50
1-09.9 Payments 50
1-09.9(1) Retainage 51
1-09.11 Disputes and Claims 51
1-09.11(3) Time Limitation and Jurisdiction 51
1-09.13 Claims Resolution 52
1-09.13(3) Arbitration 52
1-09.13(4) Venue for Litigation 52
Division 2 Temporary Features 53
2-01 Mobilization 53
2-01.1 Description 53
2-01.3 Construction Requirements 53
2-01.5 Payment 53
2-03 Public Convenience And Safety 53
2-03.3 Construction Requirements 53
2-03.3(1) Construction Under Traffic 53
2-04 Temporary Features 55
2-04.3 Construction Requirements 55
2-04.3(1) Traffic Control Management 55
2-04.5 Payment 56
2-04.5(2) Item Bids with Lump Sum for Incidentals 56
Division 3 Earthwork 57
3-01 Clearing, Grubbing, and Roadside Cleanup 57
3-01.2 Disposal of Usable Material and Debris 57
3-01.2(1) Disposal Method No. 1 - Open Burning 57
3-01.3 Construction Requirements 57
3-01.3(1) Clearing 57
Division 6 Structures 57
6-01 General Requirements for Structures 57
6-01.5 Vacant 57
Work Access 57
6-02 Concrete Structures 58
6-02.1 Description 58
6-02 Concrete Structures 58
6-02.1 Description 58
Concrete Spall Repair 58
Epoxy Crack Sealing 58
FRP Reinforcement 58
6-02.2 Materials 58
Concrete Spall Repair 58
Epoxy Crack Sealing 59
FRP Reinforcement Composites System 59
FIBER REINFORCED POLYMER COMPOSITE PROPERTIES 60
6-02.3 Construction Requirements 61
Concrete Spall Repair 62
Epoxy Crack Sealing 63
Fiber Reinforced Polymer (FRP) Composite System 64
6-02.3(24) Reinforcement 71
6-02.4 Measurement 71
6-02.5 Payment 72
(June 26, 2000) 72
Bridge and Structures Minor Items 72
Division 8 Miscellaneous Construction 73
8-01 Erosion Control and Water Pollution Control 73
8-01.1 Description 73
8-01.3 Construction Requirements 73

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

8-01.3(2) Temporary Seeding and Mulching 73
8-01.5 Payment 74
8-01.5(2) Item Bids 74
8-02 Roadside Restoration 74
8-02.3 Construction Requirements 74
8-02.3(9) Seeding, Fertilizing, and Mulching 74
8-02.4 Measurement 75
8-02.5 Payment 75
Division 9 Materials 75
9-28 Signing Materials and Fabrication 75
9-28.1 General 75
9-28.12 Reflective Sheeting 75
9-35 Temporary Traffic Control Materials 76
9-35.2 Construction Signs 76
9-35.6 Barricades 77
9-35.7 Traffic Safety Drums 77
9-35.9 Traffic Cones 77
9-35.10 Tubular Markers 78
9-35.12 Transportable Attenuator 78
9-35.13 42-Inch Tall Channelization Devices 78
9-35.16 Pedestrian Channelization Devices 78
Standard Plans 80

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

SPECIAL PROVISIONS

(July 8, 2024 APWA GSP, Option B)
The work on this project shall be accomplished in accordance with the *Standard Specifications for Road, Bridge and Municipal Construction*, 2026 edition, as issued by the Washington State Department of Transportation (WSDOT) and the American Public Works Association (APWA), Washington State Chapter (hereafter "Standard Specifications"). The Standard Specifications, as modified or supplemented by these Special Provisions, all of which are made a part of the Contract Documents, shall govern all of the Work.

These Special Provisions are made up of both General Special Provisions (GSPs) from various sources, which may have project-specific fill-ins; and project-specific Special Provisions. Each Provision supplements, modifies, or replaces the comparable Standard Specification, or is a new Provision. The deletion, amendment, alteration, or addition to any subsection or portion of the Standard Specifications is meant to pertain only to that particular portion of the section, and in no way should it be interpreted that the balance of the section does not apply.

The GSPs are labeled under the headers of each GSP, with the effective date of the GSP and its source. For example:

(March 8, 2013 APWA GSP)
(April 1, 2013) for WSDOT GSPs, only use date
(May 1, 2013 CCWP GSP) Agency Special Provision

The project-specific Special Provisions are labeled without a date as such:

(******)

Also incorporated into the Contract Documents by reference are:

1. *Manual on Uniform Traffic Control Devices for Streets and Highways*, currently adopted edition, with Washington State modifications, if any
2. *Standard Plans for Road, Bridge and Municipal Construction*, WSDOT Manual M21-01, current edition
3. *Clark County Standard Details Manual*, current edition

Contractor shall obtain copies of these publications, at Contractor's own expense.

Division 1
General Requirements

Description of Work
(March 13, 1995)
This Contract provides for the improvement of *** three bridges, by installing bridge strengthening components to the bridge superstructures, traffic control *** and other work, all in accordance with the attached Contract Plans, these Contract Provisions, and the Standard Specifications.

1-01 Definitions and Terms
1-01.3 Definitions
(January 19, 2022 APWA GSP)

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Delete the heading Completion Dates and the three paragraphs that follow it, and replace them with the following:

Dates

Bid Opening Date
The date on which the Contracting Agency publicly opens and reads the Bids.

Award Date
The date of the formal decision of the Contracting Agency to accept the lowest responsible and responsive Bidder for the Work.

Contract Execution Date
The date the Contracting Agency officially binds the Agency to the Contract.

Notice to Proceed Date
The date stated in the Notice to Proceed on which the Contract time begins.

Substantial Completion Date
The day the Engineer determines the Contracting Agency has full and unrestricted use and benefit of the facilities, both from the operational and safety standpoint, any remaining traffic disruptions will be rare and brief, and only minor incidental work, replacement of temporary substitute facilities, plant establishment periods, or correction or repair remains for the Physical Completion of the total Contract.

Physical Completion Date
The day all of the Work is physically completed on the project. All documentation required by the Contract and required by law does not necessarily need to be furnished by the Contractor by this date.

Completion Date
The day all the Work specified in the Contract is completed and all the obligations of the Contractor under the contract are fulfilled by the Contractor. All documentation required by the Contract and required by law must be furnished by the Contractor before establishment of this date.

Final Acceptance Date
The date on which the Contracting Agency accepts the Work as complete.

Supplement this Section with the following:

All references in the Standard Specifications or WSDOT General Special Provisions, to the terms “Department of Transportation”, “Washington State Transportation Commission”, “Commission”, “Secretary of Transportation”, “Secretary”, “Headquarters”, and “State Treasurer” shall be revised to read “Contracting Agency”.

All references to the terms “State” or “state” shall be revised to read “Contracting Agency” unless the reference is to an administrative agency of the State of Washington, a State statute or regulation, or the context reasonably indicates otherwise.

All references to “State Materials Laboratory” shall be revised to read “Contracting Agency designated location”.

All references to “final contract voucher certification” shall be interpreted to mean the Contracting Agency form(s) by which final payment is authorized, and final completion and acceptance granted.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Additive
A supplemental unit of work or group of bid items, identified separately in the Bid Proposal, which may, at the discretion of the Contracting Agency, be awarded in addition to the base bid.

Alternate
One of two or more units of work or groups of bid items, identified separately in the Bid Proposal, from which the Contracting Agency may make a choice between different methods or material of construction for performing the same work.

Business Day
A business day is any day from Monday through Friday except holidays as listed in Section 1-08.5.

Contract Bond
The definition in the Standard Specifications for "Contract Bond" applies to whatever bond form(s) are required by the Contract Documents, which may be a combination of a Payment Bond and a Performance Bond.

Contract Documents
See definition for "Contract".

Contract Time
The period of time established by the terms and conditions of the Contract within which the Work must be physically completed.

Notice of Award
The written notice from the Contracting Agency to the successful Bidder signifying the Contracting Agency's acceptance of the Bid Proposal.

Notice to Proceed
The written notice from the Contracting Agency or Engineer to the Contractor authorizing and directing the Contractor to proceed with the Work and establishing the date on which the Contract time begins.

Traffic
Both vehicular and non-vehicular traffic, such as pedestrians, bicyclists, wheelchairs, and equestrian traffic.

Section 1-01.3 is supplemented with the following:

(March 2016 CCPW GSP)
All references to "Call for Bids" shall be revised to read "Notice to Contractors".

1-02 Bid Procedures and Conditions

1-02.1 Prequalification of Bidders

Section 1-02.1, including title, is revised to read:

(February 17, 2026 APWA GSP, Option B)

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

1-02.1 Qualifications of Bidder

Before award of a public works contract, a Bidder must meet at least the minimum qualifications of RCW 39.04.350(1)(b-g) to be considered a responsible Bidder and qualified to be awarded a public works project.

1-02.2 Plans and Specifications

Section 1-02.2 is revised to read:

(April 2016 CCPW GSP)
Information as to where Bid Documents can be obtained or reviewed can be found in the Notice to Contractors for the work.

After award of the contract, plans and specifications will be issued to the Contractor at no cost as detailed below:

To Prime Contractor	No. of Sets	Basis of Distribution
Reduced plans (11" x 17")	*** 3 ***	Furnished automatically upon award.
Contract Provisions	*** 3 ***	Furnished automatically upon award.
Large plans (e.g., 22" x 34")	*** 2 ***	Furnished automatically upon award.
	*** 0 ***	Furnished only upon request.

Additional plans and Contract Provisions may be obtained by the Contractor from the source stated in the Notice to Contractors, at the Contractor's own expense.

Section 1-02.2 is supplemented with the following:

(February 2021 CCPW GSP)
Computer Aided Drafting (CAD) files are not available.

1-02.4 Examination of Plans, Specifications, and Site of Work

1-02.4(1) General

The first sentence of the ninth paragraph in Section 1-02.4(1) is revised to read:

(December 30, 2022 APWA GSP Option A)
Prospective Bidders desiring an explanation or interpretation of the Bid Documents, shall request the explanation or interpretation in writing soon enough to allow a written reply to reach all prospective Bidders before the submission of their Bids.

Section 1-02.4(1) is supplemented with the following:

(February 2021 CCPW GSP)
Questions and requests for clarification must be submitted using the electronic "CRP Inquiry Submittal Form" located on the County website:

https://www.clark.wa.gov/general-services/public-works-roads-parks-clean-water-projects

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

A minimum of 24 hours must be allowed for response to questions. Responses will be posted on the project's "Bid Inquiry Log".

(September 3, 2019)
The Reference Information for this project is available for review by the bidder at the following location:

***
Clark County
Department of Public Works
Engineering and Construction Division, Fourth Floor
1300 Franklin Street (P.O. Box 9810)
Vancouver, WA 98660
Telephone (360) 397-6118
***

The Reference Information includes the following:

***
Plans of the existing bridges
***

(October 2021 CCPW GSP)
The Reference Information used for study and design of this project is also available at the Builders Exchange of Washington (BXWA) website, www.bxwa.com (Posted Projects, Public Works, Clark County and Projects Bidding)

1-02.5 Proposal Forms

Section 1-02.5 is revised to read:

(February 17, 2026 APWA GSP)
The Proposal Form will identify the project and its location and describe the work. It will also list estimated quantities, units of measurement, the items of work, and the materials to be furnished at the unit bid prices. The bidder shall complete spaces on the proposal form that call for, but are not limited to, unit prices; extensions; summations; the total bid amount; signatures; date; and, where applicable, retail sales taxes and acknowledgment of addenda; the bidder's name, address, telephone number, and signature. Bids shall be in legible figures (not words) written in ink or typed and expressed in U.S. dollars. The required certifications are included as part of the Proposal Form.

The Contracting Agency reserves the right to arrange the proposal forms with alternates and additives, if such be to the advantage of the Contracting Agency. The bidder shall bid on all alternates and additives set forth in the Proposal Form unless otherwise specified.

1-02.6 Preparation of Proposal

The first sentence in the first paragraph of Section 1-02.6 is revised to read:

(******)
The Contracting Agency will accept only those Proposals properly executed on the physical forms it provides.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

(February 17, 2026 APWA GSP, Option C)
The first sentence of the second paragraph is revised to read as follows:

All prices shall be in legible figures (not words) written in ink or typed, and expressed in U.S. dollars.

Supplement the second paragraph with the following:

4. If a minimum bid amount has been established for any item, the unit or lump sum price must equal or exceed the minimum amount stated.

Delete the last two paragraphs, and replace them with the following:

The Bidder shall submit with their Bid a completed Contractor Certification Wage Law Compliance form, provided by the Contracting Agency. Failure to return this certification as part of the Bid Proposal package will make this Bid Nonresponsive and ineligible for Award. A Contractor Certification of Wage Law Compliance form is included in the Proposal Forms.

The Bidder shall make no stipulation on the Bid Form, nor qualify the bid in any manner.

A bid by a corporation shall be executed in the corporate name, by the president or a vice president (or other corporate officer accompanied by evidence of authority to sign).

A bid by a partnership shall be executed in the partnership name and signed by a partner.

A bid by a joint venture shall be executed in the joint venture name and signed by a member of the joint venture.

(November 20, 2023)
The fourth and fifth paragraphs of Section 1-02.6 are deleted.

Section 1-02.6 is supplemented with the following:

(November 4, 2025)
Bidder Questionnaire
The Bidder shall submit with their Bid a Bidder Questionnaire form (WSDOT Form #272-022). This shall be filled out for each firm who submitted a bid or quote in attempt to participate in the project whether they were successful or not and include the following information:

1. Firm name;

2. Firm address including ZIP code;

3. Firm's status as a DBE or non-DBE;

4. NAICS code applicable to each scope of work the firm sought to perform in its bid;

5. Age of the firm; and

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

6. The annual gross receipts of the firm. The Bidder may obtain this information by asking each firm to indicate into what gross receipts bracket they fit (less than $1 million; $1-3 million; $3-6 million; $6-10 million; $10-20 million; $20-30.72 million; or greater than $30.72 million) rather than requesting an exact figure from the firm.

This form shall be received at the same location and no later than the time required for the delivery of the Proposal. Failure to comply with this requirement will cause this Bid to be considered irregular in accordance with Section 1-02.13.

The Contractor may correct errors to items 2 through 6 above on the Bidder Questionnaire form for a period up to 48 hours after bid opening. Bidder Questionnaire forms that are still incorrect after the correction period will be determined irregular. New Firm/Subcontractors may not be added to the form during the correction period. A Bidder Questionnaire form that fails to list a Firm/Subcontractor that appears on a different form will be considered irregular in accordance with Section 1-02.13.

(January 4, 2016 APWA GSP)

1-02.6(1) Recycled Materials Proposal

The Bidder shall submit with the Bid, its proposal for incorporating recycled materials into the project, using the form provided in the Contract Provisions.

1-02.7 Bid Deposit

(January 2016 CCPW GSP)

The second sentence in the first paragraph of Section 1-02.7 is revised to read:

This deposit may be certified check, cashier's check, or a proposal bond (Surety bond).

The third sentence in the first paragraph of Section 1-02.7 is deleted.

The fourth sentence in the first paragraph of Section 1-02.7 is revised to read:

(December 2023 CCPW GSP)

The Bid deposit shall be received by the Contracting Agency at the location specified for receipt of Bids prior to the time set for receipt of Bids.

The second paragraph in Section 1-02.7 is revised to read:

(December 2023 CCPW GSP)

The failure to furnish a Bid deposit of a minimum of 5 percent with the Bid shall make the Bid nonresponsive and shall cause the Bid to be rejected by the Contracting Agency.

Section 1-02.7 is supplemented with the following:

(March 2019 CCPW GSP)

Proposal bonds shall contain the following:

1. Contracting Agency-assigned number for the project;
2. Name of the project;
3. The Contracting Agency named as obligee;
4. The amount of the proposal bond stated either as a dollar figure or as a percentage which represents five percent of the maximum bid amount that could be awarded;

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

5. Signature of the bidder's officer empowered to sign official statements. The signature of the person authorized to submit the bid should agree with the signature on the bond, and the title of the person must accompany the said signature;
6. The signature of the surety's officer empowered to sign the bond and the power of attorney.

1-02.9 Delivery of Proposal

Section 1-02.9 is revised to read:

(January 2026 CCPW GSP)

General

Each Proposal shall be submitted in a sealed envelope, with the Project Name and Project Number, Bidder's company name, project bid opening date, and the words "SEALED BID" as stated in the Notice to Contractors clearly marked on the outside of the envelope, or as otherwise required in the Bid Documents, to ensure proper handling and delivery.

Proposals that are received as required will be publicly opened and read as specified in the Notice to Contractors. The Contracting Agency will not open or consider any Bid Proposal that is received after the time specified in the Notice to Contractors for receipt of Bid Proposals or received in a location other than that specified in the Notice to Contractors. The Contracting Agency will not open or consider any "Supplemental Information" that is received after the time specified or received in a location other than that specified in the Notice to Contractors.

If an emergency or unanticipated event interrupts normal work processes of the Contracting Agency so that Proposals cannot be received at the office designated for receipt of bids as specified in the Notice to Contractors, the time specified for receipt of the Proposal will be deemed to be extended to the same time of day specified in the solicitation on the first Tuesday on which the normal work processes of the Contracting Agency resume.

Supplemental bid information submitted after the proposal submittal but within 48 hours of the time and date the proposal is due, shall be submitted by e-mail to:

<<name of construction manager>>, Construction Manager
<<construction manager email address>>

List the project number, project title, and "Supplemental Information" in the e-mail subject line.

The Contracting Agency is not responsible for delayed, partial, failed, illegible or partially legible e-mail document transmissions, and such documents may be rejected as incomplete at the Bidder's risk.

All other information required to be submitted with the Bid Proposal must be submitted with the Bid Proposal itself, at the time stated in the Call for Bids.

1-02.10 Withdrawing, Revising, or Supplementing Proposal

Section 1-02.10 is revised to read:

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

(February 17, 2026 APWA GSP)
After submitting a physical or an electronic bid, if allowed under 1-02.9, Bid Proposal to the Contracting Agency, the Bidder may withdraw, revise, or supplement it if:

1. The Bidder submits a written request signed by an authorized person and physically delivers it to the place designated for receipt of Bid Proposals, if a physical Bid Proposal was submitted, or recalled electronically via electronic method described in 1-02.9 if an electronic Bid Proposal was submitted, and
2. The Contracting Agency receives the request before the time set for receipt of Bid Proposals, and
3. The revised or supplemented Bid Proposal (if any) is received by the Contracting Agency before the time set for receipt of Bid Proposals.

If the Bidder's request to withdraw, revise, or supplement its Bid Proposal is received before the time set for receipt of Bid Proposals, the Contracting Agency will return the unopened Proposal package to the Bidder. The Bidder must then submit the revised or supplemented package in its entirety. If the Bidder does not submit a revised or supplemented package before the time set for receipt of Bid Proposals, then its bid shall be considered withdrawn.

Late revised or supplemented Bid Proposals or late withdrawal requests will be date recorded by the Contracting Agency and returned unopened. Requests to withdraw, revise, or supplement a Bid Proposal may be submitted by the following methods:

1. In person
*** N/A ***.

1-02.12 Public Opening of Proposals

The last paragraph of Section 1-02.12 is revised to read:

(December 2023 CCPW GSP)
If an emergency or unanticipated event interrupts normal work processes of the Contracting Agency so that Proposals cannot be opened at the time indicated in the Notice to Contractors the time specified for opening of Proposals will be deemed to be extended to the same time of day on the first Tuesday on which the normal work processes of the Contracting Agency resume.

1-02.13 Irregular Proposals

Section 1-02.13 is revised to read:

(July 15, 2026 APWA GSP)
1. A Proposal will be considered irregular and will be rejected if:
   a. The Bidder is not prequalified when so required;
   b. The Bidder adds provisions reserving the right to reject or accept the Award, or enter into the Contract;
   c. A price per unit cannot be determined from the Bid Proposal;
   d. The Proposal form is not properly executed;
   e. The Bidder fails to submit or properly complete a subcontractor list as required in Section 1-02.6; or
   f. The Bid Proposal does not constitute a definite and unqualified offer to meet the material terms of the Bid invitation.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

2. A Proposal may be considered irregular and may be rejected if:
   a. The Proposal does not include a unit price for every Bid item;
   b. Any of the unit prices are excessively unbalanced (either above or below the amount of a reasonable Bid) to the potential detriment of the Contracting Agency;
   c. The authorized Proposal Form furnished by the Contracting Agency is not used or is altered;
   d. The completed Proposal form contains unauthorized additions, deletions, alternate Bids, or conditions;
   e. Receipt of Addenda is not acknowledged;
   f. A member of a joint venture or partnership and the joint venture or partnership submit Proposals for the same project (in such an instance, both Bids may be rejected);
   g. The Bidder fails to submit the Bidder Questionnaire, if applicable, as required by Section 1-02.6, or if the documentation that is submitted fails to meet the requirements of the Special Provisions; or
   h. If Proposal form entries are not made in ink.

1-02.14 Disqualification of Bidders

Section 1-02.14 is revised to read:

(May 17, 2018 APWA GSP Option A)
A Bidder will be deemed not responsible if the Bidder does not meet the mandatory bidder responsibility criteria in RCW 39.04.350(1), as amended.

The Contracting Agency will verify that the Bidder meets the mandatory bidder responsibility criteria in RCW 39.04.350(1). To assess bidder responsibility, the Contracting Agency reserves the right to request documentation as needed from the Bidder and third parties concerning the Bidder's compliance with the mandatory bidder responsibility criteria.

If the Contracting Agency determines the Bidder does not meet the mandatory bidder responsibility criteria in RCW 39.04.350(1) and is therefore not a responsible Bidder, the Contracting Agency shall notify the Bidder in writing, with the reasons for its determination. If the Bidder disagrees with this determination, it may appeal the determination within two (2) business days of the Contracting Agency's determination by presenting its appeal and any additional information to the Contracting Agency. The Contracting Agency will consider the appeal and any additional information before issuing its final determination. If the final determination affirms that the Bidder is not responsible, the Contracting Agency will not execute a contract with any other Bidder until at least two business days after the Bidder determined to be not responsible has received the Contracting Agency's final determination.

1-03 Award and Execution of Contract

1-03.1 Consideration of Bids

The first paragraph of Section 1-03.1 is revised to read:

(December 30, 2022 APWA GSP)
After opening and reading proposals, the Contracting Agency will check them for correctness of extensions of the prices per unit and the total price. If a discrepancy exists between the price per unit and the extended amount of any bid item, the price per unit will control. If a minimum bid amount has been established for any item and the bidder's unit or lump sum price is less than the minimum specified amount, the Contracting Agency will unilaterally

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

revise the unit or lump sum price, to the minimum specified amount and recalculate the extension. The total of extensions, corrected where necessary, including sales taxes where applicable and such additives and/or alternates as selected by the Contracting Agency, will be used by the Contracting Agency for award purposes and to fix the Awarded Contract Price amount and the amount of the contract bond.

1-03.1(1) Identical Bid Totals

Section 1-03.1(1) is revised to read:

(February 17, 2026 APWA GSP)
After opening Bids, if two or more lowest responsive Bid totals are exactly equal, then the tie-breaker will be the Bidder that proposed to use the highest percentage of recycled materials in the Project, per the form submitted with the Bid Proposal, if required. If those percentages are also exactly equal or if the form was not required, then the tie-breaker will be determined by drawing as follows: Two or more slips of paper will be marked as follows: one marked "Winner" and the other(s) marked "unsuccessful". The slips will be folded to make the marking unseen. The slips will be placed inside a box. One authorized representative of each Bidder shall draw a slip from the box. Bidders shall draw in alphabetical order by the name of the firm. The slips shall be unfolded and the firm with the slip marked "Winner" will be determined to be the successful Bidder and eligible for Award of the Contract. Only those Bidders who submitted a Bid total that is exactly equal to the lowest responsive Bid, and with a proposed recycled materials percentage that is exactly equal to the highest proposed recycled materials amount, are eligible to draw.

1-03.3 Execution of Contract

Section 1-03.3 is revised to read:

(February 17, 2026 APWA Option A)
Copies of the Contract Provisions, including the unsigned Form of Contract, will be available for signature by the successful bidder on the first business day following award. The number of copies to be executed by the Contractor will be determined by the Contracting Agency.

Within *** 10 *** calendar days after the award date, the successful Bidder shall return the signed Contracting Agency-prepared Contract, an insurance certification as required by Section 1-07.18, a satisfactory bond as required by law and Section 1-03.4, the Transfer of Coverage form for the Construction Stormwater General Permit with sections I, III, and VIII completed when provided. Before execution of the Contract by the Contracting Agency, the successful Bidder shall provide, if required, any of the following: pre-Award information required by the Contracting Agency as listed under Section 1-02.15, proof of licensure for electrical, HVAC, or plumbing subcontractors. If the Prime Contractor lists themselves as performing electrical, HVAC, or plumbing they are required to submit proof of licensure prior to execution.

Until the Contracting Agency executes a Contract, no Proposal shall bind the Contracting Agency nor shall any Work begin within the project limits or within Contracting Agency-furnished sites. The Contractor shall bear all risks for any Work begun outside such areas and for any materials ordered before the Contract is executed by the Contracting Agency.

If the Bidder experiences circumstances beyond their control that prevents return of the Contract documents within the calendar days after the Award date stated above, the Contracting Agency may grant up to a maximum of *** 10 *** additional calendar days for

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

return of the documents, provided the Contracting Agency deems the circumstances warrant it.

1-03.4 Contract Bond

The first paragraph of Section 1-03.4 is revised to read:

(July 23, 2015 APWA GSP)

The successful bidder shall provide executed payment and performance bond(s) for the full contract amount. The bond may be a combined payment and performance bond; or be separate payment and performance bonds. In the case of separate payment and performance bonds, each shall be for the full contract amount. The bond(s) shall:

1. Be on Contracting Agency-furnished form(s);
2. Be signed by an approved surety (or sureties) that:
   a. Is registered with the Washington State Insurance Commissioner, and
   b. Appears on the current Authorized Insurance List in the State of Washington published by the Office of the Insurance Commissioner,
3. Guarantee that the Contractor will perform and comply with all obligations, duties, and conditions under the Contract, including but not limited to the duty and obligation to indemnify, defend, and protect the Contracting Agency against all losses and claims related directly or indirectly from any failure:
   a. Of the Contractor (or any of the employees, subcontractors, or lower tier subcontractors of the Contractor) to faithfully perform and comply with all contract obligations, conditions, and duties, or
   b. Of the Contractor (or the subcontractors or lower tier subcontractors of the Contractor) to pay all laborers, mechanics, subcontractors, lower tier subcontractors, material person, or any other person who provides supplies or provisions for carrying out the work;
4. Be conditioned upon the payment of taxes, increases, and penalties incurred on the project under titles 50, 51, and 82 RCW; and
5. Be accompanied by a power of attorney for the Surety's officer empowered to sign the bond; and
6. Be signed by an officer of the Contractor empowered to sign official statements (sole proprietor or partner). If the Contractor is a corporation, the bond(s) must be signed by the president or vice president, unless accompanied by written proof of the authority of the individual signing the bond(s) to bind the corporation (i.e., corporate resolution, power of attorney, or a letter to such effect signed by the president or vice president).

1-03.7 Judicial Review

Section 1-03.7 is revised to read

(December 30, 2022 APWA GSP)

All decisions made by the Contracting Agency regarding the Award and execution of the Contract or Bid rejection shall be conclusive subject to the scope of judicial review permitted under Washington Law. Such review, if any, shall be timely filed in the Superior Court of the county where the Contracting Agency headquarters is located, provided that where an action is asserted against a county, RCW 36.01.050 shall control venue and jurisdiction.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

1-04 Scope of the Work

1-04.2 Coordination of Contract Documents, Plans, Special Provisions, Specifications, and Addenda

The second paragraph of Section 1-04.2 is revised to read:

(December 30, 2022 APWA GSP)

Any inconsistency in the parts of the contract shall be resolved by following this order of precedence (e.g., 1 presiding over 2, 2 over 3, 3 over 4, and so forth):

1. Addenda,
2. Proposal Form,
3. Special Provisions,
4. Contract Plans,
5. Standard Specifications,
6. Contracting Agency's Standard Plans or Details (if any), and
7. WSDOT Standard Plans for Road, Bridge, and Municipal Construction.

1-04.3 Reference Information

Section 1-04.3 is supplemented with the following:

(April 2023 CCPW GSP)

Electronic Information

Electronic information provided to the Contractor will be considered Reference Information and is provided for the Contractor's convenience.

1-04.4 Changes

The first two sentences of the last paragraph of Section 1-04.4 are deleted.

The third sentence in the last paragraph of Section 1-04.4 is revised to read:

(April 2023 CCPW GSP)

Within 5 days of execution of the Contract, the Contractor shall submit a Type 1 Working Drawing consisting of the names, email addresses, and text-message capable phone numbers for the authorized change order signers and shall bear the name, phone number and email of the officer providing this authorization.

1-04.11 Final Cleanup

The list in the first paragraph of Section 1-04.11 is supplemented with the following:

(April 2023 CCPW GSP)

3. Clean site; sweep paved areas, rake clean landscaped surfaces; and
4. Remove construction stakes and construction facilities from the site.

1-05 Control of Work

1-05.4 Conformity With And Deviations From Plans And Stakes

Section 1-05.4 is supplemented with the following:

(July 2026 CCPW GSP)

Monuments

The Contractor shall notify the Engineer immediately if a monument not identified in the Plans will be disturbed due to construction. The Contractor shall allow 5 working days

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

for the Engineer to acquire information so that a reference monument may be set by the Engineer. A monument shall not be disturbed until it has been referenced by the Engineer. All costs associated with the replacement of monuments damaged or destroyed prior to being referenced shall be deducted from monies due to the Contractor.

(May 2026 CCPW GSP)

Construction Surveying

The Contractor shall provide and be responsible for all surveying necessary to construct the project and correctly guide construction activities. All surveying shall be done in accordance with the WSDOT Construction Manual standards of care and standards and practice. All surveying shall be performed under the supervision of a Professional Land Surveyor registered in the State of Washington.

The survey work by the Contractor shall include but not be limited to the following:

1. Verify the primary horizontal and vertical control furnished by the Contracting Agency, and expand into secondary control by adding stakes and hubs as well as additional survey control needed for the project. Provide descriptions of secondary control to the Contracting Agency. The description shall include coordinates and elevations of all secondary control points.
2. Make calculations, field notes, and survey drawings for the layout and control of the work
4. Establish horizontal and vertical alignments, by placing hubs, stakes, or marks on centerline or on offsets to centerline at all curve points (PCs, PTs, and PIs) and at points on the alignments spaced no further than 50 feet.
5. Establish grading and clearing limits, by placing slope stakes at centerline increments not more than 50 feet apart. Establish offset reference to all slope stakes.
6. Establish grading, roadbed and surfacing elevations by placing stakes at the top of subgrade and at the top of each course of surfacing. Subgrade and surfacing stakes shall be set at horizontal intervals not greater than 50 feet in tangent sections, 25 feet in curve sections with a radius less than 300 feet, and at 10-foot intervals in intersection radii with a radius less than 10 feet. Transversely, stakes shall be placed at all locations where the roadway slope changes and at additional points such that the transverse spacing of stakes is not more than 12 feet.
7. Establish, by placing hubs and/or marked stakes, the horizontal and vertical location of
   a. Erosion control items
   b. Roadway location and grade
   c. Pipes, inlets, manholes, and other drainage and water quality structures and facilities
   d. Curbs, sidewalk, ramps, mailboxes, and other miscellaneous structures.
   e. Guardrail, barrier, and barricades
   f. Fencing and gates
   g. Retaining walls, noise barriers, and other structures
   h. Poles and footings, cabinets, junction boxes, sensors and other features associated with illumination and signal systems
   i. Signing, including poles and footings
   j. Landscaping items
8. Cleanup and removal of all flagging, lath, stakes, and other temporary staking material after the project is completed.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Detailed survey records shall be maintained, including a description of the work performed on each shift, the methods utilized, and the control points used. The record shall be adequate to allow the survey to be reproduced. A copy of each day's record shall be made available to the Engineer anytime upon request and at the end of each work week.

The Contractor shall perform all calculations necessary for the contracted survey work and shall provide copies of these calculations and staking data when requested by the Engineer.

Survey Control Provided by the Contracting Agency

The Contracting Agency will provide the Contractor with primary survey control information consisting of descriptions of a minimum of two primary control points used for the horizontal and vertical control. Primary control points will be described by reference to the project alignment and the coordinate system and elevation datum utilized by the project. In addition, the Contracting Agency will supply horizontal coordinates for the beginning and ending points and for each Point of Intersection (PI) on each alignment included in the project.

The Contractor shall provide all survey control except as specified herein, including but not limited to horizontal and vertical control, as necessary to assure proper placement of all project elements based on the control points provided by the Contracting Agency.

Survey Tolerances

Surveying work shall be within the following tolerances:

	Vertical	Horizontal
Slope stakes	±0.10 feet	±0.10 feet
Subgrade grade stakes set 0.04 feet below grade	±0.01 feet	±0.5 feet (parallel to alignment) ±0.1 feet (normal to alignment)
Stationing	N/A	±0.02 feet
Alignment	N/A	±0.02 feet
Surfacing grade stakes	±0.01 feet	±0.5 feet (parallel to alignment) ±0.05 feet (normal to alignment)
Roadway paving pins for surfacing or paving	±0.01 feet	±0.2 feet (parallel to alignment) ±0.1 feet (normal to alignment)
Drainage structures	±0.01 feet	±0.02 feet
Storm pipes	±0.01 feet	±0.05 feet (parallel to alignment) ±0.05 feet (normal to alignment)

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Retaining walls, noise barriers, foundations, and other structures	±0.01 feet	±0.02 feet

Errors in Contractor Surveying

The Engineer may spot-check the Contractor's surveying. These spot-checks will not change the requirements for normal checking by the Contractor. If errors are found the Contractor shall correct the errors, which may include removal and replacement of incorrectly installed improvements. All costs incurred in correcting the work shall be at the Contractor's expense.

The Contractor shall direct questions regarding the correct interpretation of provided survey points or data to the Engineer. Failure to correctly interpret and utilize the primary survey control or Plans as provided by the Engineer, shall not constitute justification by the Contractor for extra work, or causation for not replacing or repairing incorrect work at the Contractor's expense.

The Contractor shall immediately notify the Engineer, in writing, of any survey discrepancies that are discovered during the course of the project.

Payment

Payment will be made in accordance with Section 1-04.1 for the following bid item when included in the proposal:

"Construction Surveying", lump sum.

The lump sum contract price for "Construction Surveying" shall be full pay for all labor, equipment, materials, and supervision utilized to perform the work specified, including any resurveying, checking, correction of errors, replacement of missing or damaged stakes, and coordination efforts.

1-05.7 Nonconforming Work

Section 1-05.7 is supplemented with the following:

(February 17, 2026 APWA GSP)

The rights exercised under the provisions of this Section shall not diminish the Contracting Agency's right to pursue any other avenue for additional remedy or damages with respect to the Contractor's failure to perform the Work as required. The Engineer has the right to reject all or part of the Nonconforming Work, and the Engineer's decision is final and not subject to protest.

No additional contract time or compensation will be allowed when the Contracting Agency exercises their rights provided by this Section.

1-05.7(1) Identification of Nonconforming Work

Section 1-05.7(1) is revised to read:

(February 17, 2026 APWA GSP)

The Contractor is responsible for quality control and shall identify all Nonconforming Work. The Contracting Agency may also identify Nonconforming Work. However, failure by the Contracting Agency to identify Nonconforming Work shall not relieve the Contractor from their responsibility for the quality of the Work, nor shall it constitute acceptance or approval of the Nonconforming Work.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

1-05.7(2) Reporting of Nonconforming Work

Section 1-05.7(2) is revised to read:

(February 17, 2026 APWA GSP)

The Contractor shall immediately report all Nonconforming Work to the Engineer and shall include any relevant information known for suggested remediation of Nonconforming Work.

When the Contracting Agency identifies Nonconforming Work, the Engineer will notify the Contractor in writing specifying a time when a remedy must be complete. If the Contractor fails to remedy Nonconforming Work within the time specified in a written notice from the Engineer, or fails to perform any part of the Work required by the Contract Documents, the Engineer may correct and remedy such Work as may be identified in the written notice.

1-05.7(3) Remediation of Nonconforming Work

Section 1-05.7(3) is supplemented with the following:

(February 17, 2026 APWA GSP)

The Contractor shall be responsible and bear all costs for remediating Nonconforming Work.

If the Contracting Agency remedies Nonconforming Work after the specified time when a remedy was to be completed, by any means deemed necessary, direct and indirect costs incurred by the Contracting Agency attributable to correcting and remedying Nonconforming Work not corrected by the time provided in the notice, or Work the Contractor failed or refused to perform, shall be paid by the Contractor.

If the Contractor fails to comply with a written order to remedy what the Engineer determines to be an emergency situation, the Engineer may have the Nonconforming Work corrected immediately, have the Work removed and replaced, or have Work the Contractor refuses to perform completed by using Contracting Agency or other forces. An emergency situation is any situation when, in the opinion of the Engineer, a delay in its remedy could be potentially unsafe, or might cause risk of loss or damage to the public.

When costs are incurred by the Contracting Agency, payment will be deducted by the Engineer from monies due, or to become due, to the Contractor. Such direct and indirect costs shall include in particular, but without limitation, compensation for additional professional services required, and compensation for removal, repair, replacement and/or correction of the Contractor's Nonconforming Work.

1-05.11 Final Inspection

Section 1-05.11 is revised to read:

(October 1, 2005 APWA GSP)

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

1-05.11 Final Inspections and Operational Testing

1-05.11(1) Substantial Completion Date

When the Contractor considers the work to be substantially complete, the Contractor shall so notify the Engineer and request the Engineer establish the Substantial Completion Date. The Contractor's request shall list the specific items of work that remain to be completed in order to reach physical completion. The Engineer will schedule an inspection of the work with the Contractor to determine the status of completion. The Engineer may also establish the Substantial Completion Date unilaterally.

If, after this inspection, the Engineer concurs with the Contractor that the work is substantially complete and ready for its intended use, the Engineer, by written notice to the Contractor, will set the Substantial Completion Date. If, after this inspection the Engineer does not consider the work substantially complete and ready for its intended use, the Engineer will, by written notice, so notify the Contractor giving the reasons therefore.

Upon receipt of written notice concurring in or denying substantial completion, whichever is applicable, the Contractor shall pursue vigorously, diligently and without unauthorized interruption, the work necessary to reach Substantial and Physical Completion. The Contractor shall provide the Engineer with a revised schedule indicating when the Contractor expects to reach substantial and physical completion of the work.

The above process shall be repeated until the Engineer establishes the Substantial Completion Date and the Contractor considers the work physically complete and ready for final inspection.

1-05.11(2) Final Inspection and Physical Completion Date

When the Contractor considers the work physically complete and ready for final inspection, the Contractor by written notice, shall request the Engineer to schedule a final inspection. The Engineer will set a date for final inspection. The Engineer and the Contractor will then make a final inspection and the Engineer will notify the Contractor in writing of all particulars in which the final inspection reveals the work incomplete or unacceptable. The Contractor shall immediately take such corrective measures as are necessary to remedy the listed deficiencies. Corrective work shall be pursued vigorously, diligently, and without interruption until physical completion of the listed deficiencies. This process will continue until the Engineer is satisfied the listed deficiencies have been corrected.

If action to correct the listed deficiencies is not initiated within 7 days after receipt of the written notice listing the deficiencies, the Engineer may, upon written notice to the Contractor, take whatever steps are necessary to correct those deficiencies pursuant to Section 1-05.7.
The Contractor will not be allowed an extension of contract time because of a delay in the performance of the work attributable to the exercise of the Engineer's right hereunder.

Upon correction of all deficiencies, the Engineer will notify the Contractor and the Contracting Agency, in writing, of the date upon which the work was considered physically complete. That date shall constitute the Physical Completion Date of the

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

contract, but shall not imply acceptance of the work or that all the obligations of the Contractor under the contract have been fulfilled.

1-05.11(3) Operational Testing

It is the intent of the Contracting Agency to have at the Physical Completion Date a complete and operable system. Therefore when the work involves the installation of machinery or other mechanical equipment; street lighting, electrical distribution or signal systems; irrigation systems; buildings; or other similar work it may be desirable for the Engineer to have the Contractor operate and test the work for a period of time after final inspection but prior to the physical completion date. Whenever items of work are listed in the Contract Provisions for operational testing they shall be fully tested under operating conditions for the time period specified to ensure their acceptability prior to the Physical Completion Date. During and following the test period, the Contractor shall correct any items of workmanship, materials, or equipment which prove faulty, or that are not in first class operating condition. Equipment, electrical controls, meters, or other devices and equipment to be tested during this period shall be tested under the observation of the Engineer, so that the Engineer may determine their suitability for the purpose for which they were installed. The Physical Completion Date cannot be established until testing and corrections have been completed to the satisfaction of the Engineer.

The costs for power, gas, labor, material, supplies, and everything else needed to successfully complete operational testing, shall be included in the unit contract prices related to the system being tested, unless specifically set forth otherwise in the proposal.

Operational and test periods, when required by the Engineer, shall not affect a manufacturer's guaranties or warranties furnished under the terms of the contract.

1-05.13 Superintendents, Labor and Equipment of Contractor

(August 14, 2013 APWA GSP)

The sixth and seventh paragraphs of Section 1-05.13 are deleted.

1-05.15 Method of Serving Notices

The second paragraph in Section 1-05.15 is revised to read:

(January 4, 2024 APWA GSP)

All correspondence from the Contractor shall be served and directed to the Engineer. All correspondence from the Contractor constituting any notification, notice of protest, notice of dispute, or other correspondence constituting notification required to be furnished under the Contract, must be written in paper format, hand delivered or sent via certified mail delivery service with return receipt requested to the Engineer's office. Electronic copies such as e-mails or electronically delivered copies of correspondence will not constitute such notice and will not comply with the requirements of the Contract.

Add the following new sections:

(October 1, 2005 APWA GSP)

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

1-05.16 Water and Power

The Contractor shall make necessary arrangements, and shall bear the costs for power and water necessary for the performance of the work, unless the contract includes power and water as a pay item.

1-06 Control of Material

Section 1-06 is supplemented with the following:

Buy America Requirements

(October 1, 2025)

General Requirements

In accordance with Buy America requirements contained in 23 CFR 635.410 and 2 CFR 184, the following materials must be produced in the United States:

1. All Iron or Steel Products used in the project. This means all manufacturing processes, from the initial melting stage through the application of coatings, occurred in the United States.

2. All Manufactured Products used in the project. This means the manufactured product was manufactured (final assembly) in the United States.

3. All Construction Materials used in the project. This means that all manufacturing processes for the construction material occurred in the United States.

An article, material, or supply will be classified in one of four categories: 1) Iron or Steel Product, 2) Manufactured Product, 3) Construction Material, or 4) Excluded Material. Only a single category will apply to an item except as follows:

1. With respect to precast concrete products that are classified as Manufactured Products, the components of precast concrete products that consist wholly or predominantly of iron, steel, or combination of both shall meet the requirements for and be tracked as an Iron or Steel Product. The item shall also meet the requirements for and be tracked as a Manufactured Product.

2. With respect to intelligent transportation systems and other electronic hardware systems that are classified as Manufactured Products, the cabinets or other enclosures of such systems that consist wholly or predominantly of iron, steel, or a combination of both, shall meet the requirements for and be tracked as an Iron or Steel Products. The item shall also meet the requirements for and be tracked as a Manufactured Product.

Some contract items are composed of multiple parts that may fall into different categories. Individual components will be categorized as a Construction Material, a Manufactured Product, an Iron or Steel Product, or an excluded material based on their composition when they arrive at the staging area or work site.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Definitions

1. Construction Material: Defined as any article, material, or supply brought to the construction site for incorporation into the final product. Construction materials include an article, material, or supply that is or consists primarily of:

    a. Non-ferrous metals including all manufacturing processes, from initial smelting or melting through final shaping, coating, and assembly;

    b. Plastic and polymer-based products including all manufacturing processes, from initial combination of constituent plastic or polymer-based inputs, or, where applicable, constituent composite materials, until the item is in its final form);

    c. Glass including all manufacturing processes, from initial batching and melting of raw materials through annealing, cooling, and cutting);

    d. Fiber optic cable (includes drop cable) including all manufacturing processes, from initial ribboning (if applicable), through buffering, fiber stranding and jacketing, (fiber optic cable also includes the standards for glass and optical fiber);

    e. Optical fiber including all manufacturing processes, from the initial preform fabrication stage, though the completion of the draw;

    f. Lumber including all manufacturing processes, from initial debarking through treatment and planing;

    g. Drywall including all manufacturing processes, from initial blending of mined or synthetic gypsum plaster and additives through cutting and drying of sandwiched panels; or

    h. Engineered wood including all manufacturing processes from the initial combination of constituent materials until the wood product is in its final form.

    If a Construction Material is not manufactured in the United States it shall be considered a Foreign Construction Material.

2. Excluded Material: A material where Buy America requirements do not apply. This includes the following:

    a. Materials excluded by Section 70917(c) of the Buy America, Build America Act with respect to aggregates this includes cement and cementitious materials, aggregates such as stone, sand, or gravel or aggregate binding agents or additives. These materials shall be classified as excluded materials based on the composition when brought to the work site. It also includes combinations of these excluded materials when mixtures of Excluded Materials are delivered to the work site without final form for incorporation into the project (i.e. wet concrete and HMA). If they are formed prior to delivery, they are a Manufactured Product and not an Excluded Material.

    b. Temporary materials that are not being permanently incorporated into the project.

    c. Raw or minimal processed materials where the article, material, or supply does not fall into any of the categories, as it is not a Manufactured Product, an Iron or Steel

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Product, or a Construction Material and when these materials are delivered to the work site without final form for incorporation into the product (i.e. seed mix and topsoil). If they are formed prior to delivery, and are not an Iron or Steel Product or a Construction Material, they are a Manufactured Product and not an Excluded Material.

3. Iron or Steel Product: An article, material, or supply that consist of wholly or predominantly of iron or steel or a combination of both. To be considered predominantly of iron or steel or a combination of both means that the cost of the iron and steel content exceeds 50 percent of the total cost of all its components. The cost of iron and steel is based on a good faith estimate of the cost of the iron or steel components.

4. Manufactured Product: A Manufactured Product includes any item produced as a result of the manufacturing process. Items that should be treated as a manufactured product (rather than a construction material) are: 1) items that consist of two or more of the listed construction materials that have been combined together through a manufacturing process, and 2) items that include at least one of the listed construction materials as defined above, combined with a material that is not listed through a manufacturing process.

   If a product is not an Iron or Steel Product, a Construction Material, or an Excluded Material, it is a Manufactured Product.

   If a Manufactured Material is not manufactured in the United States, it shall be considered a Foreign Manufactured Product.

5. United States: To further define the coverage, a domestic product is a manufactured steel construction material that was produced in one of the 50 states, the District of Columbia, Puerto Rico, or in the territories and possessions of the United States.

Iron or Steel Product Requirements

Iron or Steel Products that are permanently incorporated into the project shall consist of American-made materials only. Buy America requirements do not apply to temporary steel or iron items, e.g., temporary sheet piling, temporary bridges, steel scaffolding and falsework.

Minor amounts of foreign steel and iron may be utilized in this project provided the cost of the foreign material used does not exceed one-tenth of one percent of the total contract cost or $2,500.00, whichever is greater.

American-made material is defined as material having all manufacturing processes occurring domestically.

If domestically produced steel billets or iron ingots are exported outside of the United States, as defined above, for any manufacturing process then the resulting product does not conform to the Buy America requirements. Additionally, products manufactured domestically from foreign source steel billets or iron ingots do not conform to the Buy America requirements because the initial melting and mixing of alloys to create the material occurred in a foreign country.

Manufacturing begins with the initial melting and mixing and continues through the coating stage. Any process which modifies the chemical content, the physical size or shape, or the

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

final finish is considered a manufacturing process. The processes include rolling, extruding, machining, bending, grinding, drilling, welding, and coating. The action of applying a coating to steel or iron is deemed a manufacturing process. Coating includes epoxy coating, galvanizing, aluminizing, painting, and any other coating that protects or enhances the value of steel or iron. Any process from the original reduction from ore to the finished product constitutes a manufacturing process for iron.

Due to a nationwide waiver, Buy America requirements do not apply to raw materials (iron ore and alloys), scrap (recycled steel or iron), and pig iron ore processed, pelletized, and reduced iron ore.

The following are considered to be steel manufacturing processes:

1. Production of steel by any of the following processes:

    a. Open hearth furnace.

    b. Basic oxygen.

    c. Electric furnace.

    d. Direct reduction.

2. Rolling, heat treating, and any other similar processing.

3. Fabrication of the products:

    a. Spinning wire into cable or strand.

    b. Corrugating and rolling into culverts.

    c. Shop fabrication.

A certification of materials origin will be required for all iron or steel products prior to such items being incorporated into the permanent work. The Contractor will not receive payment until the certification is received by the Engineer. The certification shall be on WSDOT Form 350-109 provided by the Engineer, or such other form approved by the Contracting Agency, provided it contains the same information as WSDOT Form 350-109.

Manufactured Products and Construction Material Requirements

A Contractor provided certification of materials origin will be required before each progress estimate or payment. The Contractor will not receive payment until the certification is received by the Engineer. The Contractor shall certify that all Manufactured Products and all Construction Materials installed during the current progress estimate period meet the Buy America requirements. The certification shall be on WSDOT Form 350-108 provided by the Engineer, or such other form approved by the Contracting Agency, provided it contains the same information as WSDOT Form 350-108.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Iron or Steel Products in a Manufactured Product
In addition to providing the certification of materials origin for the Manufactured Product, the iron or steel products in a manufactured product are subject to the Buy America requirements as follows:

1. When a precast concrete product is classified as a Manufactured Product, the components that are an Iron or Steel Product shall follow the "Iron or Steel Requirements" of this Specification.

2. When an electronic hardware system such as an intelligent transportation system is classified as a Manufactured Product, the cabinets and the other enclosures of such systems that are an Iron or Steel Product shall follow the "Iron or Steel Requirements" of this Specification.

Waiver for De Minimis Costs
Minor amounts of Foreign Construction Materials and Foreign Manufactured Products may be utilized in this project, provided that the total cost of the Foreign Construction Materials and Foreign Manufactured Products does not exceed $1,000,000 and does not exceed 5 percent of the total applicable material costs calculated as follows:

$$\frac{Total\ cost\ of\ Foreign\ Construction\ Materials + Total\ cost\ of\ Foreign\ Manufactured\ Products}{Total\ applicable\ material\ costs} < 0.05$$

The total applicable material costs shall be the sum of the costs of all Construction Materials, all Iron or Steel Products, and all Manufactured Products. Total applicable material costs does not include Excluded Materials.

(******)
Form 350-109 shall be signed by the Prime Contractor's authorized officer as defined in WSDOT Form 420-010.

1-06.1 Approval of Material Prior to Use

Section 1-06.1 is supplemented with the following:

(December 2023 CCPW GSP)
The Contractor shall use the Request for Approval of Material (RAM) form to identify the source of all materials proposed to be used on the project regardless of whether the material is listed in the Aggregate Source Approval (ASA) Database or Qualified Product List (QPL).

(July 2026 CCPW GSP)
Along with the submittal of the RAM,the Contractor shall submit test results to the Engineer for review and approval for all aggregate sources showing that the material meets Contract requirements.

If a material fails to meet specifications, and a re-test is performed on material from the same source by a private laboratory or agency other than Clark County, the re-testing shall be at the Contractor's expense.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

1-06.2 Acceptance of Materials

1-06.2(1) Samples and Tests for Acceptance

Section 1-06.2(1) is supplemented with the following:

(June 2014 CCPW GSP)

Material sampling for testing may be performed up to and including the point of incorporation of the respective material into the project. The definition of "qualified testing personnel and calibrated or verified equipment" shall not be referenced to the WAQTC requirements.

1-06.6 Recycled Materials

Section 1-06.6 is revised to read:

(January 4, 2016 APWA GSP)

The Contractor shall make their best effort to utilize recycled materials in the construction of the project. Approval of such material use shall be as detailed elsewhere in the Standard Specifications.

Prior to Physical Completion the Contractor shall report the quantity of recycled materials that were utilized in the construction of the project for each of the items listed in Section 9-03.21. The report shall include hot mix asphalt, recycled concrete aggregate, recycled glass, steel furnace slag and other recycled materials (e.g. utilization of on-site material and aggregates from concrete returned to the supplier). The Contractor's report shall be provided on DOT form 350-075 Recycled Materials Reporting.

1-07 Legal Relations and Responsibilities to the Public

1-07.1 Laws to be Observed

Section 1-07.1 is supplemented with the following:

(October 1, 2005 APWA GSP)

In cases of conflict between different safety regulations, the more stringent regulation shall apply.

The Washington State Department of Labor and Industries shall be the sole and paramount administrative agency responsible for the administration of the provisions of the Washington Industrial Safety and Health Act of 1973 (WISHA).

The Contractor shall maintain at the project site office, or other well known place at the project site, all articles necessary for providing first aid to the injured. The Contractor shall establish, publish, and make known to all employees, procedures for ensuring immediate removal to a hospital, or doctor's care, persons, including employees, who may have been injured on the project site. Employees should not be permitted to work on the project site before the Contractor has established and made known procedures for removal of injured persons to a hospital or a doctor's care.

The Contractor shall have sole responsibility for the safety, efficiency, and adequacy of the Contractor's plant, appliances, and methods, and for any damage or injury resulting from their failure, or improper maintenance, use, or operation. The Contractor shall be solely and completely responsible for the conditions of the project site, including safety for all persons and property in the performance of the work. This requirement shall apply continuously, and

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

not be limited to normal working hours. The required or implied duty of the Engineer to conduct construction review of the Contractor's performance does not, and shall not, be intended to include review and adequacy of the Contractor's safety measures in, on, or near the project site.

(March 9, 2026)

Unmanned Aircraft Systems (UAS)

The procurement and/or use of any drone (UAS) on this Contract shall comply with the following directives:

- National Defense Authorization Act (NDAA) – American Security Drone Act of 2023 (ASDA, Pub. L. No. 118-31).

- Office of Management and Budget Memorandum M-26-02 – Restrictions on using federal funds to purchase or operate prohibited foreign UAS.

Contractors, subcontractors, and lower-tier subcontractors shall not procure, operate, maintain, or process data from prohibited UAS manufactured or assembled by "covered foreign entities" as defined in the Federal Acquisition Security Council (FASC) in the performance of this Contract.

1-07.2 State Taxes

Section 1-07.2 is revised to read:

(June 27, 2011 APWA GSP)

1-07.2 State Sales Tax

The Washington State Department of Revenue has issued special rules on the State sales tax. Sections 1-07.2(1) through 1-07.2(3) are meant to clarify those rules. The Contractor should contact the Washington State Department of Revenue for answers to questions in this area. The Contracting Agency will not adjust its payment if the Contractor bases a bid on a misunderstood tax liability.

The Contractor shall include all Contractor-paid taxes in the unit bid prices or other contract amounts. In some cases, however, state retail sales tax will not be included. Section 1-07.2(2) describes this exception.

The Contracting Agency will pay the retained percentage (or release the Contract Bond if a FHWA funded Project) only if the Contractor has obtained from the Washington State Department of Revenue a certificate showing that all contract-related taxes have been paid (RCW 60.28.051). The Contracting Agency may deduct from its payments to the Contractor any amount the Contractor may owe the Washington State Department of Revenue, whether the amount owed relates to this contract or not. Any amount so deducted will be paid into the proper State fund.

1-07.2(1) State Sales Tax — Rule 171

WAC 458-20-171, and its related rules, apply to building, repairing, or improving streets, roads, etc., which are owned by a municipal corporation, or political subdivision of the state, or by the United States, and which are used primarily for foot or vehicular traffic. This includes storm or combined sewer systems within and included as a part of the street or road drainage system and power lines when such are part of the roadway

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

lighting system. For work performed in such cases, the Contractor shall include Washington State Retail Sales Taxes in the various unit bid item prices, or other contract amounts, including those that the Contractor pays on the purchase of the materials, equipment, or supplies used or consumed in doing the work.

1-07.2(2) State Sales Tax — Rule 170

WAC 458-20-170, and its related rules, apply to the constructing and repairing of new or existing buildings, or other structures, upon real property. This includes, but is not limited to, the construction of streets, roads, highways, etc., owned by the state of Washington; water mains and their appurtenances; sanitary sewers and sewage disposal systems unless such sewers and disposal systems are within, and a part of, a street or road drainage system; telephone, telegraph, electrical power distribution lines, or other conduits or lines in or above streets or roads, unless such power lines become a part of a street or road lighting system; and installing or attaching of any article of tangible personal property in or to real property, whether or not such personal property becomes a part of the realty by virtue of installation.

For work performed in such cases, the Contractor shall collect from the Contracting Agency, retail sales tax on the full contract price. The Contracting Agency will automatically add this sales tax to each payment to the Contractor. For this reason, the Contractor shall not include the retail sales tax in the unit bid item prices, or in any other contract amount subject to Rule 170, with the following exception.

Exception: The Contracting Agency will not add in sales tax for a payment the Contractor or a subcontractor makes on the purchase or rental of tools, machinery, equipment, or consumable supplies not integrated into the project. Such sales taxes shall be included in the unit bid item prices or in any other contract amount.

1-07.2(3) Services

The Contractor shall not collect retail sales tax from the Contracting Agency on any contract wholly for professional or other services (as defined in Washington State Department of Revenue Rules 138 and 244).

1-07.5 Environmental Regulations

Section 1-07.5 is supplemented with the following:

(September 20, 2010)

Environmental Commitments

The following Provisions summarize the requirements, in addition to those required elsewhere in the Contract, imposed upon the Contracting Agency by the various documents referenced in the Special Provision **Permits and Licenses**. Throughout the work, the Contractor shall comply with the following requirements:

(April 1, 2019)

The Contractor shall notify the Engineer a minimum of *** 15 *** calendar days prior to commencing any work in sensitive areas, mitigation areas, and wetland buffers. Installation of construction fencing is excluded from this notice requirement.

(******)

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

No staging of dangerous or hazardous chemicals or substances is allowed within 100 feet of wetlands or waterbodies.

(August 3, 2009)

Payment

All costs to comply with this special provision for the environmental commitments and requirements are incidental to the contract and are the responsibility of the Contractor. The Contractor shall include all related costs in the associated bid prices of the contract.

1-07.5(2) State Department of Fish and Wildlife

Section 1-07.5(2) is supplemented with the following:

(April 2, 2018)

The following Provisions summarize the requirements, in addition to those required elsewhere in the Contract, imposed upon the Contracting Agency by the Washington State Department of Fish and Wildlife. Throughout the work, the Contractor shall comply with the following requirements:

(******)

Work within the wetted perimeter may only occur between July 15, 2026 to September 15, 2026.

Removal of vegetation/debris and small woody material from within, on or adjacent to a water crossing structure, using hand-held equipment and hand-held tools, may be conducted year-round for maintenance.

Other work may occur year-around in areas that are below the OHWL but above the wetted perimeter and have not been made dry by project activities.

Additional work may occur outside the in-water work windows with approval from the Area Habitat Biologist.

Disturbance of the bed or bottom of the water body is not permitted. No other temporary work access, equipment, or materials shall be placed below the ordinary high water line at any time.

(April 2, 2018)

All costs to comply with this special provision are incidental to the Contract and are the responsibility of the Contractor. The Contractor shall include all related costs in the associated bid prices of the Contract.

1-07.6 Permits and Licenses

Section 1-07.6 is supplemented with the following:

(January 2, 2018)

The Contracting Agency has obtained the below-listed permit(s) for this project. A copy of the permit(s) is available for the Bidder at the Engineer's Office (see address in Section 1-02.4 of these Special Provisions). Copies of these permits, including a copy of the Transfer of Coverage form, when applicable, are required to be onsite at all times.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Contact with the permitting agencies, concerning the below-listed permit(s), shall be made through the Engineer with the exception of when the Construction Stormwater General Permit coverage is transferred to the Contractor, direct communication with the Department of Ecology is allowed. The Contractor shall be responsible for obtaining Ecology's approval for any Work requiring additional approvals (e.g. Request for Chemical Treatment Form). The Contractor shall obtain additional permits as necessary. All costs to obtain and comply with additional permits shall be included in the applicable Bid items for the Work involved.

***

Name Of Document	Permitting Agency	Permit Reference No.
Hydraulic Project Approval	Department of Fish & Wildlife	2026-5-35+01
Shoreline Permit, Variance, or Exemption	Clark County	SLR-2025-00026

***

1-07.7 Load Limits

Section 1-07.7 is supplemented with the following:

(January 2016 CCPW GSP)

If the sources of materials provided by the Contractor necessitate hauling over roads other than County roads, the Contractor shall, at the Contractor's expense, make all arrangements for the use of the haul routes including all necessary permits.

1-07.8 High-Visibility Apparel

1-07.8(1) Traffic Control Personnel

Section 1-07.8(1) is revised to read:

(September 16, 2025)

All personnel performing the Work described in Section 2-04 (including traffic control supervisors, flaggers, and others performing traffic control labor of any kind) shall comply with the following:

1. During daylight hours with clear visibility, workers shall wear a high-visibility ANSI/ISEA 107 Type R Class 2 or 3 garment with background material that are fluorescent yellow-green, fluorescent orange-red, or fluorescent red in color; and a high visibility hardhat that is white, yellow, yellow-green, orange, or red in color; and

2. During hours of darkness (½ hour before sunset to ½ hour after sunrise) or other low-visibility conditions (snow, fog, etc.), workers shall wear a high-visibility ANSI/ISEA 107 Type R Class 2 or 3 garment with background material that are fluorescent yellow-green, fluorescent orange-red, or fluorescent red in color; a high-visibility lower garment meeting ANSI/ISEA 107 Class E, and a high visibility hardhat marked with at least 12 square inches of retroreflective material applied to provide 360 degrees of visibility.

1-07.9 Wages

1-07.9(1) General

Section 1-07.9(1) is supplemented with the following:

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

(January 6, 2026)
The Federal wage rates incorporated in this contract have been established by the Secretary of Labor under United States Department of Labor General Decision No. WA20260001.

The State rates incorporated in this contract are applicable to all construction activities associated with this contract.

1-07.9(5) Required Documents

1-07.9(5)A General

Section 1-07.9(5)A is revised to read:

(February 17, 2026 APWA GSP, Option A)
All Statements of Intent to Pay Prevailing Wages and Affidavits of Wages Paid, including a signed Statement of Compliance for Federal-aid projects, shall be submitted to the Engineer and entered into the State L&I online Prevailing Wage Intent & Affidavit (PWIA) system. In addition to entries made in the PWIA system, all Certified Payrolls must be submitted weekly to the Contracting Agency with a legally valid signature.

Section 1-07.9(5)A is supplemented with the following:

(August 2022 CCPW GSP)
Copies of the "Statements of Intent to Pay Prevailing Wages", "Affidavits of Wages Paid" and Certified Payrolls, including a signed Statement of Compliance for Federal-aid projects, shall also be submitted by the Contractor electronically to the Engineer in PDF format.

1-07.11 Requirements For Nondiscrimination

Section 1-07.11 is supplemented with the following:

(May 5, 2025)
Requirement for Affirmative Action to Ensure Equal Employment Opportunity

In accordance with 41 CFR § 60-4.2, the clauses contained in 1-4 below are required to be included in this Contract. Nothing in this contract alters the Contractor's responsibility to comply with all applicable Federal regulations, including but not limited to 41 CFR part 60 as currently existing or later amended.

1. The Contractor's attention is called to the "Equal Opportunity Clause and the Standard Federal Equal Employment Opportunity Construction Contract Specifications" set forth herein.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

2. The goals and timetables for minority and female participation set by the Office of Federal Contract Compliance Programs, expressed in percentage terms for the Contractor's aggregate work force in each construction craft and in each trade on all construction work in the covered area, are as follows:

Women - Statewide

Timetable	Goal
Until further notice	6.9%

Minorities - by Standard Metropolitan Statistical Area (SMSA)

Spokane, WA:
SMSA Counties:
Spokane, WA 2.8
WA Spokane.
Non-SMSA Counties 3.0
WA Adams; WA Asotin; WA Columbia; WA Ferry; WA Garfield; WA Lincoln, WA Pend Oreille; WA Stevens; WA Whitman.

Richland, WA
SMSA Counties:
Richland Kennewick, WA 5.4
WA Benton; WA Franklin.
Non-SMSA Counties 3.6
WA Walla Walla.

Yakima, WA:
SMSA Counties:
Yakima, WA 9.7
WA Yakima.
Non-SMSA Counties 7.2
WA Chelan; WA Douglas; WA Grant; WA Kittitas; WA Okanogan.

Seattle, WA:
SMSA Counties:
Seattle Everett, WA 7.2
WA King; WA Snohomish.
Tacoma, WA 6.2
WA Pierce.
Non-SMSA Counties 6.1
WA Clallam; WA Grays Harbor; WA Island; WA Jefferson; WA Kitsap; WA Lewis; WA Mason; WA Pacific; WA San Juan; WA Skagit; WA Thurston; WA Whatcom.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Portland, OR:
SMSA Counties:
Portland, OR-WA 4.5
WA Clark.
Non-SMSA Counties 3.8
WA Cowlitz; WA Klickitat; WA Skamania; WA Wahkiakum.

These goals are applicable to each nonexempt Contractor's total on-site construction workforce, regardless of whether or not part of that workforce is performing work on a Federal, or federally assisted project, contract, or subcontract until further notice. Compliance with these goals and timetables is enforced by the Office of Federal Contract compliance Programs.

The Contractor's compliance with the Executive Order and the regulations in 41 CFR Part 60-4 shall be based on its implementation of the Equal Opportunity Clause, specific affirmative action obligations required by the specifications set forth in 41 CFR 60-4.3(a), and its efforts to meet the goals. The hours of minority and female employment and training must be substantially uniform throughout the length of the contract, in each construction craft and in each trade, and the Contractor shall make a good faith effort to employ minorities and women evenly on each of its projects. The transfer of minority or female employees or trainees from Contractor to Contractor or from project to project for the sole purpose of meeting the Contractor's goals shall be a violation of the contract, the Executive Order and the regulations in 41 CFR Part 60-4. Compliance with the goals will be measured against the total work hours performed.

3. The Contractor shall provide written notification to the Office of Federal Contract Compliance Programs (OFCCP) within 10 working days of award of any construction subcontract in excess of $10,000 or more that are Federally funded, at any tier for construction work under the contract resulting from this solicitation. The notification shall list the name, address and telephone number of the subcontractor; employer identification number of the subcontractor; estimated dollar amount of the subcontract; estimated starting and completion dates of the subcontract; and the geographical area in which the contract is to be performed. The notification shall be sent to:

   U.S. Department of Labor
   Office of Federal Contract Compliance Programs Pacific Region
   Attn: Regional Director
   San Francisco Federal Building
   90 – 7th Street, Suite 18-300
   San Francisco, CA 94103(415) 625-7800 Phone
   (415) 625-7799 Fax

4. As used in this Notice, and in the contract resulting from this solicitation, the Covered Area is as designated herein.

In accordance with 41 CFR § 60-4.3, the clauses contained in 1-15 below are required to be included in this Contract. Nothing in this Contract alters the Contractor's responsibility to comply with all applicable Federal regulations, including but not limited to 41 CFR part 60 as currently existing or later amended.

Standard Federal Equal Employment Opportunity Construction Contract Specifications

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

1. As used in these specifications:

   a. "Covered Area" means the geographical area described in the solicitation from which this contract resulted;

   b. "Director" means Director, Office of Federal Contract Compliance Programs, United States Department of Labor, or any person to whom the Director delegates authority;

   c. "Employer Identification Number" means the Federal Social Security number used on the Employer's Quarterly Federal Tax Return, U.S. Treasury Department Form 941;

   d. "Minority" includes:

      (1) Black (all persons having origins in any of the Black African racial groups not of Hispanic origin);

      (2) Hispanic (all persons of Mexican, Puerto Rican, Cuban, Central American, South American, or other Spanish culture or origin, regardless of race);

      (3) Asian and Pacific Islander (all persons having origins in any of the original peoples of the Far East, Southeast Asia, the Indian Subcontinent, or the Pacific Islands); and

      (4) American Indian or Alaskan Native (all persons having origins in any of the original peoples of North America and maintaining identifiable tribal affiliations through membership and participation or community identification.)

2. Whenever the Contractor, or any subcontractor at any tier, subcontracts a portion of the work involving any construction trade, it shall physically include in each subcontract in excess of $10,000 the provisions of these specifications and the Notice which contains the applicable goals for minority and female participation and which is set forth in the solicitations from which this contract resulted.

3. If the Contractor is participating (pursuant to 41 CFR 60-4.5) in a Hometown Plan approved by the U.S. Department of Labor in the covered area either individually or through an association, its affirmative action obligations on all work in the Plan area (including goals and timetables) shall be in accordance with that Plan for those trades which have unions participating in the Plan. Contractors must be able to demonstrate their participation in and compliance with the provisions of any such Hometown Plan. Each Contractor or subcontractor participating in an approved Plan is individually required to comply with its obligations under the EEO clause, and to make a good faith effort to achieve each goal under the Plan in each trade in which it has employees. The overall good faith performance by other Contractors or subcontractors toward a goal in an approved Plan does not excuse any covered Contractor's or subcontractor's failure to take good faith efforts to achieve the Plan goals and timetables.

4. The Contractor shall implement the specific affirmative action standards provided in paragraphs 7a through 7p of this Special Provision. The goals set forth in the solicitation

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

from which this contract resulted are expressed as percentages of the total hours of employment and training of minority and female utilization the Contractor should reasonably be able to achieve in each construction trade in which it has employees in the covered area. Covered construction contractors performing construction work in geographical areas where they do not have a Federal or federally assisted construction contract shall apply the minority and female goals established for the geographical area where the work is being performed. The Contractor is expected to make substantially uniform progress in meeting its goals in each craft during the period specified.

5. Neither the provisions of any collective bargaining agreement, nor the failure by a union with whom the Contractor has a collective bargaining agreement, to refer either minorities or women shall excuse the Contractor's obligations under these specifications, Executive Order 11246, or the regulations promulgated pursuant thereto.

6. In order for the nonworking training hours of apprentices and trainees to be counted in meeting the goals, such apprentices and trainees must be employed by the Contractor during the training period, and the Contractor must have made a commitment to employ the apprentices and trainees at the completion of their training, subject to the availability of employment opportunities. Trainees must be trained pursuant to training programs approved by the U.S. Department of Labor.

7. The Contractor shall take specific affirmative actions to ensure equal employment opportunity. The evaluation of the Contractor's compliance with these specifications shall be based upon its effort to achieve maximum results from its actions. The Contractor shall document these efforts fully, and shall implement affirmative action steps at least as extensive as the following:

    a. Ensure and maintain a working environment free of harassment, intimidation, and coercion at all sites, and in all facilities at which the Contractor's employees are assigned to work. The Contractor, where possible, will assign two or more women to each construction project. The Contractor shall specifically ensure that all foremen, superintendents, and other on-site supervisory personnel are aware of and carry out the Contractor's obligation to maintain such a working environment, with specific attention to minority or female individuals working at such sites or in such facilities.

    b. Establish and maintain a current list of minority and female recruitment sources, provide written notification to minority and female recruitment sources and to community organizations when the Contractor or its unions have employment opportunities available, and maintain a record of the organizations' responses.

    c. Maintain a current file of the names, addresses and telephone numbers of each minority and female off-the-street applicant and minority or female referral from a union, a recruitment source or community organization and of what action was taken with respect to each such individual. If such individual was sent to the union hiring hall for referral and was not referred back to the Contractor by the union or, if referred, not employed by the Contractor, this shall be documented in the file with the reason therefor, along with whatever additional actions the Contractor may have taken.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

d. Provide immediate written notification to the Director when the union or unions with which the Contractor has a collective bargaining agreement has not referred to the Contractor a minority person or woman sent by the Contractor, or when the Contractor has other information that the union referral process has impeded the Contractor's efforts to meet its obligations.

e. Develop on-the-job training opportunity and/or participate in training programs for the area which expressly include minorities and women, including upgrading programs and apprenticeship and trainee programs relevant to the Contractor's employment needs, especially those programs funded or approved by the U.S. Department of Labor. The Contractor shall provide notice of these programs to the sources compiled under 7b above.

f. Disseminate the Contractor's EEO policy by providing notice of the policy to unions and training programs and requesting their cooperation in assisting the Contractor in meeting its EEO obligations; by including it in any policy manual and collective bargaining agreement; by publicizing it in the company newspaper, annual report, etc.; by specific review of the policy with all management personnel and with all minority and female employees at least once a year; and by posting the company EEO policy on bulletin boards accessible to all employees at each location where construction work is performed.

g. Review, at least annually, the company's EEO policy and affirmative action obligations under these specifications with all employees having any responsibility for hiring, assignment, layoff, termination or other employment decisions including specific review of these items with on-site supervisory personnel such as Superintendents, General Foremen, etc., prior to the initiation of construction work at any job site. A written record shall be made and maintained identifying the time and place of these meetings, persons attending, subject matter discussed, and disposition of the subject matter.

h. Disseminate the Contractor's EEO policy externally by including it in any advertising in the news media, specifically including minority and female news media, and providing written notification to and discussing the Contractor's EEO policy with other Contractors and Subcontractors with whom the Contractor does or anticipates doing business.

i. Direct its recruitment efforts, both oral and written, to minority, female and community organizations, to schools with minority and female students and to minority and female recruitment and training organizations serving the Contractor's recruitment area and employment needs. Not later than one month prior to the date for the acceptance of applications for apprenticeship or other training by any recruitment source, the Contractor shall send written notification to organizations such as the above, describing the openings, screening procedures, and tests to be used in the selection process.

j. Encourage present minority and female employees to recruit other minority persons and women and where reasonable, provide after school, summer and vacation employment to minority and female youth both on the site and in other areas of a Contractor's work force.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

k. Validate all tests and other selection requirements where there is an obligation to do so under 41 CFR Part 60-3.

l. Conduct, at least annually, an inventory and evaluation of all minority and female personnel for promotional opportunities and encourage these employees to seek or to prepare for, through appropriate training, etc., such opportunities.

m. Ensure that seniority practices, job classifications, work assignments and other personnel practices, do not have a discriminatory effect by continually monitoring all personnel and employment related activities to ensure that the EEO policy and the Contractor's obligations under these specifications are being carried out.

n. Ensure that all facilities and company activities are nonsegregated except that separate or single-user toilet and necessary changing facilities shall be provided to assure privacy between the sexes.

o. Document and maintain a record of all solicitations of offers for subcontracts from minority and female construction contractors and suppliers, including circulation of solicitations to minority and female contractor associations and other business associations.

p. Conduct a review, at least annually, of all supervisors' adherence to and performance under the Contractor's EEO policies and affirmative action obligations.

8. Contractors are encouraged to participate in voluntary associations which assist in fulfilling one or more of their affirmative action obligations (7a through 7p). The efforts of a contractor association, joint contractor-union, contractor-community, or other similar group of which the Contractor is a member and participant, may be asserted as fulfilling any one or more of the obligations under 7a through 7p of this Special Provision provided that the Contractor actively participates in the group, makes every effort to assure that the group has a positive impact on the employment of minorities and women in the industry, ensure that the concrete benefits of the program are reflected in the Contractor's minority and female work-force participation, makes a good faith effort to meet its individual goals and timetables, and can provide access to documentation which demonstrate the effectiveness of actions taken on behalf of the Contractor. The obligation to comply, however, is the Contractor's and failure of such a group to fulfill an obligation shall not be a defense for the Contractor's noncompliance.

9. A single goal for minorities and a separate single goal for women have been established. The Contractor, however, is required to provide equal employment opportunity and to take affirmative action for all minority groups, both male and female, and all women, both minority and non-minority. Consequently, the Contractor may be in violation of the Executive Order if a particular group is employed in substantially disparate manner (for example, even though the Contractor has achieved its goals for women generally, the Contractor may be in violation of the Executive Order if a specific minority group of women is underutilized).

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

10. The Contractor shall not use the goals and timetables or affirmative action standards to discriminate against any person because of race, color, religion, sex, sexual orientation, gender identity, or national origin.

11. The Contractor shall not enter into any subcontract with any person or firm debarred from Government contracts pursuant to Executive Order 11246.

12. The Contractor shall carry out such sanctions and penalties for violation of these specifications and of the Equal Opportunity Clause, including suspensions, terminations and cancellations of existing subcontracts as may be imposed or ordered pursuant to Executive Order 11246, as amended, and its implementing regulations, by the Office of Federal Contract Compliance Programs. Any Contractor who fails to carry out such sanctions and penalties shall be in violation of these specifications and Executive Order 11246, as amended.

13. The Contractor, in fulfilling its obligations under these specifications, shall implement specific affirmative action steps, at least as extensive as those standards prescribed in paragraph 7 of this Special Provision, so as to achieve maximum results from its efforts to ensure equal employment opportunity. If the Contractor fails to comply with the requirements of the Executive Order, the implementing regulations, or these specifications, the Director shall proceed in accordance with 41 CFR 60-4.8.

14. The Contractor shall designate a responsible official to monitor all employment related activity to ensure that the company EEO policy is being carried out, to submit reports relating to the provisions hereof as may be required by the government and to keep records. Records shall at least include, for each employee, their name, address, telephone numbers, construction trade, union affiliation if any, employee identification number when assigned, social security number, race, sex, status (e.g., mechanic, apprentice, trainee, helper, or laborer), dates of changes in status, hours worked per week in the indicated trade, rate of pay, and locations at which the work was performed. Records shall be maintained in an easily understandable and retrievable form; however, to the degree that existing records satisfy this requirement, the Contractors will not be required to maintain separate records.

15. Nothing herein provided shall be construed as a limitation upon the application of other laws which establish different standards of compliance or upon the application of requirements for the hiring of local or other area residents (e.g., those under the Public Works Employment Act of 1977 and the Community Development Block Grant Program).

    Additional assistance for Federal Construction Contractors on contracts administered by Washington State Department of Transportation or by Local Agencies may be found at:

    Washington State Dept. of Transportation
    Office of Equity and Civil Rights
    PO Box 47314
    310 Maple Park Ave. SE
    Olympia WA
    98504-7314
    Ph: 360-705-7090
    Fax: 360-705-6801

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

http://www.wsdot.wa.gov/equalopportunity/default.htm

1-07.11(1) Regulatory Authorities

1-07.11(1)C Nondiscrimination Authorities

Section 1-07.11(1)C is revised to read:

(March 9, 2026)

During the performance of this Contract, the Contractor, for itself, its assignees, and successors in interest agrees to comply with the following nondiscrimination statues and authorities; including but not limited to:

1. Title VI of the Civil Rights Act of 1964 (42 U.S.C. § 2000d et seq., 78 stat. 252), and its implementing regulations and case law, prohibit discrimination on the basis of race, color, or national origin. 49 C.F.R. 21.5(b)(2) prohibits a recipient of federal funds from utilizing "criteria or methods of administration which have the effect of subjecting persons to discrimination because of their race, color, or national origin, or have the effect of defeating or substantially impairing accomplishment of the objectives of the program with respect to individuals of a particular race, color, or national origin." This includes taking reasonable steps to provide limited English proficiency (LEP) persons meaningful access to all programs, activities and services, where necessary to avoid discrimination on the basis of national origin.

2. The Uniform Relocation Assistance and Real Property Acquisition Policies Act of 1970, (42 U.S.C §4601), (prohibits unfair treatment of persons displaced or whose property has been acquired because of Federal or Federal-aid programs and projects).

3. Federal-Aid Highway Act of 1973, (23 U.S.C. § 324 et. seq.), as amended, (prohibits discrimination on the basis of sex).

4. Section 504 of the Rehabilitation Act of 1973, (29 U.S.C. § 794 et seq.), as amended (prohibits discrimination on the basis of disability); and 49 C.F.R. Part 27.

5. The Age Discrimination Act of 1975, as amended (42 U.S.C. § 6101 et seq.), (prohibits discrimination on the basis of age).

6. Airport and Airway Improvement Act of 1982, (49 U.S.C. § 471, Section 47123), as amended, (prohibits discrimination based on race, creed, color, national origin, or sex).

7. The Civil Rights Restoration Act of 1987, (PL 100-209), (Broadened the scope, coverage and applicability of Title VI of the Civil Rights Act of 1964, The Age of Discrimination Act of 1975 and Section 504 of the Rehabilitation Act of 1973, by expanding the definition and terms "programs or activities" to include all of the programs or activities of the Federal-aid recipients, sub-recipients and contractors, whether such programs or activities are Federally funded or not).

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

8. Titles II and III of the Americans with Disabilities Act, which prohibit discrimination on the basis of disability in the operation of public entities, public and private transportation systems, places of public accommodation, and certain testing entities (42 U.S.C. § 12131-12189) as implemented by Department of Transportation regulations at 49 C.F.R. parts 37 and 38.

9. The Federal Aviation Administration's Nondiscrimination statute (49 U.S.C. § 47123), (prohibits discrimination on the basis of race, color national origin, and sex).

10. Title IX of the Education Amendments of 1972, as amended, which prohibits you from discriminating because of sex in education programs or activities (20 U.S.C. 1681 et seq.).

1-07.11(2) Contractual Requirements

(November 25, 2024 APWA GSP)

Item #11 in the first paragraph of Section 1-07.11(2) is deleted.

1-07.12 Federal Agency Inspection

Section 1-07.12 is supplemented with the following:

(October 3, 2023)

Required Federal Aid Provisions

The Required Contract Provisions Federal Aid Construction Contracts (FHWA 1273) Revised October 23, 2023 and the amendments thereto supersede any conflicting provisions of the Standard Specifications and are made a part of this Contract; provided, however, that if any of the provisions of FHWA 1273, as amended, are less restrictive than Washington State Law, then the Washington State Law shall prevail.

The provisions of FHWA 1273, as amended, included in this Contract require that the Contractor insert the FHWA 1273 and amendments thereto in each subcontract, together with the wage rates which are part of the FHWA 1273, as amended. Also, a clause shall be included in each subcontract requiring the subcontractors to insert the FHWA 1273 and amendments thereto in any lower tier subcontracts, together with the wage rates. The Contractor shall also ensure that this section, REQUIRED FEDERAL AID PROVISIONS, is inserted in each subcontract for subcontractors and lower tier subcontractors. For this purpose, upon request to the Engineer, the Contractor will be provided with extra copies of the FHWA 1273, the amendments thereto, the applicable wage rates, and this Special Provision.

1-07.17 Utilities and Similar Facilities

Section 1-07.17 is supplemented with the following:

(April 2, 2007)

Locations and dimensions shown in the Plans for existing facilities are in accordance with available information obtained without uncovering, measuring, or other verification.

The following addresses and telephone numbers of utility companies known or suspected of having facilities within the project limits are supplied for the Contractor's convenience:

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

***

Clark Public Utilities - Electric
P. O. Box 8900
Vancouver, WA 98668
Contact: Jason Nemjo, Josh Vincent, or Jaylon Muonio
Office: (360) 992-8011, (360) 992-8508, (360) 992-8826

Lumen - Telecommunication
Engineering Department
4501 NE Minnehaha Building II
Vancouver, WA 98661
Contact: Bill Nicolosi
Office: (360) 946-2894
***

(December 2023 CCPW GSP)
The location of utilities shown in the Plans is approximate.

The Northwest Utility Notification Center (One Call Center) toll-free telephone number is 1-800-424-5555 or 811.

No excavation shall begin until all utilities in the vicinity of the excavation area have been located and marked. If any damage is done to a utility, the Contractor shall notify the Engineer immediately.

1-07.18 Public Liability and Property Damage Insurance

Section 1-07.18 is deleted in its entirety, and replaced with the following:

(February 17, 2026 APWA GSP)

1-07.18 Insurance

1-07.18(1) General Requirements

A. The Contractor shall procure and maintain the insurance described in all subsections of section 1-07.18 of these Special Provisions, from insurers with a current A. M. Best rating of not less than A-: VII and licensed to do business in the State of Washington. The Contracting Agency reserves the right to approve or reject the insurance provided, based on the insurer's financial condition.

B. The Contractor shall keep this insurance in force without interruption from the commencement of the Contractor's Work through the term of the Contract and for thirty (30) days after the Physical Completion date, unless otherwise indicated below.

C. If any insurance policy is written on a claims-made form, its retroactive date, and that of all subsequent renewals, shall be no later than the effective date of this Contract. The policy shall state that coverage is claims made and state the retroactive date. Claims-made form coverage shall be maintained by the Contractor for a minimum of 36 months following the Completion Date or earlier termination of this Contract, and the Contractor shall annually provide the Contracting Agency with proof of renewal. If renewal of the claims made form of coverage becomes

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

unavailable, or economically prohibitive, the Contractor shall purchase an extended reporting period ("tail") or execute another form of guarantee acceptable to the Contracting Agency to assure financial responsibility for liability for services performed.

D. The Contractor's Automobile Liability, Commercial General Liability and Excess or Umbrella Liability insurance policies shall be primary and non-contributory insurance as respects the Contracting Agency's insurance, self-insurance, or self-insured pool coverage. Any insurance, self-insurance, or self-insured pool coverage maintained by the Contracting Agency shall be excess of the Contractor's insurance and shall not contribute with it.

E. The Contractor shall provide the Contracting Agency and all additional insureds with written notice of any policy cancellation, within two business days of their receipt of such notice.

F. The Contractor shall not begin Work under the Contract until the required insurance has been obtained and approved by the Contracting Agency.

G. Failure on the part of the Contractor to maintain the insurance as required shall constitute a material breach of contract, upon which the Contracting Agency may, after giving five business days' notice to the Contractor to correct the breach, immediately terminate the Contract or, at its discretion, procure or renew such insurance and pay any and all premiums in connection therewith, with any sums so expended to be repaid to the Contracting Agency on demand, or at the sole discretion of the Contracting Agency, offset against funds due the Contractor from the Contracting Agency.

H. All costs for insurance shall be incidental to and included in the unit or lump sum prices of the Contract and no additional payment will be made.

I. Under no circumstances shall a wrap up policy be obtained, for either initiating or maintaining coverage, to satisfy insurance requirements for any policy required under this Section. A "wrap up policy" is defined as an insurance agreement or arrangement under which all the parties working on a specified or designated project are insured under one policy for liability arising out of that specified or designated project.

1-07.18(2) Additional Insured

All insurance policies, with the exception of Workers Compensation, and of Professional Liability and Builder's Risk (if required by this Contract) shall name the following listed entities as additional insured(s) using the forms or endorsements required herein:

- the Contracting Agency and its officers, elected officials, employees, agents, and volunteers

The above-listed entities shall be additional insured(s) for the full available limits of liability maintained by the Contractor, irrespective of whether such limits maintained by the Contractor are greater than those required by this Contract, and irrespective of whether the Certificate of Insurance provided by the Contractor pursuant to 1-07.18(4) describes limits lower than those maintained by the Contractor.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

For Commercial General Liability insurance coverage, the required additional insured endorsements shall be at least as broad as ISO forms CG 20 10 10 01 for ongoing operations and CG 20 37 10 01 for completed operations.

1-07.18(3) Subcontractors

The Contractor shall cause each subcontractor of every tier to provide insurance coverage that complies with all applicable requirements of the Contractor-provided insurance as set forth herein, except the Contractor shall have sole responsibility for determining the limits of coverage required to be obtained by subcontractors.

The Contractor shall ensure that all subcontractors of every tier add all entities listed in 1-07.18(2) as additional insureds, and provide proof of such on the policies as required by that section as detailed in 1-07.18(2) using an endorsement as least as broad as ISO CG 20 10 10 01 for ongoing operations and CG 20 37 10 01 for completed operations.

Upon request by the Contracting Agency, the Contractor shall forward to the Contracting Agency evidence of insurance and copies of the additional insured endorsements of each subcontractor of every tier as required in 1-07.18(4) Verification of Coverage.

1-07.18(4) Verification of Coverage

The Contractor shall deliver to the Contracting Agency a Certificate(s) of Insurance and endorsements for each policy of insurance meeting the requirements set forth herein when the Contractor delivers the signed Contract for the Work. Failure of Contracting Agency to demand such verification of coverage with these insurance requirements or failure of Contracting Agency to identify a deficiency from the insurance documentation provided shall not be construed as a waiver of Contractor's obligation to maintain such insurance.

Verification of coverage shall include:

1. An ACORD certificate or a form determined by the Contracting Agency to be equivalent.

2. Copies of all endorsements naming Contracting Agency and all other entities listed in 1-07.18(2) as additional insured(s), showing the policy number. The Contractor may submit a copy of any blanket additional insured clause from its policies instead of a separate endorsement.

3. Any other amendatory endorsements to show the coverage required herein.

4. A notation of coverage enhancements on the Certificate of Insurance shall not satisfy these requirements – actual endorsements must be submitted.

5. All insurance coverage maintained or procured pursuant to this agreement shall be endorsed to waive subrogation against the Contracting Agency, its elected or appointed officers, agents, officials, employees, and volunteers or shall specifically allow the Contractor or others providing insurance evidence in compliance with these Specifications to waive their right of subrogation prior to a loss. The Contractor hereby waives its own right of subrogation against the

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Contracting Agency and shall require similar written express waivers and insurance clauses from each of its subcontractors.

Upon request by the Contracting Agency, the Contractor shall forward to the Contracting Agency a full and certified copy of the insurance policy(s). If Builders Risk insurance is required on this Project, a full and certified copy of that policy is required when the Contractor delivers the signed Contract for the Work.

1-07.18(5) Coverages and Limits

The insurance shall provide the minimum coverages and limits set forth below. Contractor's maintenance of insurance, its scope of coverage, and limits as required herein shall not be construed to limit the liability of the Contractor to the coverage provided by such insurance, or otherwise limit the Contracting Agency's recourse to any remedy available at law or in equity.

All deductibles and self-insured retentions must be disclosed and are subject to approval by the Contracting Agency. The cost of any claim payments falling within the deductible or self-insured retention shall be the responsibility of the Contractor. In the event an additional insured incurs a liability subject to any policy's deductibles or self-insured retention, said deductibles or self-insured retention shall be the responsibility of the Contractor.

1-07.18(5)A Commercial General Liability

Commercial General Liability insurance shall be written on coverage forms at least as broad as ISO occurrence form CG 00 01, including but not limited to liability arising from premises, operations, stop gap liability, independent contractors, products-completed operations, personal and advertising injury, and liability assumed under an insured contract. There shall be no exclusion for liability arising from explosion, collapse or underground property damage.

The Commercial General Liability insurance shall be endorsed to provide a per project general aggregate limit, using ISO form CG 25 03 05 09 or an equivalent endorsement.

Contractor shall maintain Commercial General Liability Insurance arising out of the Contractor's completed operations for at least three years following Substantial Completion of the Work.

Such policy must provide the following minimum limits:

$2,000,000	Each Occurrence
$3,000,000	General Aggregate
$3,000,000	Products & Completed Operations Aggregate
$2,000,000	Personal & Advertising Injury each offence
$2,000,000	Stop Gap / Employers' Liability each accident

1-07.18(5)B Automobile Liability

Automobile Liability shall cover owned, non-owned, hired, and leased vehicles; and shall be written on a coverage form at least as broad as ISO form CA 00 01. If the Work involves the transport of pollutants, the automobile liability policy shall include MCS 90 and CA 99 48 endorsements.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Such policy must provide the following minimum limit:

$1,000,000 Combined single limit each accident

1-07.18(5)C Workers' Compensation

The Contractor shall comply with Workers' Compensation coverage as required by the Industrial Insurance laws of the State of Washington.

(January 4, 2016 APWA GSP)

1-07.18(5)D Excess or Umbrella Liability

The Contractor shall provide Excess or Umbrella Liability insurance with limits of not less than *** 1 *** million each occurrence and annual aggregate. This excess or umbrella liability coverage shall be excess over and as least as broad in coverage as the Contractor's Commercial General and Auto Liability insurance

All entities listed under 1-07.18(2) of these Special Provisions shall be named as additional insureds on the Contractor's Excess or Umbrella Liability insurance policy.

This requirement may be satisfied instead through the Contractor's primary Commercial General and Automobile Liability coverages, or any combination thereof that achieves the overall required limits of insurance.

1-07.24 Rights of Way

Section 1-07.24 is deleted in its entirety and replaced with the following:

(April 22, 2025 APWA GSP)

Street Right of Way lines, limits of easements, and limits of construction permits are indicated in the Plans. The Contractor's construction activities shall be confined within these limits unless arrangements for use of private property are made as described below.

Generally, the Contracting Agency will have obtained, prior to bid opening, all rights of way and easements, both permanent and temporary, necessary for carrying out the work. Exceptions to this are noted in the Bid Documents or will be brought to the Contractor's attention by a duly issued Addendum.

Whenever any of the work is accomplished on or through property other than public Right of Way, the Contractor shall meet and fulfill all covenants and stipulations of any easement agreement obtained by the Contracting Agency from the owner of the private property. Copies of the easement agreements may be included in the Contract Provisions or made available to the Contractor as soon as practical after they have been obtained by the Engineer.

Whenever easements or rights of entry have not been acquired prior to advertising, these areas are so noted in the Plans. The Contractor shall not proceed with any portion of the work in areas where right of way, easements or rights of entry have not been acquired until the Engineer certifies to the Contractor that the right of way or easement is available or that the right of entry has been received. If the Contractor is delayed due to acts of omission on the part of the Contracting Agency in obtaining easements, rights of entry or right of way, the Contractor will be entitled to an extension of time. The Contractor agrees that such delay shall not be a breach of contract.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Each property owner shall be given 48 hours' notice prior to entry by the Contractor. This includes entry onto easements and private property where private improvements must be adjusted.

The Contractor shall be responsible for providing, without expense or liability to the Contracting Agency, any additional land and access thereto that the Contractor may desire for temporary construction facilities, storage of materials, or other Contractor needs. However, before using any private property, whether adjoining the work or not, the Contractor shall file with the Engineer a written permission of the private property owner, and, upon vacating the premises, a written release from the property owner of each property disturbed or otherwise interfered with by reasons of construction pursued under this contract. The statement shall be signed by the private property owner, or proper authority acting for the owner of the private property affected, stating that permission has been granted to use the property and all necessary permits have been obtained or, in the case of a release, that the restoration of the property has been satisfactorily accomplished. The statement shall include the parcel number, address, and date of signature. Written releases must be filed with the Engineer before the Completion Date will be established.

1-08 Prosecution and Progress

Section 1-08 is supplemented with the following:

(January 2026 CCPW GSP)

Preconstruction Conference

Prior to the Contractor beginning work, a preconstruction conference will be held between the Contractor, the Engineer, and other interested parties. The purpose of the preconstruction conference will be:

1. To review the initial progress schedule;
2. To establish a working understanding among the various parties associated or affected by the work;
3. To establish and review procedures for progress payment, notifications, approvals, submittals, etc.;
4. To review Training or Apprenticeship Plans, when applicable;
5. To discuss FSBE Goals when applicable.
6. To establish normal working hours for the work;
7. To review safety standards and traffic control; and
8. To discuss such other related items as may be pertinent to the work.

The Contractor shall prepare and submit at the preconstruction conference the following:

1. A breakdown of all lump sum items;
2. A preliminary schedule of working drawing submittals; and
3. A list of material sources for approval if applicable.
4. Copies of the Progress schedule
5. Contractor adopted traffic control plans or proposed changes to the traffic control plans.
6. Spill Prevention, Control, and Countermeasures (SPCC) plan
7. Stormwater Pollution Prevention (SWPP) plan based on staging provided by the Contractor
8. Updated list of subcontractors
9. Weighted wage rates for all employee classifications anticipated to be used on the project
10. Name and credentials of the Traffic Control Supervisor(s)
11. Name and credentials of the Erosion and Sediment Control Lead(s)

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

12. Copies of applications and permits from agencies required for the work.

(November 2021 CCPW GSP)

Progress Meetings

The Contractor shall schedule and attend progress meetings between the Contractor and the Engineer. The meeting frequency shall be weekly unless otherwise directed by the Engineer.

1-08.1 Subcontracting

Section 1-08.1 is supplemented with the following:

(December 30, 2022 APWA GSP, Option A)

Prior to any subcontractor or lower tier subcontractor beginning work, the Contractor shall submit to the Engineer a certification (WSDOT Form 420-004) that a written agreement between the Contractor and the subcontractor or between the subcontractor and any lower tier subcontractor has been executed. This certification shall also guarantee that these subcontract agreements include all the documents required by the Special Provision Federal Agency Inspection.

A subcontractor or lower tier subcontractor will not be permitted to perform any work under the contract until the following documents have been completed and submitted to the Engineer:

1. Request to Sublet Work (WSDOT Form 421-012), and
2. Contractor and Subcontractor or Lower Tier Subcontractor Certification for Federal-aid Projects (WSDOT Form 420-004).

The Contractor shall submit to the Engineer a completed Monthly Retainage Report (WSDOT Form 272-065) within 15 calendar days after receipt of every monthly progress payment until every subcontractor and lower tier subcontractor's retainage has been released.

The Contractor's records pertaining to the requirements of this Special Provision shall be open to inspection or audit by representatives of the Contracting Agency during the life of the contract and for a period of not less than three years after the date of acceptance of the contract. The Contractor shall retain these records for that period. The Contractor shall also guarantee that these records of all subcontractors and lower tier subcontractors shall be available and open to similar inspection or audit for the same time period.

1-08.1(7) Payments to Subcontractors and Lower-Tier Subcontractors

1-08.1(7)A Payment Reporting

Section 1-08.1(7)A is revised to read:

(March 9, 2026)

The Contractor shall report the actual amounts paid to all firms that were used as subcontractors of any tier, materials suppliers, manufacturers, regular dealers, or service providers on the Contract including all Disadvantaged, Minority, Small, Veteran, or Women's Business Enterprise firms. The following do not need reported: (1) retail sales or services that are paid for at the time of purchase; (2) payments to materials suppliers or manufacturers that are in normal course of business unless it is to a Disadvantaged, Minority, Small, Veteran, or Women's Business Enterprise firm in accordance with Section 1-07.11. The Contractor shall report this information

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

by entering it into the Contracting Agency's Diversity Management and Compliance System at: https://wsdot.diversitycompliance.com. Payments shall be reported no later than the 20th of the month for all payments made to firms the previous calendar month. For example, the Contractor shall enter all payments made to firms during the month of March into DMCS by April 20th. Payments shall be reported between execution of the Contract and the Contract Completion Date. When no Work occurred or no payments were made for a firm, the reported payment shall be zero.

The Contractor shall require all recipients of such payments to use DMCS to acknowledge their receipt of payment.

1-08.1(8) Required Subcontract Clauses

1-08.1(8)B Clauses Required in Subcontracts of All Tiers

(November 25, 2024 APWA GSP)

Item #8 in the second paragraph of Section 1-08.1(8)B is deleted.

1-08.1(9) Submittal of Executed Subcontracts

(April 22, 2025 APWA GSP, Option B)

Section 1-08.1(9) content and title are deleted and replaced with the following:

Vacant

1-08.3 Progress Schedule

1-08.3(2) General Requirements

(November 2023 CCPW GSP)

In addition to information required in Items 1 through 7, the Progress Schedule shall include the following milestones and/or activities:

***
Work by utility companies and/or their Contractors, if any.
***

1-08.3(2)A Type A Progress Schedule

Section 1-08.3(2)A is revised to read:

(February 17, 2026 APWA GSP)

The Contractor shall submit *** 5 *** copies of a Type A Progress Schedule no later than at the preconstruction conference, or some other mutually agreed upon submittal time. The schedule may be a critical path method (CPM) schedule, bar chart, or other standard schedule format. Regardless of which format used, the schedule shall identify the critical path. The Engineer will evaluate the Type A Progress Schedule and accept or return the schedule for corrections within 15 calendar days of receiving the submittal.

1-08.4 Prosecution of Work

Section 1-08.4 including title is revised to read:

(February 17, 2026 APWA GSP)

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

1-08.4 Notice to Proceed and Prosecution of Work

Notice to Proceed will be given after the Contract has been executed and the contract bond and evidence of insurance have been approved and filed by the Contracting Agency. The Contractor shall not commence with the Work until the Notice to Proceed has been given by the Engineer. The Contractor shall commence construction activities on the project site within ten days of the Notice to Proceed Date, unless otherwise approved in writing. The Contractor shall diligently pursue the Work to the Physical Completion Date within the time specified in the Contract. Voluntary shutdown or slowing of operations by the Contractor shall not relieve the Contractor of the responsibility to complete the Work within the time(s) specified in the Contract.

When shown in the Plans, the first order of Work shall be the installation of high visibility fencing to delineate all areas for protection or restoration, as described in the Contract. Installation of high visibility fencing adjacent to the roadway shall occur after the placement of all necessary signs and traffic control devices in accordance with 2-04.3. Upon construction of the fencing, the Contractor shall request the Engineer to inspect the fence. No other Work shall be performed on the site until the Contracting Agency has accepted the installation of high visibility fencing, as described in the Contract.

Section 1-08.4 is supplemented with the following:

(November 2010 CCPW GSP)

Order of Work

Unless otherwise approved by the Engineer, the Contractor shall complete the work in accordance with the construction phasing plans, the Special Provisions CONSTRUCTION UNDER TRAFFIC and TIME FOR COMPLETION, and the following:

*** Whipple Creek Bridge and Knapps Station Bridge shall not be closed at the same time. ***

1-08.5 Time for Completion

Section 1-08.5 is supplemented with the following:

(March 13, 1995)

This project shall be physically completed within *** 90 *** working days.

The third and fourth paragraphs of Section 1-08.5 are revised to read:

(February 17, 2026 APWA GSP Option A)

Contract time shall begin on the first working day following the Notice to Proceed Date.

Each working day shall be charged to the Contract as it occurs, until the Contract Work is physically complete. If substantial completion has been granted and all the authorized working days have been used, charging of working days will cease. Each week the Engineer will provide the Contractor a statement that shows the number of working days: (1) charged to the Contract the week before; (2) specified for the physical completion of the Contract; and (3) remaining for the physical completion of the Contract. The statement will also show the nonworking days and all partial or whole days the Engineer declares as unworkable. The statement will be identified as a Written Determination by the Engineer. If the Contractor does not agree with the Written Determination of working days, the Contractor shall pursue the

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

protest procedures in accordance with Section 1-04.5. By failing to follow the procedures of Section 1-04.5, the Contractor shall be deemed as having accepted the statement as correct. If the Contractor is approved to work 10 hours a day and 4 days a week (a 4-10 schedule) and the fifth day of the week in which a 4-10 shift is worked would ordinarily be charged as a working day then the fifth day of that week will be charged as a working day whether or not the Contractor works on that day.

The sixth paragraph of Section 1-08.5 is revised to read:

(February 17, 2026 APWA GSP, Option A)
The Engineer will give the Contractor written notice of the Completion Date of the Contract after all the Contractor's obligations under the Contract have been performed by the Contractor. The following events must occur before the Completion Date can be established:

1. The physical Work on the project must be complete; and
2. The Contractor must furnish all documentation required by the Contract and required by law, to allow the Contracting Agency to process final acceptance of the Contract. The following documents must be received by the Engineer prior to establishing a completion date:
   a. Certified Payrolls (per Section 1-07.9(5)).
   b. Material Acceptance Certification Documents
   c. Monthly Reports in DMCS of the amounts paid including the final payment confirmation to all firms required by Section 1-08.1(7)A if applicable
   d. Final Contract Voucher Certification
   e. Copies of the approved "Affidavit of Prevailing Wages Paid" for the Contractor and all subcontractors
   f. A copy of the Notice of Termination sent to the Washington State Department of Ecology (Ecology); the elapse of 30 calendar days from the date of receipt of the Notice of Termination by Ecology; and no rejection of the Notice of Termination by Ecology. This requirement will not apply if the Construction Stormwater General Permit is transferred back to the Contracting Agency in accordance with Section 8-01.3(16).
   g. Property owner releases per Section 1-07.24

Section 1-08.5 is supplemented with the following:

(February 2018 CCPW GSP)
Work Restrictions
Work will only be allowed from *** Monday to Friday 7:00 A.M. to 5:00 P.M. *** No work will be allowed to occur on *** a Saturday, Sunday, holiday, or outside the above listed hours. ***

Written permission from the Engineer is required, if the Contractor desires to perform work outside the above listed days or outside the above listed hours on any day. The Contractor shall apply in writing to the Engineer for such permission a minimum of 3 working days prior to the day for which the Contractor is requesting permission to work.

1-08.9 Liquidated Damages

Section 1-08.9 is revised to read:

(February 17, 2026 APWA GSP, Option A)

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Time is of the essence of the Contract. Delays inconvenience the traveling public, obstruct traffic, interfere with and delay commerce, and increase risk to Highway users. Delays also cost tax payers undue sums of money, adding time needed for administration, engineering, inspection, and supervision.

Accordingly, the Contractor agrees:

1. To pay liquidated damages in the amount of *** $950.00 *** for each working day beyond the number of working days established for Physical Completion, and

2. To authorize the Engineer to deduct these liquidated damages from any money due or coming due to the Contractor.

When the Contract Work has progressed to Substantial Completion as defined in the Contract, the Engineer may determine the Contract Work is Substantially Complete. The Engineer will notify the Contractor in writing of the Substantial Completion Date. For overruns in Contract time occurring after the date so established, liquidated damages identified above will not apply. For overruns in Contract time occurring after the Substantial Completion Date, liquidated damages shall be assessed on the basis of direct engineering and related costs assignable to the project until the actual Physical Completion Date of all the Contract Work. The Contractor shall complete the remaining Work as promptly as possible. Upon request by the Engineer, the Contractor shall furnish a written schedule for completing the physical Work on the Contract.

Liquidated damages will not be assessed for any days for which an extension of time is granted. No deduction or payment of liquidated damages will, in any degree, release the Contractor from further obligations and liabilities to complete the entire Contract.

1-09 Measurement and Payment

1-09.6 Force Account

Section 1-09.6 is supplemented with the following:

(December 30, 2022 APWA GSP)
The Contracting Agency has estimated and included in the Proposal, dollar amounts for all items to be paid per force account, only to provide a common proposal for Bidders. All such dollar amounts are to become a part of Contractor's total bid. However, the Contracting Agency does not warrant expressly or by implication, that the actual amount of work will correspond with those estimates. Payment will be made on the basis of the amount of work actually authorized by the Engineer.

1-09.9 Payments

The fourth paragraph of Section 1-09.9 is revised to read:

(July 8, 2024 APWA GSP, Option B)
Progress payments for completed work and material on hand will be based upon progress estimates prepared by the Engineer. A progress estimate cutoff date will be established at the preconstruction conference.

The initial progress estimate will be made not later than 30 days after the Contractor commences the work, and successive progress estimates will be made every month

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

thereafter until the Completion Date. Progress estimates made during progress of the work are tentative, and made only for the purpose of determining progress payment. The progress estimates are subject to change at any time prior to the calculation of the Final Payment.

The value of the progress estimate will be the sum of the following:

1. Unit Price Items in the Bid Form — the approximate quantity of acceptable units of work completed multiplied by the unit price.
2. Lump Sum Items in the Bid Form — based on the approved Contractor's lump sum breakdown for that item, or absent such a breakdown, based on the Engineer's determination.
3. Materials on Hand — 100 percent of invoiced cost of material delivered to Job site or other storage area approved by the Engineer.
4. Change Orders — entitlement for approved extra cost or completed extra work as determined by the Engineer.

Progress payments will be made in accordance with the progress estimate less:

1. Retainage per Section 1-09.9(1), on non FHWA-funded projects;
2. The amount of Progress Payments previously made; and
3. Funds withheld by the Contracting Agency for disbursement in accordance with the Contract Documents.

Progress payments for work performed shall not be evidence of acceptable performance or an admission by the Contracting Agency that any work has been satisfactorily completed. The determination of payments under the contract will be final in accordance with Section 1 05.1.

1-09.9(1) Retainage

Section 1-09.9(1) content and title is deleted and replaced with the following:

(June 27, 2011)
Vacant

1-09.11 Disputes and Claims

1-09.11(3) Time Limitation and Jurisdiction

Section 1-09.11(3) is revised to read:

(December 30, 2022 APWA GSP)
For the convenience of the parties to the Contract it is mutually agreed by the parties that all claims or causes of action which the Contractor has against the Contracting Agency arising from the Contract shall be brought within 180 calendar days from the date of final acceptance (Section 1-05.12) of the Contract by the Contracting Agency; and it is further agreed that all such claims or causes of action shall be brought only in the Superior Court of the county where the Contracting Agency headquarters is located, provided that where an action is asserted against a county, RCW 36.01.050 shall control venue and jurisdiction. The parties understand and agree that the Contractor's failure to bring suit within the time period provided, shall be a complete bar to all such claims or causes of action. It is further mutually agreed by the parties that when claims or causes of action which the Contractor asserts against the Contracting Agency arising from the Contract are filed with the Contracting Agency or initiated in court, the Contractor shall

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

permit the Contracting Agency to have timely access to all records deemed necessary by the Contracting Agency to assist in evaluating the claims or action.

1-09.13 Claims Resolution

1-09.13(3) Arbitration

1-09.13(3)A Arbitration General

The third paragraph of Section 1-09.13(3)A is revised to read:

(January 19, 2022 APWA GSP)

The Contracting Agency and the Contractor mutually agree to be bound by the decision of the arbitrator, and judgment upon the award rendered by the arbitrator may be entered in the Superior Court of the county in which the Contracting Agency's headquarters is located, provided that where claims subject to arbitration are asserted against a county, RCW 36.01.050 shall control venue and jurisdiction of the Superior Court. The decision of the arbitrator and the specific basis for the decision shall be in writing. The arbitrator shall use the Contract as a basis for decisions.

1-09.13(4) Venue for Litigation

Section 1-09.13(4) is revised to read:

(December 30, 2022 APWA GSP)

Litigation shall be brought in the Superior Court of the county in which the Contracting Agency's headquarters is located, provided that where claims are asserted against a county, RCW 36.01.050 shall control venue and jurisdiction of the Superior Court. It is mutually agreed by the parties that when litigation occurs, the Contractor shall permit the Contracting Agency to have timely access to all records deemed necessary by the Contracting Agency to assist in evaluating the claims or action.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Division 2
Temporary Features

2-01 Mobilization

Section 2-01 is deleted in its entirety, and replaced with the following:

(February 17, 2026 APWA GSP)

2-01.1 Description

This Work consists of operations and preparatory Work necessary to become ready to perform the Work or an item of Work.

2-01.3 Construction Requirements

Mobilization consists of preconstruction expenses and the costs of preparatory Work and operations performed by the Contractor typically occurring before 10 percent of the total original amount of an individual Bid Schedule is earned from other Contract items on that Bid Schedule. Items which are not to be included in the item of Mobilization include but are not limited to:

1. Portions of the Work covered by the specific Contract item or incidental Work which is to be included in a Contract item or items.
2. Profit, interest on borrowed money, overhead, or management costs.
3. Costs incurred for mobilizing equipment for force account Work.

2-01.5 Payment

Payment will be by lump sum as "Mobilization".

Based on the lump sum Contract price for "Mobilization", partial payments will be made as follows:

1. When 5 percent of the total original Bid Schedule amount is earned from other Contract items on that original Bid Schedule, excluding amounts paid for materials on hand, 50 percent of the Bid Item for mobilization on that original Bid Schedule, 5 percent of the total of that original Bid Schedule, or 5 percent of the total original Contract amount, whichever is the least, will be paid.
2. When 10 percent of the total original Bid Schedule amount is earned from other Contract items on that original Bid Schedule, excluding amounts paid for materials on hand, 100 percent of the Bid Item for mobilization on that original Bid Schedule, 10 percent of the total of that original Bid Schedule, or 10 percent of the total original Contract amount, whichever is the least, will be paid.
3. When the Substantial Completion Date has been established for the project, payment of any remaining amount Bid for mobilization will be paid.

Nothing herein shall be construed to limit or preclude partial payments otherwise provided by the Contract.

2-03 Public Convenience And Safety

2-03.3 Construction Requirements

2-03.3(1) Construction Under Traffic

The third paragraph of Section 2-03.3(1) is revised to read:

(February 17, 2026 APWA GSP)

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Accessibility to existing or temporary pedestrian push buttons shall not be impaired, if approved by the Contracting Agency activating pedestrian recall timing or other accommodation may be allowed during construction.

Section 2-03.3(1) is supplemented with the following:

(******)
Lane closures are prohibited at all times except as provided in these Special Provisions.

One lane, to be shared by traffic in each direction, will be permitted with flagger control during work hours. Two lanes, one in each direction, will be required on all roadways between the hours of *** 7:00 AM and 8:30 AM and 4:00 PM and 6:00 PM *** and during non-work hours.

(******)
Whipple Creek Bridge No. 011 Closure
The Contractor will be permitted one (1) full roadway closure of NW 179th Street at the Whipple Creek Bridge No. 011 for construction of the bridge improvements at this location. The detour shall be in place before the closure begins. The full roadway closure shall be a maximum of 20 working days. Once the closure begins, the Contractor shall immediately begin work within the closure area. Access to adjacent properties shall be maintained at all times during the closure. The Contractor shall notify the Engineer a minimum of 15 working days in advance of the road closure.

(******)
Knapps Station Bridge No. 012 Closure
The Contractor will be permitted one (1) full roadway closure of NW Krieger Road at the Knapps Station Bridge No. 012 for construction of the bridge improvements at this location. The detour shall be in place before the closure begins. The full roadway closure shall be a maximum of 20 working days. Once the closure begins, the Contractor shall immediately begin work within the closure area. Access to adjacent properties shall be maintained at all times during the closure. The Contractor shall notify the Engineer a minimum of 15 working days in advance of the road closure.

(******)
Carson Bridge No. 063 Closure
The Contractor will be permitted one (1) full roadway closure of NE 67th Avenue at the Carson Bridge No. 063 for construction of the bridge improvements at this location. The detour shall be in place before the closure begins. The full roadway closure shall be a maximum of 20 working days. Once the closure begins, the Contractor shall immediately begin work within the closure area. Access to adjacent properties shall be maintained at all times during the closure. The Contractor shall notify the Engineer a minimum of 15 working days in advance of the road closure.

(March 2023 CCPW GSP)
Contractor employee parking areas shall be approved by the Engineer.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

2-04 Temporary Features

2-04.3 Construction Requirements

2-04.3(1) Traffic Control Management

Section 2-04.3(1) is supplemented with the following:

(September 2, 2025)

Work Zone Safety Contingency

Enhancements to improve the effectiveness of the accepted traffic control plans to increase the safety of the work zones shall be discussed on a weekly basis between the Contractor and the Contracting Agency. Enhancements shall be mutually agreed upon by the Contractor and Engineer prior to performing any Work to implement the enhancement.

Enhancements do not include the use of Uniformed Police Officers or WSP, address changes to the allowed work hour restrictions, or changes to the staging plans in the Contract (if applicable). If allowed by the Engineer, these items will be addressed in accordance with Section 1-04.4.

The Contractor shall be solely responsible for submitting any traffic control plan revision to implement the enhancement in accordance with Section 2-04.3(2).

(March 9, 2026)

The Traffic Control Supervisor shall be certified by one of the following:

The American Traffic Safety Services Association
15 Riverside Parkway, Suite 100
Fredericksburg, Virginia 22406-1022
Training Dept. Toll Free (877) 642-4637
Phone: (540) 368-1701
https://atssa.com/training

Evergreen Safety Council
12545 135th Ave. NE
Kirkland, WA 98034-8709
1-800-521-0778
https://www.esc.org

Integrity Safety
13912 NE 20th Ave.
Vancouver, WA 98686
(360) 574-6071
https://www.integritysafety.com

K&D Services Inc.
2719 Rockefeller Ave.
Everett, WA 98201
(800) 343-4049
https://www.kndservices.net

The Northwest Laborers-Employers Training Trust

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

27055 Ohio Ave.
Kingston, WA 98346
(360) 297-3035
https://www.nwlett.edu

Trafficorp
5077 N Bldg Center Drive
Coeur d'Alene, ID 83815
(208) 665-4683
https://trafficorp.com/contact-us/

US Safety Alliance
(904) 705-5660
https://www.ussafetyalliance.com

2-04.5 Payment

2-04.5(2) Item Bids with Lump Sum for Incidentals

Section 2-04.5(2) is supplemented with the following:

(November 2, 2022)
"Work Zone Safety Contingency", by force account.

All costs as authorized by the Engineer will be paid for by force account as specified in Section 1-09.6.

For purpose of providing a common proposal for all bidders, the Contracting Agency has entered an amount for the item "Work Zone Safety Contingency" in the Proposal to become a part of the Contractor's total bid.

The Engineer may choose to use existing bid items for the implementation of the agreed upon enhancement.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Division 3
Earthwork

3-01 Clearing, Grubbing, and Roadside Cleanup
3-01.2 Disposal of Usable Material and Debris
3-01.2(1) Disposal Method No. 1 - Open Burning

Section 3-01.2(1) is supplemented with the following:

(1997 CCPW GSP)
Disposal Method No. 1, Open Burning, as specified in Section 3-01.2(1) will not be allowed on this project.

3-01.3 Construction Requirements
3-01.3(1) Clearing

Item 4 of Section 3-01.3(1) is revised to read:

(January 2016 CCPW GSP)
4. Leave standing and protect trees and vegetation not indicated to be removed.

Division 6
Structures

6-01 General Requirements for Structures
6-01.5 Vacant

Section 6-01.5 is re-titled and revised to read:

(******)

Work Access

The Contractor shall construct work access to accommodate all work within the wetted perimeter, or vertically above the sensitive area, of Whipple Creek and Mill Creek, as shown in the plans or staked by the Engineer. The Contractor shall construct and remove the work access in accordance with all environmental regulations and permits, including those specified in Sections 1-07.5 and 1-07.6.

Submittals

The Contractor shall submit Type 3 Working Drawings of the work access, except that if the Contractor chooses an access alternative using a work trestle structure, the Working Drawings shall be Type 3E. The Contractor shall design the work access structure to withstand all applicable loads in accordance with accepted design codes. The Contractor shall specify the design code(s) in the design calculations and working drawings.

The Contractor shall include information with the work access submittal on the construction equipment that will use the work access. The Contractor shall specify the type and model of construction equipment to be used, and shall include equipment catalogue cuts with capacities and geometry. The Contractor shall include anticipated wheel or track loads, axle spacings, outrigger geometry and reactions, crane pick angles and reach, and other equipment details.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

6-02 Concrete Structures

6-02.1 Description

Section 6-02.1 is supplemented with the following:

(******)

Concrete Spall Repair

This work consists of the patching of concrete spalls on the bottom of the cast-in-place superstructure of the existing Rock Creek Bridge No. 0096 with Grout Type 2.

Epoxy Resin Injection

This work consists of injecting existing concrete cracks on the bottom of the cast-in-place superstructure of the existing Rock Creek Bridge No. 0096 with Epoxy Resin.

FRP Reinforcement

This work consists of furnishing and installing a Fiber Reinforced Polymer (FRP) composite system on existing bridge elements to increase capacity. The work also includes preparing the existing concrete surface for the FRP system and applying a surface finish to the final composite surface. The Contractor shall install the FRP composite system with all components provided through a single system provider.

6-02 Concrete Structures

6-02.1 Description

Section 6-02.1 is supplemented with the following:

(******)

Concrete Spall Repair

This work consists of the patching of concrete spalls on the bottom of the cast-in-place superstructure of the existing "Bridge No. ____" with Grout Type 2.

Epoxy Crack Sealing

This work consists of injecting existing concrete cracks on the bottom of the cast-in-place superstructure of the existing "Bridge No. ____" with Epoxy Resin.

FRP Reinforcement

This work consists of furnishing and installing a Fiber Reinforced Polymer (FRP) composite system on existing bridge elements to increase capacity. The work also includes preparing the existing concrete surface for the FRP system and applying a surface finish to the final composite surface. The Contractor shall install the FRP composite system with all components provided through a single system provider.

6-02.2 Materials

Section 6-02.2 is supplemented with the following:

(******)

Concrete Spall Repair

The Contractor shall use Grout Type 2 for use on vertical and overhead patching applications. The patching material shall also be compatible with the FRP system.

(******)

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Epoxy Crack Sealing

The Contractor shall use an Epoxy Resin that is compatible with the FRP composite system selected for this project. The Epoxy Resin shall be a two-part type, low viscosity epoxy adhesive material containing 100% solids and shall meet or exceed the following characteristics when tested in accordance with the following standards:

1. Characteristics of Components:
    a. Component A – shall be a blend of modified epoxy resins.
    b. Component B – shall be a blend of modified amine curing agents.
2. Test Method Requirements:
    a. Component A – Brookfield RVT, 700 maximum; Viscosity @ 77 +/- 3 degrees F., cps; Spindle No. 2 @ 20 rpm.
    b. Component B – Brookfield RVT, 240 maximum; Viscosity @ 77 +/- 3 degrees F., cps; Spindle No. 2 @ 20 rpm.
3. Properties of Combined Components: When mixed in the ration of two parts Component A to one part Component B by volume; or 100 parts Component A to 44 parts Component B by weights, shall be:
    a. Potlife, 60g @ 77 +/- 3 degrees F., minutes; 25 minutes maximum.
4. Properties of the Cured Adhesive: When cured for seven days @ 77 +/- 3 degrees F., unless otherwise specified, shall be:
    a. Ultimate Tensile Strength: ASTM D638; 8000 minimum.
    b. Compressive Yield Strength, psi: ASTM D695; 15,000 minimum.
    c. Heat Deflection Temperature: ASTM D648; 130 F. minimum.

Test specimens must be cured in a manner such that the peak exothermic temperature of the adhesive does not exceed 77 degrees F.

The Contractor shall submit a Manufacturer's Certificate of Compliance to the Engineer confirming that the materials are both compatible with the FRP system and that they conform to the material properties specified above.

(******)

FRP Reinforcement Composites System

Fiber reinforced polymer (FRP) composites system shall consist of dry, uni-directional, reinforced-fiber woven sheets installed with a polymer saturating resin using a wet lay-up technique. The FRP system shall conform to one of the following systems as produced by one of the corresponding manufacturers:

System 1	
Product	Manufacturer
Tyfo SCH 41 composite With Tyfo S epoxy	Fyfe Company, LLC 4995 Murphy Canyon Road Suite 110 San Diego, CA 92123 (858) 642 0694 www.fyfeco.com

System 2	
Product	Manufacturer
MBrace FIB 300/50CFS or FIB 600/50 CFS composite with	BASF Building Systems 889 Valley Park Drive

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

MBrace primer, putty, and saturant	Shakopee, MN 55379 (800) 243 6739 www.buildingsystems.basf.com

System 3

Product	Manufacturer
REPLARK 30/L700S-LS with L700S-LS epoxy	Mitsubishi Chemical, USA One North Lexington Ave, White Plains, NY 10601 (914) 286 0360

System 4

Product	Manufacturer
UT70-30/L700S-LS with L700S-LS epoxy	Toray Carbon Fibers America, Inc. 700 Parker Square, Suite 275 Flower Mound, TX 75028 (972) 899 2930 www.toray.com

System 5

Product	Manufacturer
CSS-CUCF11 with CSS-EP/ES Epoxy	Simpson Strong-Tie (800) 999 5099 www.strongtie.com/RFP

System 6

Product	Manufacturer
SikaWrap Hex 103C with Sikadur 300/Hex300 epoxy	Sika Corporation 201 Polito Avenue Lyndhurst, NJ 07071 (201) 933 8800 www.sikausa.com

System 7

Product	Manufacturer
RenewWrap ESR CF335 with RenewWrap ESR Saturant	Geotree Solutions (855) 655 6750 www.geotreesolutions.com

FRP composites for the corresponding system shall conform to the following requirements:

FIBER REINFORCED POLYMER COMPOSITE PROPERTIES

Property	ASTM *	System 1	System 2	System 3	System 4	System 5	System 6	System 7
Min. Dry Ult. Tensile Strength, primary fiber direction, ksi	D3039	580	550	500	545	670	550	700

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Min. Ult. Elongation, percent	D3039	1.70	1.67	1.35	1.56	1.90	1.50	1.12
Minimum Tensile Modulus of primary fibers, based on dry fiber thickness, ksi	D3039	33,400	33,000	31,200	28,800	37,000	34,000	33,400
Min. Fiber Volume percent	D3171	20	20	20	20	20	20	20
Min. Glass Transition Temperature, F	D3418 or D4065	140	140	140	140	140	140	145
Short Beam Shear ksi	D2344	4.4	6.9	6.4	6.9	-	6.3	-
Dry Fiber Thickness per layer, inch		0.0065	0.0065	0.0065	0.0065	0.0081	0.0135	0.0065

* Subject to the approval of the Engineer, other non-ASTM test methods, such as those published by Suppliers of Advanced Composite Materials Association (SACMA) or the manufacturer's published Quality Control Procedures may be used when equivalency and suitability have been documented.

Fiber sheets shall be composed of unidirectional polyacrylonitrile (PAN) based continuous sheet carbon fiber.

The Contractor shall submit a Manufacturer's Certificate of Compliance to the Engineer, in accordance with Section 1-06.3, confirming that the composite fabric for the system chosen for this project conforms to the material properties specified above.

Repair mortar and putty, epoxy resin primer, adhesive, top coat, and finish paint coating shall be as recommended by the FRP manufacturer and as specified in the FRP Retrofit Plan as approved by the Engineer.

Finish paint coat shall be acrylic based. Color of the finish coat shall be approved by the Engineer and shall match as closely as possible the color of the existing concrete.

6-02.3 Construction Requirements

Section 6-02.3 is supplemented with the following:

(******)

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Concrete Spall Repair

Sounding

Prior to removal of concrete, the Contractor shall sound the concrete surfaces to identify delaminated concrete. The Contractor shall establish and clearly mark the limits of concrete removal based on the results of the sounding and visual inspection. The marked areas may be reviewed by the Engineer before concrete removal begins.

Preparation of Repair Area

Spalled, deteriorated, damaged or defective concrete as shown on the plans, required by the specifications, or as directed by the Engineer, shall be removed. The Contractor shall saw cut the outer perimeter of the repair area ½" deep or as directed by the Engineer. Feathered edges will not be acceptable. Concrete shall be removed a minimum of one inch beyond and around the existing reinforcing steel to permit new construction to bond the entire periphery of the reinforcing steel.

The Contractor shall remove all areas of unsound concrete by chipping or other approved methods. Only chipping hammers of the 30 pound class or less shall be used. The Contractor shall take care to ensure that the existing reinforcing steel is not damaged during saw cutting and removal operations. Any damage caused by the Contractor to any portion of the structure not intended for repair shall be repaired in kind by the Contractor at the Contractor's expense.

Immediately prior to placing the Grout Type 2, the Contractor shall thoroughly clean the existing concrete surface to remove all paint, grease and debris. Unless otherwise specified by the commercial mixture manufacturer, the existing surface shall be damp and all free water shall be removed prior to placement of the required material. A compatible bonding agent shall be sued if recommended by the concrete patching material manufacturer.

Placing and Finishing

The concrete spall Grout Type 2 shall be mixed and applied in accordance with the manufacturer's recommendations.

The Contractor shall place the repair mortar such that the existing surface profile is restored to the original dimensions. Any deviations of ¼" or greater from the repaired areas to the existing surface shall be repaired by the Contractor at the Contractor's expense.

The Contractor shall apply a finish to a level that is similar to the adjacent existing concrete surfaces as directed by the Engineer.

Curing

Curing shall be in accordance with the manufacturer's recommendations or as otherwise directed by the Engineer.

Storage and Handling

Storage and handling of all components of the patching system shall conform to the manufacturer's recommendations as approved by the Engineer.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

All materials shall be used and installed before the shelf life expiration date. All materials for which the shelf life date has been reached and surpassed shall be removed from the project site.

(******)

Epoxy Crack Sealing

General

All existing cracks in the slabs with a width greater than or equal to 0.015 inches shall be pressure injected with epoxy in accordance with ACI 224.1R-07. Crack width determination shall be taken a minimum of 1/8 inch below the concrete surface using a measuring device capable of penetrating into the crack.

Equipment

1. Type. The equipment used to meter and mix the two injection adhesive components and inject the mixed adhesive into the crack shall be portable, positive displacement type pumps with interlock to provide positive ration control of exact proportions of the two components at the nozzle. The pumps shall be electric or air powered and shall provide in-line metering and mixing. The same manufacturer shall be used for both the injection equipment and the epoxy resin adhesive.
2. Discharge Pressure. The injection equipment shall have automatic pressure control capable of discharging the mixed adhesive at any pre-set pressure up to 200 psi + 5 psi and shall be equipped with a manual pressure control override. For injection of the gel epoxy, the equipment shall be equipped with the above features and be able to pump at up to 5,000 psi.
3. Ratio Tolerance. The equipment shall have the capability of maintaining the volume ratio for the injection adhesive prescribed by the manufacturer of the adhesive within a tolerance of + 5% by volume at any discharge pressure up to 200 psi. For gel epoxies, the ratio will be checked by weight at up to 5,000 psi.
4. Automatic Shut-Off Control. The injection equipment shall be equipped with sensors on both the Component A and B reservoirs that will automatically stop the machine when only one component is being pumped to the mixing head.

Surface Preparation

Installation of epoxy shall not proceed until contaminants capable of interfering with their adhesion are removed from joint substrates.

Surfaces adjacent to cracks or other areas of application shall be cleaned of dirt, dust, grease, oil or other foreign matter detrimental to bond of epoxy injection surface seal system.

Entry ports shall be provided along the crack at intervals of not less than the thickness of the concrete member at that location.

Surface seal material shall be applied to the face of the crack or end. For through cracks, surface seal shall be applied to both faces.

Enough time for the surface seal material to gain adequate strength shall pass before proceeding with the injection.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Installation and Application

Both sides of the crack shall be sealed with an epoxy mortar or oil-free clay, leaving small holes through which epoxy resin shall be injected. 1/8" or ¼" diameter tubing may be used to form holes. Holes shall be 2"-4" long, roughly 8" apart.

Injection of epoxy adhesive shall begin at lower entry port and continue until there is an appearance of epoxy adhesive at the next entry port adjacent to the entry port being pumped.

When epoxy adhesive travel is indicated by appearance at the next adjacent port, injection shall be discontinued on the entry port being pumped, and epoxy injection shall be transferred to next adjacent port where epoxy adhesive has appeared.

Epoxy adhesive injection shall be continuously performed until cracks are completely filled.

If port to port travel of epoxy adhesive is not indicated, the Contractor shall stop work immediately and notify the Engineer.

When cracks or joints are completely filled, epoxy adhesive shall be cured for sufficient time to allow removal of injection of port sealing devices.

Storage and Handling

Storage and handling of all components of the epoxy system shall conform to the manufacturer's recommendations as approved by the Engineer.

All materials shall be used and installed before the shelf life expiration date. All materials for which the shelf life date has been reached and surpassed shall be removed from the project site.

(******)

Fiber Reinforced Polymer (FRP) Composite System

Submittals

The Contractor shall submit Type 3E Working drawings showing the FRP Retrofit Plan to the Engineer for approval in accordance with Section 6-01.9. The Contractor shall not begin FRP retrofit work at the site until receiving the Engineer's approval of the FRP Retrofit Plan.

The FRP Retrofit Plan shall include, but not be limited to, the following:

1. Identification of the FRP composite system, product, and manufacturer selected for use in this project from the list in Section 6-02.2 of these Special Provisions. Only one FRP composite system, product, and manufacturer shall be used in this project.
2. Identification of the FRP composite system manufacturer's technical representative(s) assigned to be present at the project site, along with documentation of the training in the installation of FRP composite materials completed by these technical representatives.
3. Identification of the Contractor's personnel responsible for conducting the Quality Control inspections.
4. A sample copy of the Daily Installation Data Log.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

5. Identification of the independent laboratory, with location and contact information, responsible for performing the Contractor's Quality Control and Job Control testing.
6. Shop drawings and design calculations.
7. Working Drawings of access platforms and other means and methods used to access the site and complete the work and contain and prevent debris from entering the stream and streambed below.
8. Material safety data sheets (MSDS) for all materials sued to complete the FRP composite system.
9. Material technical data sheets, and supplemental sheets as required, for all materials used to complete the FRP composite system, including information on, but not limited to, the following:
    a. Material storage and handling requirement.
    b. Shelf life of all materials.
    c. Equipment required for surface preparation, mixing of the FRP composite system components, application of the FRP composite system components, curing of the applied and installed FRP composite system, and coating of the applied and installed FRP composite system.
    d. Equipment to be used to remove spalled or unsound concrete.
    e. Step by step description of the process required for surface preparation, mixing of components, application of components, curing of the applied and installed system, and coating the applied and installed system.
    f. Environmental restriction and conditions (temperature, humidity, etc.) required to be present during mixing, application and curing of the FRP composite system.
    g. Containment, collection, and disposal procedures for all debris and waste generated by surface preparation and the process of installing the FRP composite system assuming all waste is captured and disposed of at an approved off-site location.
10. Methods and equipment used to fabricate or core the Job Control and Check test samples taken for Contractor Quality Control Testing.
11. Materials and equipment used to provide an enclosure and to environmentally control the enclosed volume, if the Contractor elects to enclose the work area(s).
12. Color of final surface finish. (Finished surface shall closely match the existing concrete sections).

Design Calculation Content Requirements

The design and analysis is to be prepared by the Contractor's or material supplier's engineer based on the FRP composites system product chosen. The design parameters are:

1. Design shall be in accordance with the AASHTO Guide Specifications For Design of Bonded FRP Systems For Repair And Strengthening Of Concrete Bridge Elements, 2nd Edition, 2023 and the AASHTO LRFD Bridge Design Specifications, 10th Edition, 2024, with current interim specifications.
2. Use the plan specified capacities with appropriate design factors.
3. Use one of the pre-approved FRP products as shown in Section 6-02.2 of these Special Provisions.
4. For Flexural Strengthening, the maximum usable composite strain at the FRP/concrete interface shall be no greater than 0.005 inch/inch.
5. Termination points of the Flexural FRP reinforcement layers shall be tapered and provided with fiber anchors. The outermost layer shall be terminated no less than 12

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

inches beyond the limits shown in the plans. Each successive layer shall be terminated a minimum of 12 inches beyond the previous layer.

6. Termination points of the Shear FRP reinforcement shall be as shown in the plans.
7. Calculations shall indicate the development length of FRP reinforcement as shown in the plans.

Working Drawing Content Requirements

All design details shown in the working drawings shall be from the selected design details of the FRP composite system details (plies, wraps, fiber or winding thickness, fiber volume, fiber orientation, composite thickness, etc.). The working drawings shall include all details, dimensions, quantities, materials, and cross sections necessary to complete the FRP composite system and product selected to provide the minimum additional factored moment resistances and shear resistance specified in the Plans for the bridge. The working drawings shall include the following details:

1. Dry sheet details.
2. Details of joints and ends of fiber construction.
3. Details of transitions in composite thickness.
4. Method and equipment to be used to achieve an approximate one inch radius rounding at all concrete corners.
5. Resin mix ration by weight and by volume.
6. Pot life of mixed components at manufacturer specified environmental conditions.
7. Esin gel time at manufacturer specified environmental conditions.
8. Details of access platforms and other means and methods used to access the site and contain and prevent debris from entering the stream and streambed below.

FRP-Preconstruction Conference

An FRP-preconstruction conference shall be held, at least one working day prior to the Contractor's beginning the FRP retrofit work at the site, to discuss safety methods, repair procedures, materials, personnel and equipment to be used. Those in attendance shall include:

1. (Representing the Contractor) The superintendent, on site supervisor, and all crew members in charge of the FRP retrofit work, and the FRP composite manufacturer's technical representative; and
2. (Representing the Contracting Agency) The Project Engineer and key inspection personnel.

If the Contractor's key personnel change between any work operations, an addition conference may be help.

Quality Control Program

The Contractor shall conduct a quality control program that includes, but is not limited to, the following:

1. Inspection of all materials to assure conformity with contract requirements, and to assure that all materials are undamaged and conform to Section 1-06.1.
2. Inspection of all surface preparation prior to FRP composite system installation.
3. Inspection and monitoring of the automatic proportioning and mixing equipment used to proportion and mix the epoxy resin.
4. Inspection of work in progress to assure compliance with the manufacturer's recommendations.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

5. Inspection of all work completed including sounding all repairs to check for debonding and correction of all defective work. All costs in connection with corrections to defective work shall be at no additional expense to the Owner.
6. Maintain a Daily Inspection Data Log.
7. Present at the work site of an FRP composite system manufacturer's technical representative. The FRP composite system manufacturer's technical representative shall be present at the preconstruction conference, shall be present at the work site for at least the first full day of FRP composite fabric installation, and shall be readily available for contact to resolve project specific technical issues for the full duration of the project when not present at the work site.

Handling and Storage

Handling and storage of all components of the FRP composite system shall conform to Section 1-06.4 and the FRP retrofit plan as approved by the Engineer.

All materials shall be used and installed before the shelf life expiration date. All materials for which the shelf life date has been reached and surpassed shall be removed from the project site.

General Preparation for Application

1. Environmental Conditions. Unless otherwise specified by the FRP composite manufacturer in the FRP retrofit plan as approved by the Engineer, the ambient and epoxy temperature, relative humidity, and concrete surface temperature at the time of FRP composite application shall be as follows:

   Ambient Temperature Range: 45 degrees F to 90 degrees F

   Epoxy Resin Temperature Range: 45 degrees F to 90 degrees F

   Relative Humidity: Less than 90 percent

   Concrete Surface Temperature: Greater than 5 degrees F above the dew point

   Subject to the approval of the Engineer, the Contractor may erect enclosures around the area receiving the FRP composite system and provide a heating system in order to facilitate application, curing and coating of the FRP composite system under a controlled contained environment. The materials and equipment used to provide the enclosure, to control the contained volume, and provide heat, shall be submitted to the Engineer for approval.

2. Concrete Surface. The concrete surface receiving the FRP composite system shall be completely dry and free of dust and debris, including dust and debris created by surface preparation activities.

Concrete Soundness

The tensile strength of the prepared concrete surface shall be verified by conducting a pull-off adhesion test in accordance with ICRI Guideline 03739 and have a minimum concrete substrate tensile strength of 200 psi. A minimum of one test shall be conducted at a location determined by the Engineer.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Surface Preparation

The concrete surface to receive the FRP system shall be prepared to a minimum concrete surface profile (CSP) 3 in accordance with ACI 546R, ICRI Guideline 03730 and the manufacturer's recommendations. Concrete surfaces specified to receive the FRP composite system shall be sound concrete free from fins, sharp edges and protrusions that, in the opinion of the Engineer will cause damage to the FRP fibers or that will cause voids between the FRP wrap and the concrete. Voids shall be defined as volumes greater than ½ inch in diameter by 1/8 inch deep.

Spalled or unsound concrete within the area specified to receive the FRP composite system shall be removed, in accordance with the FRP retrofit plan as approved by the Engineer, prior to performing any other surface preparation activities.

Existing uneven surfaces within the application area, including voids, shall be filled with epoxy or epoxy-based filler compatible with the FRP composite system. Flat surfaces of girders shall be filled straight from corner to corner or made slightly convex.

Concrete corners shall be broken by light grinding or another method specified in the FRP retrofit plan as approved by the Engineer to achieve an approximate one inch radius rounding.

Epoxy Injection of Cracks

Existing cracks in the precast slabs shall be pressure injected with epoxy in accordance with Section 6-02.3(101) of these special provisions.

Applying Resin Primer

Following surface preparation, primer shall be prepared and applied in accordance with the manufacturer's recommendations. The primer shall be compatible with the FRP composite system, product and manufacturer selected.

Applying the Fabric, Resin Overcoat, and Curing

Components of the epoxy resin shall be proportioned, mixed, and applied in accordance with the manufacturer's recommendations as specified in the FRP Retrofit Plan as approved by the Engineer. If the system manufacturer requires automatic proportioning and mixing equipment, the Contractor's Quality Control Program shall include provisions for monitoring the accuracy of the automatic proportioning and mixing.

The fabric composite shall be applied to the resin primed surface within one hour after the resin primer has been mixed.

The epoxy resin and the fabric composite shall be measure, combined, and applied uniformly onto the resin primed surface at the rates specified in the FRP retrofit plan as approved by the Engineer.

The fabric composite shall be applied to the surface by wrapping, using methods that produce a uniform constant tensile force that is distributed across the entire width of the fabric.

Successive layers of the fabric composite shall be applied before the gelation of the previous layer of epoxy, to ensure complete bond between the layers. If the epoxy gels prior to the application of the subsequent layer, a seven day cure, followed by light

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

abrasive blasting, cleaning with fresh water, and drying, is required prior to restarting application of layers.

The primary fibers of the fabric composite shall not deviate more than ½ inch from a line measured parallel to the horizontal or vertical direction of fibers in each lift.

The epoxy application rate for each layer of fabric composite shall be such as to ensure complete saturation of the fabric. Gaps between adjoining fabric layers shall be filled with epoxy. Undulations in the surfaces of the fabric composite as applied to the surface shall not exceed ¼ inch per foot in any direction. The cured composite shall have uniform thickness and density, and bond between layers.

Fiber sheets may be lap spliced in the direction of fibers in accordance with the manufacturer's recommendations. When lap splicing in the direction of fibers, the length of lap splice shall be such that the full tensile strength of the carbon fiber sheets is maintained across the splice. The minimum lap splice length shall be six inches.

Entrapped air beneath each layer of fabric composite shall be released or rolled out before the epoxy sets, and each individual fabric layer and ending of composite shall be firmly bedded and adhered to the preceding layer or substrate.

The Contractor shall premix and apply saturating resin overcoat in accordance with the manufacturer's application instructions.

The finished FRP composite application shall be cured in accordance with the manufacturer's application instructions. The installed FRP shall be protected from rain, dust, sand and other deleterious material during curing. The external FRP shall not be disturbed for a minimum of 24 hours.

Contractor Quality Control Operations and Repair of Deficient Work
Daily Installation Data Log

The Contractor's Quality Control personnel shall maintain a daily installation data log. The log shall document materials traceability and process records for each FRP composite application location, and shall include, but not be limited to, the following:

1. Identification of repair area and construction and installation requirements with accompanying FRP Retrofit Plan working drawing details as approved by the Engineer, or references thereto.
2. Materials information including product description, date of manufacture, and lot or batch identification.
3. Fabrication, inspection, and verification data for the manufacturing and construction operations, including, but not limited to, the following:
    a. Lists of materials and quantities used during each shift.
    b. Wrap counts.
    c. Composite thickness measurements.
    d. Installation time per slab.
    e. Ambient temperature and relative humidity readings at eh beginning, middle, and end of each FRP installation shift.
    f. Curing process including full documentation of time and temperature relationship during the curing period through to final cure.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

g. Temperature and thickness measurements of the finish epoxy coating applied after curing.

The Contractor shall keep the Daily Installation Data Log available for review by the Engineer upon the Engineer's request, and shall submit the daily installation data log to the Engineer at eh completion of construction and installation operations for each day's production.

Contractor Quality Control Testing

The Contractor shall take fabric composite test samples and test cores of production composite casing for quality control testing at the Independent Testing Laboratory. Unless otherwise approved by the Engineer, the Contractor shall take all fabric composite test samples and test cores in the presence of the Engineer.

The Contractor shall utilize an Independent Testing Laboratory to perform a minimum of two random field pull-off tests (ASTM D7522) every 500 square feet of finished FRP surface installed. The Contractor shall repair the areas damaged by the pull-off tests by applying an additional layer of FRP over the test area, or by filling with a system compatible resin and finishing smooth. If the random pull-off tests fail to meet the established criteria, the section shall be repaired or replaced at the Contractor's expense.

The Independent Testing Laboratory shall prepare two sample laminate panels in accordance with ASTM 3039. Panels shall be 12" x 12". The Contractor's Independent Testing Laboratory shall prepare test specimens and perform tensile tests, in accordance with ASTM 3039, for one of each pair of sample laminate test panels. The second panel shall be held in reserve in case test results on the first panel do not meet the specified performance criteria. A copy of the results of all testing completed by the Independent Testing Laboratory shall be submitted to the Engineer within 30 calendar days of the submittal of the samples to the laboratory. If the sample test sections do not mee the established criteria for this test, the 1,000-foot section represented by the test shall be repaired or replaced at the Contractor's expense.

All samples shall be placed in labeled and sealed polyethylene bags prior to shipment to the Independent Testing Laboratory. The label shall identify, at a minimum, the precast section number and date of coring.

Contractor Quality Control Inspection and Repair of Deficient Work

The Contractor shall inspect the completed work against the following criteria:

1. The completed work shall be inspected for defects consisting of external abrasions or blemishes, delamination, voids, external cracks, chips, cuts, loose fibers, foreign inclusions, depressible raised areas, fabric wrinkles, and damage from weather, humidity and moisture.
2. Each layer shall have full contact with the concrete surface or subsequent layers, subject to the following replacement and repair requirements:
3. All defects or voids with a dimension greater than 1-1/2 inches, defect areas greater than one square inch, and defect areas with any dimension greater than one inch within one foot of another defect area of similar or larger size, shall be repaired or replaced as specified by the Engineer.
4. Surfaces of horizontal joints shall be flush with adjacent surfaces.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

5. Undulations and sags that do not conform to previously specified tolerances shall be repaired or replaced as specified by the Engineer.
6. Within either the full slab length, or any 10 feet of slab length, whichever is smaller, composite slabs with a total number of 10 or more defects of any size shall be repaired or replaced as specified by the Engineer.

All defects found by the Contractor's quality control inspection and those found by Owner inspection, and all defective materials indicated by quality control test results not conforming to specified material and installation requirements, shall be repaired or removed and replaced in accordance with section 1-07.13. All repairs shall be completed and cured, and shall have been inspected and approved by the Engineer, prior to preparing the surfaces for painting.

Finish Coating
Protective coating shall be applied in accordance with the Manufacturer's recommendations.

6-02.3(24) Reinforcement

6-02.3(24)C Placing and Fastening
Section 6-02.3(24)C is supplemented with the following:

(September 8, 2020)
Drilling Holes for, and Setting, Steel Reinforcing Bar Dowels
Where called for in the Plans, holes shall be drilled into existing concrete to the size and dimension shown in the Plans. The Contractor may use any method for drilling the holes provided the method selected does not damage the concrete and the steel reinforcing bar that is to remain. Core drilling will be required when specifically noted in the Plans.

The Contractor shall exercise care in locating and drilling the holes to avoid damage to existing steel reinforcing bars and concrete. Location of the holes may be shifted slightly with the acceptance of the Engineer in order to avoid damaging the existing steel reinforcing bars. All damage caused by the Contractor's operations shall be repaired by the Contractor in accordance with Section 1-07.13.

Steel reinforcing bars shall be set into the holes noted in the Plans with epoxy resin. The holes shall be cleaned before placing the resin.

The Contractor shall demonstrate, to the satisfaction of the Engineer, that the method used for setting the steel reinforcing bars completely fills the void between the steel reinforcing bar and the concrete with epoxy resin. Dams shall be placed at the front of the holes to confine the epoxy and shall not be removed until the epoxy has cured in the hole.

6-02.4 Measurement

Section 6-02.4 is supplemented with the following:

(August 6, 2012)
Epoxy crack sealing will be measured by the linear foot along the sealed crack at the concrete surface.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

(******)
"Br. Rehab. – Whipple Creek Bridge No. 011" contains the following approximate quantities of materials and work:

Concrete Class 4000		11	CY
Steel Reinforcing Bar		2,600	LB
Core Drill	392	EA	
Epoxy Crack Sealing		0	LF

"Br. Rehab. – Knapps Station Bridge No. 012" contains the following approximate quantities of materials and work:

FRP Strengthening	885	SF	
Final Surface Finish	885	SF	
Epoxy Crack Sealing		40	LF
Concrete Spall Repair		20	SF

"Br. Rehab. – Carson Bridge No. 063" contains the following approximate quantities of materials and work:

Concrete Class 4000		10	CY
Steel Reinforcing Bar		4,500	LB
Core Drill	210	EA	

The quantities are listed only for the convenience of the Contractor in determining the volume of work involved and are not guaranteed to be accurate. The prospective bidders shall verify these quantities before submitting a bid. No adjustments other than for accepted changes will be made in the lump sum Contract price for "BR Rehab. - _____ Bridge No. _____" even though the actual quantities required may deviate from those listed.

6-02.5 Payment

Section 6-02.5 is supplemented with the following:

(******)
"BR. Rehab. - _____ Bridge No. _____", lump sum.
The lump sum contract price for "Br. Rehab. - _____ Bridge No. _____" shall be full pay for constructing the bridge rehabilitation work, including providing construction access to the bridge, containment measures, reconstruction of the existing reinforced concrete bridge deck, and reconstruction of the existing asphalt bridge deck overlay as shown in the plans.

(June 26, 2000)

Bridge and Structures Minor Items

For the purpose of payment, such bridge and structures items as *** grout, butyl rubber sheeting, adhesive, elastomeric concrete, epoxy resin, hot poured sealant, removal and replacement of hot mix asphalt or bituminous surface treatment, and containment of material debris from drilling into the existing concrete bridge, concrete spall repair, epoxy crack sealing, and other bridge related work, *** etc., for which there is no pay item included in the proposal, are considered as bridge and structures minor items. All costs in connection with furnishing and installing these bridge and structures minor items as shown and noted in the

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Plans and as outlined in these specifications and in the Standard Specifications shall be included in the *** lump sum contract price for "Br. Rehab. - _____ Bridge No. _____" ***

Division 8
Miscellaneous Construction

8-01 Erosion Control and Water Pollution Control

8-01.1 Description

Section 8-01.1 is supplemented with the following:

(January 2018 CCPW GSP)
All references in Section 8-01 to "Temporary Erosion and Sediment Control" and "TESC" shall be revised to read "Stormwater Pollution Prevention" and "SWPP" respectively.

8-01.3 Construction Requirements

8-01.3(2) Temporary Seeding and Mulching

8-01.3(2)B Temporary Seeding

Section 8-01.3(2)B is supplemented with the following:

(******)
Seed of the following mix, proportion, and quality shall be applied on all areas requiring temporary seeding within the project:

Botanical Name	Common Name	Percent by weight
Lolium multiflorum	Annual rye grass	100
	TOTAL	100

Source Identified seed shall be generation four or less. Non-Source Identified seed shall meet or exceed Washington State Department of Agriculture Certified Seed Standards and be from within the appropriate genetic zones of the Willamette Valley Ecoregion(s) as defined by the US Environmental Protection Agency (EPA).

The seed certification class shall be Certified (blue tag) in accordance with WAC 16-302 and meet the following requirements:

Prohibited Weed	0% max.
Noxious Weed	0% max.
Other Weed	0.20% max.
Other Crop	0.40% max.

The Contractor shall document all Source Identified seed by providing the Association of Official Seed Certifying Agents (AOSCA) yellow seed label for each species in the mix. Site Identification Logs can be supplied for collections where the AOSCA yellow label is not available.

8-01.3(2)E Tackifiers

Section 8-01.3(2)E is supplemented with the following:

(******)

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Polyacrylamide (PAM) shall not be used.

8-01.5 Payment

8-01.5(2) Item Bids

In Section 8-01.5(2) the bid item "Erosion/Water Pollution Control", by force account as provided in Section 1-09.6 and the two paragraphs following the bid item are revised to read:

(January 2018 CCPW GSP)
Maintenance and removal of erosion and water pollution control devices including removal and disposal of sediment, and stabilization and rehabilitation of soil disturbed by these activities, shall be included in the unit Contract prices for the individual erosion and water pollution control device.

8-02 Roadside Restoration

8-02.3 Construction Requirements

8-02.3(9) Seeding, Fertilizing, and Mulching

8-02.3(9)B Seeding and Fertilizing

Section 8-02.3(9)B is supplemented with the following:

(******)
Seed of the following mix, proportion, and quality shall be applied on all areas requiring permanent seeding within the project:

Seed Mix D – Native Upland Seeding

Botanical Name	Common Name	Percent by weight
Elymus glaucus	blue wildrye	50
Agrostis exarata Trin.	spike bentgrass	10
Bromus carinatus	California brome	10
Festuca idahoensis	Idaho fescue	30
	TOTAL	100

Seed application rate shall be in accordance with the manufacturer's recommendations. Minimum percent germination for each type of seed shall be 90.0%.

Source Identified seed shall be generation four or less. Non-Source Identified seed shall meet or exceed Washington State Department of Agriculture Certified Seed Standards and be from within the appropriate genetic zones of the Willamette Valley Ecoregion(s) as defined by the US Environmental Protection Agency (EPA).

The seed certification class shall be Certified (blue tag) in accordance with WAC 16-302 and meet the following requirements:

Prohibited Weed	0% max.
Noxious Weed	0% max.
Other Weed	0.20% max.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Other Crop	0.40% max.

The Contractor shall document all Source Identified seed by providing the Association of Official Seed Certifying Agents (AOSCA) yellow seed label for each species in the mix. Site Identification Logs can be supplied for collections where the AOSCA yellow label is not available.

8-02.4 Measurement

The fourth paragraph of Section 8-02.4 is revised to read:

(April 2019 CCPW GSP)
Seeding, fertilizing, and mulching will be measured by the acre, square yard, or square foot by ground slope measurement or through the use of design data.

8-02.5 Payment

Section 8-02.5 is supplemented with the following:

(February 2021 CCPW GSP)
Seeding and Mulching, per acre, square yard, or square foot

Division 9
Materials

9-28 Signing Materials and Fabrication

9-28.1 General

The last paragraph of Section 9-28.1 is revised to read:

(January 5, 2026)
All STOP, YIELD, DO NOT ENTER, WRONG WAY, FREEWAY ENTRANCE, HIGHWAY ENTRANCE signs shall be constructed entirely of Type XI reflective sheeting. All S series signs shall be constructed entirely of Type XI reflective sheeting unless otherwise specified. Overhead mounted signs shall use Type XI background reflective sheeting. Background reflective sheeting for all other signs shall be Type IV reflective sheeting or as noted in the Plans. Sign legends for all overhead signs shall be Type XI reflective sheeting, while legends on all other signs shall be constructed of Type IV reflective sheeting unless otherwise specified. Sign legends include: borders, letters, numerals, symbols, shields, and arrows. Reflective legend sheeting types shall not be mixed on individual signs.

9-28.12 Reflective Sheeting

Section 9-28.12 is revised to read:

(January 5, 2026)
Reflective sheeting material shall conform to ASTM D4956 - Standard Specification for Retroreflective Sheeting for Traffic Control. The following standard reflective sheeting types have been modified to reflect Contracting Agency requirements:

Device Type	Use	Sheeting Color	Sheeting Types
Permanent Signing			
Ground Mounted	All	All	IV[1]
Overhead	All	All	XI[5]
Object Markers	All	All	IV

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Temporary Construction Signing			
Warning Signs	All	Fluorescent Orange	VIII, IX, X[2], XI
Regulatory Signs	All	White	IV
Regulatory Signs	Rural	White	II[3], IV
Regulatory Signs	Urban/Rural	White	II[3], IV
Regulatory Signs	All	Red	III, IV
Regulatory Signs	All	Green	II, IV
Regulatory Letters, Border or Symbols	-	Green	III[3], IV
Temporary Construction Signs	All	All Other Background Colors	III[3], IV
Other Devices			
Barricades	All	White or Orange	III[3], IV
Barrier Delineators	All	White or Yellow	III, IV, V, XI
Bollards	All	All	IV
Flexible Guidepost	All	All	III, IV, V
Pedestrian Channelization Devices	All	White or Orange	III[3], IV
Signal Backplates	Portable Signals		IV
Signal Backplates	Permanent Signals		See Section 9-29.16
Tall Channelization Devices - 42-inch	All	Fluorescent Orange/White	III[3], IV[4]
Traffic Cones 28-inch and 36-inch	All	White or Higher White	VI
Traffic Safety Drums	All	Fluorescent Orange/White	III[3], IV[4]
Transportable Attenuators	All	Yellow and Black Chevron	III[3], IV
Transportable Attenuators	All	White and Red Chevron	IV
Tubular Markers (portable or pavement mounted)	All	White or Yellow	III[3], IV
Utilities Attached to Bridges			I, See Section 6-01.10

1. Except S Series, STOP, YIELD, DO NOT ENTER, FREEWAY ENTRANCE, and HIGHWAY ENTRANCE signs shall use Type XI.
2. Former Type X, not shown in ASTM 04956, however meets requirements of Types VII, IX, and XI.
3. Only devices in inventory may be used through December 31, 2026.
4. Type IV or higher fluorescent orange and white sheeting.
5. Type IV sheeting shall be used for overhead street name signs if specified in the Plans.

9-35 Temporary Traffic Control Materials

9-35.2 Construction Signs

Section 9-35.2 is revised to read:

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

(January 5, 2026)
Construction signs shall conform to the requirements of the MUTCD and shall meet the requirements of NCHRP Report 350 for Category 2 devices or MASH. Except as noted below, any sign/sign stand combination that satisfies these requirements will be acceptable. Post mounted Class A construction signs shall conform to the requirements of this section and additionally shall conform to the requirements stated in Section 9-28.

Aluminum sheeting shall be used to fabricate all construction signs. The signs shall have a minimum thickness of 0.080 inches and a maximum thickness of 0.125 inches.

All construction signs shall be fabricated with reflective sheeting in accordance with Section 9-28.12. All post mounted signs shall use a nylon washer between the twist fasteners (screw heads, bolts or nuts) and the reflective sheeting.

The use of plywood, fiberglass reinforced plastic, fabric rollup signs, and any other previously approved sign materials except aluminum or aluminum composite is prohibited.

All Class A and Class B signs shall utilize materials and be fabricated in accordance with Section 9-28 and the Washington State Sign Fabrication Manual M 55-05. A fabrication decal as stated in Section 9-28.1 is not required for construction signs.

9-35.6 Barricades

Section 9-35.6 is revised to read:

(January 5, 2026)
Barricades shall conform to the requirements of the MUTCD. The alternating orange and white reflective bands shall be fabricated with reflective sheeting in accordance with Section 9-28.12.

9-35.7 Traffic Safety Drums

The third and fourth paragraphs of Section 9-35.7 are revised to read:

(January 5, 2026)
Until December 31, 2026, traffic safety drums may have 4-inch or 6-inch reflective bands fabricated from Type III or Type IV or higher sheeting type as described in Section 9-28.12.

Beginning January 1, 2027, traffic safety drums shall have 6-inch reflective bands. A minimum of 4 reflective horizontal bands, alternating fluorescent orange and white starting with the top stripe being fluorescent orange, shall be used. Reflective bands shall be fabricated from Type IV or higher (reflective sheeting as described in Section 9-28.12. Drums of different reflective band types shall not be intermixed within the same closure. When recommended by the manufacturer, drums shall be treated to ensure proper adhesion of the reflective sheeting.

9-35.9 Traffic Cones

The last paragraph of Section 9-35.9 is revised to read:

(January 5, 2026)
White reflective bands shall be fabricated with reflective sheeting in accordance with Section 9-28.12.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

9-35.10 Tubular Markers

The last paragraph of Section 9-35.10 is revised to read:

(January 5, 2026)
White reflective bands shall be fabricated with reflective sheeting in accordance with Section 9-28.12. When recommended by the manufacturer, tubular markers shall be treated to ensure proper adhesion of the reflective sheeting.

9-35.12 Transportable Attenuator

The last paragraph of Section 9-35.12 is revised to read:

(January 5, 2026)
The transportable attenuator shall have a chevron pattern on the rear of the unit. The pattern shall consist of 4-inch to 8-inch alternating nonreflective black and reflective yellow or alternating reflective red and white sheeting, slanted at 45 degrees in an inverted "V" with the "V" at the center of the unit. Reflective sheeting shall be in accordance with Section 9-28.12.

9-35.13 42-Inch Tall Channelization Devices

The third and fourth paragraphs of Section 9-35.13 are revised to read:

(January 5, 2026)
Until December 31, 2026, 42-inch tall channelization devices may have 4-inch or 6-inch reflective bands fabricated from Type III or Type IV or higher sheeting type as described in Section 9-28.12.

Beginning January 1, 2027, 42-inch tall channelization devices shall have 6-inch reflective bands. A minimum of 4 reflective horizontal bands, alternating fluorescent orange and white starting with the top stripe being fluorescent orange, shall be used. Reflective bands shall be fabricated from Type IV or higher IV (reflective sheeting as described in Section 9-28.12. 42-inch tall channelization devices of different reflective band types shall not be intermixed within the same closure. When recommended by the manufacturer, 42-inch tall channelization devices shall be treated to ensure proper adhesion of the reflective sheeting.

9-35.16 Pedestrian Channelization Devices

Section 9-35.16 is revised to read:

(January 5, 2026)
When exposed to vehicular traffic, pedestrian channelizing devices shall meet the crashworthiness requirements of NCHRP 350 or MASH as described in Section 2-04.3(3). The bottom and top surfaces of the pedestrian channelizing device shall have 6-inch reflective bands matching the body color of the device fabricated from reflective sheeting as described in Section 9-28.12.

Section 9-35.16 is supplemented with the following:

(******)
Pedestrian Channelization Devices (PCD) shall meet the following additional requirements:

1. Orange or white in color
2. Constructed of plastic

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

3. Be a minimum of 32 inches tall
4. Devices shall have continuous bottom and top surfaces. The lower edge of the bottom portion shall be no more than 2 inches above the walking surface. The top edge of the bottom portion shall be at least 8 inches above the walking surface.
5. The top of the device shall have a top rail a minimum of 6 inches high and that is a smooth continuous surface free of sharp or rough edges
6. Have a minimum of 72 square inches of retroreflective markings. Retroreflective markings shall be:
   a. Orange or white in color
   b. The top of the markings shall be a minimum of 36 inches and a maximum of 48 inches above the roadway surface
   c. Located on the side of the device facing vehicular traffic.
7. Capable of being attached end to end to provide a continuous length with a gap of no more than 1 inch between units
8. Device supports shall have a maximum height of ½ inch when they extend into the pedestrian route.
8. Ballast shall be located behind or internal to the device
9.

Construction fencing or fencing of any type, tubular markers, traffic safety drums, and tall channelization devices shall not be used as pedestrian channelization devices.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Standard Plans

(January 5, 2026)

The Washington State Department of Transportation *Standard Plans* M21-01, published September 2024, is made a part of this Contract with the following revisions:

A-10.30

RISER RING detail (Including SECTION view and RISER RING DIMENSIONS table): The RISER RING detail is deleted from the plan.

INSTALLATION detail, SECTION A: The "1/4"" callout is revised to read "+/- 1/4" (SEE CONTRACT ~ Note: The + 1/4" installation is shown in the Section A view)"

A-40.20

Sheet 1, NOTES 1, 2, 3, and 4 are replaced with the following:

1. Use the ½ inch joint details for bridges with expansion length less than 100 feet and for bridges with L type abutments. Use the 1 inch joint details for other applications.

2. Use detail 5, 6, 7 on steel trusses and timber bridges with concrete bridge deck panels.

3. For details 1, 2, 3, and 4, the item "HMA Joint Seal at Bridge End" shall be used for payment. For details 5 and 6, the item "HMA Joint Seal at Bridge Deck Panel Joint" shall be used for payment. For detail 7, the item "Clean and Seal Bridge Deck Panel Joint" shall be used for payment.

Sheet 2, Detail 8 reference to "6-09.3(6)" is revised to read "6-21.3(7)".

A-50.40

Sheet 1, Plan View: The callout "BEAM GUARDRAIL TYPE 31 TRANSITION SECTION TYPE 21 OR TYPE 24 (SEE STANDARD PLAN C-25.20 OR C-25.30)" is revised to read "BEAM GUARDRAIL TYPE 31 TRANSITION SECTION TYPE 21, 24, OR 25 (SEE STANDARD PLAN C-25.20, C-25.30, OR C-25.32)"

A-60.40

Note 2 reference to "6-09.3(6)" is revised to read "6-21.3(7)".

B-55.20

General Note 3 reference to "2-09.4" is revised to read "3-07.4".

B-90.40

Valve Detail – DELETED

C-20.41

Note 4, First Sentence, "Box Culvert guardrail steel posts are not needed for fill depths greater than 40 inches." is revised to read; "Box culvert guardrail steel posts are not needed for fill depths greater than 46 inches. Provide 6-inches or greater of separation between the bottom of the guardrail post and top of the culvert"

BOX CULVERT POST ASSEMBLY, ELEVATION VIEW, post assembly length dimension "41" MIN. 72" MAX." is revised to read; "41" MIN. 78" MAX."

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

SECTION A, base material depth dimension - “9” MIN. 40” MAX. (SEE NOTE 4)” is revised to read: “9” MIN. 46” MAX. (SEE NOTE 4)”

C20-43

Note 4, First Sentence: “Box culvert guardrail steel posts are not needed for fill depths greater than 40 inches.” is revised to read: “Box culvert guardrail steel posts are not needed for fill depths greater than 46 inches. Provide 6-inches or greater separation between the bottom of guardrail post and top of culvert.”

Add a new KEY NOTE 4 - “IT IS PERMISSIBLE TO USE A 1” DIAM. ANCHOR ROD WITH TWO NUTS AND TWO – 1” DIAM. WASHERS PER STD. SPEC. SECTION 9-06.5(4) IN LIEU OF A HEX HEAD BOLT.”

BOX CULVERT POST & BASE PLATE ASSEMBLY, ELEVATION VIEW, post assembly length dimension – “41” MIN. 72” MAX.” is revised to read: “41” MIN. 78” MAX.”

SECTION A, base material depth dimension - “9” MIN. 40” MAX. (SEE NOTE 4)” is revised to read: “9” MIN. 46” MAX. (SEE NOTE 4)”

Section A, callout – “1” (IN) DIAM. HEX HEAD BOLT (ASTM A 307, GR. A) W/NUT & 2 – 1” DIAM. WASHERS PER STD. SPEC. SECTION 9-06.5(1) ~ SEE NOTE 1”, is revised to read: “1” (IN) DIAM. HEX HEAD BOLT (ASTM A 307, GR. A) W/NUT & TWO – 1” DIAM. WASHERS PER STD. SPEC. SECTION 9-06.5(1) ~ SEE KEY NOTES 1 AND 4”

Elevation View, Weld symbol – callout, See (key Note Symbol) “4” is revised to read: See (key Note Symbol) “3”

C-23.70

Sheet 2, ANCHOR BRACKET ASSEMBLY DETAIL, dimension, “R. 5/16” is revised to read; R. 15/16”

ANCHOR PLATE DETAIL, weld callout (fillet), 1/4" is revised to read; 3/16”

C-60.20

Sheet 1, Plan view, callout – “1/2” (IN) DIAMETER X 6 1/2" (IN) LONG ANCHOR BOLT ~ PER STD. SPEC. SECT. 9-06.5(4) (TYPICAL) (SEE NOTE 7)” is revised to read: “5/8” DIAMETER x 6 1/2" (IN) LONG ANCHOR BOLT ~ PER STD. SPEC. SECT. 9-06.5(4) (TYPICAL) (SEE NOTE 7)”

C-70.15

BARRIER CONNECTION DETAIL, callout – “CENTER GRID IN CONNECTION BLOCKOUT AND FILL VOID WITH TYPE 3 GROUT (STD. SPECIFICATION SECTION 9-20.3(3) PLACED IN ACCORDANCE WITH STD. SPECIFICATION SECTION 6-20.3(20)” is revised to read “CENTER GRID IN CONNECTION BLOCKOUT AND FILL VOID WITH GROUT TYPE 3 (STD. SPECIFICATION SECTION 9-20.3(3) PLACED IN ACCORDANCE WITH STD. SPECIFICATION SECTION 6-02.3(20)”

C81.10

Sheet 1, TYPICAL SECTION – TRAFFIC BARRIER the R4 #6 bar on the traffic face may be placed 4” down from the top of the barrier to allow additional room to install BP railing or other attachments. The R4 bar shall be kept tight to the front R2 bar.

Sheet 4, the existing table “IMPACT SHEAR AND IMPACT MOMENT TABLE” is renamed to “IMPACT SHEAR AND MOMENT TABLE DECK OVERHANG AND CONNECTIONS” keynote 25 is still applicable.

Sheet 4, NOTES, the following Note is added: “3. Deck overhangs for this use constitute plain reinforced concrete typically around 8" in thickness, non-prestressed moment slabs or approach slabs, or plain reinforced and longitudinally prestressed box girders which employ

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

a topping slab. Other Supporting Structure Systems inclusive of post-tensioned decks, walls, and or Structure segments tied together without a topping slab, with the ties in the barrier resistance load path, shall use the impact shear and moments for other supporting structures."

Sheet 4, the following table is added with a keynote 25.

IMPACT SHEAR AND MOMENT TABLE OTHER SUPPORTING STRUCTURES										
	Interior Segment					End Segment				
Roadway and Fill Height at Curb Line (in)	0	6	12	18	24	0	6	12	18	24
End Segment Length (ft)	-	-	-	-	-	10.00	10.50	11.25	11.75	12.50
Impact Moment (kip*ft/ft)	19.86	24.12	28.55	33.16	37.97	20.80	25.17	29.65	34.27	39.04
Impact Shear (kip/ft)	7.89	8.04	8.23	8.44	8.68	8.27	8.39	8.54	8.72	8.92

C-81.15

Sheet 1, General Notes, Add Note 7, to read;"7. The concrete class for the moment slab shall be class 4000 typically and class 4000A when the top of the slab is used as the roadway, or sidewalk, surface. The concrete class for the barrier is defined in Standard Specification Section 6-10.3."

C-85.11

On Section B, the callout "3" EXPANDED POLYSTYRENE AROUND COLUMN (TYP.)" is revised to read "3" EXPANDED POLYSTYRENE OR POLYETHYLENE FOAM AROUND COLUMN (TYP.)"

D-3.09

Sheet 1, GEOSYNTHETIC WALL WITH 2 FT TRAFFIC SURCHARGE detail, callout – "BARRIER ON WALL ~ SEE Standard Plan D-3.15 or D-3.16" is revised to read: "BARRIER ON WALL ~ SEE CONTRACT PLANS"

D-3.10

Sheet 1, Typical Section, callout – "FOR WALLS WITH SINGLE SLOPE TRAFFIC BARRIER. USE THE DETAILS ABOVE THE MATCH LINE ON STANDARD PLAN D-3.15" is revised to read; "FOR WALLS WITH SINGLE SLOPE TRAFFIC BARRIER, SEE CONTRACT PLANS"
Sheet 1, Typical Section, callout – "FOR WALLS WITH F-SHAPE TRAFFIC BARRIER. USE THE DETAILS ABOVE THE MATCH LINE ON STANDARD PLAN D-3.16" is revised to read; "FOR WALLS WITH F-SHAPE TRAFFIC BARRIER, SEE CONTRACT PLANS"

D-3.11

Sheet 1, Typical Section, callout – ""B" BRIDGE APPROACH SLAB (SEE BRIDGE PLANS) OR PERMANENT GEOSYNTHETIC WALL BARRIER ~ SEE STANDARD PLANS D-3.15 OR D-3.16" is revised to read; "B" BRIDGE APPROACH SLAB OR MOMENT SLAB (SEE CONTRACT PLANS)
Sheet 1, Typical Section, callout – "TYPICAL BARRIER ON BRIDGE APPROACH SLAB (SEE BRIDGE PLANS) OR PERMANENT GEOSYNTHETIC WALL BARRIER ~ SEE STANDARD PLANS D-3.15 OR D-3.16" is revised to read; "TYPICAL BARRIER ON BRIDGE APPROACH SLAB OR MOMENT SLAB (SEE CONTRACT PLANS)

D-10.10

Note 7, "If Traffic Barriers are required, See Standard Plans D-15.10, D-15.20 and D-15.30" is revised to read "Traffic Barriers shall not be structurally connected to the Reinforced Concrete Retaining Wall Type 1 and 1SW'.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

D-10.15
Note 7, "If Traffic Barriers are required, See Standard Plans D-15.10, D-15.20 and D-15.30" is revised to read "Traffic Barriers shall not be structurally connected to the Reinforced Concrete Retaining Wall Type 2 and 2SW".

D-10.30
Wall Type 5 may be used in all cases.

D-10.35
Wall Type 6 may be used in all cases.

D-10.40
Note 5, "If Traffic Barriers are required, See Standard Plans D-15.10, D-15.20 and D-15.30" is revised to read "Traffic Barriers shall not be structurally connected to the Reinforced Concrete Retaining Wall Type 7".

D-10.45
Note 5, "If Traffic Barriers are required, See Standard Plans D-15.10, D-15.20 and D-15.30" is revised to read "Traffic Barriers shall not be structurally connected to the Reinforced Concrete Retaining Wall Type 8".

E-20.10
On Sheet 2, the reference to "2-09.4" is revised to read "3-07.4".

F-10.18
Note 1; "Construct curb joints at cement concrete pavement transverse joint locations. If all adjacent pavement is HMA, see Standard Plan F-30.10 for Curb Expansion and Contraction Joint Spacing." is revised to read – "See Standard Plan F-30.10 and Standard Specification Section 8-04.3 for Curb Expansion and Contraction Joint details and spacing."
CURB 3 Detail, the diamond note 1 callout on the 6" dimension at the bottom left side of the detail, is revised to be a diamond note 2 callout.

F-30.10
All five instances of the "2.0% MAX." are replaced with "2.1% MAX."

F-40.12
The one instance of "2.0% MAX." is replaced with "2.1% MAX."
Note 7 is replaced with the following:
7. The running slope of curb ramps shall not exceed 8.3% maximum except as noted herein. If the 8.3% running slope creates a ramp that exceeds 15ft, see contract plans for details. Use a single constant slope from bottom of ramp to top of ramp to match into the landing. Do not include the abutting landing in the Curb Ramp length measurement. When a ramp is constructed on a radius, the Curb Ramp length is measured on the inside radius along the back of the walkway.
Section B is amended as follows:
Delete: "15' – 0" MAX. (TYP.)"
Section C is amended as follows:
Delete: "15' – 0" MAX. (TYP.)"

F-40.14

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

The one instance of "2.0% MAX." is replaced with "2.1% MAX."
Note 7 is replaced with the following:
7. The running slope of curb ramps shall not exceed 8.3% maximum except as noted herein. If the 8.3% running slope creates a ramp that exceeds 15ft, see contract plans for details. Use a single constant slope from bottom of ramp to top of ramp to match into the landing. Do not include the abutting landing in the Curb Ramp length measurement. When a ramp is constructed on a radius, the Curb Ramp length is measured on the inside radius along the back of the walkway.
Section A is amended as follows:
Delete: "15' – 0" MAX. (TYP.)"
Section C is amended as follows:
Delete: "15' – 0" MAX. (TYP.)"

F-40.15
The one instance of "2.0% MAX." is replaced with "2.1% MAX."
Note 7 is replaced with the following:
7. The running slope of curb ramps shall not exceed 8.3% maximum except as noted herein. If the 8.3% running slope creates a ramp that exceeds 15ft, see contract plans for details. Use a single constant slope from bottom of ramp to top of ramp to match into the landing. Do not include the abutting landing in the Curb Ramp length measurement.
Section A is amended as follows:
Delete: "15' – 0" MAX. (TYP.)"

F-40.16
The one instance of "2.0% MAX." is replaced with "2.1% MAX."
Note 8 is replaced with the following:
7. The running slope of curb ramps shall not exceed 8.3% maximum except as noted herein. If the 8.3% running slope creates a ramp that exceeds 15ft, see contract plans for details. Use a single constant slope from bottom of ramp to top of ramp to match into the landing. Do not include the abutting landing in the Curb Ramp length measurement.
Section A is amended as follows:
Delete: "15' – 0" MAX. (TYP.)"
Section B is amended as follows:
Delete: "15' – 0" MAX. (TYP.)"

F-80.10
The one instance of "2.0% MAX." is replaced with "2.1% MAX."
Note 6 is replaced with the following:
The running slope of the Pedestrian Ramp shall not exceed 8.3% maximum except as noted herein. If the 8.3% running slope creates a ramp that exceeds 15ft, see contract plans for details. Use a single constant slope from bottom of ramp to top of ramp to match into the sidewalk.
Section A is amended as follows:
Delete: "15" Max."

J-5.50
General Note 4 reference to "2-09.3(1)E" is revised to read "3-07.3(1)E"
General Note 5 reference to "2-09.3(1)E" is revised to read "3-07.3(1)E"

J-10.10

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Sheet 4 of 6, “Foundation Size Reference Table”, PAD WIDTH column, Type 33xD=6’ – 3” is revised to read: 7’ – 3”. Type 342LX / NEMA P44=5’ – 10” is revised to read: 6’ – 10”
Sheet 5 of 6, Plan View, “FOR EXAMPLE PAD SHOWN HERE:, “first bullet” item, “-SPACE BETWEEN TYPE B MOD. CABINET AND 33x CABINET IS 6” (IN)” IS REVISED TO READ: “SPACE BETWEEN TYPE B MOD. CABINET (BACK OF ALL CHANNEL STEEL) AND 33x CABINET IS 6” (IN) (CHANNEL STEEL ADDS ABOUT 5” (IN)”

J-10.16
Key Note 1, Standard Plan J-10.30 revised to Standard Plan J-10.14

J-10.17
Key Note 1, Standard Plan J-10.30 revised to Standard Plan J-10.14

J-10.18
Key Note 1, Standard Plan J-10.30 revised to Standard Plan J-10.14

J-15.15
The reference to “2-09.3(1)E” is revised to read “3-07.3(1)E”

J-20.01
STANDARD DIMENSIONS AND REFERENCES table, TYPE FB, Standard Height column – “15’-0” ”is revised to read; “14’-0” ”

J-20.10
DELETED

J-20.11
DELETED

J-20.26
Add Note 1, “1. One accessible pedestrian pushbutton station per pedestrian pushbutton post.”
Add General Note 2, to read: “Signs shown are for locations with pedestrian signal displays (Accessible Pedestrian Signals/APS). Accessible information device (AID) pushbuttons signs not shown.”
Revise View Titles (Both Sheets) to read: “ACCESSIBLE PEDESTRIAN PUSHBUTTON ASSEMBLY”

J-20.16
View A, callout, was – LOCK NIPPLE, is revised to read; CHASE NIPPLE

J-21.10
Sheet 1, Anchor Bolt Template, callout; “9” (IN) BOLT CIRCLE” is revised to read: “9” (IN) DIA.BOLT CIRCLE”
Base Plate Detail, callout; “3/4” (IN) STEEL PLATE WITH HOLE = POLE BASE + 1/6” (IN)” IS REVISED TO READ; “3/4” (IN) STEEL PLATE WITH HOLE = POLE BASE + 1/16” (IN)”
Flat Foundation Detail – Elevation, callout; “ANCHOR BOLTS ~ ¾” (IN) x 30” (IN) FULL THREAD ~ THREE REQ’D. PER ASSEMBLY” is revised to read; “ANCHOR BOLTS ~ ¾” (IN) x 30” (IN) FULL THREAD ~ FOUR REQ’D. PER ASSEMBLY”
Flat Foundation Detail – Elevation, dimension; 4’ – 0” is revised to read; “4’ – 0” ROUND OR 3’ – 0” SQUARE”

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

J-21.15
Partial View, callout, was – LOCK NIPPLE ~ 1 ½" DIAM., is revised to read; CHASE NIPPLE ~ 1 ½" (IN) DIAM.

J-21.16
On both elevation views, the overall standard height dimension "15'-0" " is revised to read; "14'-0" "

J-26.10
The reference to "2-09.3(1)E" is revised to read "3-07.3(1)E"

J-27.10
The reference to "2-09.3(1)E" is revised to read "3-07.3(1)E"

J-28.30
General Note 13 – "See Standard Plans C-8b and C-85.14 for steel light standards on traffic barrier" is revised to read; "See Standard Plan C-85.15 for steel light standards on traffic barrier."

J-29.10
The reference to "2-09.3(1)E" is revised to read "3-07.3(1)E"

J-40.10
Sheet 2 of 2, Detail F, callout, "12 – 13 x 1 ½" S.S. PENTA HEAD BOLT AND 12" S. S. FLAT WASHER" is revised to read; "12 – 13 x 1 ½" S.S. PENTA HEAD BOLT AND 1/2" (IN) S. S. FLAT WASHER"

J-40.36
Note 1, second sentence; "Finish shall be # 2B for backbox and # 4 for the cover." Is revised to read; "Finish shall be # 2B for barrier box and HRAP (Hot Rolled Annealed and Pickled) for the cover.

J-40.37
Note 1, second sentence; "Finish shall be # 2B for backbox and # 4 for the cover." Is revised to read; "Finish shall be # 2B for barrier box and HRAP (Hot Rolled Annealed and Pickled) for the cover.

J-50.15
Sheet 1, SECTION A, the call out "LOOP LEAD-IN WIRES, TWISTED PAIRS ~ MAX. 3 PAIRS" is revised to read "LOOP LEAD-IN WIRES, TWISTED PAIRS ~ MAX. 6 PAIRS"
General Note 1 reference to "2-09.3(1)E" is revised to read "3-07.3(1)E"

J-75.20
Key Notes, note 16, second bullet point, was: "1/2" (IN) x 0.45" (IN) Stainless Steel Bands", add the following to the end of the note: "Alternate: Stainless steel cable with stainless steel ends, nuts, bolts, and washers may be used in place of stainless steel bands and associated hardware."

J-75.55
Notes, Note A1, Revise reference, was – G-90.29, should be – G-90.20.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

K-80.32
Sheet 1, END VIEW, the callout located at the base of barrier – "SEE NOTE 2" is revised to read: "SEE NOTE 3"
Sheet 2, WIRE ROPE LOOP DETAIL, dimension (overall length) – "SEE NOTE 1" is revised to read: "SEE NOTE 2"
Sheet 2, Side View (Right), callout – "WIRE ROPE LOOPS – SEE NOTE 1" is revised to read: "WIRE ROPE LOOPS – SEE NOTE 2"

L-5.10
Add new general Note 9 on sheet 1 – "9. The top of wall in Section A on Sheet 1 shall be located as follows: 1) flush with the finished grade when placed within the deflection distance of the long span guardrail system (Std. Plan C-20.40), 2) Two inches maximum above finished grade when placed behind a box culvert guardrail steel post system (Std. Plan C-20.41 or C-20.43), 3) Six inches minimum for all other applications. The bottom rail shall be located at mid height between the top rail and the top of structure."

M-20.30
Wide Dotted Lane Line Detail, reference below title, (SEE NOTE 6) is revised to read: (SEE NOTE 5)

M-40.10
Guide Post Type ~ Reflective Sheeting Applications Table, remove reference - "(SEE NOTE 5)"

The following are the Standard Plan numbers applicable at the time this project was advertised. The date shown with each plan number is the publication approval date shown in the lower right-hand corner of that plan. Standard Plans showing different dates shall not be used in this contract.

A-10.10-00 ..... 8/7/07	A-30.35-00 ..... 10/12/07	A-50.10-02 ..... 7/18/24
A-10.20-00 ..... 10/5/07	A-40.00-01 ..... 7/6/22	A-50.40-01 ..... 8/17/21
A-10.30-00 ..... 10/5/07	A-40.10-04 ..... 7/31/19	A-60.10-03 ..... 12/23/14
A-20.10-00 ..... 8/31/07	A-40.15-00 ..... 8/11/09	A-60.20-03 ..... 12/23/14
A-30.10-00 ..... 11/8/07	A-40.20-04 ..... 1/18/17	A-60.30-01 ..... 6/28/18
A-30.30-01 ..... 6/16/11	A-40.50-03 ..... 9/12/23	A-60.40-00 ..... 8/31/07
B-5.20-03 ..... 9/9/20	B-30.50-03 ..... 2/27/18	B-75.20-03 ..... 8/17/21
B-5.40-02 ..... 1/26/17	B-30.60-00 ..... 9/9/20	B-75.50-02 ..... 3/15/22
B-5.60-02 ..... 1/26/17	B-30.40-03 ..... 2/27/18	B-70.60-01 ..... 1/26/17
B-10.20-03 ..... 8/23/23	B-30.70-04 ..... 2/27/18	B-75.60-00 ..... 6/8/06
B-10.40-02 ..... 8/17/21	B-30.80-01 ..... 2/27/18	B-80.20-00 ..... 6/8/06
B-10.70-03 ..... 8/23/23	B-30.90-02 ..... 1/26/17	B-80.40-00 ..... 6/1/06
B-15.20-01 ..... 2/7/12	B-35.20-00 ..... 6/8/06	B-85.10-01 ..... 6/10/08
B-15.40-01 ..... 2/7/12	B-35.40-01 ..... 8/23/23	B-85.20-00 ..... 6/1/06
B-15.60-02 ..... 1/26/17	B-40.20-00 ..... 6/1/06	B-85.30-00 ..... 6/1/06
B-20.20-02 ..... 3/16/12	B-40.40-02 ..... 1/26/17	B-85.40-00 ..... 6/8/06
B-20.40-04 ..... 2/27/18	B-45.20-01 ..... 7/11/17	B-85.50-01 ..... 6/10/08
B-20.60-03 ..... 3/15/12	B-45.40-01 ..... 7/21/17	B-90.10-00 ..... 6/8/06
B-25.20-02 ..... 2/27/18	B-50.20-00 ..... 6/1/06	B-90.20-00 ..... 6/8/06
B-25.60-03 ..... 8/23/23	B-55.20-03 ..... 8/17/21	B-90.30-00 ..... 6/8/06

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

B-30.05-00 ..... 9/9/20
B-30.10-03 ..... 2/27/18
B-30.15-00 ..... 2/27/18
B-30.20-04 ..... 2/27/18
B-30.30-03 ..... 2/27/18
B-60.20-02 ..... 9/9/20
B-60.40-01 ..... 2/27/18
B-65.20-01 ..... 4/26/12
B-65.40-00 ..... 6/1/06
B-70.20-01 ..... 3/15/22
B-90.40-01 ..... 1/26/17
B-90.50-00 ..... 6/8/06
B-95.20-02 ..... 8/17/21
B-95.40-01 ..... 6/28/18

1

C-1 ..... 9/8/22
C-1b 10/12/23
C-1d 10/31/03
C-6a 9/8/22
C-7 ..... 9/8/22
C-7a 9/8/22
C-20.10-09 ..... 10/12/23
C-20.14-05 ..... 9/8/22
C-20.15-03 ..... 10/12/23
C-20.18-04 ..... 9/8/22
C-20.40-10 ..... 10/12/23
C-20.41-05 ..... 7/18/24
C-20.43-01 ..... 7/18/24
C-20.44-00 ..... 8/13/24
C-20.45-03 ..... 9/8/22
C-20.55-00 ..... 7/30/24
C-22.16-08 ..... 10/17/23
C-22.40-11 ..... 7/21/24
C-22.45-07 ..... 7/21/24
C-23.70-01 ..... 10/16/23
C.24.10-05 ..... 7/21/24
C-24.15-00 ..... 3/15/22
C-25.20-07 ..... 8/20/21
C-25.22-06 ..... 8/20/21
C-25.26-05 ..... 8/20/21
C-25.30-01 ..... 8/20/21
C-25.32-00 ..... 7/29/24
C-25.80-05 ..... 8/12/19
C-60.10-04 ..... 7/21/24
C-60.15-01 ..... 7/21/24
C-60.20-01 ..... 9/8/22
C-60.30-02 ..... 7/21/24
C-60.40-01 ..... 7/21/24
C-60.45-01 ..... 7/21/24
C-60.50-01 ..... 7/21/24
C-60.60-01 ..... 7/21/24
C-60.70-01 ..... 9/8/22
C-60.80-02 ..... 7/21/24
C-70.10-04 ..... 10/16/23
C-70.15-01 ..... 7/21/24
C-75.10-02 ..... 9/16/20
C-75.20-03 ..... 8/20/21
C-75.30-03 ..... 8/20/21
C-80.10-03 ..... 10/16/23
C-80.20-01 ..... 6/11/14
C-80.30-02 ..... 8/20/21
C-80.40-01 ..... 6/11/14
C-85.10-00 ..... 4/8/12
C-85.11-01 ..... 9/16/20
C-85.15-03 ..... 10/17/23
C-85-18-03 ..... 9/8/22
C-81.10-00 ..... 9/12/23
C-81.15-00 ..... 9/12/23

2

D-2.36-03 ..... 6/11/14
D-2.46-02 ..... 8/13/21
D-2.84-00 ..... 11/10/05
D-2.92-01 ..... 4/26/22
D-3.09-00 ..... 5/17/12
D-3.10-01 ..... 5/29/13
D-3.11-03 ..... 6/11/14
D-4 ..... 12/11/98
D-6 ..... 6/19/98
D-10.10-01 ..... 12/2/08
D-10.15-01 ..... 12/2/08
D-10.20-01 ..... 8/7/19
D-10.25-01 ..... 8/7/19
D-10.30-00 ..... 7/8/08
D-10.35-00 ..... 7/8/08
D-10.40-01 ..... 12/2/08
D-10.45-01 ..... 12/2/08
D-20.10-00 ..... 10/9/23

3

E-1 ..... 2/21/07
E-2 ..... 5/29/98
E-4 ..... 8/27/03
E-4a 8/27/03
E-20.10-00 ..... 9/12/23
E-20.20-00 ..... 10/4/23

4

F-10.12-04 ..... 9/24/20
F-10.16-00 ..... 12/20/06
F-10.18-04 ..... 6/28/24
F-10.40-04 ..... 9/24/20
F-10.42-00 ..... 1/23/07
F-10.62-02 ..... 4/22/14
F-10.64-03 ..... 4/22/14
F-30.10-04 ..... 9/25/20
F-40.12-03 ..... 6/29/16
F-40.14-03 ..... 6/29/16
F-40.15-04 ..... 9/25/20
F-40.16-03 ..... 6/29/16
F-45.10-05 ..... 6/4/24
F-80.10-04 ..... 7/15/16

5

G-10.10-00 ..... 9/20/07
G-20.10-03 ..... 8/20/21
G-22.10-04 ..... 6/28/18
G-24.10-00 ..... 11/8/07
G-24.20-01 ..... 2/7/12
G-24.30-02 ..... 6/28/18
G-24.40-07 ..... 6/28/18
G-24.50-05 ..... 8/7/19
G-24.60-05 ..... 6/28/18
G-25.10-05 ..... 9/16/20
G-26.10-00 ..... 7/31/19
G-30.10-04 ..... 6/23/15
G-50.10-03 ..... 6/28/18
G-90.10-03 ..... 7/11/17
G-90.20-05 ..... 7/11/17
G-90.30-04 ..... 7/11/17
G-95.10-02 ..... 6/28/18
G-95.20-03 ..... 6/28/18
G-95.30-03 ..... 6/28/18

6

H-10.10-01 ..... 6/2/24
H-30.10-00 ..... 10/12/07
H-70.10-02 ..... 8/17/21

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

H-10.11-00 ..... 6/2/24
H-10.15-01 ..... 6/2/24
H-10.16-00 ..... 6/2/24
H-32.10-00..... 9/20/07
H-60.10-01..... 7/3/08
H-60.20-01..... 7/3/08
H-70.20-02 .....8/17/21

1

I-10.10-01..... 8/11/09
I-30.10-02.....3/22/13
I-30.15-02.....3/22/13
I-30.16-01..... 7/11/19
I-30.17-01.....6/12/19
I-30.20-00 ..... 9/20/07
I-30.30-02 ..... 6/12/19
I-30.40-02 ..... 6/12/19
I-30.60-02 ..... 6/12/19
I-40.10-00 ..... 9/20/07
I-40.20-00 .....9/20/07
I-50.20-02 .....7/6/22
I-60.10-01 .....6/10/13
I-60.20-01 .....6/10/13
I-80.10-02 .....7/15/16

2

J-05.50-00.....8/30/22
J-10.....7/18/97
J-10.10-04.....9/16/20
J-10.12-00.....9/16/20
J-10.14-00.....9/16/20
J-10.15-01 ..... 6/11/14
J-10.16-02.....8/18/21
J-10.17-02.....8/18/21
J-10.18-02.....8/18/21
J-10.20-04.....8/18/21
J-10.21-02.....8/18/21
J-10.22-03.....10/4/23
J-10.25-01.....6/21/24
J-10.26-00..... .8/30/22
J-12.15-00.....6/28/18
J-12.16-00.....6/28/18
J-15.10-01 ..... 6/11/14
J-15.15-02.....7/10/15
J-20.01-01 ..... .6/21/24
J-20.05-00.....6/21/24
J-20.10-05.....10/4/23
J-20.11-03.....7/31/19
J-20.15-04.....6/21/24
J-20.16-02.....6/30/14
J-20.20-02.....5/20/13
J-20.26-01.....7/12/12
J-21.10-05.....6/21/24
J-21.15-01.....6/10/13
J-21.16-02.....6/21/24
J-21.17-01.....6/10/13
J-21.20-01.....6/10/13
J-22.15-03.....6/21/24
J-22.16-03.....7/10/15
J-22.17-00.....6/21/24
J-26.10-03 ..... 7/21/16
J-26.15-01 ..... 5/17/12
J-26.20-01 ..... 6/28/18
J-27.10-01 ..... 7/21/16
J-27.15-00 ..... 3/15/12
J-28.01-00 ..... 8/30/22
J-28.10-02 ..... 8/7/19
J-28.22-00 ..... 8/07/07
J-28.24-02 ..... 9/16/20
J-28.26-01 .....12/02/08
J-28.30-04 ..... 6/18/24
J-28.40-02 .....6/11/14
J-28.42-01 .....6/11/14
J-28.43-01 ..... 6/28/18
J-28.45-03 ..... 7/21/16
J-28.50-03 ..... 7/21/16
J-28.60-03 ..... 8/27/21
J-28.70-04 ..... 8/30/22
J-29.10-02 ..... 8/26/22
J-29.15-01 ..... 7/21/16
J-29.16-02 ..... 7/21/16
J-30.10-01 ..... 8/26/22
J-40.01-00 ..... 8/30/22
J-40.05-00 ..... 7/21/16
J-40.10-04 ..... 4/28/16
J-40.20-03 ..... 4/28/16
J-40.30-04 ..... 4/28/16
J-40.35-01 ..... 5/29/13
J-40.36-02 ..... 7/21/17
J-40.37-02 ..... 7/21/17
J-40.38-01 ..... 5/20/13
J-40.39-00 ..... 5/20/13
J-40.40-02 ..... 7/31/19
J-45.36-00 ..... 7/21/17
J-50.05-00 .....7/21/17
J-50.10-01 .....7/31/19
J-50.11-02.....7/31/19
J-50.12-02 .....8/7/19
J-50.13-01 .....8/30/22
J-50.15-01 .....7/21/17
J-50.16-01 .....3/22/13
J-50.18-00 .....8/7/19
J-50.19-00 .....8/7/19
J-50.20-00 .....6/3/11
J-50.25-00 .....6/3/11
J-50.30-00 .....6/3/11
J-60.05-01 .....7/21/16
J-60.11-00.....5/20/13
J-60.12-00 .....5/20/13
J-60.13-00 .....6/16/10
J-60.14-01 .....7/31/19
J-75.10-02 .....7/10/15
J-75.20-01 .....7/10/15
J-75.30-02 .....7/10/15
J-75.50-00 .....8/30/22
J-75.55-00 .....8/30/22
J-80.05-00 .....8/30/22
J-80.10-01 .....8/18/21
J-80.12-00 .....8/18/21
J-80.15-00 .....6/28/18
J-81.10-02 .....8/18/21
J-81.12-00 .....9/3/21
J-84.05-00 .....8/30/22
J-86.10-00 .....6/28/18
J-90.10-03 .....6/28/18
J-90.20-03 .....6/28/18
J-90.21-02 .....6/28/18
J-90.50-00 .....6/28/18

3

K-70.20-01 ..... 6/1/16
K-80.10-02 ..... 9/25/20
K-80.32-00..... 8/17/21
K-80.34-00..... 8/17/21
K-80.35-01.....9/16/20
K-80.37-01.....9/16/20

4

L-5.10-02.....6/5/24
L-5.15-00.....9/19/22
L-10.10-02.....6/21/12
L-20.10-03 ..... 7/14/15
L-30.10-02 .....6/11/14
L-40.15-01 .....6/16/11
L-40.20-02 .....6/21/12
L-70.10-01 .....5/21/08
L-70.20-01 .....5/21/08

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

1

M-1.20-04..... 9/25/20
M-1.40-03..... 9/25/20
M-1.60-03..... 9/25/20
M-1.80-03..... 6/3/11
M-2.20-03..... 7/10/15
M-2.21-00..... 7/10/15
M-3.10-04..... 9/25/20
M-3.20-04..... 8/2/22
M-3.30-04..... 9/25/20
M-3.40-04..... 9/25/20
M-3.50-03..... 9/25/20
M-5.10-03..... 9/25/20
M-7.50-01..... 1/30/07
M-9.50-02..... 6/24/14
M-9.60-00 ..... 2/10/09
M-11.10-04..... 8/2/22
M-12.10-04 ..... 6/28/24
M-15.10-02 ..... 7/17/23
M-17.10-02 ..... 7/3/08
M-20.10-04 ..... 8/2/22
M-20.20-02 ..... 4/20/15
M-20.30-05 ..... 6/28/24
M-20.40-03 ..... 6/24/14
M-20.50-02 .....6/3/11
M-24.20-02 ..... 4/20/15
M-24.40-02 ..... 4/20/15
M-24.60-04 ..... 6/24/14
M-24.65-00 .....7/11/17
M-24.66-00 .....7/11/17
M-40.10-04 .....10/17/23
M-40.20-00 .....10/12/07
M-40.30-01 .....7/11/17
M-40.40-00 .....9/20/07
M-40.50-00 .....9/20/07
M-40.60-00 .....9/20/07
M-60.10-01 .....6/3/11
M-60.20-03 .....8/17/21
M-65.10-03 .....8/17/21
M-80.10-01 .....6/3/11
M-80.20-00 .....6/10/08
M-80.30-00 .....6/10/08

2

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

MISCELLANEOUS ITEMS

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

TITLE VI NON-DISCRIMINATION ASSURANCES

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

DocuSign Envelope ID: 7146D854-B4BA-492E-9C46-73146FF2E4F7

The United States Department of Transportation (USDOT) Standard Title VI/Non-Discrimination Assurances

DOT Order No. 1050.2A

The Clark County (herein referred to as the "Recipient"), **HEREBY AGREES THAT**, as a condition to receiving any Federal financial assistance from the U.S. Department of Transportation (DOT), through Washington State Department of Transportation (WSDOT), is subject to and will comply with the following:

Statutory/Regulatory Authorities

- Title VI of the Civil Rights Act of 1964 (42 U.S.C. § 2000d et seq., 78 stat. 252), (prohibits discrimination on the basis of race, color, national origin);
- 49 C.F.R. Part 21 (entitled Non-discrimination In Federally-Assisted Programs Of The Department Of Transportation-Effectuation Of Title VI Of The Civil Rights Act Of 1964);
- 28 C.F.R. section 50.3 (U.S. Department of Justice Guidelines for Enforcement of Title VI of the Civil Rights Act of 1964);

The preceding statutory and regulatory cites hereinafter are referred to as the "Acts" and "Regulations," respectively.

General Assurances

In accordance with the Acts, the Regulations, and other pertinent directives, circulars, policy, memoranda, and/or guidance, the Recipient hereby gives assurance that it will promptly take any measures necessary to ensure that:

> *"No person in the United States shall, on the grounds of race, color, or national origin, be excluded from participation in, be denied the benefits of, or be otherwise subjected to discrimination under any program or activity, "for which the Recipient receives Federal financial assistance from DOT, including the Washington State Department of Transportation.*

The Civil Rights Restoration Act of 1987 clarified the original intent of Congress, with respect to Title VI and other Non-discrimination requirements (The Age Discrimination Act of 1975, and Section 504 of the Rehabilitation Act of 1973), by restoring the broad, institutional-wide scope and coverage of these non-discrimination statutes and requirements to include all programs and activities of the Recipient, so long as any portion of the program is Federally assisted.

Specific Assurances

More specifically, and without limiting the above general Assurance, the Recipient agrees with and gives the following Assurances with respect to its Federally assisted program:

1. The Recipient agrees that each "activity," "facility," or "program," as defined in §§ 21.23(b) and 21.23(e) of 49 C.F.R. § 21 will be (with regard to an "activity") facilitated, or will be (with regard

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

DocuSign Envelope ID: 7146D854-B4BA-492E-9C46-73146FF2E4F7

to a "facility") operated, or will be (with regard to a "program") conducted in compliance with all requirements imposed by, or pursuant to the Acts and the Regulations.

2. The Recipient will insert the following notification in all solicitations for bids, Requests For Proposals for work, or material subject to the Acts and the Regulations made in connection with all Federal-Aid Highway Programs and, in adapted form, in all proposals for negotiated agreements regardless of funding source:

> "The Clark County, in accordance with the provisions of Title VI of the Civil Rights Act of 1964 (78 Stat. 252, 42 U.S.C. §§ 2000d to 2000d-4) and the Regulations, hereby notifies all bidders that it will affirmatively ensure that any contract entered into pursuant to this advertisement, disadvantaged business enterprises will be afforded full and fair opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award."

3. The Recipient will insert the clauses of Appendix A and E of this Assurance in every contract or agreement subject to the Acts and the Regulations.

4. The Recipient will insert the clauses of Appendix B of this Assurance, as a covenant running with the land, in any deed from the United States effecting or recording a transfer of real property, structures, use, or improvements thereon or interest therein to a Recipient.

5. That where the Recipient receives Federal financial assistance to construct a facility, or part of a facility, the Assurance will extend to the entire facility and facilities operated in connection therewith.

6. That where the Recipient receives Federal financial assistance in the form, or for the acquisition of real property or an interest in real property, the Assurance will extend to rights to space on, over, or under such property.

7. That the Recipient will include the clauses set forth in Appendix C and Appendix D of this Assurance, as a covenant running with the land, in any future deeds, leases, licenses, permits, or similar instruments entered into by the Recipient with other parties:

   a. for the subsequent transfer of real property acquired or improved under the applicable activity, project, or program; and
   b. for the construction or use of, or access to, space on, over, or under real property acquired or improved under the applicable activity, project, or program.

8. That this Assurance obligates the Recipient for the period during which Federal financial assistance is extended to the program, except where the Federal financial assistance is to provide, or is in the form of, personal property, or real property, or interest therein, or structures or improvements thereon, in which case the Assurance obligates the Recipient, or any transferee for the longer of the following periods:

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

DocuSign Envelope ID: 7146D854-B4BA-492E-9C46-73146FF2E4F7

a. the period during which the property is used for a purpose for which the Federal financial assistance is extended, or for another purpose involving the provision of similar services or benefits; or
b. the period during which the Recipient retains ownership or possession of the property.

9. The Recipient will provide for such methods of administration for the program as are found by the Secretary of Transportation or the official to whom he/she delegates specific authority to give reasonable guarantee that it, other recipients, sub-recipients, sub-grantees, contractors, subcontractors, consultants, transferees, successors in interest, and other participants of Federal financial assistance under such program will comply with all requirements imposed or pursuant to the Acts, the Regulations, and this Assurance.

10. The Recipient agrees that the United States has a right to seek judicial enforcement with regard to any matter arising under the Acts, the Regulations, and this Assurance.

By signing this ASSURANCE, ***Clark County*** also agrees to comply (and require any sub-recipients, sub-grantees, contractors, successors, transferees, and/or assignees to comply) with all applicable provisions governing the Washington State Department of Transportation's access to records, accounts, documents, information, facilities, and staff. You also recognize that you must comply with any program or compliance reviews, and/or complaint investigations conducted by the Washington State Department of Transportation. You must keep records, reports, and submit the material for review upon request to Washington State Department of Transportation, or its designee in a timely, complete, and accurate way. Additionally, you must comply with all other reporting, data collection, and evaluation requirements, as prescribed by law or detailed in program guidance.

Clark County gives this ASSURANCE in consideration of and for obtaining any Federal grants, loans, contracts, agreements, property, and/or discounts, or other Federal-aid and Federal financial assistance extended after the date hereof to the recipients by the U.S. Department of Transportation under the Federal Highway Administration. This ASSURANCE is binding on Washington State Department of Transportation, other recipients, sub-recipients, sub-grantees, contractors, subcontractors and their subcontractors', transferees, successors in interest, and any other participants in the Federal-Aid Highway Program. The person(s) signing below is authorized to sign this ASSURANCE on behalf of the Recipient.

CLARK COUNTY
(***Name of Recipient***)

by Kathleen Otto
(***Signature of Authorized Official***)

DATED 11/08/23

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

DocuSign Envelope ID: 7146D854-B4BA-492E-9C46-73146FF2E4F7

APPENDIX A

During the performance of this contract, the contractor, for itself, its assignees, and successors in interest (hereinafter referred to as the "contractor") agrees as follows:

1. **Compliance with Regulations**: The contractor (hereinafter includes consultants) will comply with the Acts and the Regulations relative to Non-discrimination in Federally-assisted programs of the U.S. Department of Transportation, Washington State Department of Transportation, as they may be amended from time to time, which are herein incorporated by reference and made a part of this contract.

2. **Non-discrimination**: The contractor, with regard to the work performed by it during the contract, will not discriminate on the grounds of race, color, or national origin in the selection and retention of subcontractors, including procurements of materials and leases of equipment. The contractor will not participate directly or indirectly in the discrimination prohibited by the Acts and the Regulations, including employment practices when the contract covers any activity, project, or program set forth in Appendix B of 49 CFR Part 21.

3. **Solicitations for Subcontracts, Including Procurements of Materials and Equipment**: In all solicitations, either by competitive bidding, or negotiation made by the contractor for work to be performed under a subcontract, including procurements of materials, or leases of equipment, each potential subcontractor or supplier will be notified by the contractor of the contractor's obligations under this contract and the Acts and the Regulations relative to Non-discrimination on the grounds of race, color, or national origin.

4. **Information and Reports**: The contractor will provide all information and reports required by the Acts, the Regulations, and directives issued pursuant thereto and will permit access to its books, records, accounts, other sources of information, and its facilities as may be determined by the Recipient or the Washington State Department of Transportation to be pertinent to ascertain compliance with such Acts, Regulations, and instructions. Where any information required of a contractor is in the exclusive possession of another who fails or refuses to furnish the information, the contractor will so certify to the Recipient or the Washington State Department of Transportation, as appropriate, and will set forth what efforts it has made to obtain the information.

5. **Sanctions for Noncompliance**: In the event of a contractor's noncompliance with the Non-discrimination provisions of this contract, the Recipient will impose such contract sanctions as it or the Washington State Department of Transportation may determine to be appropriate, including, but not limited to:

    a. withholding payments to the contractor under the contract until the contractor complies; and/or
    b. cancelling, terminating, or suspending a contract, in whole or in part.

6. **Incorporation of Provisions**: The contractor will include the provisions of paragraphs one through six in every subcontract, including procurements of materials and leases of equipment,

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

DocuSign Envelope ID: 7146D854-B4BA-492E-9C46-73146FF2E4F7

unless exempt by the Acts, the Regulations and directives issued pursuant thereto. The contractor will take action with respect to any subcontract or procurement as the Recipient or the Washington State Department of Transportation may direct as a means of enforcing such provisions including sanctions for noncompliance. Provided, that if the contractor becomes involved in, or is threatened with litigation by a subcontractor, or supplier because of such direction, the contractor may request the Recipient to enter into any litigation to protect the interests of the Recipient. In addition, the contractor may request the United States to enter into the litigation to protect the interests of the United States.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

DocuSign Envelope ID: 7146D854-B4BA-492E-9C46-73146FF2E4F7

APPENDIX E

During the performance of this contract, the contractor, for itself, its assignees, and successors in interest (hereinafter referred to as the "contractor") agrees to comply with the following non-discrimination statutes and authorities; including but not limited to:

Pertinent Non-Discrimination Authorities:

- Title VI of the Civil Rights Act of 1964 (42 U.S.C. § 2000d et seq., 78 stat. 252), (prohibits discrimination on the basis of race, color, national origin); and 49 CFR Part 21.
- The Uniform Relocation Assistance and Real Property Acquisition Policies Act of 1970, (42 U.S.C. § 4601), (prohibits unfair treatment of persons displaced or whose property has been acquired because of Federal or Federal-aid programs and projects);
- Federal-Aid Highway Act of 1973, (23 U.S.C. § 324 et seq.), (prohibits discrimination on the basis of sex);
- Section 504 of the Rehabilitation Act of 1973, (29 U.S.C. § 794 et seq.), as amended, (prohibits discrimination on the basis of disability); and 49 CFR Part 27;
- The Age Discrimination Act of 1975, as amended, (42 U.S.C. § 6101 et seq.), (prohibits discrimination on the basis of age);
- Airport and Airway Improvement Act of 1982, (49 USC § 471, Section 47123), as amended, (prohibits discrimination based on race, creed, color, national origin, or sex);
- The Civil Rights Restoration Act of 1987, (PL 100-209), (Broadened the scope, coverage and applicability of Title VI of the Civil Rights Act of 1964, The Age Discrimination Act of 1975 and Section 504 of the Rehabilitation Act of 1973, by expanding the definition of the terms "programs or activities" to include all of the programs or activities of the Federal-aid recipients, sub-recipients and contractors, whether such programs or activities are Federally funded or not);
- Titles II and III of the Americans with Disabilities Act, which prohibit discrimination on the basis of disability in the operation of public entities, public and private transportation systems, places of public accommodation, and certain testing entities (42 U.S.C. §§ 12131-12189) as implemented by Department of Transportation regulations at 49 C.F.R. parts 37 and 38;
- The Federal Aviation Administration's Non-discrimination statute (49 U.S.C. § 47123) (prohibits discrimination on the basis of race, color, national origin, and sex);
- Executive Order 12898, Federal Actions to Address Environmental Justice in Minority Populations and Low-Income Populations, which ensures Non-discrimination against minority populations by discouraging programs, policies, and activities with disproportionately high and adverse human health or environmental effects on minority and low-income populations;
- Executive Order 13166, Improving Access to Services for Persons with Limited English Proficiency, and resulting agency guidance, national origin discrimination includes discrimination because of Limited English proficiency (LEP). To ensure compliance with Title VI, you must take reasonable steps to ensure that LEP persons have meaningful access to your programs (70 Fed. Reg. at 74087 to 74100);
- Title IX of the Education Amendments of 1972, as amended, which prohibits you from discriminating because of sex in education programs or activities (20 U.S.C. 1681 et seq).

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

BXWA

REQUIRED CONTRACT PROVISIONS
FEDERAL AID CONSTRUCTION CONTRACTS

WHIPPLE, KNAPPS, CARSON BRIDGE BUNDLE
PRJ NO. 0001799 / CRP NO. 320322

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

CONTRACT PROVISIONS FOR FEDERAL-AID CONSTRUCTION CONTRACTS

I. General
II. Nondiscrimination
III. Davis-Bacon and Related Act Provisions
IV. Contract Work Hours and Safety Standards Act Provisions
V. Subletting or Assigning the Contract
VI. Safety: Accident Prevention
VII. False Statements Concerning Highway Projects
VIII. Implementation of Clean Air Act and Federal Water Pollution Control Act
IX. Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion
X. Certification Regarding Use of Contract Funds for Lobbying
XI. Use of United States-Flag Vessels

ATTACHMENTS

A. Employment and Materials Preference for Appalachian Development Highway System or Appalachian Local Access Road Contracts (included in Appalachian contracts only).

I. GENERAL

1. Historically, contracting agencies using Federal-aid highway funds were required to ensure Form FHWA-1273 was physically incorporated into all contracts and subcontracts. Effective June 10, 2026, this requirement was eliminated [91 FR 25492]. Future use of Form FHWA-1273 is now optional on the part of the contracting agency using Federal-aid highway funds. FHWA continues to make Form FHWA-1273 available as a convenience to contracting agencies. Contracting agencies must continue to ensure compliance with the provisions cited in Form FHWA-1273 in accordance with the provisions regardless of the use of Form FHWA-1273. Accordingly, the contracting agency retains the authority to determine whether the contractor must use Form FHWA-1273 to physically incorporate required contract provisions in each subcontract and in lower tier contracts. Where permitted by the contracting agency, the contractor may choose other ways to include required contract provisions in each subcontract, besides incorporating Form FHWA-1273. Contract provisions in Form FHWA-1273 are not required to be physically included in subcontracts for design services on Federal-aid design-build contracts, or in purchase orders, rental agreements and other agreements for supplies or services.

The applicable provisions of Form FHWA-1273 are incorporated by reference for work done under any purchase order, rental agreement or agreement for other services. The prime contractor or design-builder shall be responsible for compliance by any subcontractor, lower-tier subcontractor or service provider.

Contracting agencies may reference Form FHWA-1273 in solicitation-for-bids or request-for-proposals documents.

2. Subject to the applicability criteria noted in the following sections, these contract provisions shall apply to all work performed on the contract by the contractor's own organization and with the assistance of workers under the contractor's immediate superintendence and to all work performed on the contract by piecework, station work, or by subcontract.

3. A breach of any of the stipulations contained in these Required Contract Provisions may be sufficient grounds for withholding of progress payments, withholding of final payment, termination of the contract, suspension / debarment or any other action determined to be appropriate by the contracting agency and FHWA.

4. Selection of Labor: During the performance of this contract, the contractor shall not use convict labor for any purpose within the limits of a construction project on a Federal-aid highway unless it is labor performed by convicts who are on parole, supervised release, or probation. 23 U.S.C. 114(b). The term Federal-aid highway does not include roadways functionally classified as local roads or rural minor collectors. 23 U.S.C. 101(a).

II. NONDISCRIMINATION

The contractor and all subcontractors must comply with the following policies: 29 CFR Parts 1625-1627, 23 U.S.C. 140, Section 504 of the Rehabilitation Act of 1973, as amended (29 U.S.C. 794), Title VI of the Civil Rights Act of 1964, as amended (42 U.S.C. 2000d et seq.), and related regulations including 49 CFR Parts 21, 26, and 27, including any amendments thereto.

Note: The U.S. Department of Labor has exclusive authority to determine compliance with 29 CFR Parts 1625-1627. The contracting agency and the FHWA have the authority and the responsibility to ensure compliance with 23 U.S.C. 140, Section 504 of the Rehabilitation Act of 1973, as amended (29 U.S.C. 794), and Title VI of the Civil Rights Act of 1964, as amended (42 U.S.C. 2000d et seq.), and related regulations including 49 CFR Parts 21, 26, and 27, including any amendments thereto.

The provisions of the Americans with Disabilities Act of 1990 (42 U.S.C. 12101 et seq.) set forth under 28 CFR Part 35 and 29 CFR Part 1630 are incorporated by reference in this contract.

1. Assurances Required:

a. The requirements of 49 CFR Part 26, including any amendments thereto, and the State DOT's FHWA-approved Disadvantaged Business Enterprise (DBE) program are incorporated by reference.

b. The contractor, subrecipient or subcontractor shall not discriminate on the basis of race, color, national origin, or sex in the performance of this contract. The contractor shall carry out applicable requirements of 49 CFR part 26, including any amendments thereto, in the award and administration of DOT-assisted contracts. Failure by the contractor to carry out these requirements is a material breach of this contract, which may result in the termination of this contract or such other remedy as the recipient deems appropriate, which may include, but is not limited to:

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

(1) Withholding monthly progress payments;
(2) Assessing sanctions;
(3) Liquidated damages; and/or
(4) Disqualifying the contractor from future bidding as non-responsible.

c. The Title VI and nondiscrimination provisions of U.S. DOT Order 1050.2A at Appendixes A and E, including any amendments thereto, are incorporated by reference. 49 CFR Part 21.

III. DAVIS-BACON AND RELATED ACT PROVISIONS

This section is applicable to all Federal-aid construction projects exceeding $2,000 and to all related subcontracts and lower-tier subcontracts (regardless of subcontract size), in accordance with 29 CFR 5.5. The requirements apply to all projects located within the right-of-way of a roadway that is functionally classified as Federal-aid highway. 23 U.S.C. 113. This excludes roadways functionally classified as local roads or rural minor collectors, which are exempt. 23 U.S.C. 101. Where applicable law requires that projects be treated as a project on a Federal-aid highway, the provisions of this subpart will apply regardless of the location of the project. Examples include: Surface Transportation Block Grant Program projects funded under 23 U.S.C. 133 [excluding recreational trails projects], the Nationally Significant Freight and Highway Projects funded under 23 U.S.C. 117, and National Highway Freight Program projects funded under 23 U.S.C. 167.

The following provisions are from the U.S. Department of Labor regulations in 29 CFR 5.5 "Contract provisions and related matters" with minor revisions to conform to the FHWA-1273 format and FHWA program requirements.

1. Minimum wages (29 CFR 5.5)

a. *Wage rates and fringe benefits.* All laborers and mechanics employed or working upon the site of the work (or otherwise working in construction or development of the project under a development statute), will be paid unconditionally and not less often than once a week, and without subsequent deduction or rebate on any account (except such payroll deductions as are permitted by regulations issued by the Secretary of Labor under the Copeland Act (29 CFR part 3)), the full amount of basic hourly wages and bona fide fringe benefits (or cash equivalents thereof) due at time of payment computed at rates not less than those contained in the wage determination of the Secretary of Labor which is attached hereto and made a part hereof, regardless of any contractual relationship which may be alleged to exist between the contractor and such laborers and mechanics. As provided in paragraphs (d) and (e) of 29 CFR 5.5, the appropriate wage determinations are effective by operation of law even if they have not been attached to the contract. Contributions made or costs reasonably anticipated for bona fide fringe benefits under the Davis-Bacon Act (40 U.S.C. 3141(2)(B)) on behalf of laborers or mechanics are considered wages paid to such laborers or mechanics, subject to the provisions of paragraph 1.e. of this section; also, regular contributions made or costs incurred for more than a weekly period (but not less often than quarterly) under plans, funds, or programs which cover the particular weekly period, are deemed to be constructively made or incurred during such weekly period. Such laborers and mechanics must be paid the appropriate wage rate and fringe benefits on the wage determination for the classification(s) of work actually performed, without regard to skill, except as provided in paragraph 4. of this section. Laborers or mechanics performing work in more than one classification may be compensated at the rate specified for each classification for the time actually worked therein: *Provided,* That the employer's payroll records accurately set forth the time spent in each classification in which work is performed. The wage determination (including any additional classifications and wage rates conformed under paragraph 1.c. of this section) and the Davis-Bacon poster (WH–1321) must be posted at all times by the contractor and its subcontractors at the site of the work in a prominent and accessible place where it can be easily seen by the workers.

b. *Frequently recurring classifications.* (1) In addition to wage and fringe benefit rates that have been determined to be prevailing under the procedures set forth in 29 CFR part 1, a wage determination may contain, pursuant to § 1.3(f), wage and fringe benefit rates for classifications of laborers and mechanics for which conformance requests are regularly submitted pursuant to paragraph 1.c. of this section, provided that:

(i) The work performed by the classification is not performed by a classification in the wage determination for which a prevailing wage rate has been determined;

(ii) The classification is used in the area by the construction industry; and

(iii) The wage rate for the classification bears a reasonable relationship to the prevailing wage rates contained in the wage determination.

(2) The Administrator will establish wage rates for such classifications in accordance with paragraph 1.c.(1)(iii) of this section. Work performed in such a classification must be paid at no less than the wage and fringe benefit rate listed on the wage determination for such classification.

c. *Conformance.* (1) The contracting officer must require that any class of laborers or mechanics, including helpers, which is not listed in the wage determination and which is to be employed under the contract be classified in conformance with the wage determination. Conformance of an additional classification and wage rate and fringe benefits is appropriate only when the following criteria have been met:

(i) The work to be performed by the classification requested is not performed by a classification in the wage determination; and

(ii) The classification is used in the area by the construction industry; and

(iii) The proposed wage rate, including any bona fide fringe benefits, bears a reasonable relationship to the wage rates contained in the wage determination.

(2) The conformance process may not be used to split, subdivide, or otherwise avoid application of classifications listed in the wage determination.

(3) If the contractor and the laborers and mechanics to be employed in the classification (if known), or their representatives, and the contracting officer agree on the

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

classification and wage rate (including the amount designated for fringe benefits where appropriate), a report of the action taken will be sent by the contracting officer by email to DBAconformance@dol.gov. The Administrator, or an authorized representative, will approve, modify, or disapprove every additional classification action within 30 days of receipt and so advise the contracting officer or will notify the contracting officer within the 30–day period that additional time is necessary.

(4) In the event the contractor, the laborers or mechanics to be employed in the classification or their representatives, and the contracting officer do not agree on the proposed classification and wage rate (including the amount designated for fringe benefits, where appropriate), the contracting officer will, by email to DBAconformance@dol.gov, refer the questions, including the views of all interested parties and the recommendation of the contracting officer, to the Administrator for determination. The Administrator, or an authorized representative, will issue a determination within 30 days of receipt and so advise the contracting officer or will notify the contracting officer within the 30–day period that additional time is necessary.

(5) The contracting officer must promptly notify the contractor of the action taken by the Wage and Hour Division under paragraphs 1.c.(3) and (4) of this section. The contractor must furnish a written copy of such determination to each affected worker or it must be posted as a part of the wage determination. The wage rate (including fringe benefits where appropriate) determined pursuant to paragraph 1.c.(3) or (4) of this section must be paid to all workers performing work in the classification under this contract from the first day on which work is performed in the classification.

d. *Fringe benefits not expressed as an hourly rate.* Whenever the minimum wage rate prescribed in the contract for a class of laborers or mechanics includes a fringe benefit which is not expressed as an hourly rate, the contractor may either pay the benefit as stated in the wage determination or may pay another bona fide fringe benefit or an hourly cash equivalent thereof.

e. *Unfunded plans.* If the contractor does not make payments to a trustee or other third person, the contractor may consider as part of the wages of any laborer or mechanic the amount of any costs reasonably anticipated in providing bona fide fringe benefits under a plan or program, *Provided,* That the Secretary of Labor has found, upon the written request of the contractor, in accordance with the criteria set forth in § 5.28, that the applicable standards of the Davis-Bacon Act have been met. The Secretary of Labor may require the contractor to set aside in a separate account assets for the meeting of obligations under the plan or program.

f. *Interest.* In the event of a failure to pay all or part of the wages required by the contract, the contractor will be required to pay interest on any underpayment of wages.

2. Withholding (29 CFR 5.5)

a. *Withholding requirements.* The contracting agency may, upon its own action, or must, upon written request of an authorized representative of the Department of Labor, withhold or cause to be withheld from the contractor so much of the accrued payments or advances as may be considered necessary to satisfy the liabilities of the prime contractor or any subcontractor for the full amount of wages and monetary relief, including interest, required by the clauses set forth in this section for violations of this contract, or to satisfy any such liabilities required by any other Federal contract, or federally assisted contract subject to Davis-Bacon labor standards, that is held by the same prime contractor (as defined in § 5.2). The necessary funds may be withheld from the contractor under this contract, any other Federal contract with the same prime contractor, or any other federally assisted contract that is subject to Davis-Bacon labor standards requirements and is held by the same prime contractor, regardless of whether the other contract was awarded or assisted by the same agency, and such funds may be used to satisfy the contractor liability for which the funds were withheld. In the event of a contractor's failure to pay any laborer or mechanic, including any apprentice or helper working on the site of the work all or part of the wages required by the contract, or upon the contractor's failure to submit the required records as discussed in paragraph 3.d. of this section, the contracting agency may on its own initiative and after written notice to the contractor, take such action as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds until such violations have ceased.

b. *Priority to withheld funds.* The Department has priority to funds withheld or to be withheld in accordance with paragraph 2.a. of this section or Section IV, paragraph 3.a., or both, over claims to those funds by:

(1) A contractor's surety(ies), including without limitation performance bond sureties and payment bond sureties;

(2) A contracting agency for its reprocurement costs;

(3) A trustee(s) (either a court-appointed trustee or a U.S. trustee, or both) in bankruptcy of a contractor, or a contractor's bankruptcy estate;

(4) A contractor's assignee(s);

(5) A contractor's successor(s); or

(6) A claim asserted under the Prompt Payment Act, 31 U.S.C. 3901–3907.

3. Records and certified payrolls (29 CFR 5.5)

a. *Basic record requirements* (1) *Length of record retention.* All regular payrolls and other basic records must be maintained by the contractor and any subcontractor during the course of the work and preserved for all laborers and mechanics working at the site of the work (or otherwise working in construction or development of the project under a development statute) for a period of at least 3 years after all the work on the prime contract is completed.

(2) *Information required.* Such records must contain the name; Social Security number; last known address, telephone number, and email address of each such worker; each worker's correct classification(s) of work actually performed; hourly rates of wages paid (including rates of contributions or costs anticipated for bona fide fringe benefits or cash equivalents thereof of the types described in 40 U.S.C. 3141(2)(B) of the Davis-Bacon Act); daily and weekly number

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

of hours actually worked in total and on each covered contract; deductions made; and actual wages paid.

(3) *Additional records relating to fringe benefits.* Whenever the Secretary of Labor has found under paragraph 1.e. of this section that the wages of any laborer or mechanic include the amount of any costs reasonably anticipated in providing benefits under a plan or program described in 40 U.S.C. 3141(2)(B) of the Davis-Bacon Act, the contractor must maintain records which show that the commitment to provide such benefits is enforceable, that the plan or program is financially responsible, and that the plan or program has been communicated in writing to the laborers or mechanics affected, and records which show the costs anticipated or the actual cost incurred in providing such benefits.

(4) *Additional records relating to apprenticeship.* Contractors with apprentices working under approved programs must maintain written evidence of the registration of apprenticeship programs, the registration of the apprentices, and the ratios and wage rates prescribed in the applicable programs.

b. *Certified payroll requirements* (1) *Frequency and method of submission.* The contractor or subcontractor must submit weekly, for each week in which any DBA- or Related Acts-covered work is performed, certified payrolls to the contracting agency. The prime contractor is responsible for the submission of all certified payrolls by all subcontractors. A contracting agency or prime contractor may permit or require contractors to submit certified payrolls through an electronic system, as long as the electronic system requires a legally valid electronic signature; the system allows the contractor, the contracting agency, and the Department of Labor to access the certified payrolls upon request for at least 3 years after the work on the prime contract has been completed; and the contracting agency or prime contractor permits other methods of submission in situations where the contractor is unable or limited in its ability to use or access the electronic system.

(2) *Information required.* The certified payrolls submitted must set out accurately and completely all of the information required to be maintained under paragraph 3.a.(2) of this section, except that full Social Security numbers and last known addresses, telephone numbers, and email addresses must not be included on weekly transmittals. Instead, the certified payrolls need only include an individually identifying number for each worker (*e.g.,* the last four digits of the worker's Social Security number). The required weekly certified payroll information may be submitted using Optional Form WH–347 or in any other format desired. Optional Form WH–347 is available for this purpose from the Wage and Hour Division website at *https://www.dol.gov/sites/dolgov/files/WHD/legacy/files/wh347.pdf* or its successor website. It is not a violation of this section for a prime contractor to require a subcontractor to provide full Social Security numbers and last known addresses, telephone numbers, and email addresses to the prime contractor for its own records, without weekly submission by the subcontractor to the contracting agency.

(3) *Statement of Compliance.* Each certified payroll submitted must be accompanied by a "Statement of Compliance," signed by the contractor or subcontractor, or the contractor's or subcontractor's agent who pays or supervises the payment of the persons working on the contract, and must certify the following:

(i) That the certified payroll for the payroll period contains the information required to be provided under paragraph 3.b. of this section, the appropriate information and basic records are being maintained under paragraph 3.a. of this section, and such information and records are correct and complete;

(ii) That each laborer or mechanic (including each helper and apprentice) working on the contract during the payroll period has been paid the full weekly wages earned, without rebate, either directly or indirectly, and that no deductions have been made either directly or indirectly from the full wages earned, other than permissible deductions as set forth in 29 CFR part 3; and

(iii) That each laborer or mechanic has been paid not less than the applicable wage rates and fringe benefits or cash equivalents for the classification(s) of work actually performed, as specified in the applicable wage determination incorporated into the contract.

(4) *Use of Optional Form WH–347.* The weekly submission of a properly executed certification set forth on the reverse side of Optional Form WH–347 will satisfy the requirement for submission of the "Statement of Compliance" required by paragraph 3.b.(3) of this section.

(5) *Signature.* The signature by the contractor, subcontractor, or the contractor's or subcontractor's agent must be an original handwritten signature or a legally valid electronic signature.

(6) *Falsification.* The falsification of any of the above certifications may subject the contractor or subcontractor to civil or criminal prosecution under 18 U.S.C. 1001 and 31 U.S.C. 3729.

(7) *Length of certified payroll retention.* The contractor or subcontractor must preserve all certified payrolls during the course of the work and for a period of 3 years after all the work on the prime contract is completed.

c. *Contracts, subcontracts, and related documents.* The contractor or subcontractor must maintain this contract or subcontract and related documents including, without limitation, bids, proposals, amendments, modifications, and extensions. The contractor or subcontractor must preserve these contracts, subcontracts, and related documents during the course of the work and for a period of 3 years after all the work on the prime contract is completed.

d. *Required disclosures and access* (1) *Required record disclosures and access to workers.* The contractor or subcontractor must make the records required under paragraphs 3.a. through 3.c. of this section, and any other documents that the contracting agency, the State DOT, the FHWA, or the Department of Labor deems necessary to determine compliance with the labor standards provisions of any of the applicable statutes referenced by § 5.1, available for inspection, copying, or transcription by authorized representatives of the contracting agency, the State DOT, the FHWA, or the Department of Labor, and must permit such representatives to interview workers during working hours on the job.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

(2) *Sanctions for non-compliance with records and worker access requirements.* If the contractor or subcontractor fails to submit the required records or to make them available, or refuses to permit worker interviews during working hours on the job, the Federal agency may, after written notice to the contractor, sponsor, applicant, owner, or other entity, as the case may be, that maintains such records or that employs such workers, take such action as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds. Furthermore, failure to submit the required records upon request or to make such records available, or to permit worker interviews during working hours on the job, may be grounds for debarment action pursuant to § 5.12. In addition, any contractor or other person that fails to submit the required records or make those records available to WHD within the time WHD requests that the records be produced will be precluded from introducing as evidence in an administrative proceeding under 29 CFR part 6 any of the required records that were not provided or made available to WHD. WHD will take into consideration a reasonable request from the contractor or person for an extension of the time for submission of records. WHD will determine the reasonableness of the request and may consider, among other things, the location of the records and the volume of production.

(3) *Required information disclosures.* Contractors and subcontractors must maintain the full Social Security number and last known address, telephone number, and email address of each covered worker, and must provide them upon request to the contracting agency, the State DOT, the FHWA, the contractor, or the Wage and Hour Division of the Department of Labor for purposes of an investigation or other compliance action.

4. Apprentices and equal employment opportunity (29 CFR 5.5)

a. *Apprentices* (1) *Rate of pay.* Apprentices will be permitted to work at less than the predetermined rate for the work they perform when they are employed pursuant to and individually registered in a bona fide apprenticeship program registered with the U.S. Department of Labor, Employment and Training Administration, Office of Apprenticeship (OA), or with a State Apprenticeship Agency recognized by the OA. A person who is not individually registered in the program, but who has been certified by the OA or a State Apprenticeship Agency (where appropriate) to be eligible for probationary employment as an apprentice, will be permitted to work at less than the predetermined rate for the work they perform in the first 90 days of probationary employment as an apprentice in such a program. In the event the OA or a State Apprenticeship Agency recognized by the OA withdraws approval of an apprenticeship program, the contractor will no longer be permitted to use apprentices at less than the applicable predetermined rate for the work performed until an acceptable program is approved.

(2) *Fringe benefits.* Apprentices must be paid fringe benefits in accordance with the provisions of the apprenticeship program. If the apprenticeship program does not specify fringe benefits, apprentices must be paid the full amount of fringe benefits listed on the wage determination for the applicable classification. If the Administrator determines that a different practice prevails for the applicable apprentice classification, fringe benefits must be paid in accordance with that determination.

(3) *Apprenticeship ratio.* The allowable ratio of apprentices to journeyworkers on the job site in any craft classification must not be greater than the ratio permitted to the contractor as to the entire work force under the registered program or the ratio applicable to the locality of the project pursuant to paragraph 4.a.(4) of this section. Any worker listed on a payroll at an apprentice wage rate, who is not registered or otherwise employed as stated in paragraph 4.a.(1) of this section, must be paid not less than the applicable wage rate on the wage determination for the classification of work actually performed. In addition, any apprentice performing work on the job site in excess of the ratio permitted under this section must be paid not less than the applicable wage rate on the wage determination for the work actually performed.

(4) *Reciprocity of ratios and wage rates.* Where a contractor is performing construction on a project in a locality other than the locality in which its program is registered, the ratios and wage rates (expressed in percentages of the journeyworker's hourly rate) applicable within the locality in which the construction is being performed must be observed. If there is no applicable ratio or wage rate for the locality of the project, the ratio and wage rate specified in the contractor's registered program must be observed.

b. *Equal employment opportunity.* The use of apprentices and journeyworkers under this part must be in conformity with 29 CFR part 30, including any amendments thereto.

c. Apprentices and Trainees (programs of the U.S. DOT).

Apprentices and trainees working under apprenticeship and skill training programs which have been certified by the Secretary of Transportation as promoting EEO in connection with Federal-aid highway construction programs are not subject to the requirements of paragraph 4 of this Section III. 23 CFR 230.111(e)(2). The straight time hourly wage rates for apprentices and trainees under such programs will be established by the particular programs. The ratio of apprentices and trainees to journeyworkers shall not be greater than permitted by the terms of the particular program.

5. Compliance with Copeland Act requirements. The contractor shall comply with the requirements of 29 CFR part 3, which are incorporated by reference in this contract as provided in 29 CFR 5.5.

6. Subcontracts. The contractor or subcontractor must insert in any subcontracts the clauses set forth in paragraphs (1) through (11) of this section, along with the applicable wage determination(s) and such other clauses or contract modifications as the contracting agency may by appropriate instructions require, and a clause requiring the subcontractors to include these clauses and wage determination(s) in any lower tier subcontracts. The prime contractor is responsible for the compliance by any subcontractor or lower tier subcontractor with all the contract clauses in this section. In the event of any violations of these clauses, the prime contractor and any subcontractor(s) responsible will be liable for any unpaid wages and monetary relief, including interest from the date of the underpayment or loss, due to any workers of lower-tier subcontractors, and may be subject to debarment, as appropriate. 29 CFR 5.5.

7. Contract termination: debarment. A breach of the contract clauses in 29 CFR 5.5 may be grounds for termination of the

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

contract, and for debarment as a contractor and a subcontractor as provided in 29 CFR 5.12.

8. Compliance with Davis-Bacon and Related Act requirements. All rulings and interpretations of the Davis-Bacon and Related Acts contained in 29 CFR parts 1, 3, and 5 are herein incorporated by reference in this contract as provided in 29 CFR 5.5.

9. Disputes concerning labor standards. As provided in 29 CFR 5.5, disputes arising out of the labor standards provisions of this contract shall not be subject to the general disputes clause of this contract. Such disputes shall be resolved in accordance with the procedures of the Department of Labor set forth in 29 CFR parts 5, 6, and 7. Disputes within the meaning of this clause include disputes between the contractor (or any of its subcontractors) and the contracting agency, the U.S. Department of Labor, or the employees or their representatives.

10. Certification of eligibility. a. By entering into this contract, the contractor certifies that neither it nor any person or firm who has an interest in the contractor's firm is a person or firm ineligible to be awarded Government contracts by virtue of 40 U.S.C. 3144(b) or § 5.12(a).

b. No part of this contract shall be subcontracted to any person or firm ineligible for award of a Government contract by virtue of 40 U.S.C. 3144(b) or § 5.12(a).

c. The penalty for making false statements is prescribed in the U.S. Code, Title 18 Crimes and Criminal Procedure, 18 U.S.C. 1001.

11. Anti-retaliation. It is unlawful for any person to discharge, demote, intimidate, threaten, restrain, coerce, blacklist, harass, or in any other manner discriminate against, or to cause any person to discharge, demote, intimidate, threaten, restrain, coerce, blacklist, harass, or in any other manner discriminate against, any worker or job applicant for:

a. Notifying any contractor of any conduct which the worker reasonably believes constitutes a violation of the DBA, Related Acts, this part, or 29 CFR part 1 or 3;

b. Filing any complaint, initiating or causing to be initiated any proceeding, or otherwise asserting or seeking to assert on behalf of themselves or others any right or protection under the DBA, Related Acts, this part, or 29 CFR part 1 or 3;

c. Cooperating in any investigation or other compliance action, or testifying in any proceeding under the DBA, Related Acts, this part, or 29 CFR part 1 or 3; or

d. Informing any other person about their rights under the DBA, Related Acts, this part, or 29 CFR part 1 or 3.

IV. CONTRACT WORK HOURS AND SAFETY STANDARDS ACT

Pursuant to 29 CFR 5.5(b), the following clauses apply to any Federal-aid construction contract in an amount in excess of $100,000 and subject to the overtime provisions of the Contract Work Hours and Safety Standards Act. These clauses shall be inserted in addition to the clauses required by 29 CFR 5.5(a) or 29 CFR 4.6. As used in this paragraph, the terms laborers and mechanics include watchpersons and guards.

1. Overtime requirements. No contractor or subcontractor contracting for any part of the contract work which may require or involve the employment of laborers or mechanics shall require or permit any such laborer or mechanic in any workweek in which he or she is employed on such work to work in excess of forty hours in such workweek unless such laborer or mechanic receives compensation at a rate not less than one and one-half times the basic rate of pay for all hours worked in excess of forty hours in such workweek. 29 CFR 5.5.

2. Violation; liability for unpaid wages; liquidated damages. In the event of any violation of the clause set forth in paragraph 1. of this section the contractor and any subcontractor responsible therefor shall be liable for the unpaid wages and interest from the date of the underpayment. In addition, such contractor and subcontractor shall be liable to the United States (in the case of work done under contract for the District of Columbia or a territory, to such District or to such territory), for liquidated damages. Such liquidated damages shall be computed with respect to each individual laborer or mechanic, including watchpersons and guards, employed in violation of the clause set forth in paragraph 1. of this section, in the sum currently provided in 29 CFR 5.5(b)(2)* for each calendar day on which such individual was required or permitted to work in excess of the standard workweek of forty hours without payment of the overtime wages required by the clause set forth in paragraph 1. of this section.

* $33 as of January 15, 2025 (See 90 FR 1859) as may be adjusted annually by the Department of Labor, pursuant to the Federal Civil Penalties Inflation Adjustment Act of 1990.

3. Withholding for unpaid wages and liquidated damages

a. *Withholding process*. The FHWA or the contracting agency may, upon its own action, or must, upon written request of an authorized representative of the Department of Labor, withhold or cause to be withheld from the contractor so much of the accrued payments or advances as may be considered necessary to satisfy the liabilities of the prime contractor or any subcontractor for any unpaid wages; monetary relief, including interest; and liquidated damages required by the clauses set forth in this section on this contract, any other Federal contract with the same prime contractor, or any other federally assisted contract subject to the Contract Work Hours and Safety Standards Act that is held by the same prime contractor (as defined in § 5.2). The necessary funds may be withheld from the contractor under this contract, any other Federal contract with the same prime contractor, or any other federally assisted contract that is subject to the Contract Work Hours and Safety Standards Act and is held by the same prime contractor, regardless of whether the other contract was awarded or assisted by the same agency, and such funds may be used to satisfy the contractor liability for which the funds were withheld.

b. *Priority to withheld funds*. The Department has priority to funds withheld or to be withheld in accordance with Section III paragraph 2.a. or paragraph 3.a. of this section, or both, over claims to those funds by:

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

(1) A contractor's surety(ies), including without limitation performance bond sureties and payment bond sureties;

(2) A contracting agency for its reprocurement costs;

(3) A trustee(s) (either a court-appointed trustee or a U.S. trustee, or both) in bankruptcy of a contractor, or a contractor's bankruptcy estate;

(4) A contractor's assignee(s);

(5) A contractor's successor(s); or

(6) A claim asserted under the Prompt Payment Act, 31 U.S.C. 3901–3907.

4. Subcontracts. The contractor or subcontractor must insert in any subcontracts the clauses set forth in paragraphs 1. through 5. of this section and a clause requiring the subcontractors to include these clauses in any lower tier subcontracts. The prime contractor is responsible for compliance by any subcontractor or lower tier subcontractor with the clauses set forth in paragraphs 1. through 5. In the event of any violations of these clauses, the prime contractor and any subcontractor(s) responsible will be liable for any unpaid wages and monetary relief, including interest from the date of the underpayment or loss, due to any workers of lower-tier subcontractors, and associated liquidated damages and may be subject to debarment, as appropriate.

5. Anti-retaliation. It is unlawful for any person to discharge, demote, intimidate, threaten, restrain, coerce, blacklist, harass, or in any other manner discriminate against, or to cause any person to discharge, demote, intimidate, threaten, restrain, coerce, blacklist, harass, or in any other manner discriminate against, any worker or job applicant for:

a. Notifying any contractor of any conduct which the worker reasonably believes constitutes a violation of the Contract Work Hours and Safety Standards Act (CWHSSA) or its implementing regulations in this part;

b. Filing any complaint, initiating or causing to be initiated any proceeding, or otherwise asserting or seeking to assert on behalf of themselves or others any right or protection under CWHSSA or this part;

c. Cooperating in any investigation or other compliance action, or testifying in any proceeding under CWHSSA or this part; or

d. Informing any other person about their rights under CWHSSA or this part.

V. SUBLETTING OR ASSIGNING THE CONTRACT

This provision is applicable to all Federal-aid construction contracts on the National Highway System pursuant to 23 CFR 635.116.

1. The contractor shall perform with its own organization contract work amounting to not less than 30 percent (or a greater percentage if specified elsewhere in the contract) of the total original contract price, excluding any specialty items designated by the contracting agency. Specialty items may be performed by subcontract and the amount of any such specialty items performed may be deducted from the total original contract price before computing the amount of work required to be performed by the contractor's own organization (23 CFR 635.116).

a. The term “perform work with its own organization” in paragraph 1. of this section refers to workers employed or leased by the prime contractor, and equipment owned or rented by the prime contractor, with or without operators. Such term does not include employees or equipment of a subcontractor or lower tier subcontractor, agents of the prime contractor, or any other assignees. The term may include payments for the costs of hiring leased employees from an employee leasing firm meeting all relevant Federal and State regulatory requirements. Leased employees may only be included in this term if the prime contractor meets all of the following conditions: (based on longstanding interpretation)

(1) the prime contractor maintains control over the supervision of the day-to-day activities of the leased employees;
(2) the prime contractor remains responsible for the quality of the work of the leased employees;
(3) the prime contractor retains all power to accept or exclude individual employees from work on the project; and
(4) the prime contractor remains ultimately responsible for the payment of predetermined minimum wages, the submission of payrolls, statements of compliance and all other Federal regulatory requirements.

b. "Specialty Items" shall be construed to be limited to work that requires highly specialized knowledge, abilities, or equipment not ordinarily available in the type of contracting organizations qualified and expected to bid or propose on the contract as a whole and in general are to be limited to minor components of the overall contract. 23 CFR 635.102.

2. Pursuant to 23 CFR 635.116(a), the contract amount upon which the requirements set forth in paragraph 1. of this section is computed includes the cost of material and manufactured products which are to be purchased or produced by the contractor under the contract provisions.

3. Pursuant to 23 CFR 635.116(c), the contractor shall furnish (a) a competent superintendent or supervisor who is employed by the firm, has full authority to direct performance of the work in accordance with the contract requirements, and is in charge of all construction operations (regardless of who performs the work) and (b) such other of its own organizational resources (supervision, management, and engineering services) as the contracting officer determines is necessary to assure the performance of the contract.

4. No portion of the contract shall be sublet, assigned or otherwise disposed of except with the written consent of the contracting officer, or authorized representative, and such consent when given shall not be construed to relieve the contractor of any responsibility for the fulfillment of the contract. Written consent will be given only after the contracting agency has assured that each subcontract is evidenced in writing and that it contains all pertinent provisions and requirements of the prime contract. (based on long-standing interpretation of 23 CFR 635.116).

5. The 30-percent self-performance requirement of paragraph (1) is not applicable to design-build contracts; however,

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

contracting agencies may establish their own self-performance requirements. 23 CFR 635.116(d).

VI. SAFETY: ACCIDENT PREVENTION

This provision is applicable to all Federal-aid construction contracts and to all related subcontracts.

1. In the performance of this contract the contractor shall comply with all applicable Federal, State, and local laws governing safety, health, and sanitation (23 CFR Part 635). The contractor shall provide all safeguards, safety devices and protective equipment and take any other needed actions as it determines, or as the contracting officer may determine, to be reasonably necessary to protect the life and health of employees on the job and the safety of the public and to protect property in connection with the performance of the work covered by the contract. 23 CFR 635.108.

2. It is a condition of this contract, and shall be made a condition of each subcontract, which the contractor enters into pursuant to this contract, that the contractor and any subcontractor shall not permit any employee, in performance of the contract, to work in surroundings or under conditions which are unsanitary, hazardous or dangerous to his/her health or safety, as determined under construction safety and health standards (29 CFR Part 1926) promulgated by the Secretary of Labor, in accordance with Section 107 of the Contract Work Hours and Safety Standards Act (40 U.S.C. 3704). 29 CFR 1926.10.

3. Pursuant to 29 CFR 1926.3, it is a condition of this contract that the Secretary of Labor or authorized representative thereof, shall have right of entry to any site of contract performance to inspect or investigate the matter of compliance with the construction safety and health standards and to carry out the duties of the Secretary under Section 107 of the Contract Work Hours and Safety Standards Act (40 U.S.C. 3704).

VII. FALSE STATEMENTS CONCERNING HIGHWAY PROJECTS

This provision is applicable to all Federal-aid construction contracts and to all related subcontracts.

In order to assure high quality and durable construction in conformity with approved plans and specifications and a high degree of reliability on statements and representations made by engineers, contractors, suppliers, and workers on Federal-aid highway projects, it is essential that all persons concerned with the project perform their functions as carefully, thoroughly, and honestly as possible. Willful falsification, distortion, or misrepresentation with respect to any facts related to the project is a violation of Federal law. To prevent any misunderstanding regarding the seriousness of these and similar acts, Form FHWA-1022 shall be posted on each Federal-aid highway project (23 CFR Part 635) in one or more places where it is readily available to all persons concerned with the project:

18 U.S.C. 1020 reads as follows:

"Whoever, being an officer, agent, or employee of the United States, or of any State or Territory, or whoever, whether a person, association, firm, or corporation, knowingly makes any false statement, false representation, or false report as to the character, quality, quantity, or cost of the material used or to be used, or the quantity or quality of the work performed or to be performed, or the cost thereof in connection with the submission of plans, maps, specifications, contracts, or costs of construction on any highway or related project submitted for approval to the Secretary of Transportation; or

Whoever knowingly makes any false statement, false representation, false report or false claim with respect to the character, quality, quantity, or cost of any work performed or to be performed, or materials furnished or to be furnished, in connection with the construction of any highway or related project approved by the Secretary of Transportation; or

Whoever knowingly makes any false statement or false representation as to material fact in any statement, certificate, or report submitted pursuant to provisions of the Federal-aid Roads Act approved July 11, 1916, (39 Stat. 355), as amended and supplemented;

Shall be fined under this title or imprisoned not more than 5 years or both."

VIII. IMPLEMENTATION OF CLEAN AIR ACT AND FEDERAL WATER POLLUTION CONTROL ACT (42 U.S.C. 7606; 2 CFR 200.88; EO 11738)

This provision is applicable to all Federal-aid construction contracts in excess of $150,000 and to all related subcontracts. 48 CFR 2.101; 2 CFR 200.327.

By submission of this bid/proposal or the execution of this contract or subcontract, as appropriate, the bidder, proposer, Federal-aid construction contractor, subcontractor, supplier, or vendor agrees to comply with all applicable standards, orders or regulations issued pursuant to the Clean Air Act (42 U.S.C. 7401-7671q) and the Federal Water Pollution Control Act, as amended (33 U.S.C. 1251-1387). Violations must be reported to the Federal Highway Administration and the Regional Office of the Environmental Protection Agency. 2 CFR Part 200, Appendix II.

The contractor agrees to include or cause to be included the requirements of this Section in every subcontract, and further agrees to take such action as the contracting agency may direct as a means of enforcing such requirements. 2 CFR 200.327.

IX. CERTIFICATION REGARDING DEBARMENT, SUSPENSION, INELIGIBILITY AND VOLUNTARY EXCLUSION

This provision is applicable to all Federal-aid construction contracts, design-build contracts, subcontracts, lower-tier subcontracts, purchase orders, lease agreements, consultant contracts or any other covered transaction requiring FHWA approval or that is estimated to cost $25,000 or more – as defined in 2 CFR Parts 180 and 1200. 2 CFR 180.220 and 1200.220.

1**. Instructions for Certification – First Tier Participants:**

a. By signing and submitting this proposal, the prospective first tier participant is providing the certification set out below.

b. The inability of a person to provide the certification set out below will not necessarily result in denial of participation in this

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

covered transaction. The prospective first tier participant shall submit an explanation of why it cannot provide the certification set out below. The certification or explanation will be considered in connection with the department or agency's determination whether to enter into this transaction. However, failure of the prospective first tier participant to furnish a certification or an explanation shall disqualify such a person from participation in this transaction. 2 CFR 180.320.

c. The certification in this clause is a material representation of fact upon which reliance was placed when the contracting agency determined to enter into this transaction. If it is later determined that the prospective participant knowingly rendered an erroneous certification, in addition to other remedies available to the Federal Government, the contracting agency may terminate this transaction for cause of default. 2 CFR 180.325.

d. The prospective first tier participant shall provide immediate written notice to the contracting agency to whom this proposal is submitted if any time the prospective first tier participant learns that its certification was erroneous when submitted or has become erroneous by reason of changed circumstances. 2 CFR 180.345 and 180.350.

e. The terms "covered transaction," "debarred," "suspended," "ineligible," "participant," "person," "principal," and "voluntarily excluded," as used in this clause, are defined in 2 CFR Parts 180, Subpart I, 180.900-180.1020, and 1200. “First Tier Covered Transactions” refers to any covered transaction between a recipient or subrecipient of Federal funds and a participant (such as the prime or general contract). “Lower Tier Covered Transactions” refers to any covered transaction under a First Tier Covered Transaction (such as subcontracts). “First Tier Participant” refers to the participant who has entered into a covered transaction with a recipient or subrecipient of Federal funds (such as the prime or general contractor). “Lower Tier Participant” refers any participant who has entered into a covered transaction with a First Tier Participant or other Lower Tier Participants (such as subcontractors and suppliers).

f. The prospective first tier participant agrees by submitting this proposal that, should the proposed covered transaction be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department or agency entering into this transaction. 2 CFR 180.330.

g. The prospective first tier participant further agrees by submitting this proposal that it will include the clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transactions," provided by the department or contracting agency, entering into this covered transaction, without modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions exceeding the $25,000 threshold. 2 CFR 180.220 and 180.300.

h. A participant in a covered transaction may rely upon a certification of a prospective participant in a lower tier covered transaction that is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. 2 CFR 180.300; 180.320, and 180.325. A participant is responsible for ensuring that its principals are not suspended, debarred, or otherwise ineligible to participate in covered transactions. 2 CFR 180.335. To verify the eligibility of its principals, as well as the eligibility of any lower tier prospective participants, each participant may, but is not required to, check the System for Award Management website (https://www.sam.gov/). 2 CFR 180.300, 180.320, and 180.325.

i. Nothing contained in the foregoing shall be construed to require the establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of the prospective participant is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.

j. Except for transactions authorized under paragraph (f) of these instructions, if a participant in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible, or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department or agency may terminate this transaction for cause or default. 2 CFR 180.325.

* * * * *

2. Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion – First Tier Participants:

a. The prospective first tier participant certifies to the best of its knowledge and belief, that it and its principals:

(1) Are not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participating in covered transactions by any Federal department or agency, 2 CFR 180.335;

(2) Have not within a three-year period preceding this proposal been convicted of or had a civil judgment rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, State, or local) transaction or contract under a public transaction; violation of Federal or State antitrust statutes or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements, or receiving stolen property, 2 CFR 180.800;

(3) Are not presently indicted for or otherwise criminally or civilly charged by a governmental entity (Federal, State or local) with commission of any of the offenses enumerated in paragraph (a)(2) of this certification, 2 CFR 180.700 and 180.800; and

(4) Have not within a three-year period preceding this application/proposal had one or more public transactions (Federal, State or local) terminated for cause or default. 2 CFR 180.335(d).

(5) Are not a corporation that has been convicted of a felony violation under any Federal law within the two-year period preceding this proposal (USDOT Order 4200.6 implementing appropriations act requirements); and

(6) Are not a corporation with any unpaid Federal tax liability that has been assessed, for which all judicial and administrative remedies have been exhausted, or have lapsed, and that is not being paid in a timely manner pursuant to an agreement with the authority responsible for collecting the tax liability (USDOT Order 4200.6 implementing appropriations act requirements).

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

b. Where the prospective participant is unable to certify to any of the statements in this certification, such prospective participant should attach an explanation to this proposal. 2 CFR 180.335 and 180.340.

* * * * *

3. **Instructions for Certification - Lower Tier Participants:**

(Applicable to all subcontracts, purchase orders, and other lower tier transactions requiring prior FHWA approval or estimated to cost $25,000 or more - 2 CFR Parts 180 and 1200). 2 CFR 180.220 and 1200.220.

a. By signing and submitting this proposal, the prospective lower tier participant is providing the certification set out below.

b. The certification in this clause is a material representation of fact upon which reliance was placed when this transaction was entered into. If it is later determined that the prospective lower tier participant knowingly rendered an erroneous certification, in addition to other remedies available to the Federal Government, the department, or agency with which this transaction originated may pursue available remedies, including suspension and/or debarment.

c. The prospective lower tier participant shall provide immediate written notice to the person to which this proposal is submitted if at any time the prospective lower tier participant learns that its certification was erroneous by reason of changed circumstances. 2 CFR 180.365.

d. The terms "covered transaction," "debarred," "suspended," "ineligible," "participant," "person," "principal," and "voluntarily excluded," as used in this clause, are defined in 2 CFR Parts 180, Subpart I, 180.900 – 180.1020, and 1200. You may contact the person to which this proposal is submitted for assistance in obtaining a copy of those regulations. “First Tier Covered Transactions” refers to any covered transaction between a recipient or subrecipient of Federal funds and a participant (such as the prime or general contract). “Lower Tier Covered Transactions” refers to any covered transaction under a First Tier Covered Transaction (such as subcontracts). “First Tier Participant” refers to the participant who has entered into a covered transaction with a recipient or subrecipient of Federal funds (such as the prime or general contractor). “Lower Tier Participant” refers any participant who has entered into a covered transaction with a First Tier Participant or other Lower Tier Participants (such as subcontractors and suppliers).

e. The prospective lower tier participant agrees by submitting this proposal that, should the proposed covered transaction be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department or agency with which this transaction originated. 2 CFR 1200.220 and 1200.332.

f. The prospective lower tier participant further agrees by submitting this proposal that it will include this clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transaction," without modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions exceeding the $25,000 threshold. 2 CFR 180.220 and 1200.220.

g. A participant in a covered transaction may rely upon a certification of a prospective participant in a lower tier covered transaction that is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A participant is responsible for ensuring that its principals are not suspended, debarred, or otherwise ineligible to participate in covered transactions. To verify the eligibility of its principals, as well as the eligibility of any lower tier prospective participants, each participant may, but is not required to, check the System for Award Management website (https://www.sam.gov/), which is compiled by the General Services Administration. 2 CFR 180.300, 180.320, 180.330, and 180.335.

h. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of participant is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.

i. Except for transactions authorized under paragraph e of these instructions, if a participant in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible, or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department or agency with which this transaction originated may pursue available remedies, including suspension and/or debarment. 2 CFR 180.325.

* * * * *

4. Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion--Lower Tier Participants:

a. The prospective lower tier participant certifies, by submission of this proposal, that neither it nor its principals:

(1) is presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participating in covered transactions by any Federal department or agency, 2 CFR 180.355;

(2) is a corporation that has been convicted of a felony violation under any Federal law within the two-year period preceding this proposal (USDOT Order 4200.6 implementing appropriations act requirements); and

(3) is a corporation with any unpaid Federal tax liability that has been assessed, for which all judicial and administrative remedies have been exhausted, or have lapsed, and that is not being paid in a timely manner pursuant to an agreement with the authority responsible for collecting the tax liability. (USDOT Order 4200.6 implementing appropriations act requirements)

b. Where the prospective lower tier participant is unable to certify to any of the statements in this certification, such prospective participant should attach an explanation to this proposal.

* * * * *

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

X. CERTIFICATION REGARDING USE OF CONTRACT FUNDS FOR LOBBYING

This provision is applicable to all Federal-aid construction contracts and to all related subcontracts which exceed $100,000. 49 CFR Part 20, App. A.

1. The prospective participant certifies, by signing and submitting this bid or proposal, to the best of his or her knowledge and belief, that:

a. No Federal appropriated funds have been paid or will be paid, by or on behalf of the undersigned, to any person for influencing or attempting to influence an officer or employee of any Federal agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with the awarding of any Federal contract, the making of any Federal grant, the making of any Federal loan, the entering into of any cooperative agreement, and the extension, continuation, renewal, amendment, or modification of any Federal contract, grant, loan, or cooperative agreement.

b. If any funds other than Federal appropriated funds have been paid or will be paid to any person for influencing or attempting to influence an officer or employee of any Federal agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with this Federal contract, grant, loan, or cooperative agreement, the undersigned shall complete and submit Standard Form-LLL, "Disclosure Form to Report Lobbying," in accordance with its instructions.

2. This certification is a material representation of fact upon which reliance was placed when this transaction was made or entered into. Submission of this certification is a prerequisite for making or entering into this transaction imposed by 31 U.S.C. 1352. Any person who fails to file the required certification shall be subject to a civil penalty of not less than $10,000 and not more than $100,000 for each such failure.

3. The prospective participant also agrees by submitting its bid or proposal that the participant shall require that the language of this certification be included in all lower tier subcontracts, which exceed $100,000 and that all such recipients shall certify and disclose accordingly.

XI. USE OF UNITED STATES-FLAG VESSELS:

This provision is applicable to all Federal-aid construction contracts, design-build contracts, subcontracts, lower-tier subcontracts, purchase orders, lease agreements, or any other covered transaction. 46 CFR Part 381.

This requirement applies to material or equipment that is acquired for a specific Federal-aid highway project. 46 CFR 381.7. It is not applicable to goods or materials that come into inventories independent of an FHWA funded-contract.

When oceanic shipments (or shipments across the Great Lakes) are necessary for materials or equipment acquired for a specific Federal-aid construction project, the bidder, proposer, contractor, subcontractor, or vendor agrees:

1. To utilize privately owned United States-flag commercial vessels to ship at least 50 percent of the gross tonnage (computed separately for dry bulk carriers, dry cargo liners, and tankers) involved, whenever shipping any equipment, material, or commodities pursuant to this contract, to the extent such vessels are available at fair and reasonable rates for United States-flag commercial vessels. 46 CFR 381.7.

2. To furnish within 20 days following the date of loading for shipments originating within the United States or within 30 working days following the date of loading for shipments originating outside the United States, a legible copy of a rated, 'on-board' commercial ocean bill-of-lading in English for each shipment of cargo described in paragraph (b)(1) of this section to both the Contracting Officer (through the prime contractor in the case of subcontractor bills-of-lading) and to the Office of Cargo and Commercial Sealift (MAR-620), Maritime Administration, Washington, DC 20590. (MARAD requires copies of the ocean carrier's (master) bills of lading, certified onboard, dated, with rates and charges. These bills of lading may contain business sensitive information and therefore may be submitted directly to MARAD by the Ocean Transportation Intermediary on behalf of the contractor). 46 CFR 381.7.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

ATTACHMENT A - EMPLOYMENT AND MATERIALS PREFERENCE FOR APPALACHIAN DEVELOPMENT HIGHWAY SYSTEM OR APPALACHIAN LOCAL ACCESS ROAD CONTRACTS (40 U.S.C. sections 14501(d) and 14701 and the Appalachian Regional Commission Code as authorized under 40 U.S.C. section 14302)
This provision is applicable to all Federal-aid projects funded under the Appalachian Regional Development Act of 1965.

1. During the performance of this contract, the contractor undertaking to do work which is, or reasonably may be, done as on-site work, shall give preference to qualified persons who regularly reside in the labor area as designated by the DOL wherein the contract work is situated, or the subregion, or the Appalachian counties of the State wherein the contract work is situated, except:

a. To the extent that qualified persons regularly residing in the area are not available.

b. For the reasonable needs of the contractor to employ supervisory or specially experienced personnel necessary to assure an efficient execution of the contract work.

c. For the obligation of the contractor to offer employment to present or former employees as the result of a lawful collective bargaining contract, provided that the number of nonresident persons employed under this subparagraph (1c) shall not exceed 20 percent of the total number of employees employed by the contractor on the contract work, except as provided in subparagraph (4) below.

2. The contractor shall place a job order with the State Employment Service indicating (a) the classifications of the laborers, mechanics and other employees required to perform the contract work, (b) the number of employees required in each classification, (c) the date on which the participant estimates such employees will be required, and (d) any other pertinent information required by the State Employment Service to complete the job order form. The job order may be placed with the State Employment Service in writing or by telephone. If during the course of the contract work, the information submitted by the contractor in the original job order is substantially modified, the participant shall promptly notify the State Employment Service.

3. The contractor shall give full consideration to all qualified job applicants referred to him by the State Employment Service. The contractor is not required to grant employment to any job applicants who, in his opinion, are not qualified to perform the classification of work required.

4. If, within one week following the placing of a job order by the contractor with the State Employment Service, the State Employment Service is unable to refer any qualified job applicants to the contractor, or less than the number requested, the State Employment Service will forward a certificate to the contractor indicating the unavailability of applicants. Such certificate shall be made a part of the contractor's permanent project records. Upon receipt of this certificate, the contractor may employ persons who do not normally reside in the labor area to fill positions covered by the certificate, notwithstanding the provisions of subparagraph (1c) above.

5. The provisions of 40 U.S.C. 14501 allow the contracting agency to provide a contractual preference for the use of mineral resource materials native to the Appalachian region.

6. The contractor shall include the provisions of Sections 1 through 4 of this Attachment A in every subcontract for work which is, or reasonably may be, done as on-site work.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

PREVAILING WAGE RATES

Federal Wage Determination
Washington State Prevailing Wages
Supplement to State Wage Rates
Benefit Code Key

WHIPPLE, KNAPPS, CARSON BRIDGE BUNDLE
PRJ NO. 0001799 / CRP NO. 320322

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

"General Decision Number: WA20260001 06/16/2026

State: Washington

Construction Types: Highway

Counties: Washington Counties of
Adams, Asotin, Benton, Chelan, Clallam,
Clark, Columbia, Cowlitz, Douglas,
Ferry, Franklin, Garfield, Grant, Grays
Harbor, Island, Jefferson, King, Kitsap,
Kittitas, Klickitat, Lewis, Lincoln,
Mason, Okanogan, Pacific, Pend Oreille,
Pierce, San Juan, Skagit, Skamania,
Snohomish, Spokane, Stevens, Thurston,
Wahkiakum, Walla Walla, Whatcom, Whitman
and Yakima

Excludes D.O.E. Hanford Site in Benton and Franklin Counties

Modification Number	Publication Date
1	01/23/2026
2	05/18/2026
3	05/20/2026
4	**06/16/2026**

CARP0059-021 06/01/2025

	Rates	Fringes
CARPENTER: PILEDRIVER: INCLUDES DRIVING, PULLING, CUTTING, PLACING COLLARS, SETTING, WELDING, OR CREOSOTE TREATED MATERIAL, ON ALL PILING (ADAMS, ASOTIN, BENTON, CHELAN, COLUMBIA, DOUGLAS, FERRY, FRANKLIN, GARFIELD, GRANT, KITTITAS, LINCOLN, OKANOGAN, PEND OREILLE, SPOKANE, STEVENS, WALLA WALLA, WHITMAN, AND YAKIMA COUNTIES) EMPLOYEES MAY BE REQUIRED TO PERFORM ANY COMBINATION OF WORK WITHIN THE DIVING TEAM/CREW, (EXCEPT FOR DIVE SUPERVISOR) PROVIDED THEY ARE PAID AT THE HIGHEST RATE OF PAY THAT THEY RECEIVED DURING THEIR SHIFT	$ 49.76	17.28
CARPENTER: DIVER TENDER, MANIFOLD OPERATOR, ROV OPERATOR (ADAMS, ASOTIN, BENTON, CHELAN, COLUMBIA, DOUGLAS, FERRY, FRANKLIN, GARFIELD, GRANT, KITTITAS, LINCOLN, OKANOGAN, PEND OREILLE, SPOKANE, STEVENS, WALLA WALLA, WHITMAN, AND YAKIMA COUNTIES) EMPLOYEES MAY BE REQUIRED TO PERFORM ANY COMBINATION OF WORK WITHIN THE DIVING TEAM/CREW, (EXCEPT FOR DIVE SUPERVISOR) PROVIDED THEY ARE PAID AT THE HIGHEST RATE OF PAY THAT THEY RECEIVED DURING THEIR SHIFT	$ 54.24	17.28
CARPENTER: MANIFOLD OPERATOR-MIXED GAS (ADAMS, ASOTIN, BENTON, CHELAN, COLUMBIA, DOUGLAS, FERRY, FRANKLIN, GARFIELD, GRANT, KITTITAS, LINCOLN,		

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

OKANOGAN, PEND OREILLE, SPOKANE, STEVENS, WALLA WALLA, WHITMAN, AND YAKIMA COUNTIES) EMPLOYEES MAY BE REQUIRED TO PERFORM ANY COMBINATION OF WORK WITHIN THE DIVING TEAM/CREW, (EXCEPT FOR DIVE SUPERVISOR) PROVIDED THEY ARE PAID AT THE HIGHEST RATE OF PAY THAT THEY RECEIVED DURING THEIR SHIFT...$ 58.24 17.28

CARPENTER: CARPENTER (ADAMS, ASOTIN, BENTON, CHELAN, COLUMBIA, DOUGLAS, FERRY, FRANKLIN, GARFIELD, GRANT, KITTITAS, LINCOLN, OKANOGAN, PEND OREILLE, SPOKANE, STEVENS, WALLA WALLA, WHITMAN, AND YAKIMA COUNTIES) EMPLOYEES MAY BE REQUIRED TO PERFORM ANY COMBINATION OF WORK WITHIN THE DIVING TEAM/CREW, (EXCEPT FOR DIVE SUPERVISOR) PROVIDED THEY ARE PAID AT THE HIGHEST RATE OF PAY THAT THEY RECEIVED DURING THEIR SHIFT.....$ 44.21 17.28

CARPENTER: ASSISTANT DIVER TENDER, ROV TENDER/TECHNICIAN (ADAMS, ASOTIN, BENTON, CHELAN, COLUMBIA, DOUGLAS, FERRY, FRANKLIN, GARFIELD, GRANT, KITTITAS, LINCOLN, OKANOGAN, PEND OREILLE, SPOKANE, STEVENS, WALLA WALLA, WHITMAN, AND YAKIMA COUNTIES) EMPLOYEES MAY BE REQUIRED TO PERFORM ANY COMBINATION OF WORK WITHIN THE DIVING TEAM/CREW, (EXCEPT FOR DIVE SUPERVISOR) PROVIDED THEY ARE PAID AT THE HIGHEST RATE OF PAY THAT THEY RECEIVED DURING THEIR SHIFT.....$ 50.76 17.28

CARPENTER :BRIDGE, DOCK, AND WHARF CARPENTER (ADAMS, ASOTIN, BENTON, CHELAN, COLUMBIA, DOUGLAS, FERRY, FRANKLIN, GARFIELD, GRANT, KITTITAS, LINCOLN, OKANOGAN, PEND OREILLE, SPOKANE, STEVENS, WALLA WALLA, WHITMAN, AND YAKIMA COUNTIES) EMPLOYEES MAY BE REQUIRED TO PERFORM ANY COMBINATION OF WORK WITHIN THE DIVING TEAM/CREW, (EXCEPT FOR DIVE SUPERVISOR) PROVIDED THEY ARE PAID AT THE HIGHEST RATE OF PAY THAT THEY RECEIVED DURING THEIR SHIFT.....$ 48.21 17.28

CARPENTER: DIVER STANDBY (ADAMS, ASOTIN, BENTON, CHELAN, COLUMBIA, DOUGLAS, FERRY, FRANKLIN, GARFIELD, GRANT, KITTITAS, LINCOLN, OKANOGAN, PEND OREILLE, SPOKANE, STEVENS, WALLA WALLA, WHITMAN, AND YAKIMA COUNTIES) EMPLOYEES MAY BE REQUIRED TO PERFORM ANY COMBINATION OF WORK WITHIN THE DIVING TEAM/CREW, (EXCEPT FOR DIVE SUPERVISOR) PROVIDED THEY ARE PAID AT THE HIGHEST RATE OF PAY THAT THEY RECEIVED DURING THEIR SHIFT.....$ 55.24 17.28

CARPENTER: DIVER WET (ADAMS, ASOTIN, BENTON, CHELAN, COLUMBIA, DOUGLAS, FERRY, FRANKLIN, GARFIELD, GRANT, KITTITAS, LINCOLN, OKANOGAN, PEND OREILLE, SPOKANE, STEVENS, WALLA WALLA, WHITMAN, AND YAKIMA COUNTIES) EMPLOYEES MAY BE REQUIRED TO PERFORM ANY COMBINATION OF WORK WITHIN THE DIVING TEAM/CREW, (EXCEPT FOR DIVE SUPERVISOR) PROVIDED THEY ARE PAID AT THE HIGHEST RATE OF PAY THAT THEY RECEIVED DURING THEIR SHIFT.....$ 110.48 17.28

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

CARP0096-002 06/01/2025

	Rates	Fringes
MILLWRIGHT (CLALLAM, GRAYS HARBOR, ISLAND, JEFFERSON, KING, KITSAP, LEWIS,MASON, PACIFIC (NORTH OF A STRAIGHT LINE MADE BY EXTENDING THENORTH BOUNDARY LINE OF WAHKIAKUM COUNTY WEST TO THE PACIFICOCEAN), PIERCE, SAN JUAN, SKAGIT, SNOHOMISH, THURSTON AND WHATCOM COUNTIES)	$ 55.39	22.38

CARP0096-007 06/01/2025

	Rates	Fringes
MILLWRIGHT (SOUTHWEST WASHINGTON: CLARK, COWLITZ, LEWIS (PILEDRIVER ONLY), PACIFIC (SOUTH OF A STRAIGHT LINE MADE BY EXTENDING THE NORTH BOUNDARY LINE OF WAHKIAKUM COUNTY WEST TO WILLAPA BAY TO THE PACIFIC OCEAN), SKAMANIA, AND WAHKIAKUM COUNTIES.)	$ 59.35	22.38

CARP0196-004 06/01/2025

	Rates	Fringes
PILEDRIVER (CLARK, COWLITZ, *PACIFIC, SKAMANIA, AND WAHKIAKUM COUNTIES *PORTION OF PACIFIC COUNTY SOUTH OF A STRAIGHT LINE MADE BY EXTENDING THE NORTH BOUNDARY LINE OF WAHKIAKUM COUNTY WEST TO WILLAPA BAY TO THE PACIFIC OCEAN, AND THENCE NORTH THROUGH THE NATURAL WATERWAY TO THE PACIFIC OCEAN (THIS INCLUDES THE ENTIRE PENINSULA WEST OF WILLAPA BAY))	$ 56.06	16.81

CARP0196-006 06/01/2025

	Rates	Fringes
PILEDRIVER (CLALLAM, GRAYS HARBOR, ISLAND, JEFFERSON, KING, KITSAP, LEWIS, MASON, *PACIFIC, PIERCE, SAN JUAN, SKAGIT, SNOHOMISH, THURSTON AND WHATCOM COUNTIES * PORTION OF PACIFIC COUNTY NORTH OF A STRAIGHT LINE MADE BY EXTENDING THE NORTH BOUNDARY LINE OF WAHKIAKUM COUNTY WEST TO THE PACIFIC OCEAN COUNTIES OR PARTS OF COUNTIES EAST OF THE 120TH MERIDIAN)	$ 65.53	19.13

CARP0206-009 06/01/2025

	Rates	Fringes
CARPENTER: BRIDGE CARPENTER (KING AND KITSAP COUNTIES)	$ 65.58	19.13
CARPENTER: CARPENTER (KING AND KITSAP COUNTIES)	$ 63.98	19.13
CARPENTER: DIVER (KING AND KITSAP COUNTIES)	$ 125.44	19.13
CARPENTER: DIVER TENDER (KING AND KITSAP COUNTIES)	$ 71.77	19.13

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

CARP0360-006 09/15/2025

Rates	Fringes
CARPENTER: BRIDGE CARPENTER (PACIFIC COUNTY. PORTION OF PACIFIC COUNTY NORTH OF A STRAIGHT LINE MADE BY EXTENDING THE NORTH BOUNDARY LINE OF WAHKIAKUM COUNTY WEST TO THE PACIFIC OCEAN COUNTIES OR PARTS OF COUNTIES EAST OF THE 120TH MERIDIAN) EMPLOYEES MAY BE REQUIRED TO PERFORM ANY COMBINATION OF WORK WITHIN THE DIVING TEAM/CREW, (EXCEPT FOR DIVE SUPERVISOR) PROVIDED THEY ARE PAID AT THE HIGEST RATE OF PAY THAT THEY RECEIVED DURING THEIR SHIFT.....$ 65.58	19.13
CARPENTER: CARPENTER/DRYWALL HANGER (PACIFIC COUNTY. PORTION OF PACIFIC COUNTY NORTH OF A STRAIGHT LINE MADE BY EXTENDING THE NORTH BOUNDARY LINE OF WAHKIAKUM COUNTY WEST TO THE PACIFIC OCEAN COUNTIES OR PARTS OF COUNTIES EAST OF THE 120TH MERIDIAN) EMPLOYEES MAY BE REQUIRED TO PERFORM ANY COMBINATION OF WORK WITHIN THE DIVING TEAM/CREW, (EXCEPT FOR DIVE SUPERVISOR) PROVIDED THEY ARE PAID AT THE HIGEST RATE OF PAY THAT THEY RECEIVED DURING THEIR SHIFT.....$ 63.98	19.13
CARPENTER: DIVER (PACIFIC COUNTY. PORTION OF PACIFIC COUNTY NORTH OF A STRAIGHT LINE MADE BY EXTENDING THE NORTH BOUNDARY LINE OF WAHKIAKUM COUNTY WEST TO THE PACIFIC OCEAN COUNTIES OR PARTS OF COUNTIES EAST OF THE 120TH MERIDIAN) EMPLOYEES MAY BE REQUIRED TO PERFORM ANY COMBINATION OF WORK WITHIN THE DIVING TEAM/CREW, (EXCEPT FOR DIVE SUPERVISOR) PROVIDED THEY ARE PAID AT THE HIGEST RATE OF PAY THAT THEY RECEIVED DURING THEIR SHIFT...$ 125.44	19.13
CARPENTER: DIVER TENDER (PACIFIC COUNTY. PORTION OF PACIFIC COUNTY NORTH OF A STRAIGHT LINE MADE BY EXTENDING THE NORTH BOUNDARY LINE OF WAHKIAKUM COUNTY WEST TO THE PACIFIC OCEAN COUNTIES OR PARTS OF COUNTIES EAST OF THE 120TH MERIDIAN) EMPLOYEES MAY BE REQUIRED TO PERFORM ANY COMBINATION OF WORK WITHIN THE DIVING TEAM/CREW, (EXCEPT FOR DIVE SUPERVISOR) PROVIDED THEY ARE PAID AT THE HIGEST RATE OF PAY THAT THEY RECEIVED DURING THEIR SHIFT...$ 71.77	19.13

CARP0360-007 06/01/2025

Rates	Fringes
CARPENTERS: CARPENTERS (PACIFIC COUNTY. PORTION OF PACIFIC COUNTY SOUTH OF A STRAIGHT LINE MADE BY EXTENDING THE NORTH BOUNDARY LINE OF WAHKIAKUM COUNTY WEST TO WILLAPA BAY TO THE PACIFIC OCEAN, AND THENCE NORTH THROUGH THE NATURAL WATERWAY TO THE PACIFIC OCEAN (THIS INCLUDES THE ENTIRE PENINSULA WEST OF WILLAPA BAY)) EMPLOYEES MAY BE REQUIRED TO PERFORM ANY COMBINATION OF WORK WITHIN THE DIVING TEAM/CREW, (EXCEPT FOR DIVE SUPERVISOR) PROVIDED THEY ARE PAID AT THE HIGEST RATE OF PAY THAT THEY RECEIVED DURING THEIR SHIFT.....$ 54.69	16.81

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

CARPENTERS: DIVERS (PACIFIC COUNTY PORTION OF PACIFIC COUNTY SOUTH OF A STRAIGHT LINE MADE BY EXTENDING THE NORTH BOUNDARY LINE OF WAHKIAKUM COUNTY WEST TO WILLAPA BAY TO THE PACIFIC OCEAN, AND THENCE NORTH THROUGH THE NATURAL WATERWAY TO THE PACIFIC OCEAN (THIS INCLUDES THE ENTIRE PENINSULA WEST OF WILLAPA BAY)) EMPLOYEES MAY BE REQUIRED TO PERFORM ANY COMBINATION OF WORK WITHIN THE DIVING TEAM/CREW, (EXCEPT FOR DIVE SUPERVISOR) PROVIDED THEY ARE PAID AT THE HIGEST RATE OF PAY THAT THEY RECEIVED DURING THEIR SHIFT.....$ 108.33 16.81

CARPENTERS: DIVERS TENDERS (PACIFIC COUNTY PORTION OF PACIFIC COUNTY SOUTH OF A STRAIGHT LINE MADE BY EXTENDING THE NORTH BOUNDARY LINE OF WAHKIAKUM COUNTY WEST TO WILLAPA BAY TO THE PACIFIC OCEAN, AND THENCE NORTH THROUGH THE NATURAL WATERWAY TO THE PACIFIC OCEAN (THIS INCLUDES THE ENTIRE PENINSULA WEST OF WILLAPA BAY)) EMPLOYEES MAY BE REQUIRED TO PERFORM ANY COMBINATION OF WORK WITHIN THE DIVING TEAM/CREW, (EXCEPT FOR DIVE SUPERVISOR) PROVIDED THEY ARE PAID AT THE HIGEST RATE OF PAY THAT THEY RECEIVED DURING THEIR SHIFT. .....$ 64.32 16.81

CARPENTERS: DRYWALL (PACIFIC COUNTY PORTION OF PACIFIC COUNTY SOUTH OF A STRAIGHT LINE MADE BY EXTENDING THE NORTH BOUNDARY LINE OF WAHKIAKUM COUNTY WEST TO WILLAPA BAY TO THE PACIFIC OCEAN, AND THENCE NORTH THROUGH THE NATURAL WATERWAY TO THE PACIFIC OCEAN (THIS INCLUDES THE ENTIRE PENINSULA WEST OF WILLAPA BAY)) EMPLOYEES MAY BE REQUIRED TO PERFORM ANY COMBINATION OF WORK WITHIN THE DIVING TEAM/CREW, (EXCEPT FOR DIVE SUPERVISOR) PROVIDED THEY ARE PAID AT THE HIGEST RATE OF PAY THAT THEY RECEIVED DURING THEIR SHIFT.....$ 54.59 16.81

CARP0360-013 06/01/2025

Rates	Fringes
CARPENTER: BRIDGE CARPENTER (GRAYS HARBOR, LEWIS, MASON, PIERCE, AND THURSTON COUNTIES) EMPLOYEES MAY BE REQUIRED TO PERFORM ANY COMBINATION OF WORK WITHIN THE DIVING TEAM/CREW, (EXCEPT FOR DIVE SUPERVISOR) PROVIDED THEY ARE PAID AT THE HIGEST RATE OF PAY THAT THEY RECEIVED DURING THEIR SHIFT...$ 65.58	19.13
CARPENTER: CARPENTER (GRAYS HARBOR, LEWIS, MASON, PIERCE, AND THURSTON COUNTIES) EMPLOYEES MAY BE REQUIRED TO PERFORM ANY COMBINATION OF WORK WITHIN THE DIVING TEAM/CREW, (EXCEPT FOR DIVE SUPERVISOR) PROVIDED THEY ARE PAID AT THE HIGEST RATE OF PAY THAT THEY RECEIVED DURING THEIR SHIFT.....$ 63.98	19.13
CARPENTER: DIVER (GRAYS HARBOR, LEWIS, MASON, PIERCE, AND THURSTON COUNTIES) EMPLOYEES MAY BE REQUIRED TO PERFORM ANY COMBINATION OF WORK WITHIN THE DIVING TEAM/CREW, (EXCEPT FOR DIVE SUPERVISOR) PROVIDED THEY ARE PAID AT THE HIGHEST RATE OF PAY THAT THEY RECEIVED DURING THEIR SHIFT.....$ 125.44	19.13

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

CARPENTER: DIVER TENDER (GRAYS HARBOR, LEWIS, MASON, PIERCE, AND THURSTON COUNTIES) EMPLOYEES MAY BE REQUIRED TO PERFORM ANY COMBINATION OF WORK WITHIN THE DIVING TEAM/CREW, (EXCEPT FOR DIVE SUPERVISOR) PROVIDED THEY ARE PAID AT THE HIGHEST RATE OF PAY THAT THEY RECEIVED DURING THEIR SHIFT...$ 71.77 19.13

CARP0425-006 09/15/2025

Rates		Fringes
CARPENTER: BRIDGE CARPENTER (CLALLAM, ISLAND, JEFFERSON, SAN JUAN, SKAGIT, SNOHOMISH, AND WHATCOM COUNTIES) EMPLOYEES MAY BE REQUIRED TO PERFORM ANY COMBINATION OF WORK WITHIN THE DIVING TEAM/CREW, (EXCEPT FOR DIVE SUPERVISOR) PROVIDED THEY ARE PAID AT THE HIGHEST RATE OF PAY THAT THEY RECEIVED DURING THEIR SHIFT	$ 65.58	19.13
CARPENTER: CARPENTER (CLALLAM, ISLAND, JEFFERSON, SAN JUAN, SKAGIT, SNOHOMISH, AND WHATCOM COUNTIES) EMPLOYEES MAY BE REQUIRED TO PERFORM ANY COMBINATION OF WORK WITHIN THE DIVING TEAM/CREW, (EXCEPT FOR DIVE SUPERVISOR) PROVIDED THEY ARE PAID AT THE HIGHEST RATE OF PAY THAT THEY RECEIVED DURING THEIR SHIFT	$ 63.98	19.13
CARPENTER: DIVER (CLALLAM, ISLAND, JEFFERSON, SAN JUAN, SKAGIT, SNOHOMISH, AND WHATCOM COUNTIES) EMPLOYEES MAY BE REQUIRED TO PERFORM ANY COMBINATION OF WORK WITHIN THE DIVING TEAM/CREW, (EXCEPT FOR DIVE SUPERVISOR) PROVIDED THEY ARE PAID AT THE HIGHEST RATE OF PAY THAT THEY RECEIVED DURING THEIR SHIFT	$ 125.44	19.13
CARPENTER: DIVER TENDER (CLALLAM, ISLAND, JEFFERSON, SAN JUAN, SKAGIT, SNOHOMISH, AND WHATCOM COUNTIES) EMPLOYEES MAY BE REQUIRED TO PERFORM ANY COMBINATION OF WORK WITHIN THE DIVING TEAM/CREW, (EXCEPT FOR DIVE SUPERVISOR) PROVIDED THEY ARE PAID AT THE HIGHEST RATE OF PAY THAT THEY RECEIVED DURING THEIR SHIFT.	$ 71.77	19.13

CARP0503-021 06/01/2025

Rates		Fringes
CARPENTERS: CARPENTERS (CLARK, COWLITZ, SKAMANIA, AND WAHKIAKUM COUNTIES) EMPLOYEES MAY BE REQUIRED TO PERFORM ANY COMBINATION OF WORK WITHIN THE DIVING TEAM/CREW (EXCEPT FOR DIVE SUPERVISOR) PROVIDED THEY ARE PAID AT THE HIGEST RATE OF PAY THAT THEY RECEIVED DURING THEIR SHIFT	$ 54.69	16.81
CARPENTERS: DIVERS (CLARK, COWLITZ, SKAMANIA, AND WAHKIAKUM COUNTIES) EMPLOYEES MAY BE REQUIRED TO PERFORM ANY COMBINATION OF WORK WITHIN THE DIVING TEAM/CREW (EXCEPT FOR DIVE SUPERVISOR) PROVIDED THEY ARE PAID AT THE HIGEST RATE OF PAY THAT THEY RECEIVED DURING THEIR SHIFT	$ 108.33	16.81

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

CARPENTERS: DIVERS TENDERS (CLARK, COWLITZ, SKAMANIA, AND WAHKIAKUM COUNTIES) EMPLOYEES MAY BE REQUIRED TO PERFORM ANY COMBINATION OF WORK WITHIN THE DIVING TEAM/CREW, (EXCEPT FOR DIVE SUPERVISOR) PROVIDED THEY ARE PAID AT THE HIGHEST RATE OF PAY THAT THEY RECEIVED DURING THEIR SHIFT.....$ 64.32 16.81

CARPENTERS: DRYWALL (CLARK, COWLITZ, SKAMANIA, AND WAHKIAKUM COUNTIES) EMPLOYEES MAY BE REQUIRED TO PERFORM ANY COMBINATION OF WORK WITHIN THE DIVING TEAM/CREW (EXCEPT FOR DIVE SUPERVISOR) PROVIDED THEY ARE PAID AT THE HIGEST RATE OF PAY THAT THEY RECEIVED DURING THEIR SHIFT.....$ 54.59 16.81

CARP1607-010 06/01/2025

Rates	Fringes
MILLWRIGHT (ADAMS, ASOTIN, BENTON, CHELAN, COLUMBIA, DOUGLAS, FERRY, FRANKLIN, GARFIELD, GRANT, KLICKITAT, KITTITAS, LINCOLNC, OKANOGAN, PEND OREILLE, SPOKANE, STEVENS, WALLA WALLA, WHITMAN, AND YAKIMA COUNTIES).....$ 61.62	20.43

ELEC0046-001 08/04/2025

Rates	Fringes
CABLE SPLICER (CALLAM, JEFFERSON, KING AND KITSAP COUNTIES).....$ 83.56	33.71
ELECTRICIAN (CALLAM, JEFFERSON, KING AND KITSAP COUNTIES).....$ 75.96	33.48

ELEC0048-003 01/01/2025

Rates	Fringes
CABLE SPLICER (CLARK, KLICKITAT AND SKAMANIA COUNTIES). HOURLY ZONE PAY: HOURLY ZONE PAY SHALL BE PAID ON JOBS LOCATED OUTSIDE OF THE FREE ZONE COMPUTED FROM THE CITY CENTER OF THE FOLLOWING LISTED CITIES: PORTLAND, THE DALLES, HOOD RIVER, TILLAMOOK, SEASIDE AND ASTORIA. ZONE PAY: ZONE 1: 31-50 MILES $1.50/HOUR ZONE 2: 51-70 MILES $3.50/HOUR ZONE 3: 71-90 MILES $5.50/HOUR ZONE 4: BEYOND 90 MILES $9.00/HOUR *THESE ARE NOT MILES DRIVEN. ZONES ARE BASED ON DELORRNE STREET ATLAS USA 2006 PLUS.....$ 44.22	21.50
ELECTRICIAN (CLARK, KLICKITAT AND SKAMANIA COUNTIES). HOURLY ZONE PAY: HOURLY ZONE PAY SHALL BE PAID ON JOBS LOCATED OUTSIDE OF THE FREE ZONE COMPUTED FROM THE CITY CENTER OF THE FOLLOWING LISTED CITIES: PORTLAND, THE DALLES, HOOD RIVER, TILLAMOOK, SEASIDE AND ASTORIA. ZONE PAY: ZONE 1: 31-50 MILES $1.50/HOUR ZONE 2: 51-70 MILES $3.50/HOUR ZONE 3: 71-90 MILES $5.50/HOUR ZONE 4: BEYOND 90 MILES $9.00/HOUR *THESE ARE NOT MILES DRIVEN. ZONES ARE BASED ON DELORRNE STREET ATLAS USA 2006 PLUS.....$ 63.50	29.73

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

ELEC0048-029 01/01/2025

	Rates	Fringes
CABLE SPLICER (COWLITZ AND WAHKIAKUM COUNTY)	$ 44.22	21.50
ELECTRICIAN (COWLITZ AND WAHKIAKUM COUNTY)	$ 63.50	29.73

ELEC0073-001 07/01/2025

	Rates	Fringes
CABLE SPLICER (ADAMS, FERRY, LINCOLN, PEND OREILLE, SPOKANE, STEVENS, WHITMAN COUNTIES)	$ 34.10	16.68
ELECTRICIAN (ADAMS, FERRY, LINCOLN, PEND OREILLE, SPOKANE, STEVENS, WHITMAN COUNTIES)	$ 49.55	19.09

ELEC0076-002 08/31/2025

	Rates	Fringes
CABLE SPLICER (GRAYS HARBOR, LEWIS, MASON, PACIFIC, PIERCE, AND THURSTON COUNTIES)	$ 71.65	26.76
ELECTRICIAN (GRAYS HARBOR, LEWIS, MASON, PACIFIC, PIERCE, AND THURSTON COUNTIES)	$ 65.14	26.56

ELEC0112-005 06/01/2025

	Rates	Fringes
CABLE SPLICER (ASOTIN, BENTON, COLUMBIA, FRANKLIN, GARFIELD, KITTITAS, WALLA WALLA, YAKIMA COUNTIES)	$ 63.00	27.87
ELECTRICIAN (ASOTIN, BENTON, COLUMBIA, FRANKLIN, GARFIELD, KITTITAS, WALLA WALLA, YAKIMA COUNTIES)	$ 60.00	27.78

ELEC0191-003 06/01/2022

	Rates	Fringes
CABLE SPLICER (ISLAND, SAN JUAN, SNOHOMISH, SKAGIT AND WHATCOM COUNTIES)	$ 44.23	17.73
ELECTRICIAN (ISLAND, SAN JUAN, SNOHOMISH, SKAGIT AND WHATCOM COUNTIES)	$ 53.20	27.51

ELEC0191-004 06/01/2018

	Rates	Fringes
CABLE SPLICER (CHELAN, DOUGLAS, GRANT AND OKANOGAN COUNTIES)	$ 40.82	17.63
ELECTRICIAN (CHELAN, DOUGLAS, GRANT AND OKANOGAN COUNTIES)	$ 42.45	21.34

ENGI0302-092 06/01/2025

	Rates	Fringes
POWER EQUIPMENT OPERATOR: GROUP 1- ASPHALT PLANT OPERATORS; CABLEWAYS; CONCRETE PUMP: TRUCK MOUNT WITH BOOM ATTACHMENT OVER 42M; CRANES: 45 TONS THROUGH 99 TONS, UNDER 150? OF BOOM (INCLUDING JIB WITH ATTACHMENTS); OVERHEAD, BRIDGE TYPE: 45 TONS THROUGH 99 TONS; DERRICKS: ON BUILDING WORK; HARD TAIL END DUMP: ARTICULATING OFF-ROAD EQUIPMENT 45		

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

YARDS & OVER; LOADER: OVERHEAD 6 YARDS BUT NOT INCLUDING 8 YARDS; MOTOR PATROL GRADERS; MUCKING MACHINE, MOLE, TUNNEL DRILL, BORING, ROAD HEADER AND/OR SHIELD; QUAD 9, HD 41, D10 AND OVER; REMOTE CONTROL OPERATOR ON RUBBER TIRED EARTH MOVING EQUIPMENT; ROLLAGON; SCRAPERS, SELF-PROPELLED: 45 YARDS AND OVER; SPREADER: TOPSIDER & SCREEDMAN; SHOVEL, EXCAVATOR, BACKHOE: OVER 30 METRIC TONS AND UP TO 50 METRIC TONS; SLIPFORM PAVERS; TRANSPORTERS: ALL TRACK OR TRUCK TYPE; WELDER. (KING AND SNOHOMISH COUNTIES).....$ 61.93 27.57

POWER EQUIPMENT OPERATOR: GROUP 1A- CRANES: 100 TONS THROUGH 199 TONS, OR 150' OF BOOM (INCLUDING JIB WITH ATTACHMENTS); DRILLING MACHINE; OVERHEAD, BRIDGE TYPE: 100 TONS AND OVER; TOWER CRANE: UP TO 175' IN HEIGHT BASE TO BOOM; LOADER: OVERHEAD 8 YARDS & OVER; SHOVEL, EXCAVATOR, BACKHOES: OVER 50 METRIC TONS AND UP TO 90 METRIC TONS; MECHANICS. (KING AND SNOHOMISH COUNTIES).....$ 62.85 27.57

POWER EQUIPMENT OPERATOR: GROUP 1AA- CRANES: 200 TONS- 299 TONS, OR 250' OF BOOM (INCLUDING JIB WITH ATTACHMENTS); CRANES: FRICTION CRANES THROUGH 199 TONS; LEVERMAN; SHOVEL, EXCAVATOR, BACKHOES: OVER 90 METRIC TONS; TOWER CRANE: OVER 175'?THROUGH 250'?IN HEIGHT, BASE TO BOOM. (KING AND SNOHOMISH COUNTIES).....$ 63.75 27.57

POWER EQUIPMENT OPERATOR: GROUP 1AAA- CRANES: 300 TONS AND OVER OR 300'?OF BOOM (INCLUDING JIB WITH ATTACHMENTS); CRANES FRICTION: 200 TONS AND OVER; TOWER CRANES: OVER 250'?IN HEIGHT FROM BASE TO BOOM. (KING AND SNOHOMISH COUNTIES).....$ 64.66 27.57

POWER EQUIPMENT OPERATOR: GROUP 2- BATCH PLANT OPERATOR: CONCRETE; BARRIER MACHINE: (ZIPPER); BUMP CUTTER; CRANES: 20 TONS THROUGH 44 TONS WITH ATTACHMENTS; OVERHEAD, BRIDGE TYPE CRANE: 20 TONS THROUGH 44 TONS; CHIPPER; CONCRETE PUMP: TRUCK MOUNT WITH BOOM ATTACHMENT UP TO 42M; CRUSHER; DECK ENGINEER/DECK WINCHES (POWER); GRADE ENGINEER: USING BLUE PRINTS, CUT SHEETS, ETC.; FINISHING MACHINE: BIDWELL AND GAMACO & SIMILAR EQUIPMENT; GUARDRAIL PUNCH; HARD TAIL END DUMP: ARTICULATING OFF-ROAD EQUIPMENT UNDER 45 YARDS; HORIZONTAL/DIRECTIONAL DRILL OPERATOR; LOADERS: OVERHEAD UNDER 6 YARDS; LOADERS: PLANT FEED; LOCOMOTIVES: ALL; MATERIAL TRANSFER DEVICE; PILEDRIVER: (OTHER THAN CRANE MOUNT); QUICK TOWER: NO CAB, UNDER 100 FEET IN HEIGHT BASE TO BOOM; ROTO-MILL, ROTO-GRINDER; SHOVEL, EXCAVATOR, BACKHOE, TRACTOR: 15 TO 30 METRIC TONS; SUBGRADER TRIMMER; SCRAPER: SELF PROPELLED UNDER 45 YARDS; TRUCK CRANE OILER/DRIVER: 100 TONS AND OVER; TRUCK MOUNT PORTABLE CONVEYOR; -VAC TRUCK (VACTOR GUZZLER, HYDRO EXCAVATOR); YO YO PAY DOZER. (KING AND SNOHOMISH COUNTIES).....$ 61.14 27.57

POWER EQUIPMENT OPERATOR: GROUP 3- CRANES: THROUGH 19 TONS WITH ATTACHMENTS, A-FRAME OVER 10 TONS;

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

CONCRETE PUMP: MOUNTED OR TRAILER HIGH PRESSURE LINE PUMP, PUMP HIGH PRESSURE; CONVEYORS; DOZERS: D-9 & UNDER; DRILL OILERS: AUGER TYPE, TRUCK OR CRANE MOUNT; FORKLIFT: 3000 LBS AND OVER WITH ATTACHMENTS; HORIZONTAL/DIRECTIONAL DRILL LOCATOR; OUTSIDE HOISTS (ELEVATORS AND MANLIFTS), AIR TUGGERS, STRATO; TOWER BUCKET ELEVATORS; HYDRALIFTS/BOOM TRUCKS: OVER 10 TONS; LOADERS: ELEVATING TYPE BELT; PLANT OILER: ASPHALT, CRUSHER; RIGGER/SIGNAL PERSON, BELLMAN (CERTIFIED); ROLLER: PLANT MIX OR MULTI-LIFT MATERIALS; SAWS: CONCRETE; SCRAPERS: CONCRETE & CARRY ALL SERVICE ENGINEERS: EQUIPMENT; TRENCHING MACHINES; TRUCK CRANE OILER/DRIVER: UNDER 100 TONS; SHOVEL, EXCAVATOR, BACKHOE, TRACTORS: UNDER 15 METRIC TONS. (KING AND SNOHOMISH COUNTIES).....$ 60.46 27.57

POWER EQUIPMENT OPERATOR: GROUP 4- ASSISTANT ENGINEER; BOBCAT; BROOMS; COMPRESSOR; CONCRETE FINISH MACHINE: LASER SCREED; CRANES, A-FRAME: 10 TONS AND UNDER; ELEVATOR AND MAN-LIFT: PERMANENT AND SHAFT TYPE; FORKLIFTS: UNDER 3000 LBS. WITH ATTACHMENTS; GRADECHECKER/STAKEMAN; HYDRALIFTS/BOOM TRUCKS: 10 TONS AND UNDER; OIL DISTRIBUTORS, BLOWER DISTRIBUTION & MULCH SEEDING OPERATOR; PAVEMENT BREAKER; POSTHOLE DIGGER: MECHANICAL; POWER PLANT; PUMPS: WATER; -RIGGER AND BELLMAN; ROLLER: OTHER THAN PLANT MIX; WHEEL TRACTORS: FARM ALL TYPE; SHOTCRETE/GUNITE EQUIPMENT; BROKK: REMOTE DEMOLITION EQUIPMENT. (KING AND SNOHOMISH COUNTIES).....$ 56.63 27.57

ENGI0302-093 06/01/2025

Rates	Fringes

POWER EQUIPMENT OPERATOR: GROUP 1- ASPHALT PLANT OPERATORS; CABLEWAYS; CONCRETE PUMP: TRUCK MOUNT WITH BOOM ATTACHMENT OVER 42M; CRANES: 45 TONS THROUGH 99 TONS, UNDER 150'?OF BOOM (INCLUDING JIB WITH ATTACHMENTS); OVERHEAD, BRIDGE TYPE: 45 TONS THROUGH 99 TONS; DERRICKS: ON BUILDING WORK; HARD TAIL END DUMP: ARTICULATING OFF-ROAD EQUIPMENT 45 YARDS & OVER; LOADER: OVERHEAD 6 YARDS BUT NOT INCLUDING 8 YARDS; MOTOR PATROL GRADERS; MUCKING MACHINE, MOLE, TUNNEL DRILL, BORING, ROAD HEADER AND/OR SHIELD; QUAD 9, HD 41, D10 AND OVER; REMOTE CONTROL OPERATOR ON RUBBER TIRED EARTH MOVING EQUIPMENT; ROLLAGON; SCRAPERS, SELF-PROPELLED: 45 YARDS AND OVER; SPREADER: TOPSIDER & SCREEDMAN; SHOVEL, EXCAVATOR, BACKHOE: OVER 30 METRIC TONS AND UP TO 50 METRIC TONS; SLIPFORM PAVERS; TRANSPORTERS: ALL TRACK OR TRUCK TYPE; WELDER. (SKAGIT AND WHATCOM COUNTIES).....$ 61.47 27.57

POWER EQUIPMENT OPERATOR: GROUP 1A- CRANES: 100 TONS THROUGH 199 TONS, OR 150'?OF BOOM (INCLUDING JIB WITH ATTACHMENTS); DRILLING MACHINE; OVERHEAD, BRIDGE TYPE: 100 TONS AND OVER; TOWER CRANE: UP TO

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

175'?IN HEIGHT BASE TO BOOM; LOADER: OVERHEAD 8 YARDS & OVER; SHOVEL, EXCAVATOR, BACKHOES: OVER 50 METRIC TONS AND UP TO 90 METRIC TONS; MECHANICS. (SKAGIT AND WHATCOM COUNTIES).....$ 62.39 27.57

POWER EQUIPMENT OPERATOR: GROUP 1AA- CRANES: 200 TONS- 299 TONS, OR 250'?OF BOOM (INCLUDING JIB WITH ATTACHMENTS); CRANES: FRICTION CRANES THROUGH 199 TONS; LEVERMAN; SHOVEL, EXCAVATOR, BACKHOES: OVER 90 METRIC TONS; TOWER CRANE: OVER 175'?THROUGH 250'?IN HEIGHT, BASE TO BOOM. (SKAGIT AND WHATCOM COUNTIES).....$ 63.29 27.57

POWER EQUIPMENT OPERATOR: GROUP 1AAA- CRANES: 300 TONS AND OVER OR 300'?OF BOOM (INCLUDING JIB WITH ATTACHMENTS); CRANES FRICTION: 200 TONS AND OVER; TOWER CRANES: OVER 250'?IN HEIGHT FROM BASE TO BOOM. (SKAGIT AND WHATCOM COUNTIES).....$ 64.19 27.57

POWER EQUIPMENT OPERATOR: GROUP 2- BATCH PLANT OPERATOR: CONCRETE; BARRIER MACHINE: (ZIPPER); BUMP CUTTER; CRANES: 20 TONS THROUGH 44 TONS WITH ATTACHMENTS; OVERHEAD, BRIDGE TYPE CRANE: 20 TONS THROUGH 44 TONS; CHIPPER; CONCRETE PUMP: TRUCK MOUNT WITH BOOM ATTACHMENT UP TO 42M; CRUSHER; DECK ENGINEER/DECK WINCHES (POWER); GRADE ENGINEER: USING BLUE PRINTS, CUT SHEETS, ETC.; FINISHING MACHINE: BIDWELL AND GAMACO & SIMILAR EQUIPMENT; GUARDRAIL PUNCH; HARD TAIL END DUMP: ARTICULATING OFF-ROAD EQUIPMENT UNDER 45 YARDS; HORIZONTAL/DIRECTIONAL DRILL OPERATOR; LOADERS: OVERHEAD UNDER 6 YARDS; LOADERS: PLANT FEED; LOCOMOTIVES: ALL; MATERIAL TRANSFER DEVICE; PILEDRIVER: (OTHER THAN CRANE MOUNT); QUICK TOWER: NO CAB, UNDER 100 FEET IN HEIGHT BASE TO BOOM; ROTO-MILL, ROTO-GRINDER; SHOVEL, EXCAVATOR, BACKHOE, TRACTOR: 15 TO 30 METRIC TONS; SUBGRADER TRIMMER; SCRAPER: SELF PROPELLED UNDER 45 YARDS; TRUCK CRANE OILER/DRIVER: 100 TONS AND OVER; TRUCK MOUNT PORTABLE CONVEYOR; -VAC TRUCK (VACTOR GUZZLER, HYDRO EXCAVATOR); YO YO PAY DOZER. (SKAGIT AND WHATCOM COUNTIES).....$ 60.69 27.57

POWER EQUIPMENT OPERATOR: GROUP 3- CRANES: THROUGH 19 TONS WITH ATTACHMENTS, A-FRAME OVER 10 TONS; CONCRETE PUMP: MOUNTED OR TRAILER HIGH PRESSURE LINE PUMP, PUMP HIGH PRESSURE; CONVEYORS; DOZERS: D-9 & UNDER; DRILL OILERS: AUGER TYPE, TRUCK OR CRANE MOUNT; FORKLIFT: 3000 LBS AND OVER WITH ATTACHMENTS; HORIZONTAL/DIRECTIONAL DRILL LOCATOR; OUTSIDE HOISTS (ELEVATORS AND MANLIFTS), AIR TUGGERS, STRATO; TOWER BUCKET ELEVATORS; HYDRALIFTS/BOOM TRUCKS: OVER 10 TONS; LOADERS: ELEVATING TYPE BELT; PLANT OILER: ASPHALT, CRUSHER; RIGGER/SIGNAL PERSON, BELLMAN (CERTIFIED); ROLLER: PLANT MIX OR MULTI-LIFT MATERIALS; SAWS: CONCRETE; SCRAPERS: CONCRETE & CARRY ALL SERVICE ENGINEERS: EQUIPMENT; TRENCHING MACHINES; TRUCK CRANE OILER/DRIVER: UNDER 100 TONS; SHOVEL, EXCAVATOR, BACKHOE, TRACTORS: UNDER 15 METRIC TONS. (SKAGIT

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

AND WHATCOM COUNTIES).....$ 60.02 27.57
POWER EQUIPMENT OPERATOR: GROUP 4- ASSISTANT ENGINEER; BOBCAT; BROOMS; COMPRESSOR; CONCRETE FINISH MACHINE: LASER SCREED; CRANES, A-FRAME: 10 TONS AND UNDER; ELEVATOR AND MAN-LIFT: PERMANENT AND SHAFT TYPE; FORKLIFTS: UNDER 3000 LBS. WITH ATTACHMENTS; GRADECHECKER/STAKEMAN; HYDRALIFTS/BOOM TRUCKS: 10 TONS AND UNDER; OIL DISTRIBUTORS, BLOWER DISTRIBUTION & MULCH SEEDING OPERATOR; PAVEMENT BREAKER; POSTHOLE DIGGER: MECHANICAL; POWER PLANT; PUMPS: WATER; -RIGGER AND BELLMAN; ROLLER: OTHER THAN PLANT MIX; WHEEL TRACTORS: FARM ALL TYPE; SHOTCRETE/GUNITE EQUIPMENT; BROKK: REMOTE DEMOLITION EQUIPMENT SKAGIT AND WHATCOM COUNTIES.$ 56.19 27.57

ENGI0302-094 06/01/2025

Rates	Fringes
POWER EQUIPMENT OPERATOR: GROUP 1- ASPHALT PLANT OPERATORS; CABLEWAYS; CONCRETE PUMP: TRUCK MOUNT WITH BOOM ATTACHMENT OVER 42M; CRANES: 45 TONS THROUGH 99 TONS, UNDER 150'?OF BOOM (INCLUDING JIB WITH ATTACHMENTS); OVERHEAD, BRIDGE TYPE: 45 TONS THROUGH 99 TONS; DERRICKS: ON BUILDING WORK; HARD TAIL END DUMP: ARTICULATING OFF-ROAD EQUIPMENT 45 YARDS & OVER; LOADER: OVERHEAD 6 YARDS BUT NOT INCLUDING 8 YARDS; MOTOR PATROL GRADERS; MUCKING MACHINE, MOLE, TUNNEL DRILL, BORING, ROAD HEADER AND/OR SHIELD; QUAD 9, HD 41, D10 AND OVER; REMOTE CONTROL OPERATOR ON RUBBER TIRED EARTH MOVING EQUIPMENT; ROLLAGON; SCRAPERS, SELF-PROPELLED: 45 YARDS AND OVER; SPREADER: TOPSIDER & SCREEDMAN; SHOVEL, EXCAVATOR, BACKHOE: OVER 30 METRIC TONS AND UP TO 50 METRIC TONS; SLIPFORM PAVERS; TRANSPORTERS: ALL TRACK OR TRUCK TYPE; WELDER. (KITSAP COUNTY).....$ 60.93	27.57
POWER EQUIPMENT OPERATOR: GROUP 1A- CRANES: 100 TONS THROUGH 199 TONS, OR 150'?OF BOOM (INCLUDING JIB WITH ATTACHMENTS); DRILLING MACHINE; OVERHEAD, BRIDGE TYPE: 100 TONS AND OVER; TOWER CRANE: UP TO 175'?IN HEIGHT BASE TO BOOM; LOADER: OVERHEAD 8 YARDS & OVER; SHOVEL, EXCAVATOR, BACKHOES: OVER 50 METRIC TONS AND UP TO 90 METRIC TONS; MECHANICS. KITSAP COUNTY.....$ 61.83	27.57
POWER EQUIPMENT OPERATOR: GROUP 1AA- CRANES: 200 TONS- 299 TONS, OR 250'?OF BOOM (INCLUDING JIB WITH ATTACHMENTS); CRANES: FRICTION CRANES THROUGH 199 TONS; LEVERMAN; SHOVEL, EXCAVATOR, BACKHOES: OVER 90 METRIC TONS; TOWER CRANE: OVER 175' THROUGH 250'?IN HEIGHT, BASE TO BOOM. (KITSAP COUNTY).....$ 62.73	27.57
POWER EQUIPMENT OPERATOR: GROUP 1AAA- CRANES: 300 TONS AND OVER OR 300'?OF BOOM (INCLUDING JIB WITH ATTACHMENTS); CRANES FRICTION: 200 TONS AND OVER; TOWER CRANES: OVER 250'?IN HEIGHT FROM BASE TO BOOM. (KITSAP COUNTY).....$ 63.62	27.57

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

POWER EQUIPMENT OPERATOR: GROUP 2- BATCH PLANT OPERATOR: CONCRETE; BARRIER MACHINE: (ZIPPER); BUMP CUTTER; CRANES: 20 TONS THROUGH 44 TONS WITH ATTACHMENTS; OVERHEAD, BRIDGE TYPE CRANE: 20 TONS THROUGH 44 TONS; CHIPPER; CONCRETE PUMP: TRUCK MOUNT WITH BOOM ATTACHMENT UP TO 42M; CRUSHER; DECK ENGINEER/DECK WINCHES (POWER); GRADE ENGINEER: USING BLUE PRINTS, CUT SHEETS, ETC.; FINISHING MACHINE: BIDWELL AND GAMACO & SIMILAR EQUIPMENT; GUARDRAIL PUNCH; HARD TAIL END DUMP: ARTICULATING OFF-ROAD EQUIPMENT UNDER 45 YARDS; HORIZONTAL/DIRECTIONAL DRILL OPERATOR; LOADERS: OVERHEAD UNDER 6 YARDS; LOADERS: PLANT FEED; LOCOMOTIVES: ALL; MATERIAL TRANSFER DEVICE; PILEDRIVER: (OTHER THAN CRANE MOUNT); QUICK TOWER: NO CAB, UNDER 100 FEET IN HEIGHT BASE TO BOOM; ROTO-MILL, ROTO-GRINDER; SHOVEL, EXCAVATOR, BACKHOE, TRACTOR: 15 TO 30 METRIC TONS; SUBGRADER TRIMMER; SCRAPER: SELF PROPELLED UNDER 45 YARDS; TRUCK CRANE OILER/DRIVER: 100 TONS AND OVER; TRUCK MOUNT PORTABLE CONVEYOR; -VAC TRUCK (VACTOR GUZZLER, HYDRO EXCAVATOR); YO YO PAY DOZER. (KITSAP COUNTY).....$ 60.14 27.57

POWER EQUIPMENT OPERATOR: GROUP 3- CRANES: THROUGH 19 TONS WITH ATTACHMENTS, A-FRAME OVER 10 TONS; CONCRETE PUMP: MOUNTED OR TRAILER HIGH PRESSURE LINE PUMP, PUMP HIGH PRESSURE; CONVEYORS; DOZERS: D-9 & UNDER; DRILL OILERS: AUGER TYPE, TRUCK OR CRANE MOUNT; FORKLIFT: 3000 LBS AND OVER WITH ATTACHMENTS; HORIZONTAL/DIRECTIONAL DRILL LOCATOR; OUTSIDE HOISTS (ELEVATORS AND MANLIFTS), AIR TUGGERS, STRATO; TOWER BUCKET ELEVATORS; HYDRALIFTS/BOOM TRUCKS: OVER 10 TONS; LOADERS: ELEVATING TYPE BELT; PLANT OILER: ASPHALT, CRUSHER; RIGGER/SIGNAL PERSON, BELLMAN (CERTIFIED); ROLLER: PLANT MIX OR MULTI-LIFT MATERIALS; SAWS: CONCRETE; SCRAPERS: CONCRETE & CARRY ALL SERVICE ENGINEERS: EQUIPMENT; TRENCHING MACHINES; TRUCK CRANE OILER/DRIVER: UNDER 100 TONS; SHOVEL, EXCAVATOR, BACKHOE, TRACTORS: UNDER 15 METRIC TONS. (KITSAP COUNTY).....$ 59.49 27.57

POWER EQUIPMENT OPERATOR: GROUP 4- ASSISTANT ENGINEER; BOBCAT; BROOMS; COMPRESSOR; CONCRETE FINISH MACHINE: LASER SCREED; CRANES, A-FRAME: 10 TONS AND UNDER; ELEVATOR AND MAN-LIFT: PERMANENT AND SHAFT TYPE; FORKLIFTS: UNDER 3000 LBS. WITH ATTACHMENTS; GRADECHECKER/STAKEMAN; HYDRALIFTS/BOOM TRUCKS: 10 TONS AND UNDER; OIL DISTRIBUTORS, BLOWER DISTRIBUTION & MULCH SEEDING OPERATOR; PAVEMENT BREAKER; POSTHOLE DIGGER: MECHANICAL; POWER PLANT; PUMPS: WATER; RIGGER AND BELLMAN; ROLLER: OTHER THAN PLANT MIX; WHEEL TRACTORS: FARM ALL TYPE; SHOTCRETE/GUNITE EQUIPMENT; BROKK: REMOTE DEMOLITION EQUIPMENT. (KITSAP COUNTY).....$ 55.68 27.57

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

ENGI0302-095 06/01/2025

Rates	Fringes
POWER EQUIPMENT OPERATOR: GROUP 1- ASPHALT PLANT OPERATORS; CABLEWAYS; CONCRETE PUMP: TRUCK MOUNT WITH BOOM ATTACHMENT OVER 42M; CRANES: 45 TONS THROUGH 99 TONS, UNDER 150'?OF BOOM (INCLUDING JIB WITH ATTACHMENTS); OVERHEAD, BRIDGE TYPE: 45 TONS THROUGH 99 TONS; DERRICKS: ON BUILDING WORK; HARD TAIL END DUMP: ARTICULATING OFF-ROAD EQUIPMENT 45 YARDS & OVER; LOADER: OVERHEAD 6 YARDS BUT NOT INCLUDING 8 YARDS; MOTOR PATROL GRADERS; MUCKING MACHINE, MOLE, TUNNEL DRILL, BORING, ROAD HEADER AND/OR SHIELD; QUAD 9, HD 41, D10 AND OVER; REMOTE CONTROL OPERATOR ON RUBBER TIRED EARTH MOVING EQUIPMENT; ROLLAGON; SCRAPERS, SELF-PROPELLED: 45 YARDS AND OVER; SPREADER: TOPSIDER & SCREEDMAN; SHOVEL, EXCAVATOR, BACKHOE: OVER 30 METRIC TONS AND UP TO 50 METRIC TONS; SLIPFORM PAVERS; TRANSPORTERS: ALL TRACK OR TRUCK TYPE; WELDER. (CHELAN (WEST OF THE 120TH MERIDIAN), CLALLAM, DOUGLAS (WEST OF THE 120TH MERIDIAN), GRAYS HARBOR, ISLAND, JEFFERSON, KITTITAS (WEST OF THE 120TH MERIDIAN), MASON, OKANOGAN (WEST OF THE 120TH MERIDIAN), SAN JUNA, AND YAKIMA (WEST OF THE 120TH MERIDIAN) COUNTIES).....	$ 60.67	27.57
POWER EQUIPMENT OPERATOR: GROUP 1A- CRANES: 100 TONS THROUGH 199 TONS, OR 150'?OF BOOM (INCLUDING JIB WITH ATTACHMENTS); DRILLING MACHINE; OVERHEAD, BRIDGE TYPE: 100 TONS AND OVER; TOWER CRANE: UP TO 175'?IN HEIGHT BASE TO BOOM; LOADER: OVERHEAD 8 YARDS & OVER; SHOVEL, EXCAVATOR, BACKHOES: OVER 50 METRIC TONS AND UP TO 90 METRIC TONS; MECHANICS. (CHELAN (WEST OF THE 120TH MERIDIAN), CLALLAM, DOUGLAS (WEST OF THE 120TH MERIDIAN), GRAYS HARBOR, ISLAND, JEFFERSON, KITTITAS (WEST OF THE 120TH MERIDIAN), MASON, OKANOGAN (WEST OF THE 120TH MERIDIAN), SAN JUNA, AND YAKIMA (WEST OF THE 120TH MERIDIAN) COUNTIES).....	$ 61.56	27.57
POWER EQUIPMENT OPERATOR: GROUP 1AA-CRANES: 200 TONS- 299 TONS, OR 250' OF BOOM (INCLUDING JIB WITH ATTACHMENTS); CRANES: FRICTION CRANES THROUGH 199 TONS; LEVERMAN; SHOVEL, EXCAVATOR, BACKHOES: OVER 90 METRIC TONS; TOWER CRANE: OVER 175' THROUGH 250' IN HEIGHT, BASE TO BOOM. (CHELAN (WEST OF THE 120TH MERIDIAN), CLALLAM, DOUGLAS (WEST OF THE 120TH MERIDIAN), GRAYS HARBOR, ISLAND, JEFFERSON, KITTITAS (WEST OF THE 120TH MERIDIAN), MASON, OKANOGAN (WEST OF THE 120TH MERIDIAN), SAN JUNA, AND YAKIMA (WEST OF THE 120TH MERIDIAN) COUNTIES)...	$ 62.47	27.57
POWER EQUIPMENT OPERATOR: GROUP 1AAA- CRANES: 300 TONS AND OVER OR 300'?OF BOOM (INCLUDING JIB WITH ATTACHMENTS); CRANES FRICTION: 200 TONS AND OVER; TOWER CRANES: OVER 250'?IN HEIGHT FROM BASE TO BOOM. (CHELAN (WEST OF THE 120TH MERIDIAN), CLALLAM, DOUGLAS (WEST OF THE 120TH MERIDIAN), GRAYS HARBOR, ISLAND, JEFFERSON, KITTITAS (WEST OF		

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

THE 120TH MERIDIAN), MASON, OKANOGAN (WEST OF THE 120TH MERIDIAN), SAN JUNA, AND YAKIMA (WEST OF THE 120TH MERIDIAN) COUNTIES).....$ 63.35 27.57

POWER EQUIPMENT OPERATOR: GROUP 2- BATCH PLANT OPERATOR: CONCRETE; BARRIER MACHINE: (ZIPPER); BUMP CUTTER; CRANES: 20 TONS THROUGH 44 TONS WITH ATTACHMENTS; OVERHEAD, BRIDGE TYPE CRANE: 20 TONS THROUGH 44 TONS; CHIPPER; CONCRETE PUMP: TRUCK MOUNT WITH BOOM ATTACHMENT UP TO 42M; CRUSHER; DECK ENGINEER/DECK WINCHES (POWER); GRADE ENGINEER: USING BLUE PRINTS, CUT SHEETS, ETC.; FINISHING MACHINE: BIDWELL AND GAMACO & SIMILAR EQUIPMENT; GUARDRAIL PUNCH; HARD TAIL END DUMP: ARTICULATING OFF-ROAD EQUIPMENT UNDER 45 YARDS; HORIZONTAL/DIRECTIONAL DRILL OPERATOR; LOADERS: OVERHEAD UNDER 6 YARDS; LOADERS: PLANT FEED; LOCOMOTIVES: ALL; MATERIAL TRANSFER DEVICE; PILEDRIVER: (OTHER THAN CRANE MOUNT); QUICK TOWER: NO CAB, UNDER 100 FEET IN HEIGHT BASE TO BOOM; ROTO-MILL, ROTO-GRINDER; SHOVEL, EXCAVATOR, BACKHOE, TRACTOR: 15 TO 30 METRIC TONS; SUBGRADER TRIMMER; SCRAPER: SELF PROPELLED UNDER 45 YARDS; TRUCK CRANE OILER/DRIVER: 100 TONS AND OVER; TRUCK MOUNT PORTABLE CONVEYOR; VAC TRUCK (VACTOR GUZZLER, HYDRO EXCAVATOR); YO YO PAY DOZER. (CHELAN (WEST OF THE 120TH MERIDIAN), CLALLAM, DOUGLAS (WEST OF THE 120TH MERIDIAN), GRAYS HARBOR, ISLAND, JEFFERSON, KITTITAS (WEST OF THE 120TH MERIDIAN), MASON, OKANOGAN (WEST OF THE 120TH MERIDIAN), SAN JUNA, AND YAKIMA (WEST OF THE 120TH MERIDIAN) COUNTIES).....$ 59.88 27.57

POWER EQUIPMENT OPERATOR: GROUP 3- CRANES: THROUGH 19 TONS WITH ATTACHMENTS, A-FRAME OVER 10 TONS; CONCRETE PUMP: MOUNTED OR TRAILER HIGH PRESSURE LINE PUMP, PUMP HIGH PRESSURE; CONVEYORS; DOZERS: D-9 & UNDER; DRILL OILERS: AUGER TYPE, TRUCK OR CRANE MOUNT; FORKLIFT: 3000 LBS AND OVER WITH ATTACHMENTS; HORIZONTAL/DIRECTIONAL DRILL LOCATOR; OUTSIDE HOISTS (ELEVATORS AND MANLIFTS), AIR TUGGERS, STRATO; TOWER BUCKET ELEVATORS; HYDRALIFTS/BOOM TRUCKS: OVER 10 TONS; LOADERS: ELEVATING TYPE BELT; PLANT OILER: ASPHALT, CRUSHER; RIGGER/SIGNAL PERSON, BELLMAN (CERTIFIED); ROLLER: PLANT MIX OR MULTI-LIFT MATERIALS; SAWS: CONCRETE; SCRAPERS: CONCRETE & CARRY ALL SERVICE ENGINEERS: EQUIPMENT; TRENCHING MACHINES; TRUCK CRANE OILER/DRIVER: UNDER 100 TONS; SHOVEL, EXCAVATOR, BACKHOE, TRACTORS: UNDER 15 METRIC TONS. (CHELAN (WEST OF THE 120TH MERIDIAN), CLALLAM, DOUGLAS (WEST OF THE 120TH MERIDIAN), GRAYS HARBOR, ISLAND, JEFFERSON, KITTITAS (WEST OF THE 120TH MERIDIAN), MASON, OKANOGAN (WEST OF THE 120TH MERIDIAN), SAN JUNA, AND YAKIMA (WEST OF THE 120TH MERIDIAN) COUNTIES).....$ 59.23 27.57

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

POWER EQUIPMENT OPERATOR: GROUP 4- ASSISTANT ENGINEER; BOBCAT; BROOMS; COMPRESSOR; CONCRETE FINISH MACHINE: LASER SCREED; CRANES, A-FRAME: 10 TONS AND UNDER; ELEVATOR AND MAN-LIFT: PERMANENT AND SHAFT TYPE; FORKLIFTS: UNDER 3000 LBS. WITH ATTACHMENTS; GRADECHECKER/STAKEMAN; HYDRALIFTS/BOOM TRUCKS: 10 TONS AND UNDER; OIL DISTRIBUTORS, BLOWER DISTRIBUTION & MULCH SEEDING OPERATOR; PAVEMENT BREAKER; POSTHOLE DIGGER: MECHANICAL; POWER PLANT; PUMPS: WATER; RIGGER AND BELLMAN; ROLLER: OTHER THAN PLANT MIX; WHEEL TRACTORS: FARM ALL TYPE; SHOTCRETE/GUNITE EQUIPMENT; BROKK: REMOTE DEMOLITION EQUIPMENT. (CHELAN (WEST OF THE 120TH MERIDIAN), CLALLAM, DOUGLAS (WEST OF THE 120TH MERIDIAN), GRAYS HARBOR, ISLAND, JEFFERSON, KITTITAS (WEST OF THE 120TH MERIDIAN), MASON, OKANOGAN (WEST OF THE 120TH MERIDIAN), SAN JUNA, AND YAKIMA (WEST OF THE 120TH MERIDIAN) COUNTIES)...$ 55.43 27.57

ENGI0302-124 06/01/2025

Rates	Fringes
POWER EQUIPMENT OPERATOR: GROUP 1- BIT GRINDERS; BOLT THREADING MACHINE; COMPRESSORS (UNDER 2000 CFM, GAS, DIESEL, OR ELECTRIC POWER); DECK HAND; FIREMAN & HEATER TENDER; HYDRO-SEEDER, MULCHER, NOZZLEMAN; OILER DRIVER, & CABLE TENDER, MUCKING MACHINE; PUMPMAN; ROLLERS, ALL TYPES ON SUBGRADE, INCLUDING SEAL AND CHIP COATINGS (FARM TYPE, CASE, JOHN DEERE & SIMILAR, OR COMPACTING VIBRATOR), EXCEPT WHEN PULLED BY DOZER WITH OPERABLE BLADE; WELDING MACHINE; CRANE OILER-DRIVER (CLD REQUIRED) & CABLE TENDER, MUCKING MACHINE. (ASOTIN, BENTON, FRANKLIN, GARFIELD, LINCOLN, SPOKANE, STEVENS, WALLA WALLA, AND WHITMAN).. .....$ 38.17	23.40
POWER EQUIPMENT OPERATOR: GROUP 2- A-FRAME TRUCK (SINGLE DRUM); ASSISTANT REFRIGERATION PLANT (UNDER 1000 TON); ASSISTANT PLANT OPERATOR, FIREMAN OR PUGMIXER (ASPHALT); BAGLEY OR STATIONARY SCRAPER; BELT FINISHING MACHINE; BLOWER OPERATOR (CEMENT); CEMENT HOG; COMPRESSOR (2000 CFM OR OVER, 2 OR MORE, GAS DIESEL OR ELECTRIC POWER); CONCRETE SAW (MULTIPLE CUT); DISTRIBUTOR LEVERMAN; DITCH WITCH OR SIMILAR; ELEVATOR HOISTING MATERIALS; DOPE POTS (POWER AGITATED); FORK LIFT OR LUMBER STACKER, HYDRA-LIFT & SIMILAR; GIN TRUCKS (PIPELINE); HOIST, SINGLE DRUM; LOADERS (BUCKET ELEVATORS AND CONVEYORS); LONGITUDINAL FLOAT; MIXER (PORTABLE-CONCRETE); PAVEMENT BREAKER, HYDRA-HAMMER & SIMILAR; POWER BROOM; RAILROAD BALLAST REGULATION OPERATOR (SELF-PROPELLED); RAILROAD POWER TAMPER OPERATOR (SELF-PROPELLED); RAILROAD TAMPER JACK OPERATOR (SELF-PROPELLED; SPRAY CURING MACHINE (CONCRETE); SPREADER BOX (SELF-PROPELLED); STRADDLE BUGGY (ROSS & SIMILAR ON CONSTRUCTION JOB ONLY); TRACTOR (FARM TYPE R/T WITH ATTACHMENT, EXCEPT	

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

BACKHOE); TUGGER OPERATOR. (ASOTIN, BENTON, FRANKLIN, GARFIELD, LINCOLN, SPOKANE, STEVENS, WALLA WALLA, AND WHITMAN).....$ 38.56 23.40

POWER EQUIPMENT OPERATOR: GROUP 3- A-FRAME TRUCK (2 OR MORE DRUMS); ASSISTANT REFRIGERATION PLANT & CHILLER OPERATOR (OVER 1000 TON); BACKFILLERS (CLEVELAND & SIMILAR); BATCH PLANT & WET MIX OPERATOR, SINGLE UNIT (CONCRETE); BELT-CRETE CONVEYORS WITH POWER PACK OR SIMILAR; BELT LOADER (KOCAL OR SIMILAR); BENDING MACHINE; BOB CAT (SKID STEER); BORING MACHINE (EARTH); BORING MACHINE (ROCK UNDER 8 INCH BIT) (QUARRY MASTER, JOY OR SIMILAR); BUMP CUTTER (WAYNE, SAGINAU OR SIMILAR); CANAL LINING MACHINE (CONCRETE); CHIPPER (WITHOUT CRANE); CLEANING & DOPING MACHINE (PIPELINE); DECK ENGINEER; ELEVATING BELT-TYPE LOADER (EUCLID, BARBER GREEN & SIMILAR); ELEVATING GRADER-TYPE LOADER (DUMOR, ADAMS OR SIMILAR); GENERATOR PLANT ENGINEERS (DIESEL OR ELECTRIC); GUNNITE COMBINATION MIXER & COMPRESSOR; LOCOMOTIVE ENGINEER; MIXERMOBILE; MUCKING MACHINE; POSTHOLE AUGER OR PUNCH; PUMP (GROUT OR JET); SOIL STABILIZER (P & H OR SIMILAR); SPREADER MACHINE; DOZER/TRACTOR (UP TO D-6 OR EQUIVALENT) AND TRAXCAVATOR; TRAVERSE FINISH MACHINE; TURNHEAD OPERATOR. (ASOTIN, BENTON, FRANKLIN, GARFIELD, LINCOLN, SPOKANE, STEVENS, WALLA WALLA, AND WHITMAN). .....$ 39.31 23.40

POWER EQUIPMENT OPERATOR: GROUP 4- CONCRETE PUMPS (SQUEEZE-CRETE, FLOW-CRETE, PUMP- CRETE, WHITMAN & SIMILAR); CURB EXTRUDER (ASPHALT OR CONCRETE); DRILLS (CHURN, CORE, CALYX OR DIAMOND); EQUIPMENT SERVICEMAN; GREASER & OILER; HOIST (2 OR MORE DRUMS OR TOWER HOIST); LOADERS (OVERHEAD & FRONT-END, UNDER 4 YDS. R/T); REFRIGERATION PLANT ENGINEER (UNDER 1000 TON); RUBBER-TIRED SKIDDERS (R/T WITH OR WITHOUT ATTACHMENTS); SURFACE HEATER & PLANT MACHINE; TRENCHING MACHINES (UNDER 7 FT. DEPTH CAPACITY); TURNHEAD (WITH RE-SCREENING); VACUUM DRILL (REVERSE CIRCULATION DRILL UNDER 8 INCH BIT). (ASOTIN, BENTON, FRANKLIN, GARFIELD, LINCOLN, SPOKANE, STEVENS, WALLA WALLA, AND WHITMAN).....$ 39.51 23.40

POWER EQUIPMENT OPERATOR: GROUP 5- BACKHOE (UNDER 45,000 GW); BACKHOE & HOE RAM (UNDER 3/4 YD.); CARRYDECK & BOOM TRUCK (UNDER 25 TONS); CRANES (25 TONS & UNDER), ALL ATTACHMENTS INCLUDING CLAMSHELL, DRAGLINE; DERRICKS & STIFFLEGS (UNDER 65 TONS); DRILLING EQUIPMENT(8 INCH BIT & OVER) (ROBBINS, REVERSE CIRCULATION & SIMILAR); HOE RAM; PILEDRIVING ENGINEERS; PAVING (DUAL DRUM); RAILROAD TRACK LINER OPERAOTR (SELF-PROPELLED); REFRIGERATION PLANT ENGINEER (1000 TONS & OVER); SIGNALMAN (WHIRLEYS, HIGHLINE HAMMERHEADS OR SIMILAR); GRADE CHECKER. (ASOTIN, BENTON, FRANKLIN, GARFIELD, LINCOLN, SPOKANE, STEVENS, WALLA WALLA, AND WHITMAN).....$ 39.71 23.40

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

POWER EQUIPMENT OPERATOR: GROUP 6- ASPHALT PLANT OPERATOR; AUTOMATIC SUBGRADER (DITCHES & TRIMMERS)(AUTOGRADE, ABC, R.A. HANSEN & SIMILAR ON GRADE WIRE); BACKHOE (45,000 GW AND OVER TO 110,000 GW); BACKHOES & HOE RAM (3/4 YD. TO 3 YD.); BATCH PLANT (OVER 4 UNITS); BATCH & WET MIX OPERATOR (MULTIPLE UNITS, 2 & INCL. 4); BLADE OPERATOR (MOTOR PATROL & ATTACHMENTS); CABLE CONTROLLER (DISPATCHER); COMPACTOR (SELF-PROPELLED WITH BLADE); CONCRETE PUMP BOOM TRUCK; CONCRETE SLIP FORM PAVER; CRANES (OVER 25 TONS, TO AND INCLUDING 45 TONS), ALL ATTACHMENTS INCLUDING CLAMSHELL, DRAGLINE; CRUSHER, GRIZZLE & SCREENING PLANT OPERATOR; DOZER, 834 R/T & SIMILAR; DRILL DOCTOR; LOADER OPERATOR (FRONT-END & OVERHEAD, 4 YDS. INCL. 8 YDS.); MULTIPLE DOZER UNITS WITH SINGLE BLADE; PAVING MACHINE (ASPHALT AND CONCRETE); QUAD-TRACK OR SIMILAR EQUIPMENT; ROLLERMAN (FINISHING ASPHALT PAVEMENT); ROTO MILL (PAVEMENT GRINDER); SCRAPERS, ALL, RUBBER-TIRED; SCREED OPERATOR; SHOVEL(UNDER 3 YDS.); TRENCHING MACHINES (7 FT. DEPTH & OVER); TUG BOAT OPERATOR VACTOR GUZZLER, SUPER SUCKER; LIME BATCH TANK OPERATOR (RECYCLE TRAIN); LIME BRAIN OPERATOR (RECYCLE TRAIN); MOBILE CRUSHER OPERATOR (RECYCLE TRAIN). (ASOTIN, BENTON, FRANKLIN, GARFIELD, LINCOLN, SPOKANE, STEVENS, WALLA WALLA, AND WHITMAN)	$ 40.00	23.40
POWER EQUIPMENT OPERATOR: GROUP 7- BACKHOE (OVER 110,000 GW); BACKHOES & HOE RAM (3 YDS & OVER); BLADE (FINISH & BLUETOP) AUTOMATIC, CMI, ABC, FINISH ATHEY & HUBER & SIMILAR WHEN USED AS AUTOMATIC; CABLEWAY OPERATORS; CONCRETE CLEANING/DECONTAMINATION MACHINE OPERATOR; CRANES (OVER 45 TONS TO BUT NOT INCLUDING 85 TONS), ALL ATTACHMENTS INCLUDING CLAMSHELL AND DRAGINE; DERRICKS & STIFFLEYS (65 TONS & OVER); ELEVATING BELT (HOLLAND TYPE); HEAVY EQUIPMENT ROBOTICS OPERATOR; LOADER (360 DEGREES REVOLVING KOEHRING SCOOPER OR SIMILAR); LOADERS (OVERHEAD & FRONT-END, OVER 8 YDS. TO 10 YDS.); RUBBER-TIRED SCRAPERS (MULTIPLE ENGINE WITH THREE OR MORE SCRAPERS); SHOVELS (3 YDS. & OVER); WHIRLEYS & HAMMERHEADS, ALL; H.D. MECHANIC; H.D. WELDER; HYDRAULIC PLATFORM TRAILERS (GOLDHOFER, SHAURERLY ANDSIMILAR); ULTRA HIGH PRESSURE WATERIET CUTTING TOOL SYSTEM OPERATOR (30,000 PSI); VACUUM BLASTING MACHINE OPERATOR. (ASOTIN, BENTON, FRANKLIN, GARFIELD, LINCOLN, SPOKANE, STEVENS, WALLA WALLA, AND WHITMAN)	$ 40.39	23.40
POWER EQUIPMENT OPERATOR: GROUP 8- CRANES (85 TONS AND OVER, AND ALL CLIMBING, OVERHEAD,RAIL AND TOWER), ALL ATTACHMENTS INCLUDING CLAMSHELL, DRAGLINE; LOADERS (OVERHEAD AND FRONT-END, 10 YARDS AND OVER); HELICOPTER PILOT. (ASOTIN, BENTON, FRANKLIN, GARFIELD, LINCOLN, SPOKANE, STEVENS, WALLA WALLA, AND WHITMAN)	$ 42.36	23.40

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

---

ENGI0302-125 06/01/2025

Rates	Fringes
POWER EQUIPMENT OPERATOR: GROUP 1- BIT GRINDERS; BOLT THREADING MACHINE; COMPRESSORS (UNDER 2000 CFM, GAS, DIESEL, OR ELECTRIC POWER); DECK HAND; FIREMAN & HEATER TENDER; HYDRO-SEEDER, MULCHER, NOZZLEMAN; OILER DRIVER, & CABLE TENDER, MUCKING MACHINE; PUMPMAN; ROLLERS, ALL TYPES ON SUBGRADE, INCLUDING SEAL AND CHIP COATINGS (FARM TYPE, CASE, JOHN DEERE & SIMILAR, OR COMPACTING VIBRATOR), EXCEPT WHEN PULLED BY DOZER WITH OPERABLE BLADE; WELDING MACHINE; CRANE OILER-DRIVER (CLD REQUIRED) & CABLE TENDER, MUCKING MACHINE. (ADAMS, CHELAN (EAST OF THE 120TH MERIDIAN), COLUMBIA, DOUGLAS (EAST OF THE 120TH MERIDIAN), FERRY, GRANT, OKANOGAN (EAST OF THE 120TH MERIDIAN), PEND OREILLE, STEVENS, AND YAKIMA (EAST OF THE 120TH MERIDIAN) COUNTIES).....	$ 41.17	23.40
POWER EQUIPMENT OPERATOR: GROUP 2- A-FRAME TRUCK (SINGLE DRUM); ASSISTANT REFRIGERATION PLANT (UNDER 1000 TON); ASSISTANT PLANT OPERATOR, FIREMAN OR PUGMIXER (ASPHALT); BAGLEY OR STATIONARY SCRAPER; BELT FINISHING MACHINE; BLOWER OPERATOR (CEMENT); CEMENT HOG; COMPRESSOR (2000 CFM OR OVER, 2 OR MORE, GAS DIESEL OR ELECTRIC POWER); CONCRETE SAW (MULTIPLE CUT); DISTRIBUTOR LEVERMAN; DITCH WITCH OR SIMILAR; ELEVATOR HOISTING MATERIALS; DOPE POTS (POWER AGITATED); FORK LIFT OR LUMBER STACKER, HYDRA-LIFT & SIMILAR; GIN TRUCKS (PIPELINE); HOIST, SINGLE DRUM; LOADERS (BUCKET ELEVATORS AND CONVEYORS); LONGITUDINAL FLOAT; MIXER (PORTABLE-CONCRETE); PAVEMENT BREAKER, HYDRA-HAMMER & SIMILAR; POWER BROOM; RAILROAD BALLAST REGULATION OPERATOR (SELF-PROPELLED); RAILROAD POWER TAMPER OPERATOR (SELF-PROPELLED); RAILROAD TAMPER JACK OPERATOR (SELF-PROPELLED; SPRAY CURING MACHINE (CONCRETE); SPREADER BOX (SELF-PROPELLED); STRADDLE BUGGY (ROSS & SIMILAR ON CONSTRUCTION JOB ONLY); TRACTOR (FARM TYPE R/T WITH ATTACHMENT, EXCEPT BACKHOE); TUGGER OPERATOR. (ADAMS, CHELAN (EAST OF THE 120TH MERIDIAN), COLUMBIA, DOUGLAS (EAST OF THE 120TH MERIDIAN), FERRY, GRANT, OKANOGAN (EAST OF THE 120TH MERIDIAN), PEND OREILLE, STEVENS, AND YAKIMA (EAST OF THE 120TH MERIDIAN) COUNTIES).....	$ 41.56	23.40
POWER EQUIPMENT OPERATOR: GROUP 3- A-FRAME TRUCK (2 OR MORE DRUMS); ASSISTANT REFRIGERATION PLANT & CHILLER OPERATOR (OVER 1000 TON); BACKFILLERS (CLEVELAND & SIMILAR); BATCH PLANT & WET MIX OPERATOR, SINGLE UNIT (CONCRETE); BELT-CRETE CONVEYORS WITH POWER PACK OR SIMILAR; BELT LOADER (KOCAL OR SIMILAR); BENDING MACHINE; BOB CAT (SKID STEER); BORING MACHINE (EARTH); BORING MACHINE (ROCK UNDER 8 INCH BIT) (QUARRY MASTER, JOY OR SIMILAR); BUMP CUTTER (WAYNE, SAGINAU OR SIMILAR);		

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

CANAL LINING MACHINE (CONCRETE); CHIPPER (WITHOUT CRANE); CLEANING & DOPING MACHINE (PIPELINE); DECK ENGINEER; ELEVATING BELT-TYPE LOADER (EUCLID, BARBER GREEN & SIMILAR); ELEVATING GRADER-TYPE LOADER (DUMOR, ADAMS OR SIMILAR); GENERATOR PLANT ENGINEERS (DIESEL OR ELECTRIC); GUNNITE COMBINATION MIXER & COMPRESSOR; LOCOMOTIVE ENGINEER; MIXERMOBILE; MUCKING MACHINE; POSTHOLE AUGER OR PUNCH; PUMP (GROUT OR JET); SOIL STABILIZER (P & H OR SIMILAR); SPREADER MACHINE; DOZER/TRACTOR (UP TO D-6 OR EQUIVALENT) AND TRAXCAVATOR; TRAVERSE FINISH MACHINE; TURNHEAD OPERATOR. (ADAMS, CHELAN (EAST OF THE 120TH MERIDIAN), COLUMBIA, DOUGLAS (EAST OF THE 120TH MERIDIAN), FERRY, GRANT, OKANOGAN (EAST OF THE 120TH MERIDIAN), PEND OREILLE, STEVENS, AND YAKIMA (EAST OF THE 120TH MERIDIAN) COUNTIES) ....$ 42.31 23.40

POWER EQUIPMENT OPERATOR: GROUP 4- CONCRETE PUMPS (SQUEEZE-CRETE, FLOW-CRETE, PUMP- CRETE, WHITMAN & SIMILAR); CURB EXTRUDER (ASPHALT OR CONCRETE); DRILLS (CHURN, CORE, CALYX OR DIAMOND); EQUIPMENT SERVICEMAN; GREASER & OILER; HOIST (2 OR MORE DRUMS OR TOWER HOIST); LOADERS (OVERHEAD & FRONT-END, UNDER 4 YDS. R/T); REFRIGERATION PLANT ENGINEER (UNDER 1000 TON); RUBBER-TIRED SKIDDERS (R/T WITH OR WITHOUT ATTACHMENTS); SURFACE HEATER & PLANT MACHINE; TRENCHING MACHINES (UNDER 7 FT. DEPTH CAPACITY); TURNHEAD (WITH RE-SCREENING); VACUUM DRILL (REVERSE CIRCULATION DRILL UNDER 8 INCH BIT). (ADAMS, CHELAN (EAST OF THE 120TH MERIDIAN), COLUMBIA, DOUGLAS (EAST OF THE 120TH MERIDIAN), FERRY, GRANT, OKANOGAN (EAST OF THE 120TH MERIDIAN), PEND OREILLE, STEVENS, AND YAKIMA (EAST OF THE 120TH MERIDIAN) COUNTIES) .....$ 42.51 23.40

POWER EQUIPMENT OPERATOR: GROUP 5- BACKHOE (UNDER 45,000 GW); BACKHOE & HOE RAM (UNDER 3/4 YD.); CARRYDECK & BOOM TRUCK (UNDER 25 TONS); CRANES (25 TONS & UNDER), ALL ATTACHMENTS INCLUDING CLAMSHELL, DRAGLINE; DERRICKS & STIFFLEGS (UNDER 65 TONS); DRILLING EQUIPMENT(8 INCH BIT & OVER) (ROBBINS, REVERSE CIRCULATION & SIMILAR); HOE RAM; PILEDRIVING ENGINEERS; PAVING (DUAL DRUM); RAILROAD TRACK LINER OPERAOTR (SELF-PROPELLED); REFRIGERATION PLANT ENGINEER (1000 TONS & OVER); SIGNALMAN (WHIRLEYS, HIGHLINE HAMMERHEADS OR SIMILAR); GRADE CHECKER. (ADAMS, CHELAN (EAST OF THE 120TH MERIDIAN), COLUMBIA, DOUGLAS (EAST OF THE 120TH MERIDIAN), FERRY, GRANT, OKANOGAN (EAST OF THE 120TH MERIDIAN), PEND OREILLE, STEVENS, AND YAKIMA (EAST OF THE 120TH MERIDIAN) COUNTIES) .....$ 42.71 23.40

POWER EQUIPMENT OPERATOR: GROUP 6- ASPHALT PLANT OPERATOR; AUTOMATIC SUBGRADER (DITCHES & TRIMMERS)(AUTOGRADE, ABC, R.A. HANSEN & SIMILAR ON GRADE WIRE); BACKHOE (45,000 GW AND OVER TO 110,000 GW); BACKHOES & HOE RAM (3/4 YD. TO 3 YD.); BATCH PLANT (OVER 4 UNITS); BATCH & WET MIX OPERATOR (MULTIPLE UNITS, 2 & INCL. 4); BLADE OPERATOR

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

(MOTOR PATROL & ATTACHMENTS); CABLE CONTROLLER (DISPATCHER); COMPACTOR (SELF-PROPELLED WITH BLADE); CONCRETE PUMP BOOM TRUCK; CONCRETE SLIP FORM PAVER; CRANES (OVER 25 TONS, TO AND INCLUDING 45 TONS), ALL ATTACHMENTS INCLUDING CLAMSHELL, DRAGLINE; CRUSHER, GRIZZLE & SCREENING PLANT OPERATOR; DOZER, 834 R/T & SIMILAR; DRILL DOCTOR; LOADER OPERATOR (FRONT-END & OVERHEAD, 4 YDS. INCL. 8 YDS.); MULTIPLE DOZER UNITS WITH SINGLE BLADE; PAVING MACHINE (ASPHALT AND CONCRETE); QUAD-TRACK OR SIMILAR EQUIPMENT; ROLLERMAN (FINISHING ASPHALT PAVEMENT); ROTO MILL (PAVEMENT GRINDER); SCRAPERS, ALL, RUBBER-TIRED; SCREED OPERATOR; SHOVEL(UNDER 3 YDS.); TRENCHING MACHINES (7 FT. DEPTH & OVER); TUG BOAT OPERATOR VACTOR GUZZLER, SUPER SUCKER; LIME BATCH TANK OPERATOR (RECYCLE TRAIN); LIME BRAIN OPERATOR (RECYCLE TRAIN); MOBILE CRUSHER OPERATOR (RECYCLE TRAIN). (ADAMS, CHELAN (EAST OF THE 120TH MERIDIAN), COLUMBIA, DOUGLAS (EAST OF THE 120TH MERIDIAN), FERRY, GRANT, OKANOGAN (EAST OF THE 120TH MERIDIAN), PEND OREILLE, STEVENS, AND YAKIMA (EAST OF THE 120TH MERIDIAN) COUNTIES).....$ 43.05 23.40

POWER EQUIPMENT OPERATOR: GROUP 7- BACKHOE (OVER 110,000 GW); BACKHOES & HOE RAM (3 YDS & OVER); BLADE (FINISH & BLUETOP) AUTOMATIC, CMI, ABC, FINISH ATHEY & HUBER & SIMILAR WHEN USED AS AUTOMATIC; CABLEWAY OPERATORS; CONCRETE CLEANING/DECONTAMINATION MACHINE OPERATOR; CRANES (OVER 45 TONS TO BUT NOT INCLUDING 85 TONS), ALL ATTACHMENTS INCLUDING CLAMSHELL AND DRAGINE; DERRICKS & STIFFLEYS (65 TONS & OVER); ELEVATING BELT (HOLLAND TYPE); HEAVY EQUIPMENT ROBOTICS OPERATOR; LOADER (360 DEGREES REVOLVING KOEHRING SCOOPER OR SIMILAR); LOADERS (OVERHEAD & FRONT-END, OVER 8 YDS. TO 10 YDS.); RUBBER-TIRED SCRAPERS (MULTIPLE ENGINE WITH THREE OR MORE SCRAPERS); SHOVELS (3 YDS. & OVER); WHIRLEYS & HAMMERHEADS, ALL; H.D. MECHANIC; H.D. WELDER; HYDRAULIC PLATFORM TRAILERS (GOLDHOFER, SHAURERLY ANDSIMILAR); ULTRA HIGH PRESSURE WATERIET CUTTING TOOL SYSTEM OPERATOR (30,000 PSI); VACUUM BLASTING MACHINE OPERATOR. (ADAMS, CHELAN (EAST OF THE 120TH MERIDIAN), COLUMBIA, DOUGLAS (EAST OF THE 120TH MERIDIAN), FERRY, GRANT, OKANOGAN (EAST OF THE 120TH MERIDIAN), PEND OREILLE, STEVENS, AND YAKIMA (EAST OF THE 120TH MERIDIAN) COUNTIES).....$ 43.39 23.40

POWER EQUIPMENT OPERATOR: GROUP 8- CRANES (85 TONS AND OVER, AND ALL CLIMBING, OVERHEAD,RAIL AND TOWER), ALL ATTACHMENTS INCLUDING CLAMSHELL, DRAGLINE; LOADERS (OVERHEAD AND FRONT-END, 10 YARDS AND OVER); HELICOPTER PILOT. (ADAMS, CHELAN (EAST OF THE 120TH MERIDIAN), COLUMBIA, DOUGLAS (EAST OF THE 120TH MERIDIAN), FERRY, GRANT, OKANOGAN (EAST OF THE 120TH MERIDIAN), PEND OREILLE, STEVENS, AND YAKIMA (EAST OF THE 120TH MERIDIAN) COUNTIES).....$ 45.36 23.40

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

ENGI0612-001 06/01/2025

Rates	Fringes
POWER EQUIPMENT OPERATOR: GROUP 1A- CRANES, 100 TONS THRU 199 TONS, OR 250 FT OF BOOM (INCLUDING JIB WITH ATTACHMENTS); TOWER CRANE OVER 175 FT IN HEIGHT, BASE TO BOOM. (ON THE FOLLOWING PROJECTS, THE RATE FOR EACH GROUP SHALL BE 90% OF THE BASE RATE PLUS FULL FRINGE BENEFITS: 1. PROJECTS INVOLVING WORK ON STRUCTURES SUCH AS BUILDINGS AND BRIDGES WHOSE TOTAL VALUE IS LESS THAN $1.5 MILLION EXCLUDING MECHANICAL, ELECTRICAL, AND UTILITY PORTIONS OF THE CONTRACT. 2. PROJECTS OF LESS THAN $1 MILLION WHERE NO BUILDING IS INVOLVED. SURFACING AND PAVING INCLUDED, BUT UTILITIES EXCLUDED. 3. MARINE PROJECTS (DOCKS, WHARFS, ETC.) LESS THAN $150,000. ON ALL OTHER WORK, THE PUBLISHED RATES APPLY.) HANDLING OF HAZARDOUS WASTE MATERIALS: PERSONNEL IN ALL CRAFT CLASSIFICATIONS SUBJECT TO WORKING INSIDE A FEDERALLY DESIGNATED HAZARDOUS PERIMETER SHALL BE ELIGIBLE FOR COMPENSATION IN ACCORDANCE WITH THE FOLLOWING GROUP SCHEDULE RELATIVE TO THE LEVEL OF HAZARDOUS WASTE AS OUTLINED IN THE SPECIFIC HAZARDOUS WASTE PROJECT SITE SAFETY PLAN. H-1 BASE WAGE RATE WHEN ON A HAZARDOUS WASTE SITE WHEN NOT OUTFITTED WITH PROTECTIVE CLOTHING, CLASS ""D"" SUIT- BASE WAGE RATE PLUS $0.50 PER HOUR. H-2 CLASS ""C"" SUIT- BASE WAGE RATE PLUS $1.00 PER HOUR. H-3 CLASS ""B"" SUIT- BASE WAGE RATE PLUS $1.50 PER HOUR. H-4 CLASS ""A"" SUIT- BASE WAGE RATE PLUS $2.00 PER HOUR. (PIERCE COUNTY; ZONE DIFFERENTIAL: ZONE 1 (0-25 RADIUS MILES)= BASE RATE. ZONE 2: (26-45 RADIUS MILES)= $1.00. ZONE 3: (OVER 45 RADIUS MILES) = $1.30. BASEPOINTS: CENTRALIA, OLYMPIA, TACOMA).....$ 62.32	27.32
POWER EQUIPMENT OPERATOR: GROUP 1AA- CRANES- 200 TONS TO 300 TONS, OR 250 FT OF BOOM (INCLUDING JIB WITH ATTACHMENTS; TOWER CRANE OVER 175 FT IN HEIGHT, BASE TO BOOM. (ON THE FOLLOWING PROJECTS, THE RATE FOR EACH GROUP SHALL BE 90% OF THE BASE RATE PLUS FULL FRINGE BENEFITS: 1. PROJECTS INVOLVING WORK ON STRUCTURES SUCH AS BUILDINGS AND BRIDGES WHOSE TOTAL VALUE IS LESS THAN $1.5 MILLION EXCLUDING MECHANICAL, ELECTRICAL, AND UTILITY PORTIONS OF THE CONTRACT. 2. PROJECTS OF LESS THAN $1 MILLION WHERE NO BUILDING IS INVOLVED. SURFACING AND PAVING INCLUDED, BUT UTILITIES EXCLUDED. 3. MARINE PROJECTS (DOCKS, WHARFS, ETC.) LESS THAN $150,000. ON ALL OTHER WORK, THE PUBLISHED RATES APPLY.) HANDLING OF HAZARDOUS WASTE MATERIALS: PERSONNEL IN ALL CRAFT CLASSIFICATIONS SUBJECT TO WORKING INSIDE A FEDERALLY DESIGNATED HAZARDOUS PERIMETER SHALL BE ELIGIBLE FOR COMPENSATION IN ACCORDANCE WITH THE FOLLOWING GROUP SCHEDULE RELATIVE TO THE LEVEL OF HAZARDOUS WASTE AS OUTLINED IN THE SPECIFIC HAZARDOUS WASTE PROJECT	

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

SITE SAFETY PLAN. H-1 BASE WAGE RATE WHEN ON A HAZARDOUS WASTE SITE WHEN NOT OUTFITTED WITH PROTECTIVE CLOTHING, CLASS ""D"" SUIT- BASE WAGE RATE PLUS $0.50 PER HOUR. H-2 CLASS ""C"" SUIT- BASE WAGE RATE PLUS $1.00 PER HOUR. H-3 CLASS ""B"" SUIT- BASE WAGE RATE PLUS $1.50 PER HOUR. H-4 CLASS ""A"" SUIT- BASE WAGE RATE PLUS $2.00 PER HOUR. (PIERCE COUNTY; ZONE DIFFERENTIAL: ZONE 1 (0-25 RADIUS MILES)= BASE RATE. ZONE 2: (26-45 RADIUS MILES)= $1.00. ZONE 3: (OVER 45 RADIUS MILES) = $1.30. BASEPOINTS: CENTRALIA, OLYMPIA, TACOMA).....$ 63.22 27.32

POWER EQUIPMENT OPERATOR: GROUP 1AAA- CRANES-OVER 300 TONS OR 300 FT OF BOOM (INCLUDING JIB WITH ATTACHMENT). (ON THE FOLLOWING PROJECTS, THE RATE FOR EACH GROUP SHALL BE 90% OF THE BASE RATE PLUS FULL FRINGE BENEFITS: 1. PROJECTS INVOLVING WORK ON STRUCTURES SUCH AS BUILDINGS AND BRIDGES WHOSE TOTAL VALUE IS LESS THAN $1.5 MILLION EXCLUDING MECHANICAL, ELECTRICAL, AND UTILITY PORTIONS OF THE CONTRACT. 2. PROJECTS OF LESS THAN $1 MILLION WHERE NO BUILDING IS INVOLVED. SURFACING AND PAVING INCLUDED, BUT UTILITIES EXCLUDED. 3. MARINE PROJECTS (DOCKS, WHARFS, ETC.) LESS THAN $150,000. ON ALL OTHER WORK, THE PUBLISHED RATES APPLY.) HANDLING OF HAZARDOUS WASTE MATERIALS: PERSONNEL IN ALL CRAFT CLASSIFICATIONS SUBJECT TO WORKING INSIDE A FEDERALLY DESIGNATED HAZARDOUS PERIMETER SHALL BE ELIGIBLE FOR COMPENSATION IN ACCORDANCE WITH THE FOLLOWING GROUP SCHEDULE RELATIVE TO THE LEVEL OF HAZARDOUS WASTE AS OUTLINED IN THE SPECIFIC HAZARDOUS WASTE PROJECT SITE SAFETY PLAN. H-1 BASE WAGE RATE WHEN ON A HAZARDOUS WASTE SITE WHEN NOT OUTFITTED WITH PROTECTIVE CLOTHING, CLASS ""D"" SUIT- BASE WAGE RATE PLUS $0.50 PER HOUR. H-2 CLASS ""C"" SUIT- BASE WAGE RATE PLUS $1.00 PER HOUR. H-3 CLASS ""B"" SUIT- BASE WAGE RATE PLUS $1.50 PER HOUR. H-4 CLASS ""A"" SUIT- BASE WAGE RATE PLUS $2.00 PER HOUR. (PIERCE COUNTY; ZONE DIFFERENTIAL: ZONE 1 (0-25 RADIUS MILES)= BASE RATE. ZONE 2: (26-45 RADIUS MILES)= $1.00. ZONE 3: (OVER 45 RADIUS MILES) = $1.30. BASEPOINTS: CENTRALIA, OLYMPIA, TACOMA).....$ 64.11 27.32

POWER EQUIPMENT OPERATOR: GROUP 1- CABLEWAY; CRANES 45 TONS THRU 99 TONS UNDER 150 FT OF BOOM (INCLUDING JIB WITH ATTACHMENTS); CRANE-OVERHEAD, BRIDGE TYPE, 45 TONS THRU 99 TONS; DERRICKS ON BUILDING WORK; EXCAVATOR, SHOVEL, BACKHOES OVER 3 YARDS AND UNDER 6 YARDS; HARD TAIL END DUMP ARTICULATING OFF-ROAD EQUIPMENT 45 YARDS AND OVER; LOADER-OVERHEAD, 6 YARDS TO, BUT NOT INCLUDING, 8 YARDS; MUCKING MACHINE, MOLE, TUNNEL, DRILL AND/OR SHIELD; QUAD 9 HD 41, D-10; REMOTE CONTROL OPERATOR ON RUBBER TIRED EARTH MOVING EQUIPMENT; ROLLAGON; SCRAPES-SELF-PROPELLED 45 YARDS AND OVER; SLIPFORM PAVERS; TRANSPORTERS, ALL TRACK OR TRUCK TYPE. (ON THE FOLLOWING PROJECTS, THE RATE FOR EACH GROUP SHALL BE 90% OF THE BASE RATE PLUS FULL FRINGE

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

BENEFITS: 1. PROJECTS INVOLVING WORK ON STRUCTURES SUCH AS BUILDINGS AND BRIDGES WHOSE TOTAL VALUE IS LESS THAN $1.5 MILLION EXCLUDING MECHANICAL, ELECTRICAL, AND UTILITY PORTIONS OF THE CONTRACT. 2. PROJECTS OF LESS THAN $1 MILLION WHERE NO BUILDING IS INVOLVED. SURFACING AND PAVING INCLUDED, BUT UTILITIES EXCLUDED. 3. MARINE PROJECTS (DOCKS, WHARFS, ETC.) LESS THAN $150,000. ON ALL OTHER WORK, THE PUBLISHED RATES APPLY.) HANDLING OF HAZARDOUS WASTE MATERIALS: PERSONNEL IN ALL CRAFT CLASSIFICATIONS SUBJECT TO WORKING INSIDE A FEDERALLY DESIGNATED HAZARDOUS PERIMETER SHALL BE ELIGIBLE FOR COMPENSATION IN ACCORDANCE WITH THE FOLLOWING GROUP SCHEDULE RELATIVE TO THE LEVEL OF HAZARDOUS WASTE AS OUTLINED IN THE SPECIFIC HAZARDOUS WASTE PROJECT SITE SAFETY PLAN. H-1 BASE WAGE RATE WHEN ON A HAZARDOUS WASTE SITE WHEN NOT OUTFITTED WITH PROTECTIVE CLOTHING, CLASS ""D"" SUIT- BASE WAGE RATE PLUS $0.50 PER HOUR. H-2 CLASS ""C"" SUIT- BASE WAGE RATE PLUS $1.00 PER HOUR. H-3 CLASS ""B"" SUIT- BASE WAGE RATE PLUS $1.50 PER HOUR. H-4 CLASS ""A"" SUIT- BASE WAGE RATE PLUS $2.00 PER HOUR. (PIERCE COUNTY; ZONE DIFFERENTIAL: ZONE 1 (0-25 RADIUS MILES)= BASE RATE. ZONE 2: (26-45 RADIUS MILES)= $1.00. ZONE 3: (OVER 45 RADIUS MILES) = $1.30. BASEPOINTS: CENTRALIA, OLYMPIA, TACOMA).....$ 61.41 27.32

POWER EQUIPMENT OPERATOR: GROUP 2- BARRIER MACHINE (ZIPPER); BATCH PLANT OPERATOR-CONCRETE; BUMP CUTTER; CRANES, 20 TONS THRU 44 TONS WITH ATTACHMENTS; CRANE-OVERHEAD, BRIDGE TYPE, 20 TONS THROUGH 44 TONS; CHIPPER; CONCRETE PUMP-TRUCK MOUNT WITH BOOM ATTACHMENT; CRUSHER; DECK ENGINEER/DECK WINCHES (POWER); DRILLING MACHINE; EXCAVATOR, SHOVEL, BACKHOE-3 YARDS AND UNDER; FINISHING MACHINE, BIDWELL, GAMACO AND SIMILAR EQUIPMENT; GUARDRAIL PUNCH; LOADERS, OVERHEAD OUNDER 6 YARDS; LOADERS-PLANT FEED; LOCOMOTIVES-ALL; MECHANICS-ALL; MIXERS, ASHALT PLANT; MOTOR PATROL GRADERS, FINISHING; PILEDRIVER (OTHER THAN CRANE MOUNT); ROTO-MILL, ROTO-GRINDER; SCREEDMAN, SPREADER, TOPSIDE OPERATOR-BLAW KNOX, CEDAR RAPIDS, JAEGER, CATERPILLAR, BARBAR GREEN; SCRAPER-SELF-PROPELLED, HARD TAIL END DUMP, ARTICULATING OFF-ROAD EQUIPMENT-UNDER 45 YARDS; SUBGRADER TRIMMER; TRACTORS, BACKHOE OVER 75 HP; TRANSFER MATERIAL SERVICE MACHINE-SHUTTLE BUGGY, BLAW KNOWX-ROADTEC; TRUCK CRANE OILER/DRIVER-100 TONS AND OVER; TRUCK MOUNT PORTABLE CONVEYOR; YO YO PAY. (ON THE FOLLOWING PROJECTS, THE RATE FOR EACH GROUP SHALL BE 90% OF THE BASE RATE PLUS FULL FRINGE BENEFITS: 1. PROJECTS INVOLVING WORK ON STRUCTURES SUCH AS BUILDINGS AND BRIDGES WHOSE TOTAL VALUE IS LESS THAN $1.5 MILLION EXCLUDING MECHANICAL, ELECTRICAL, AND UTILITY PORTIONS OF THE CONTRACT. 2. PROJECTS OF LESS THAN $1 MILLION WHERE NO BUILDING IS INVOLVED. SURFACING AND PAVING INCLUDED, BUT

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

UTILITIES EXCLUDED. 3. MARINE PROJECTS (DOCKS, WHARFS, ETC.) LESS THAN $150,000. ON ALL OTHER WORK, THE PUBLISHED RATES APPLY.) HANDLING OF HAZARDOUS WASTE MATERIALS: PERSONNEL IN ALL CRAFT CLASSIFICATIONS SUBJECT TO WORKING INSIDE A FEDERALLY DESIGNATED HAZARDOUS PERIMETER SHALL BE ELIGIBLE FOR COMPENSATION IN ACCORDANCE WITH THE FOLLOWING GROUP SCHEDULE RELATIVE TO THE LEVEL OF HAZARDOUS WASTE AS OUTLINED IN THE SPECIFIC HAZARDOUS WASTE PROJECT SITE SAFETY PLAN. H-1 BASE WAGE RATE WHEN ON A HAZARDOUS WASTE SITE WHEN NOT OUTFITTED WITH PROTECTIVE CLOTHING, CLASS ""D"" SUIT- BASE WAGE RATE PLUS $0.50 PER HOUR. H-2 CLASS ""C"" SUIT- BASE WAGE RATE PLUS $1.00 PER HOUR. H-3 CLASS ""B"" SUIT- BASE WAGE RATE PLUS $1.50 PER HOUR. H-4 CLASS ""A"" SUIT- BASE WAGE RATE PLUS $2.00 PER HOUR. (PIERCE COUNTY; ZONE DIFFERENTIAL: ZONE 1 (0-25 RADIUS MILES)= BASE RATE. ZONE 2: (26-45 RADIUS MILES)= $1.00. ZONE 3: (OVER 45 RADIUS MILES) = $1.30. BASEPOINTS: CENTRALIA, OLYMPIA, TACOMA).....$ 60.63 27.32

POWER EQUIPMENT OPERATOR: GROUP 3- CONVEYORS; CRANES THROUGH 19 TONS WITH ATTACHMENTS; CRANE-A-FRAME OVER 10 TONS; DRILL OILERS-AUGER TYPE, TRUCK OR CRANE MOUNT; DOZER-D-9 AND UNDER; FORKLIFT-3000 LBS. AND OVER WITH ATTACHMENTS; HORIZONTAL/DIRECTIONAL DRILL LOCATOR; OUTSIDE HOISTS (ELEVATORS AND MANLIFTS), AIR TUGGERS, STRATO TOWER BUCKET AND ELEVATORS; HYDRALIFTS/BOOM TRUCKS OVER 10 TONS; LOADERS-ELEVATING TYPE, BELT; MOTOR PATROL GRADER-NONFINISHING; PLANT OILER-ASPHALT, CRUSHER; PUMP-CONCRETE; ROLLER, PLANT MIX OR MULTI-LIFT MATERIALS; SAWS-CONCRETE; SCRAPERS, CONCRETE AND CARRY ALL; SERVICE ENGINEERS-EQUIPMENT; TRENCHING MACHINES; TRUCK CRANE OILER/DRIVER UNDER 100 TONS; TRACTORS, BACKHOE UNDER 75 HP. (ON THE FOLLOWING PROJECTS, THE RATE FOR EACH GROUP SHALL BE 90% OF THE BASE RATE PLUS FULL FRINGE BENEFITS: 1. PROJECTS INVOLVING WORK ON STRUCTURES SUCH AS BUILDINGS AND BRIDGES WHOSE TOTAL VALUE IS LESS THAN $1.5 MILLION EXCLUDING MECHANICAL, ELECTRICAL, AND UTILITY PORTIONS OF THE CONTRACT. 2. PROJECTS OF LESS THAN $1 MILLION WHERE NO BUILDING IS INVOLVED. SURFACING AND PAVING INCLUDED, BUT UTILITIES EXCLUDED. 3. MARINE PROJECTS (DOCKS, WHARFS, ETC.) LESS THAN $150,000. ON ALL OTHER WORK, THE PUBLISHED RATES APPLY.) HANDLING OF HAZARDOUS WASTE MATERIALS: PERSONNEL IN ALL CRAFT CLASSIFICATIONS SUBJECT TO WORKING INSIDE A FEDERALLY DESIGNATED HAZARDOUS PERIMETER SHALL BE ELIGIBLE FOR COMPENSATION IN ACCORDANCE WITH THE FOLLOWING GROUP SCHEDULE RELATIVE TO THE LEVEL OF HAZARDOUS WASTE AS OUTLINED IN THE SPECIFIC HAZARDOUS WASTE PROJECT SITE SAFETY PLAN. H-1 BASE WAGE RATE WHEN ON A HAZARDOUS WASTE SITE WHEN NOT OUTFITTED WITH PROTECTIVE CLOTHING, CLASS ""D"" SUIT- BASE WAGE RATE

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

PLUS $0.50 PER HOUR. H-2 CLASS ""C"" SUIT- BASE WAGE RATE PLUS $1.00 PER HOUR. H-3 CLASS ""B"" SUIT- BASE WAGE RATE PLUS $1.50 PER HOUR. H-4 CLASS ""A"" SUIT- BASE WAGE RATE PLUS $2.00 PER HOUR. (PIERCE COUNTY; ZONE DIFFERENTIAL: ZONE 1 (0-25 RADIUS MILES)= BASE RATE. ZONE 2: (26-45 RADIUS MILES)= $1.00. ZONE 3: (OVER 45 RADIUS MILES) = $1.30. BASEPOINTS: CENTRALIA, OLYMPIA, TACOMA).....$ 59.96 27.32

POWER EQUIPMENT OPERATOR: GROUP 4- ASSISTANT ENGINEER; BOBCAT; BROOMS; COMPRESSOR; CONCRETE FINISH MACHINE-LASER SCREED; CRANES A-FRAME 10 TONS AND UNDER; ELEVATOR AND MANLIFT (PERMANENT AND SHAFT TYPE); FORKLIFTS-UNDER 3000 LBS. WITH ATTACHMENTS; GRADECHECKER, STAKEHOP; HYDRALIFTS/BOOM TRUCKS, 10 TONS AND UNDER; OIL DISTRIBUTORS, BLOWER DISTRIBUTION AND MULCH SEEDING OPERATOR; PAVEMENT BREAKER; POSTHOLD DIGGER-MECHANICAL; POWER PLANT; PUMPS-WATER; RIGGER AND BELLMAN; ROLLER-OTHER THAN PLANT MIX; WHEEL TRACTORS, FARMALL TYPE; SHOTCRETE/GUNITE EQUIPMENT OPERATOR. (ON THE FOLLOWING PROJECTS, THE RATE FOR EACH GROUP SHALL BE 90% OF THE BASE RATE PLUS FULL FRINGE BENEFITS: 1. PROJECTS INVOLVING WORK ON STRUCTURES SUCH AS BUILDINGS AND BRIDGES WHOSE TOTAL VALUE IS LESS THAN $1.5 MILLION EXCLUDING MECHANICAL, ELECTRICAL, AND UTILITY PORTIONS OF THE CONTRACT. 2. PROJECTS OF LESS THAN $1 MILLION WHERE NO BUILDING IS INVOLVED. SURFACING AND PAVING INCLUDED, BUT UTILITIES EXCLUDED. 3. MARINE PROJECTS (DOCKS, WHARFS, ETC.) LESS THAN $150,000. ON ALL OTHER WORK, THE PUBLISHED RATES APPLY.) HANDLING OF HAZARDOUS WASTE MATERIALS: PERSONNEL IN ALL CRAFT CLASSIFICATIONS SUBJECT TO WORKING INSIDE A FEDERALLY DESIGNATED HAZARDOUS PERIMETER SHALL BE ELIGIBLE FOR COMPENSATION IN ACCORDANCE WITH THE FOLLOWING GROUP SCHEDULE RELATIVE TO THE LEVEL OF HAZARDOUS WASTE AS OUTLINED IN THE SPECIFIC HAZARDOUS WASTE PROJECT SITE SAFETY PLAN. H-1 BASE WAGE RATE WHEN ON A HAZARDOUS WASTE SITE WHEN NOT OUTFITTED WITH PROTECTIVE CLOTHING, CLASS ""D"" SUIT- BASE WAGE RATE PLUS $0.50 PER HOUR. H-2 CLASS ""C"" SUIT- BASE WAGE RATE PLUS $1.00 PER HOUR. H-3 CLASS ""B"" SUIT- BASE WAGE RATE PLUS $1.50 PER HOUR. H-4 CLASS ""A"" SUIT- BASE WAGE RATE PLUS $2.00 PER HOUR. (PIERCE COUNTY; ZONE DIFFERENTIAL: ZONE 1 (0-25 RADIUS MILES)= BASE RATE. ZONE 2: (26-45 RADIUS MILES)= $1.00. ZONE 3: (OVER 45 RADIUS MILES) = $1.30. BASEPOINTS: CENTRALIA, OLYMPIA, TACOMA).....$ 56.15 27.32

ENGI0612-008 06/01/2025

Rates Fringes

POWER EQUIPMENT OPERATOR: GROUP 1A-CRANES, 100 TONS THRU 199 TONS, OR 150 FT OF BOOM (INCLUDING JIB WITH ATTACHMENTS); CRANE-OVERHEAD, BRIDGE TYPE, 100 TONS AND OVER; TOWER CRANE UP TO 175 FT IN

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

HEIGHT BASE TO BOOM; LOADERS-OVERHEAD, 8 YARDS AND OVER; SHOVELS, EXCAVATOR, BACKHOES-6 YARDS AND OVER WITH ATTACHMENTS. (ON THE FOLLOWING PROJECTS, THE RATE FOR EACH GROUP SHALL BE 90% OF THE BASE RATE PLUS FULL FRINGE BENEFITS: 1. PROJECTS INVOLVING WORK ON STRUCTURES SUCH AS BUILDINGS AND BRIDGES WHOSE TOTAL VALUE IS LESS THAN $1.5 MILLION EXCLUDING MECHANICAL, ELECTRICAL, AND UTILITY PORTIONS OF THE CONTRACT. 2. PROJECTS OF LESS THAN $1 MILLION WHERE NO BUILDING IS INVOLVED. SURFACING AND PAVING INCLUDED, BUT UTILITIES EXCLUDED. 3. MARINE PROJECTS (DOCKS, WHARFS, ETC.) LESS THAN $150,000. ON ALL OTHER WORK, THE PUBLISHED RATES APPLY.) HANDLING OF HAZARDOUS WASTE MATERIALS: PERSONNEL IN ALL CRAFT CLASSIFICATIONS SUBJECT TO WORKING INSIDE A FEDERALLY DESIGNATED HAZARDOUS PERIMETER SHALL BE ELIGIBLE FOR COMPENSATION IN ACCORDANCE WITH THE FOLLOWING GROUP SCHEDULE RELATIVE TO THE LEVEL OF HAZARDOUS WASTE AS OUTLINED IN THE SPECIFIC HAZARDOUS WASTE PROJECT SITE SAFETY PLAN. H-1 BASE WAGE RATE WHEN ON A HAZARDOUS WASTE SITE WHEN NOT OUTFITTED WITH PROTECTIVE CLOTHING, CLASS ""D"" SUIT- BASE WAGE RATE PLUS $0.50 PER HOUR. H-2 CLASS ""C"" SUIT- BASE WAGE RATE PLUS $1.00 PER HOUR. H-3 CLASS ""B"" SUIT- BASE WAGE RATE PLUS $1.50 PER HOUR. H-4 CLASS ""A"" SUIT- BASE WAGE RATE PLUS $2.00 PER HOUR. (LEWIS AND PACIFIC (PORTION LYING NORTH OF A PARALLEL LINE EXTENDING WEST FROM THE NORTHERN BOUNDARY OF WAHKAIKUM COUNTY TO THE SEA) COUNTIES; ZONE DIFFERENTIAL: ZONE 1 (0-25 RADIUS MILES)= BASE RATE. ZONE 2: (26-45 RADIUS MILES)= $1.00. ZONE 3: (OVER 45 RADIUS MILES) = $1.30. BASEPOINTS: CENTRALIA, OLYMPIA, TACOMA).....$ 61.22 27.32

POWER EQUIPMENT OPERATOR: GROUP 1AA- CRANES- 200 TONS TO 300 TONS, OR 250 FT OF BOOM (INCLUDING JIB WITH ATTACHMENTS); TOWER CRANE OVER 175 FT IN HEIGHT, BASE TO BOOM. (ON THE FOLLOWING PROJECTS, THE RATE FOR EACH GROUP SHALL BE 90% OF THE BASE RATE PLUS FULL FRINGE BENEFITS: 1. PROJECTS INVOLVING WORK ON STRUCTURES SUCH AS BUILDINGS AND BRIDGES WHOSE TOTAL VALUE IS LESS THAN $1.5 MILLION EXCLUDING MECHANICAL, ELECTRICAL, AND UTILITY PORTIONS OF THE CONTRACT. 2. PROJECTS OF LESS THAN $1 MILLION WHERE NO BUILDING IS INVOLVED. SURFACING AND PAVING INCLUDED, BUT UTILITIES EXCLUDED. 3. MARINE PROJECTS (DOCKS, WHARFS, ETC.) LESS THAN $150,000. ON ALL OTHER WORK, THE PUBLISHED RATES APPLY.) HANDLING OF HAZARDOUS WASTE MATERIALS: PERSONNEL IN ALL CRAFT CLASSIFICATIONS SUBJECT TO WORKING INSIDE A FEDERALLY DESIGNATED HAZARDOUS PERIMETER SHALL BE ELIGIBLE FOR COMPENSATION IN ACCORDANCE WITH THE FOLLOWING GROUP SCHEDULE RELATIVE TO THE LEVEL OF HAZARDOUS WASTE AS OUTLINED IN THE SPECIFIC HAZARDOUS WASTE PROJECT SITE SAFETY PLAN. H-1 BASE WAGE RATE WHEN ON A

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

HAZARDOUS WASTE SITE WHEN NOT OUTFITTED WITH PROTECTIVE CLOTHING, CLASS ""D"" SUIT- BASE WAGE RATE PLUS $0.50 PER HOUR. H-2 CLASS ""C"" SUIT- BASE WAGE RATE PLUS $1.00 PER HOUR. H-3 CLASS ""B"" SUIT- BASE WAGE RATE PLUS $1.50 PER HOUR. H-4 CLASS ""A"" SUIT- BASE WAGE RATE PLUS $2.00 PER HOUR. (LEWIS AND PACIFIC (PORTION LYING NORTH OF A PARALLEL LINE EXTENDING WEST FROM THE NORTHERN BOUNDARY OF WAHKAIKUM COUNTY TO THE SEA) COUNTIES; ZONE DIFFERENTIAL: ZONE 1 (0-25 RADIUS MILES)= BASE RATE. ZONE 2: (26-45 RADIUS MILES)= $1.00. ZONE 3: (OVER 45 RADIUS MILES) = $1.30. BASEPOINTS: CENTRALIA, OLYMPIA, TACOMA).....$ 62.12 27.32

POWER EQUIPMENT OPERATOR: GROUP 1AAA- CRANES-OVER 300 TONS OR 300 FT OF BOOM (INCLUDING JIB WITH ATTACHMENTS). (ON THE FOLLOWING PROJECTS, THE RATE FOR EACH GROUP SHALL BE 90% OF THE BASE RATE PLUS FULL FRINGE BENEFITS: 1. PROJECTS INVOLVING WORK ON STRUCTURES SUCH AS BUILDINGS AND BRIDGES WHOSE TOTAL VALUE IS LESS THAN $1.5 MILLION EXCLUDING MECHANICAL, ELECTRICAL, AND UTILITY PORTIONS OF THE CONTRACT. 2. PROJECTS OF LESS THAN $1 MILLION WHERE NO BUILDING IS INVOLVED. SURFACING AND PAVING INCLUDED, BUT UTILITIES EXCLUDED. 3. MARINE PROJECTS (DOCKS, WHARFS, ETC.) LESS THAN $150,000. ON ALL OTHER WORK, THE PUBLISHED RATES APPLY.) HANDLING OF HAZARDOUS WASTE MATERIALS: PERSONNEL IN ALL CRAFT CLASSIFICATIONS SUBJECT TO WORKING INSIDE A FEDERALLY DESIGNATED HAZARDOUS PERIMETER SHALL BE ELIGIBLE FOR COMPENSATION IN ACCORDANCE WITH THE FOLLOWING GROUP SCHEDULE RELATIVE TO THE LEVEL OF HAZARDOUS WASTE AS OUTLINED IN THE SPECIFIC HAZARDOUS WASTE PROJECT SITE SAFETY PLAN. H-1 BASE WAGE RATE WHEN ON A HAZARDOUS WASTE SITE WHEN NOT OUTFITTED WITH PROTECTIVE CLOTHING, CLASS ""D"" SUIT- BASE WAGE RATE PLUS $0.50 PER HOUR. H-2 CLASS ""C"" SUIT- BASE WAGE RATE PLUS $1.00 PER HOUR. H-3 CLASS ""B"" SUIT- BASE WAGE RATE PLUS $1.50 PER HOUR. H-4 CLASS ""A"" SUIT- BASE WAGE RATE PLUS $2.00 PER HOUR. (LEWIS AND PACIFIC (PORTION LYING NORTH OF A PARALLEL LINE EXTENDING WEST FROM THE NORTHERN BOUNDARY OF WAHKAIKUM COUNTY TO THE SEA) COUNTIES; ZONE DIFFERENTIAL: ZONE 1 (0-25 RADIUS MILES)= BASE RATE. ZONE 2: (26-45 RADIUS MILES)= $1.00. ZONE 3: (OVER 45 RADIUS MILES) = $1.30. BASEPOINTS: CENTRALIA, OLYMPIA, TACOMA).....$ 62.99 27.32

POWER EQUIPMENT OPERATOR: GROUP 1- CABLEWAY; CRANES 45 TONS THRU 99 TONS UNDER 150 FT OF BOOM (INCLUDING JIB WITH ATTACHMENTS); CRANE-OVERHEAD, VRIDGE TYPE, 45 TONS THRU 99 TONS; DERRICKS ON BUILDING WORK; EXCAVATOR, SHOVEL, BACKHOES OVER 3 YARDS AND UNDER 6 YARDS; HARD TAIL END DUMP ARTICULATING OFF-ROAD EQUIPMENT 45 YARDS AND OVER; LOADER-OVERHEAD, 6 YARDS TO, BUT NOT INCLUDING, 8 YARDS; MUCKING MACHINE, MOLE, TUNNEL, DRILL AND/OR SHIELD; QUAD 9 HD 41, D-10; REMOTE CONTROL OPERATOR

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

ON RUBBER TIRED EARTH MOVING EQUIPMENT; ROLLAGON; SCRAPERS-SELF-PROPELLED 45 YARDS AND OVER; SLIPFORM PAVERS; TRANSPORTERS, ALL TRACK OR TRUCK TYPE. (ON THE FOLLOWING PROJECTS, THE RATE FOR EACH GROUP SHALL BE 90% OF THE BASE RATE PLUS FULL FRINGE BENEFITS: 1. PROJECTS INVOLVING WORK ON STRUCTURES SUCH AS BUILDINGS AND BRIDGES WHOSE TOTAL VALUE IS LESS THAN $1.5 MILLION EXCLUDING MECHANICAL, ELECTRICAL, AND UTILITY PORTIONS OF THE CONTRACT. 2. PROJECTS OF LESS THAN $1 MILLION WHERE NO BUILDING IS INVOLVED. SURFACING AND PAVING INCLUDED, BUT UTILITIES EXCLUDED. 3. MARINE PROJECTS (DOCKS, WHARFS, ETC.) LESS THAN $150,000. ON ALL OTHER WORK, THE PUBLISHED RATES APPLY.) HANDLING OF HAZARDOUS WASTE MATERIALS: PERSONNEL IN ALL CRAFT CLASSIFICATIONS SUBJECT TO WORKING INSIDE A FEDERALLY DESIGNATED HAZARDOUS PERIMETER SHALL BE ELIGIBLE FOR COMPENSATION IN ACCORDANCE WITH THE FOLLOWING GROUP SCHEDULE RELATIVE TO THE LEVEL OF HAZARDOUS WASTE AS OUTLINED IN THE SPECIFIC HAZARDOUS WASTE PROJECT SITE SAFETY PLAN. H-1 BASE WAGE RATE WHEN ON A HAZARDOUS WASTE SITE WHEN NOT OUTFITTED WITH PROTECTIVE CLOTHING, CLASS ""D"" SUIT- BASE WAGE RATE PLUS $0.50 PER HOUR. H-2 CLASS ""C"" SUIT- BASE WAGE RATE PLUS $1.00 PER HOUR. H-3 CLASS ""B"" SUIT- BASE WAGE RATE PLUS $1.50 PER HOUR. H-4 CLASS ""A"" SUIT- BASE WAGE RATE PLUS $2.00 PER HOUR. (LEWIS AND PACIFIC (PORTION LYING NORTH OF A PARALLEL LINE EXTENDING WEST FROM THE NORTHERN BOUNDARY OF WAHKAIKUM COUNTY TO THE SEA) COUNTIES; ZONE DIFFERENTIAL: ZONE 1 (0-25 RADIUS MILES)= BASE RATE. ZONE 2: (26-45 RADIUS MILES)= $1.00. ZONE 3: (OVER 45 RADIUS MILES) = $1.30. BASEPOINTS: CENTRALIA, OLYMPIA, TACOMA).....$ 60.32 27.32

POWER EQUIPMENT OPERATOR: GROUP 2- BARRIER MACHINE (ZIPPER); BATCH PLANT OPERATOR-CONCRETE; BUMP CUTTER; CRANES, 20 TONS THRU 44 TONS WITH ATTACHMENTS; CRANE-OVERHED, BRIDGE TYPE, 20 TONS THROUGH 44 TONS; CHIPPER; CONCRETE PUMP-TRUCK MOUNT WITH BOOM ATTACHMENT; CRUSHER; DECK ENGINEER/DECK WINCHES (POWER); DRILLING MACHINE; EXCAVATOR, SHOVEL, BACKHOE-3 YARDS AND UNDER; FINISHING MACHINE, BIDWELL, GAMACO AND SIMILAR EQUIPMENT; GUARDRAIL PUNCH; LODERS, OVERHEAD UNDER 6 YARDS; LODERS-PLANT FEED; LOCOMOTIVES-ALL; MECHANICS-ALL; MIXERS, ASPHALT PLANT; MOTOR PATROL GRADERS, FINISHING; PILEDRIVER (OTHER THAN CRANE MOUNT); ROTO-MILL, ROTO-GRINDER; SCREEDMAN, SPREADER, TOPSIDE OPERATOR-BLAW KNOX, CEDAR RAPIDS, JAEGER, CATERPILLAR, BARBAR GREEN; SCRAPER-SELF-PROPELLED, HARD TAIL END DUMP, ARTICULATING OFF-ROAD EQUIPMENT-UNDER 45 YARDS; SUBGRADER TRIMMER; TRACTORS, BACKHOE OVER 75 HP; TRANSFER MATERIAL SERVICE MACHINE-SHUTTLE BUGGY, BLAW KNOX-ROADTEC; TRUCK CRANE OILER/DRIVER-100 TONS AND OVER; TRUCK MOUNT PORTABLE CONVEYOR; YO YO PAY. (ON THE

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

FOLLOWING PROJECTS, THE RATE FOR EACH GROUP SHALL BE 90% OF THE BASE RATE PLUS FULL FRINGE BENEFITS: 1. PROJECTS INVOLVING WORK ON STRUCTURES SUCH AS BUILDINGS AND BRIDGES WHOSE TOTAL VALUE IS LESS THAN $1.5 MILLION EXCLUDING MECHANICAL, ELECTRICAL, AND UTILITY PORTIONS OF THE CONTRACT. 2. PROJECTS OF LESS THAN $1 MILLION WHERE NO BUILDING IS INVOLVED. SURFACING AND PAVING INCLUDED, BUT UTILITIES EXCLUDED. 3. MARINE PROJECTS (DOCKS, WHARFS, ETC.) LESS THAN $150,000. ON ALL OTHER WORK, THE PUBLISHED RATES APPLY.) HANDLING OF HAZARDOUS WASTE MATERIALS: PERSONNEL IN ALL CRAFT CLASSIFICATIONS SUBJECT TO WORKING INSIDE A FEDERALLY DESIGNATED HAZARDOUS PERIMETER SHALL BE ELIGIBLE FOR COMPENSATION IN ACCORDANCE WITH THE FOLLOWING GROUP SCHEDULE RELATIVE TO THE LEVEL OF HAZARDOUS WASTE AS OUTLINED IN THE SPECIFIC HAZARDOUS WASTE PROJECT SITE SAFETY PLAN. H-1 BASE WAGE RATE WHEN ON A HAZARDOUS WASTE SITE WHEN NOT OUTFITTED WITH PROTECTIVE CLOTHING, CLASS ""D"" SUIT- BASE WAGE RATE PLUS $0.50 PER HOUR. H-2 CLASS ""C"" SUIT- BASE WAGE RATE PLUS $1.00 PER HOUR. H-3 CLASS ""B"" SUIT- BASE WAGE RATE PLUS $1.50 PER HOUR. H-4 CLASS ""A"" SUIT- BASE WAGE RATE PLUS $2.00 PER HOUR. (LEWIS AND PACIFIC (PORTION LYING NORTH OF A PARALLEL LINE EXTENDING WEST FROM THE NORTHERN BOUNDARY OF WAHKAIKUM COUNTY TO THE SEA) COUNTIES; ZONE DIFFERENTIAL: ZONE 1 (0-25 RADIUS MILES)= BASE RATE. ZONE 2: (26-45 RADIUS MILES)= $1.00. ZONE 3: (OVER 45 RADIUS MILES) = $1.30. BASEPOINTS: CENTRALIA, OLYMPIA, TACOMA).....$ 59.56 27.32

POWER EQUIPMENT OPERATOR: GROUP 3- CONVEYORS; CRANES THROUGH 19 TONS WITH ATTACHMENTS; CRANE-A-FRAME OVER 10 TONS; DRILL OILERS-AUGER TYPE, TRUCK OR CRANE MOUNT; DOZER-D-9 AND UNDER; FORKLIFT-3000 LBS. AND OVER WITH ATTACHMENTS; HORIZONTAL/DIRECTIONAL DRILL LOCATOR; OUTSIDE HOISTS-(ELEVATORS AND MANLIFTS), AIR TUGGERS, STRATO TOWER BUCKET ELEVATORS; HYDRALIFTS/BOOM TRUCKS OVER 10 TONS; LOADERS-ELEVATING TYPE, BELT; MOTOR PATROL GRADER-NONFINISHING; PLANT OILER-ASPHALT, CRUSHER; PUMP-CONCRETE; ROLLER, PLANT MIX OR MULTI-LIFT MATERIALS; SAWS-CONCRETE; SCRAPERS, CONCRETE AND CARRY ALL; SERVICE ENGINEERS-EQUIPMENT; TRENCHING MACHINES; TRUCK CRANE OILER/DRIVER UNDER 100 TONS; TRACTORS, BACKHOE UNDER 75 HP. (ON THE FOLLOWING PROJECTS, THE RATE FOR EACH GROUP SHALL BE 90% OF THE BASE RATE PLUS FULL FRINGE BENEFITS: 1. PROJECTS INVOLVING WORK ON STRUCTURES SUCH AS BUILDINGS AND BRIDGES WHOSE TOTAL VALUE IS LESS THAN $1.5 MILLION EXCLUDING MECHANICAL, ELECTRICAL, AND UTILITY PORTIONS OF THE CONTRACT. 2. PROJECTS OF LESS THAN $1 MILLION WHERE NO BUILDING IS INVOLVED. SURFACING AND PAVING INCLUDED, BUT UTILITIES EXCLUDED. 3. MARINE PROJECTS (DOCKS, WHARFS, ETC.) LESS THAN

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

$150,000. ON ALL OTHER WORK, THE PUBLISHED RATES APPLY.) HANDLING OF HAZARDOUS WASTE MATERIALS: PERSONNEL IN ALL CRAFT CLASSIFICATIONS SUBJECT TO WORKING INSIDE A FEDERALLY DESIGNATED HAZARDOUS PERIMETER SHALL BE ELIGIBLE FOR COMPENSATION IN ACCORDANCE WITH THE FOLLOWING GROUP SCHEDULE RELATIVE TO THE LEVEL OF HAZARDOUS WASTE AS OUTLINED IN THE SPECIFIC HAZARDOUS WASTE PROJECT SITE SAFETY PLAN. H-1 BASE WAGE RATE WHEN ON A HAZARDOUS WASTE SITE WHEN NOT OUTFITTED WITH PROTECTIVE CLOTHING, CLASS ""D"" SUIT- BASE WAGE RATE PLUS $0.50 PER HOUR. H-2 CLASS ""C"" SUIT- BASE WAGE RATE PLUS $1.00 PER HOUR. H-3 CLASS ""B"" SUIT- BASE WAGE RATE PLUS $1.50 PER HOUR. H-4 CLASS ""A"" SUIT- BASE WAGE RATE PLUS $2.00 PER HOUR. (LEWIS AND PACIFIC (PORTION LYING NORTH OF A PARALLEL LINE EXTENDING WEST FROM THE NORTHERN BOUNDARY OF WAHKAIKUM COUNTY TO THE SEA) COUNTIES; ZONE DIFFERENTIAL: ZONE 1 (0-25 RADIUS MILES)= BASE RATE. ZONE 2: (26-45 RADIUS MILES)= $1.00. ZONE 3: (OVER 45 RADIUS MILES) = $1.30. BASEPOINTS: CENTRALIA, OLYMPIA, TACOMA).....$ 58.89 27.32

POWER EQUIPMENT OPERATOR: GROUP 4- ASSISTANT ENGINEER; BOBCAT; BROOMS; COMPRESSOR; CONCRETE FINISH MACHINE-LASER SCREED; CRANES A-FRAME 10 TONS AND UNDER; ELEVATOR AND MANLIFT (PERMANENT AND SHAFT TYPE); FORKLIFTS0UNDER 3000 LBS. WITH ATTACHMENTS; GRADECHECKER, STAKEHOP; HYDRALIFTS/BOOM TRUCKS, 10 TONS AND UNDER; OIL DISTRIBUTORS, BLOWER DISTRIBUTION AND MULCH SEEDING OPERATOR; PAVEMENT BREAKER; POSTHOLE DIGGER-MECHANICAL; POWER PLANT; PUMPS-WATER; RIGGER AND BELLMAN; ROLLER-OTHER THAN PLANT MIX; WHEEL TRACTORS, FARMALL TYPE; SHOTCRETE/GUNITE EQUIPMENT OPERATOR. (ON THE FOLLOWING PROJECTS, THE RATE FOR EACH GROUP SHALL BE 90% OF THE BASE RATE PLUS FULL FRINGE BENEFITS: 1. PROJECTS INVOLVING WORK ON STRUCTURES SUCH AS BUILDINGS AND BRIDGES WHOSE TOTAL VALUE IS LESS THAN $1.5 MILLION EXCLUDING MECHANICAL, ELECTRICAL, AND UTILITY PORTIONS OF THE CONTRACT. 2. PROJECTS OF LESS THAN $1 MILLION WHERE NO BUILDING IS INVOLVED. SURFACING AND PAVING INCLUDED, BUT UTILITIES EXCLUDED. 3. MARINE PROJECTS (DOCKS, WHARFS, ETC.) LESS THAN $150,000. ON ALL OTHER WORK, THE PUBLISHED RATES APPLY.) HANDLING OF HAZARDOUS WASTE MATERIALS: PERSONNEL IN ALL CRAFT CLASSIFICATIONS SUBJECT TO WORKING INSIDE A FEDERALLY DESIGNATED HAZARDOUS PERIMETER SHALL BE ELIGIBLE FOR COMPENSATION IN ACCORDANCE WITH THE FOLLOWING GROUP SCHEDULE RELATIVE TO THE LEVEL OF HAZARDOUS WASTE AS OUTLINED IN THE SPECIFIC HAZARDOUS WASTE PROJECT SITE SAFETY PLAN. H-1 BASE WAGE RATE WHEN ON A HAZARDOUS WASTE SITE WHEN NOT OUTFITTED WITH PROTECTIVE CLOTHING, CLASS ""D"" SUIT- BASE WAGE RATE PLUS $0.50 PER HOUR. H-2 CLASS ""C"" SUIT- BASE WAGE RATE PLUS $1.00 PER HOUR. H-3 CLASS

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

""B"" SUIT- BASE WAGE RATE PLUS $1.50 PER HOUR. H-4
CLASS ""A"" SUIT- BASE WAGE RATE PLUS $2.00 PER HOUR.
(LEWIS AND PACIFIC (PORTION LYING NORTH OF A
PARALLEL LINE EXTENDING WEST FROM THE NORTHERN
BOUNDARY OF WAHKAIKUM COUNTY TO THE SEA) COUNTIES;
ZONE DIFFERENTIAL: ZONE 1 (0-25 RADIUS MILES)= BASE
RATE. ZONE 2: (26-45 RADIUS MILES)= $1.00. ZONE 3:
(OVER 45 RADIUS MILES) = $1.30. BASEPOINTS:
CENTRALIA, OLYMPIA, TACOMA).....$ 55.13 27.32

ENGI0612-012 06/01/2025

Rates	Fringes
POWER EQUIPMENT OPERATOR: GROUP 1A-CRANES, 100 TONS THRU 199 TONS, OR 150 FT OF BOOM (INCLUDING JIB WITH ATTACHMENTS); CRANE-OVERHEAD, BRIDGE TYPE, 100 TONS AND OVER; TOWER CRANE UP TO 175 FT IN HEIGHT BASE TO BOOM; LOADERS-OVERHEAD, 8 YARDS AND OVER; SHOVELS, EXCAVATOR, BACKHOES-6 YARDS AND OVER WITH ATTACHMENTS.(ON THE FOLLOWING PROJECTS, THE RATE FOR EACH GROUP SHALL BE 90% OF THE BASE RATE PLUS FULL FRINGE BENEFITS: 1. PROJECTS INVOLVING WORK ON STRUCTURES SUCH AS BUILDINGS AND BRIDGES WHOSE TOTAL VALUE IS LESS THAN $1.5 MILLION EXCLUDING MECHANICAL, ELECTRICAL, AND UTILITY PORTIONS OF THE CONTRACT. 2. PROJECTS OF LESS THAN $1 MILLION WHERE NO BUILDING IS INVOLVED. SURFACING AND PAVING INCLUDED, BUT UTILITIES EXCLUDED. 3. MARINE PROJECTS (DOCKS, WHARFS, ETC.) LESS THAN $150,000. ON ALL OTHER WORK, THE PUBLISHED RATES APPLY.) HANDLING OF HAZARDOUS WASTE MATERIALS: PERSONNEL IN ALL CRAFT CLASSIFICATIONS SUBJECT TO WORKING INSIDE A FEDERALLY DESIGNATED HAZARDOUS PERIMETER SHALL BE ELIGIBLE FOR COMPENSATION IN ACCORDANCE WITH THE FOLLOWING GROUP SCHEDULE RELATIVE TO THE LEVEL OF HAZARDOUS WASTE AS OUTLINED IN THE SPECIFIC HAZARDOUS WASTE PROJECT SITE SAFETY PLAN. H-1 BASE WAGE RATE WHEN ON A HAZARDOUS WASTE SITE WHEN NOT OUTFITTED WITH PROTECTIVE CLOTHING, CLASS ""D"" SUIT- BASE WAGE RATE PLUS $0.50 PER HOUR. H-2 CLASS ""C"" SUIT- BASE WAGE RATE PLUS $1.00 PER HOUR. H-3 CLASS ""B"" SUIT- BASE WAGE RATE PLUS $1.50 PER HOUR. H-4 CLASS ""A"" SUIT- BASE WAGE RATE PLUS $2.00 PER HOUR. (THURSTON COUNTY; ZONE DIFFERENTIAL: ZONE 1 (0-25 RADIUS MILES)= BASE RATE. ZONE 2: (26-45 RADIUS MILES)= $1.00. ZONE 3: (OVER 45 RADIUS MILES) = $1.30. BASEPOINTS: CENTRALIA, OLYMPIA, TACOMA).....$ 61.81	27.32
POWER EQUIPMENT OPERATOR: GROUP 1AA- CRANES- 200 TONS TO 300 TONS, OR 250 FT OF BOOM (INCLUDING JIB WITH ATTACHMENTS); TOWER CRANE OVER 175 FT IN HEIGHT, BASE TO BOOM. (ON THE FOLLOWING PROJECTS, THE RATE FOR EACH GROUP SHALL BE 90% OF THE BASE RATE PLUS FULL FRINGE BENEFITS: 1. PROJECTS INVOLVING WORK ON STRUCTURES SUCH AS BUILDINGS AND BRIDGES WHOSE TOTAL VALUE IS LESS THAN $1.5 MILLION	

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

EXCLUDING MECHANICAL, ELECTRICAL, AND UTILITY PORTIONS OF THE CONTRACT. 2. PROJECTS OF LESS THAN $1 MILLION WHERE NO BUILDING IS INVOLVED. SURFACING AND PAVING INCLUDED, BUT UTILITIES EXCLUDED. 3. MARINE PROJECTS (DOCKS, WHARFS, ETC.) LESS THAN $150,000. ON ALL OTHER WORK, THE PUBLISHED RATES APPLY.) HANDLING OF HAZARDOUS WASTE MATERIALS: PERSONNEL IN ALL CRAFT CLASSIFICATIONS SUBJECT TO WORKING INSIDE A FEDERALLY DESIGNATED HAZARDOUS PERIMETER SHALL BE ELIGIBLE FOR COMPENSATION IN ACCORDANCE WITH THE FOLLOWING GROUP SCHEDULE RELATIVE TO THE LEVEL OF HAZARDOUS WASTE AS OUTLINED IN THE SPECIFIC HAZARDOUS WASTE PROJECT SITE SAFETY PLAN. H-1 BASE WAGE RATE WHEN ON A HAZARDOUS WASTE SITE WHEN NOT OUTFITTED WITH PROTECTIVE CLOTHING, CLASS ""D"" SUIT- BASE WAGE RATE PLUS $0.50 PER HOUR. H-2 CLASS ""C"" SUIT- BASE WAGE RATE PLUS $1.00 PER HOUR. H-3 CLASS ""B"" SUIT- BASE WAGE RATE PLUS $1.50 PER HOUR. H-4 CLASS ""A"" SUIT- BASE WAGE RATE PLUS $2.00 PER HOUR. (THURSTON COUNTY; ZONE DIFFERENTIAL: ZONE 1 (0-25 RADIUS MILES)= BASE RATE. ZONE 2: (26-45 RADIUS MILES)= $1.00. ZONE 3: (OVER 45 RADIUS MILES) = $1.30. BASEPOINTS: CENTRALIA, OLYMPIA, TACOMA).....$ 62.71 27.32

POWER EQUIPMENT OPERATOR: GROUP 1AAA- CRANES-OVER 300 TONS OR 300 FT OF BOOM (INCLUDING JIB WITH ATTACHMENTS). (ON THE FOLLOWING PROJECTS, THE RATE FOR EACH GROUP SHALL BE 90% OF THE BASE RATE PLUS FULL FRINGE BENEFITS: 1. PROJECTS INVOLVING WORK ON STRUCTURES SUCH AS BUILDINGS AND BRIDGES WHOSE TOTAL VALUE IS LESS THAN $1.5 MILLION EXCLUDING MECHANICAL, ELECTRICAL, AND UTILITY PORTIONS OF THE CONTRACT. 2. PROJECTS OF LESS THAN $1 MILLION WHERE NO BUILDING IS INVOLVED. SURFACING AND PAVING INCLUDED, BUT UTILITIES EXCLUDED. 3. MARINE PROJECTS (DOCKS, WHARFS, ETC.) LESS THAN $150,000. ON ALL OTHER WORK, THE PUBLISHED RATES APPLY.) HANDLING OF HAZARDOUS WASTE MATERIALS: PERSONNEL IN ALL CRAFT CLASSIFICATIONS SUBJECT TO WORKING INSIDE A FEDERALLY DESIGNATED HAZARDOUS PERIMETER SHALL BE ELIGIBLE FOR COMPENSATION IN ACCORDANCE WITH THE FOLLOWING GROUP SCHEDULE RELATIVE TO THE LEVEL OF HAZARDOUS WASTE AS OUTLINED IN THE SPECIFIC HAZARDOUS WASTE PROJECT SITE SAFETY PLAN. H-1 BASE WAGE RATE WHEN ON A HAZARDOUS WASTE SITE WHEN NOT OUTFITTED WITH PROTECTIVE CLOTHING, CLASS ""D"" SUIT- BASE WAGE RATE PLUS $0.50 PER HOUR. H-2 CLASS ""C"" SUIT- BASE WAGE RATE PLUS $1.00 PER HOUR. H-3 CLASS ""B"" SUIT- BASE WAGE RATE PLUS $1.50 PER HOUR. H-4 CLASS ""A"" SUIT- BASE WAGE RATE PLUS $2.00 PER HOUR. (THURSTON COUNTY; ZONE DIFFERENTIAL: ZONE 1 (0-25 RADIUS MILES)= BASE RATE. ZONE 2: (26-45 RADIUS MILES)= $1.00. ZONE 3: (OVER 45 RADIUS MILES) = $1.30. BASEPOINTS: CENTRALIA, OLYMPIA, TACOMA).....$ 63.59 27.32

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

POWER EQUIPMENT OPERATOR: GROUP 1- CABLEWAY; CRANES 45 TONS THRU 99 TONS UNDER 150 FT OF BOOM (INCLUDING JIB WITH ATTACHMENTS); CRANE-OVERHEAD, VRIDGE TYPE, 45 TONS THRU 99 TONS; DERRICKS ON BUILDING WORK; EXCAVATOR, SHOVEL, BACKHOES OVER 3 YARDS AND UNDER 6 YARDS; HARD TAIL END DUMP ARTICULATING OFF-ROAD EQUIPMENT 45 YARDS AND OVER; LOADER-OVERHEAD, 6 YARDS TO, BUT NOT INCLUDING, 8 YARDS; MUCKING MACHINE, MOLE, TUNNEL, DRILL AND/OR SHIELD; QUAD 9 HD 41, D-10; REMOTE CONTROL OPERATOR ON RUBBER TIRED EARTH MOVING EQUIPMENT; ROLLAGON; SCRAPERS-SELF-PROPELLED 45 YARDS AND OVER; SLIPFORM PAVERS; TRANSPORTERS, ALL TRACK OR TRUCK TYPE. (ON THE FOLLOWING PROJECTS, THE RATE FOR EACH GROUP SHALL BE 90% OF THE BASE RATE PLUS FULL FRINGE BENEFITS: 1. PROJECTS INVOLVING WORK ON STRUCTURES SUCH AS BUILDINGS AND BRIDGES WHOSE TOTAL VALUE IS LESS THAN $1.5 MILLION EXCLUDING MECHANICAL, ELECTRICAL, AND UTILITY PORTIONS OF THE CONTRACT. 2. PROJECTS OF LESS THAN $1 MILLION WHERE NO BUILDING IS INVOLVED. SURFACING AND PAVING INCLUDED, BUT UTILITIES EXCLUDED. 3. MARINE PROJECTS (DOCKS, WHARFS, ETC.) LESS THAN $150,000. ON ALL OTHER WORK, THE PUBLISHED RATES APPLY.) HANDLING OF HAZARDOUS WASTE MATERIALS: PERSONNEL IN ALL CRAFT CLASSIFICATIONS SUBJECT TO WORKING INSIDE A FEDERALLY DESIGNATED HAZARDOUS PERIMETER SHALL BE ELIGIBLE FOR COMPENSATION IN ACCORDANCE WITH THE FOLLOWING GROUP SCHEDULE RELATIVE TO THE LEVEL OF HAZARDOUS WASTE AS OUTLINED IN THE SPECIFIC HAZARDOUS WASTE PROJECT SITE SAFETY PLAN. H-1 BASE WAGE RATE WHEN ON A HAZARDOUS WASTE SITE WHEN NOT OUTFITTED WITH PROTECTIVE CLOTHING, CLASS ""D"" SUIT- BASE WAGE RATE PLUS $0.50 PER HOUR. H-2 CLASS ""C"" SUIT- BASE WAGE RATE PLUS $1.00 PER HOUR. H-3 CLASS ""B"" SUIT- BASE WAGE RATE PLUS $1.50 PER HOUR. H-4 CLASS ""A"" SUIT- BASE WAGE RATE PLUS $2.00 PER HOUR. (THURSTON COUNTY; ZONE DIFFERENTIAL: ZONE 1 (0-25 RADIUS MILES)= BASE RATE. ZONE 2: (26-45 RADIUS MILES)= $1.00. ZONE 3: (OVER 45 RADIUS MILES) = $1.30. BASEPOINTS: CENTRALIA, OLYMPIA, TACOMA).....$ 60.91 27.32

POWER EQUIPMENT OPERATOR: GROUP 2- BARRIER MACHINE (ZIPPER); BATCH PLANT OPERATOR-CONCRETE; BUMP CUTTER; CRANES, 20 TONS THRU 44 TONS WITH ATTACHMENTS; CRANE-OVERHED, BRIDGE TYPE, 20 TONS THROUGH 44 TONS; CHIPPER; CONCRETE PUMP-TRUCK MOUNT WITH BOOM ATTACHMENT; CRUSHER; DECK ENGINEER/DECK WINCHES (POWER); DRILLING MACHINE; EXCAVATOR, SHOVEL, BACKHOE-3 YARDS AND UNDER; FINISHING MACHINE, BIDWELL, GAMACO AND SIMILAR EQUIPMENT; GUARDRAIL PUNCH; LODERS, OVERHEAD UNDER 6 YARDS; LODERS-PLANT FEED; LOCOMOTIVES-ALL; MECHANICS-ALL; MIXERS, ASPHALT PLANT; MOTOR PATROL GRADERS, FINISHING; PILEDRIVER (OTHER THAN CRANE MOUNT); ROTO-MILL, ROTO-GRINDER; SCREEDMAN, SPREADER, TOPSIDE OPERATOR-BLAW KNOX, CEDAR RAPIDS, JAEGER,

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

CATERPILLAR, BARBAR GREEN; SCRAPER-SELF-PROPELLED,
HARD TAIL END DUMP, ARTICULATING OFF-ROAD
EQUIPMENT-UNDER 45 YARDS; SUBGRADER TRIMMER;
TRACTORS, BACKHOE OVER 75 HP; TRANSFER MATERIAL
SERVICE MACHINE-SHUTTLE BUGGY, BLAW KNOX-ROADTEC;
TRUCK CRANE OILER/DRIVER-100 TONS AND OVER; TRUCK
MOUNT PORTABLE CONVEYOR; YO YO PAY. (ON THE
FOLLOWING PROJECTS, THE RATE FOR EACH GROUP SHALL
BE 90% OF THE BASE RATE PLUS FULL FRINGE BENEFITS:
1. PROJECTS INVOLVING WORK ON STRUCTURES SUCH AS
BUILDINGS AND BRIDGES WHOSE TOTAL VALUE IS LESS
THAN $1.5 MILLION EXCLUDING MECHANICAL, ELECTRICAL,
AND UTILITY PORTIONS OF THE CONTRACT. 2. PROJECTS
OF LESS THAN $1 MILLION WHERE NO BUILDING IS
INVOLVED. SURFACING AND PAVING INCLUDED, BUT
UTILITIES EXCLUDED. 3. MARINE PROJECTS (DOCKS,
WHARFS, ETC.) LESS THAN $150,000. ON ALL OTHER
WORK, THE PUBLISHED RATES APPLY.) HANDLING OF
HAZARDOUS WASTE MATERIALS: PERSONNEL IN ALL CRAFT
CLASSIFICATIONS SUBJECT TO WORKING INSIDE A
FEDERALLY DESIGNATED HAZARDOUS PERIMETER SHALL BE
ELIGIBLE FOR COMPENSATION IN ACCORDANCE WITH THE
FOLLOWING GROUP SCHEDULE RELATIVE TO THE LEVEL OF
HAZARDOUS WASTE AS OUTLINED IN THE SPECIFIC
HAZARDOUS WASTE PROJECT SITE SAFETY PLAN. H-1 BASE
WAGE RATE WHEN ON A HAZARDOUS WASTE SITE WHEN NOT
OUTFITTED WITH PROTECTIVE CLOTHING, CLASS ""D"" SUIT-
BASE WAGE RATE PLUS $0.50 PER HOUR. H-2 CLASS ""C""
SUIT- BASE WAGE RATE PLUS $1.00 PER HOUR. H-3 CLASS
""B"" SUIT- BASE WAGE RATE PLUS $1.50 PER HOUR. H-4
CLASS ""A"" SUIT- BASE WAGE RATE PLUS $2.00 PER HOUR.
(THURSTON COUNTY; ZONE DIFFERENTIAL: ZONE 1 (0-25
RADIUS MILES)= BASE RATE. ZONE 2: (26-45 RADIUS
MILES)= $1.00. ZONE 3: (OVER 45 RADIUS MILES) =
$1.30. BASEPOINTS: CENTRALIA, OLYMPIA, TACOMA).....$ 60.14 27.32
POWER EQUIPMENT OPERATOR:GROUP 3- CONVEYORS; CRANES
THROUGH 19 TONS WITH ATTACHMENTS; CRANE-A-FRAME
OVER 10 TONS; DRILL OILERS-AUGER TYPE, TRUCK OR
CRANE MOUNT; DOZER-D-9 AND UNDER; FORKLIFT-3000
LBS. AND OVER WITH ATTACHMENTS;
HORIZONTAL/DIRECTIONAL DRILL LOCATOR; OUTSIDE
HOISTS-(ELEVATORS AND MANLIFTS), AIR TUGGERS,
STRATO TOWER BUCKET ELEVATORS; HYDRALIFTS/BOOM
TRUCKS OVER 10 TONS; LOADERS-ELEVATING TYPE, BELT;
MOTOR PATROL GRADER-NONFINISHING; PLANT
OILER-ASPHALT, CRUSHER; PUMP-CONCRETE; ROLLER,
PLANT MIX OR MULTI-LIFT MATERIALS; SAWS-CONCRETE;
SCRAPERS, CONCRETE AND CARRY ALL; SERVICE
ENGINEERS-EQUIPMENT; TRENCHING MACHINES; TRUCK
CRANE OILER/DRIVER UNDER 100 TONS; TRACTORS,
BACKHOE UNDER 75 HP. (ON THE FOLLOWING PROJECTS,
THE RATE FOR EACH GROUP SHALL BE 90% OF THE BASE
RATE PLUS FULL FRINGE BENEFITS: 1. PROJECTS
INVOLVING WORK ON STRUCTURES SUCH AS BUILDINGS AND
BRIDGES WHOSE TOTAL VALUE IS LESS THAN $1.5 MILLION
EXCLUDING MECHANICAL, ELECTRICAL, AND UTILITY

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

PORTIONS OF THE CONTRACT. 2. PROJECTS OF LESS THAN $1 MILLION WHERE NO BUILDING IS INVOLVED. SURFACING AND PAVING INCLUDED, BUT UTILITIES EXCLUDED. 3. MARINE PROJECTS (DOCKS, WHARFS, ETC.) LESS THAN $150,000. ON ALL OTHER WORK, THE PUBLISHED RATES APPLY.) HANDLING OF HAZARDOUS WASTE MATERIALS: PERSONNEL IN ALL CRAFT CLASSIFICATIONS SUBJECT TO WORKING INSIDE A FEDERALLY DESIGNATED HAZARDOUS PERIMETER SHALL BE ELIGIBLE FOR COMPENSATION IN ACCORDANCE WITH THE FOLLOWING GROUP SCHEDULE RELATIVE TO THE LEVEL OF HAZARDOUS WASTE AS OUTLINED IN THE SPECIFIC HAZARDOUS WASTE PROJECT SITE SAFETY PLAN. H-1 BASE WAGE RATE WHEN ON A HAZARDOUS WASTE SITE WHEN NOT OUTFITTED WITH PROTECTIVE CLOTHING, CLASS ""D"" SUIT- BASE WAGE RATE PLUS $0.50 PER HOUR. H-2 CLASS ""C"" SUIT- BASE WAGE RATE PLUS $1.00 PER HOUR. H-3 CLASS ""B"" SUIT- BASE WAGE RATE PLUS $1.50 PER HOUR. H-4 CLASS ""A"" SUIT- BASE WAGE RATE PLUS $2.00 PER HOUR. (THURSTON COUNTY; ZONE DIFFERENTIAL: ZONE 1 (0-25 RADIUS MILES)= BASE RATE. ZONE 2: (26-45 RADIUS MILES)= $1.00. ZONE 3: (OVER 45 RADIUS MILES) = $1.30. BASEPOINTS: CENTRALIA, OLYMPIA, TACOMA).....$ 59.46 27.32

POWER EQUIPMENT OPERATOR: GROUP 4- ASSISTANT ENGINEER; BOBCAT; BROOMS; COMPRESSOR; CONCRETE FINISH MACHINE-LASER SCREED; CRANES A-FRAME 10 TONS AND UNDER; ELEVATOR AND MANLIFT (PERMANENT AND SHAFT TYPE); FORKLIFTS0UNDER 3000 LBS. WITH ATTACHMENTS; GRADECHECKER, STAKEHOP; HYDRALIFTS/BOOM TRUCKS, 10 TONS AND UNDER; OIL DISTRIBUTORS, BLOWER DISTRIBUTION AND MULCH SEEDING OPERATOR; PAVEMENT BREAKER; POSTHOLE DIGGER-MECHANICAL; POWER PLANT; PUMPS-WATER; RIGGER AND BELLMAN; ROLLER-OTHER THAN PLANT MIX; WHEEL TRACTORS, FARMALL TYPE; SHOTCRETE/GUNITE EQUIPMENT OPERATOR. (ON THE FOLLOWING PROJECTS, THE RATE FOR EACH GROUP SHALL BE 90% OF THE BASE RATE PLUS FULL FRINGE BENEFITS: 1. PROJECTS INVOLVING WORK ON STRUCTURES SUCH AS BUILDINGS AND BRIDGES WHOSE TOTAL VALUE IS LESS THAN $1.5 MILLION EXCLUDING MECHANICAL, ELECTRICAL, AND UTILITY PORTIONS OF THE CONTRACT. 2. PROJECTS OF LESS THAN $1 MILLION WHERE NO BUILDING IS INVOLVED. SURFACING AND PAVING INCLUDED, BUT UTILITIES EXCLUDED. 3. MARINE PROJECTS (DOCKS, WHARFS, ETC.) LESS THAN $150,000. ON ALL OTHER WORK, THE PUBLISHED RATES APPLY.) HANDLING OF HAZARDOUS WASTE MATERIALS: PERSONNEL IN ALL CRAFT CLASSIFICATIONS SUBJECT TO WORKING INSIDE A FEDERALLY DESIGNATED HAZARDOUS PERIMETER SHALL BE ELIGIBLE FOR COMPENSATION IN ACCORDANCE WITH THE FOLLOWING GROUP SCHEDULE RELATIVE TO THE LEVEL OF HAZARDOUS WASTE AS OUTLINED IN THE SPECIFIC HAZARDOUS WASTE PROJECT SITE SAFETY PLAN. H-1 BASE WAGE RATE WHEN ON A HAZARDOUS WASTE SITE WHEN NOT OUTFITTED WITH PROTECTIVE CLOTHING, CLASS ""D"" SUIT- BASE WAGE RATE PLUS $0.50 PER HOUR. H-2 CLASS ""C""

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

SUIT- BASE WAGE RATE PLUS $1.00 PER HOUR. H-3 CLASS ""B"" SUIT- BASE WAGE RATE PLUS $1.50 PER HOUR. H-4 CLASS ""A"" SUIT- BASE WAGE RATE PLUS $2.00 PER HOUR. (THURSTON COUNTY; ZONE DIFFERENTIAL: ZONE 1 (0-25 RADIUS MILES)= BASE RATE. ZONE 2: (26-45 RADIUS MILES)= $1.00. ZONE 3: (OVER 45 RADIUS MILES) = $1.30. BASEPOINTS: CENTRALIA, OLYMPIA, TACOMA).....$ 55.68 27.32

ENGI0701-002 01/01/2025

Rates	Fringes

POWER EQUIPMENT OPERATOR: GROUP 1- CONCRETE BATCH PLANT AND/OR WET MIX THREE (3) UNITS OR MORE; CRANE, FLOATING 150 TON BUT LESS THAN 250 TON; CRANE, 200 TON THROUGH 299 TON WITH 200' BOOM OR LESS (INCLUDING JOB, INSERTS AND/OR ATTACHMENTS); CRANE, 90 TON THROUGH 199 TON WITH OVER 200' BOOM (INCLUDING JIB, INSERTS AND/OR ATTACHMENTS); CRANE, TOWER CRANE WITH 175' TOWER OR LESS AND WITH LESS THAN 200' JIB; CRANE, WHIRLEY 90 TON AND OVER; HELICOPTER WHEN USED IN ERECTING WORK. (CLARK, COWLITX, KLICKITAT, PACIFIC (SOUTH), SKAMANIA, AND WAHKIAKUM COUNTIES). ZONE DIFFERENTIALS (ADD TO ZONE 1 RATES). ZONE 1: BASE RATE. ZONE 2: $3.00. ZONE 3: $6.00. FOR THE FOLLOWING METROPOLITAN COUNTIES: MULTNOMAH; CLACKAMAS; MARION; WASHINGTON; YAMHILL; AND COLUMBIA; CLARK; AND COWLITZ COUNTY, WASHINGTON WITH MODIFICATIONS AS INDICATED: ALL JOBS OR PROJECTS LOCATED IN MULTNOMAH, CLACKAMAS, AND MARION COUNTIES, WEST OF THE WESTERN OBUNDARY OF MT. HOOD NATIONAL FOREST AND WEST OF MILE POST 30 ON I-84 AND WEST OF MILE POST 30 ON STATE HIGHWAY 26 AND WEST OF MILE POST 30 ON HIGHWAY 22 AND ALL JOBS OR PROJECTS LOCATED IN YAMHILL COUNTY, WASHINGTON COUNTY, AND COLUMBIA COUNTY AND ALL JOBS OR PROJECTS LOCATED IN CLARK & COWLITZ COUNTY IN THE MT. ST. HELENS ""BLAST ZONE"" SHALL RECEIVE ZONE 1 PAY FOR ALL CLASSIFICATIONS. ALL JOBS OR PROJECTS LOCATED IN THE AREA OUTSIDE THE IDENTIFIED BOUNDARY ABOVE, BUT LESS THAN 50 MILES FROM THE PORTLAND CITY HALL SHALL RECEIVE ZONE II PAY FOR ALL CLASSIFICATIONS. ALL JOBS OR PROJECTS LOCATED MORE THAN 50 MILES FROM THE PORTLAND CITY HALL, BUT OUTSIDE THE IDENTIFIED BORDER ABOVE, SHALL RECEIVE ZONE III PAY FOR ALL CLASSIFICATION. FOR THE FOLLOWING CITIES: ALBANY, BEND , COOS BAY, EUGENE, GRANTS PASS, KLAMATH FALLS, MEDFORD, AND ROSEBURG- ALL JOBS OR PROJECTS LOCATED WITHIN 30 MILES OF THE RESPECTIVE CITY HALL OF THE AFOREMENTIONED CITIES SHALL RECEIVE ZONE 1 PAY FOR ALL CLASSIFICATIONS. ALL JOBS OR PROJECTS LOCATED MORE THAN 30 MILES AND LESS THAN 50 MILES FROM THE RESPECTIVE CITY HALL OF THE AFOREMENTIONED CITIES SHALL RECEIVE ZONE II PAY FOR ALL CLASSIFICATIONS. ALL JOBS OR PROJECTS LOCATED MORE THAN 50 MILES FROM THE RESPECTIVE CITY HALL OF THE AFOREMENTIONED CITIES SHALL RECEIVE

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

ZONE III PAY FOR ALL CLASSIFICATIONS.....$ 58.94 17.15
POWER EQUIPMENT OPERATOR: GROUP 1A- CRANE, FLOATING 250 TON AND OVER; CRANE, 200 TON THROUGH 299 TON, WITH OVER 200' BOOM (INCLUDING JIB, INSERTS AND/OR ATTACHMENTS); CRANE, 300 TON THROUGH 399 TON; CRANE, TOWER CRANE WITH OVER 175' TOWER OR OVER 200' JIB; CRANE, TOWER CRANE ON RAIL SYSTEM OR 2ND TOWER OR MORE IN WORK RADIUS. (CLARK, COWLITX, KLICKITAT, PACIFIC (SOUTH), SKAMANIA, AND WAHKIAKUM COUNTIES). ZONE DIFFERENTIALS (ADD TO ZONE 1 RATES). ZONE 1: BASE RATE. ZONE 2: $3.00. ZONE 3: $6.00. FOR THE FOLLOWING METROPOLITAN COUNTIES: MULTNOMAH; CLACKAMAS; MARION; WASHINGTON; YAMHILL; AND COLUMBIA; CLARK; AND COWLITZ COUNTY, WASHINGTON WITH MODIFICATIONS AS INDICATED: ALL JOBS OR PROJECTS LOCATED IN MULTNOMAH, CLACKAMAS, AND MARION COUNTIES, WEST OF THE WESTERN OBUNDARY OF MT. HOOD NATIONAL FOREST AND WEST OF MILE POST 30 ON I-84 AND WEST OF MILE POST 30 ON STATE HIGHWAY 26 AND WEST OF MILE POST 30 ON HIGHWAY 22 AND ALL JOBS OR PROJECTS LOCATED IN YAMHILL COUNTY, WASHINGTON COUNTY, AND COLUMBIA COUNTY AND ALL JOBS OR PROJECTS LOCATED IN CLARK & COWLITZ COUNTY IN THE MT. ST. HELENS ""BLAST ZONE"" SHALL RECEIVE ZONE 1 PAY FOR ALL CLASSIFICATIONS. ALL JOBS OR PROJECTS LOCATED IN THE AREA OUTSIDE THE IDENTIFIED BOUNDARY ABOVE, BUT LESS THAN 50 MILES FROM THE PORTLAND CITY HALL SHALL RECEIVE ZONE II PAY FOR ALL CLASSIFICATIONS. ALL JOBS OR PROJECTS LOCATED MORE THAN 50 MILES FROM THE PORTLAND CITY HALL, BUT OUTSIDE THE IDENTIFIED BORDER ABOVE, SHALL RECEIVE ZONE III PAY FOR ALL CLASSIFICATION. FOR THE FOLLOWING CITIES: ALBANY, BEND , COOS BAY, EUGENE, GRANTS PASS, KLAMATH FALLS, MEDFORD, AND ROSEBURG- ALL JOBS OR PROJECTS LOCATED WITHIN 30 MILES OF THE RESPECTIVE CITY HALL OF THE AFOREMENTIONED CITIES SHALL RECEIVE ZONE 1 PAY FOR ALL CLASSIFICATIONS. ALL JOBS OR PROJECTS LOCATED MORE THAN 30 MILES AND LESS THAN 50 MILES FROM THE RESPECTIVE CITY HALL OF THE AFOREMENTIONED CITIES SHALL RECEIVE ZONE II PAY FOR ALL CLASSIFICATIONS. ALL JOBS OR PROJECTS LOCATED MORE THAN 50 MILES FROM THE RESPECTIVE CITY HALL OF THE AFOREMENTIONED CITIES SHALL RECEIVE
ZONE III PAY FOR ALL CLASSIFICATIONS.....$ 61.10 17.15
POWER EQUIPMENT OPERATOR: GROUP 1B- CRANE, 300 TON THROUGH 399 TON, WITH OVER 200' BOOM (INCLUDING JIB, INSERTS AND/OR ATTACHMENTS); FLOATING CRANE, 350 TON AND OVER; CRANE, 400 TON AND OVER. (CLARK, COWLITX, KLICKITAT, PACIFIC (SOUTH), SKAMANIA, AND WAHKIAKUM COUNTIES). ZONE DIFFERENTIALS (ADD TO ZONE 1 RATES). ZONE 1: BASE RATE. ZONE 2: $3.00. ZONE 3: $6.00. FOR THE FOLLOWING METROPOLITAN COUNTIES: MULTNOMAH; CLACKAMAS; MARION; WASHINGTON; YAMHILL; AND COLUMBIA; CLARK; AND COWLITZ COUNTY, WASHINGTON WITH MODIFICATIONS AS INDICATED: ALL JOBS OR PROJECTS LOCATED IN MULTNOMAH, CLACKAMAS,

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

AND MARION COUNTIES, WEST OF THE WESTERN OBUNDARY
OF MT. HOOD NATIONAL FOREST AND WEST OF MILE POST
30 ON I-84 AND WEST OF MILE POST 30 ON STATE
HIGHWAY 26 AND WEST OF MILE POST 30 ON HIGHWAY 22
AND ALL JOBS OR PROJECTS LOCATED IN YAMHILL COUNTY,
WASHINGTON COUNTY, AND COLUMBIA COUNTY AND ALL JOBS
OR PROJECTS LOCATED IN CLARK & COWLITZ COUNTY IN
THE MT. ST. HELENS ""BLAST ZONE"" SHALL RECEIVE ZONE
1 PAY FOR ALL CLASSIFICATIONS. ALL JOBS OR PROJECTS
LOCATED IN THE AREA OUTSIDE THE IDENTIFIED BOUNDARY
ABOVE, BUT LESS THAN 50 MILES FROM THE PORTLAND
CITY HALL SHALL RECEIVE ZONE II PAY FOR ALL
CLASSIFICATIONS. ALL JOBS OR PROJECTS LOCATED MORE
THAN 50 MILES FROM THE PORTLAND CITY HALL, BUT
OUTSIDE THE IDENTIFIED BORDER ABOVE, SHALL RECEIVE
ZONE III PAY FOR ALL CLASSIFICATION. FOR THE
FOLLOWING CITIES: ALBANY, BEND , COOS BAY, EUGENE,
GRANTS PASS, KLAMATH FALLS, MEDFORD, AND ROSEBURG-
ALL JOBS OR PROJECTS LOCATED WITHIN 30 MILES OF THE
RESPECTIVE CITY HALL OF THE AFOREMENTIONED CITIES
SHALL RECEIVE ZONE 1 PAY FOR ALL CLASSIFICATIONS.
ALL JOBS OR PROJECTS LOCATED MORE THAN 30 MILES AND
LESS THAN 50 MILES FROM THE RESPECTIVE CITY HALL OF
THE AFOREMENTIONED CITIES SHALL RECEIVE ZONE II PAY
FOR ALL CLASSIFICATIONS. ALL JOBS OR PROJECTS
LOCATED MORE THAN 50 MILES FROM THE RESPECTIVE CITY
HALL OF THE AFOREMENTIONED CITIES SHALL RECEIVE
ZONE III PAY FOR ALL CLASSIFICATIONS.....$ 63.26 17.15
POWER EQUIPMENT OPERATOR: GROUP 2- ASPHALT PLANT
(ANY TYPE); ASPHALT ROTO-MILL, PAVEMENT PROFILER 8'
LATERAL CUT AND OVER; AUTO GRADER OR ""TRIMMER"";
BLADE, ROBOTIC; BULLDOZER, ROBOTIC EQUIPMENT (ANY
TYPE); BULLDOZER, OVER 120,000 LBS. AND ABOVE;
CONCRETE BATCH PLANT AND/OR WET MIX 1 AND 2 DRUM;
CONCRETE DIAMOND HEAD PROFILER; CANAL TRIMMER;
CONCRETE, AUTOMATIC SLIP FORM PAVER (ASSISTANT TO
THE OPERATOR REQUIRED); CRANE, BOOM TRUCK 50 TON
AND WITH OVER 150' BOOM AND OVER; CRANE, FLOATING
(DERRICK BARGE) 30 TON BUT LESS THAN 150 TON;
CRANE, CABLEWAY 25 TON AND OVER; CRANE, FLOATING
CLAMSHELL 3 CU. YDS. AND OVER; CRANE, 90 TON
THROUGH 199 TON UP TO AND INCLUDING 200' OF BOOM
(INCLUDING JIB INSERTS AND/OR ATTACHMENTS); CRANE,
50 TON THROUGH 89 TON WITH OVER 150' BOOM
(INCLUDING JIB INSERTS AND/OR ATTACHMENTS); CRANE,
WHIRLEY UNDER 90 TON; CRUSHER PLANT; EXCAVATOR OVER
130,000 LBS.; LOADER 120,000 LBS. AND ABOVE; REMOTE
CONTROLLED EARTH MOVING EQUIPMENT; SHOVEL,
DRAGLINE, CLAMSHELL, 5 CU. YDS. AND OVER;
UNDERWATER EQUIPMENT REMOTE OR OTHERWISE, WHEN USED
IN CONSTRUCTION WORK; WHEEL EXCAVATOR ANY SIZE.
(CLARK, COWLITX, KLICKITAT, PACIFIC (SOUTH),
SKAMANIA, AND WAHKIAKUM COUNTIES). ZONE
DIFFERENTIALS (ADD TO ZONE 1 RATES). ZONE 1: BASE
RATE. ZONE 2: $3.00. ZONE 3: $6.00. FOR THE
FOLLOWING METROPOLITAN COUNTIES: MULTNOMAH;

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

CLACKAMAS; MARION; WASHINGTON; YAMHILL; AND
COLUMBIA; CLARK; AND COWLITZ COUNTY, WASHINGTON
WITH MODIFICATIONS AS INDICATED: ALL JOBS OR
PROJECTS LOCATED IN MULTNOMAH, CLACKAMAS, AND
MARION COUNTIES, WEST OF THE WESTERN OBUNDARY OF
MT. HOOD NATIONAL FOREST AND WEST OF MILE POST 30
ON I-84 AND WEST OF MILE POST 30 ON STATE HIGHWAY
26 AND WEST OF MILE POST 30 ON HIGHWAY 22 AND ALL
JOBS OR PROJECTS LOCATED IN YAMHILL COUNTY,
WASHINGTON COUNTY, AND COLUMBIA COUNTY AND ALL JOBS
OR PROJECTS LOCATED IN CLARK & COWLITZ COUNTY IN
THE MT. ST. HELENS ""BLAST ZONE"" SHALL RECEIVE ZONE
1 PAY FOR ALL CLASSIFICATIONS. ALL JOBS OR PROJECTS
LOCATED IN THE AREA OUTSIDE THE IDENTIFIED BOUNDARY
ABOVE, BUT LESS THAN 50 MILES FROM THE PORTLAND
CITY HALL SHALL RECEIVE ZONE II PAY FOR ALL
CLASSIFICATIONS. ALL JOBS OR PROJECTS LOCATED MORE
THAN 50 MILES FROM THE PORTLAND CITY HALL, BUT
OUTSIDE THE IDENTIFIED BORDER ABOVE, SHALL RECEIVE
ZONE III PAY FOR ALL CLASSIFICATION. FOR THE
FOLLOWING CITIES: ALBANY, BEND , COOS BAY, EUGENE,
GRANTS PASS, KLAMATH FALLS, MEDFORD, AND ROSEBURG-
ALL JOBS OR PROJECTS LOCATED WITHIN 30 MILES OF THE
RESPECTIVE CITY HALL OF THE AFOREMENTIONED CITIES
SHALL RECEIVE ZONE 1 PAY FOR ALL CLASSIFICATIONS.
ALL JOBS OR PROJECTS LOCATED MORE THAN 30 MILES AND
LESS THAN 50 MILES FROM THE RESPECTIVE CITY HALL OF
THE AFOREMENTIONED CITIES SHALL RECEIVE ZONE II PAY
FOR ALL CLASSIFICATIONS. ALL JOBS OR PROJECTS
LOCATED MORE THAN 50 MILES FROM THE RESPECTIVE CITY
HALL OF THE AFOREMENTIONED CITIES SHALL RECEIVE
ZONE III PAY FOR ALL CLASSIFICATIONS.....$ 57.03 17.15
POWER EQUIPMENT OPERATOR: GROUP 3- BULLDOZER, OVER
70,000 LBS. UP TO AND INCLUDING 120,000 LBS.;
CRANE, BOOM TRUCK 50 TON AND OVER WITH LESS THAN
150' BOOM; CRANE, 50 TON THROUGH 89 TON WITH 150'
BOOM OR LESS (INCLUDING JIB INSERTS AND/OR
ATTACHMENTS); CRANE, SHOVEL, DRAGLINE OR CLAMSHELL
3 CU. YDS. BUT LESS THAN 5 CU. YDS.; EXCAVATOR OVER
80,000 LBS. THROUGH 130.000 LBS.; LOADER 60,000
LBS. AND LESS THAN 120,000 LBS. (CLARK, COWLITX,
KLICKITAT, PACIFIC (SOUTH), SKAMANIA, AND WAHKIAKUM
COUNTIES). ZONE DIFFERENTIALS (ADD TO ZONE 1
RATES). ZONE 1: BASE RATE. ZONE 2: $3.00. ZONE 3:
$6.00. FOR THE FOLLOWING METROPOLITAN COUNTIES:
MULTNOMAH; CLACKAMAS; MARION; WASHINGTON; YAMHILL;
AND COLUMBIA; CLARK; AND COWLITZ COUNTY, WASHINGTON
WITH MODIFICATIONS AS INDICATED: ALL JOBS OR
PROJECTS LOCATED IN MULTNOMAH, CLACKAMAS, AND
MARION COUNTIES, WEST OF THE WESTERN OBUNDARY OF
MT. HOOD NATIONAL FOREST AND WEST OF MILE POST 30
ON I-84 AND WEST OF MILE POST 30 ON STATE HIGHWAY
26 AND WEST OF MILE POST 30 ON HIGHWAY 22 AND ALL
JOBS OR PROJECTS LOCATED IN YAMHILL COUNTY,
WASHINGTON COUNTY, AND COLUMBIA COUNTY AND ALL JOBS
OR PROJECTS LOCATED IN CLARK & COWLITZ COUNTY IN

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

THE MT. ST. HELENS ""BLAST ZONE"" SHALL RECEIVE ZONE 1 PAY FOR ALL CLASSIFICATIONS. ALL JOBS OR PROJECTS LOCATED IN THE AREA OUTSIDE THE IDENTIFIED BOUNDARY ABOVE, BUT LESS THAN 50 MILES FROM THE PORTLAND CITY HALL SHALL RECEIVE ZONE II PAY FOR ALL CLASSIFICATIONS. ALL JOBS OR PROJECTS LOCATED MORE THAN 50 MILES FROM THE PORTLAND CITY HALL, BUT OUTSIDE THE IDENTIFIED BORDER ABOVE, SHALL RECEIVE ZONE III PAY FOR ALL CLASSIFICATION. FOR THE FOLLOWING CITIES: ALBANY, BEND , COOS BAY, EUGENE, GRANTS PASS, KLAMATH FALLS, MEDFORD, AND ROSEBURG- ALL JOBS OR PROJECTS LOCATED WITHIN 30 MILES OF THE RESPECTIVE CITY HALL OF THE AFOREMENTIONED CITIES SHALL RECEIVE ZONE 1 PAY FOR ALL CLASSIFICATIONS. ALL JOBS OR PROJECTS LOCATED MORE THAN 30 MILES AND LESS THAN 50 MILES FROM THE RESPECTIVE CITY HALL OF THE AFOREMENTIONED CITIES SHALL RECEIVE ZONE II PAY FOR ALL CLASSIFICATIONS. ALL JOBS OR PROJECTS LOCATED MORE THAN 50 MILES FROM THE RESPECTIVE CITY HALL OF THE AFOREMENTIONED CITIES SHALL RECEIVE ZONE III PAY FOR ALL CLASSIFICATIONS.....$ 55.88 17.15

POWER EQUIPMENT OPERATOR: GROUP 4- ASPHALT, SCREED; ASPHALT PAVER; ASPHALT ROTO-MILL, PAVEMENT PROFILER, UNDER 8' LATERAL CUT; ASPHALT, MATEIRLA TRANSFER VEHICLE OPERATOR; BACK FILLING MACHINE; BACKHOE, ROBOTIC, TRACK AND WHEEL TYPE UP TO AND INCLUDING 20,000 LBS. WITH ANY ATTACHMENTS; BLADE (ANY TYPE); BOATMAN; BORING MACHINE; BULLDOZER OVER 20,000 LBS. AND MORE THAN 100 HORSE UP TO 70,000 LBS.; CABLE-PLOW (ANY TYPE); CABLEWAY UP TO 25 TON; CAT DRILL (JOHN HENRY); CHIPPERS; COMPACTOR, MULTI-ENGINE; COMPACTOR, ROBOTIC; COMPACTOR WITH BLAD SELF-PROPELLED; CONCRETE, BREAKER; CONCRETE, GROUT PLANT; CONCRETE, MIXER MOBILE; CONCRETE, PAVING ROAD MIXER; CONCRETE, REINFORCED TANK BANDING MACHINE; CRANE, BOOM TRUCK 20 TON AND UNDER 50 TON; CRANE, BRIDGE LOCOMOTIVE, GANTRY AND OVERHEAD; CRANE, CARRY DECK; CRANE, CHICAGO BOOM AND SIMILAR TYPES; CRANE, DERRICK OPERATOR UNDER 100 TON; CRANE, FLOATING CLAMSHELL, DRAGLINE, ETC. OPERATOR, UNDER 3 CU. YDS. OR LESS THAN 30 TON; CRANE, UNDER 50 TON; CRANE, QUICK TOWER UNDER 100' IN HEIGHT AND LESS THAN 150' JIB (ON RAIL INCLUDED); DIESEL-ELECTRIC ENGINEER (PLANT OR FLOATING); DIRECTIONAL DRILL OVER 20,000 LBS. PULLBACK; DRILL CAT OPERATOR; DRILL DOCTOR AND/OR BIT GRINDER; DRILLER, PERCUSSION, DIAMOND, CORE, CABLE, ROTARY AND SIMILAR TYPE; EXCAVATOR OPERATOR OVER 20,000 LBS. THROUGH 80,000 LBS.; GENERATOR OPERATOR; GRADE-ALL; GUARDRAIL MACHINES, I.E. PUNCH, AUGER, ETC.' HAMMER OPERATOR (PILEDRIVER); HOIST, STIFF LEG, GUY DERRICK OR SIMILAR TYPE, 50 TON AND OVER; HOIST, 2 DRUMS OR MORE; HYDRO AXE (LOADER MOUNTED OR SIMILA TYPE); JACK OPERATOR, ELEVATING BARGES, BARGE OPERATOR, SELF-UNLOADING; LOADER OPERATOR, FRONT END AND OVERHEAD, 25,000

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

LBS. AND LESS THAN 60,000 LBS.; LOG SKIDDERS; PILEDRIVER OPERATOR (NOT CRANE TYPE); PIPE, BENDING, CLEANING, DOPING AND WRAPPING MACHINES; RAIL, BALLAST TAMPER MULTI-PURPOSE; RUBBER-TIRED DOZERS AND PUSHERS; SCRAPER, ALL TYPES; SIDE-BOOM; SKIP LOADER, DRAG BOX; STRUMP GRINDER (LOADER MOUNTED OR SIMILAR TYPE); SURFACE HEATER AND PLANER; TRACTOR, RUBBER-TIRED, OVER 50 HP FLYWHEEL; TRENCHING MACHINE 3' DEPTH AND DEEPER; TUB GRINDER (USED FOR WOOD DEBRIS); TUNNEL BORING MACHINE MECHANIC; TUNNEL, MUCKING MACHINE; ULTRA HIGH PRESSURE WATER JET CUTTING TOOL SYSTEM OPERATOR; VACUUM BLASTING MACHINE OPERATOR; WATER PULLS, WATER WAGONS. (CLARK, COWLITX, KLICKITAT, PACIFIC (SOUTH), SKAMANIA, AND WAHKIAKUM COUNTIES). ZONE DIFFERENTIALS (ADD TO ZONE 1 RATES). ZONE 1: BASE RATE. ZONE 2: $3.00. ZONE 3: $6.00. FOR THE FOLLOWING METROPOLITAN COUNTIES: MULTNOMAH; CLACKAMAS; MARION; WASHINGTON; YAMHILL; AND COLUMBIA; CLARK; AND COWLITZ COUNTY, WASHINGTON WITH MODIFICATIONS AS INDICATED: ALL JOBS OR PROJECTS LOCATED IN MULTNOMAH, CLACKAMAS, AND MARION COUNTIES, WEST OF THE WESTERN OBUNDARY OF MT. HOOD NATIONAL FOREST AND WEST OF MILE POST 30 ON I-84 AND WEST OF MILE POST 30 ON STATE HIGHWAY 26 AND WEST OF MILE POST 30 ON HIGHWAY 22 AND ALL JOBS OR PROJECTS LOCATED IN YAMHILL COUNTY, WASHINGTON COUNTY, AND COLUMBIA COUNTY AND ALL JOBS OR PROJECTS LOCATED IN CLARK & COWLITZ COUNTY IN THE MT. ST. HELENS ""BLAST ZONE"" SHALL RECEIVE ZONE 1 PAY FOR ALL CLASSIFICATIONS. ALL JOBS OR PROJECTS LOCATED IN THE AREA OUTSIDE THE IDENTIFIED BOUNDARY ABOVE, BUT LESS THAN 50 MILES FROM THE PORTLAND CITY HALL SHALL RECEIVE ZONE II PAY FOR ALL CLASSIFICATIONS. ALL JOBS OR PROJECTS LOCATED MORE THAN 50 MILES FROM THE PORTLAND CITY HALL, BUT OUTSIDE THE IDENTIFIED BORDER ABOVE, SHALL RECEIVE ZONE III PAY FOR ALL CLASSIFICATION. FOR THE FOLLOWING CITIES: ALBANY, BEND , COOS BAY, EUGENE, GRANTS PASS, KLAMATH FALLS, MEDFORD, AND ROSEBURG- ALL JOBS OR PROJECTS LOCATED WITHIN 30 MILES OF THE RESPECTIVE CITY HALL OF THE AFOREMENTIONED CITIES SHALL RECEIVE ZONE 1 PAY FOR ALL CLASSIFICATIONS. ALL JOBS OR PROJECTS LOCATED MORE THAN 30 MILES AND LESS THAN 50 MILES FROM THE RESPECTIVE CITY HALL OF THE AFOREMENTIONED CITIES SHALL RECEIVE ZONE II PAY FOR ALL CLASSIFICATIONS. ALL JOBS OR PROJECTS LOCATED MORE THAN 50 MILES FROM THE RESPECTIVE CITY HALL OF THE AFOREMENTIONED CITIES SHALL RECEIVE ZONE III PAY FOR ALL CLASSIFICATIONS.....$ 52.55 17.15

POWER EQUIPMENT OPERATOR: GROUP 5- ASPHALT, EXTRUSION MACHINE; ASPHALT, ROLLER (ANY ASPHALT MIX); ASPHALT, ROTO-MILL PAVEMENT PROFILER GROUND MAN; BULLDOZER, 20,000 LBS. OR LESS, OR 100 HORSE OR LESS; CEMENT PUMP; CHIP SPREADING MACHINE; CHURN DRILL AND EARTH BORING MACHINE; COMPACTOR,

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

SELF-PROPELLED WITHOUT BLADE; COMPRESSOR, (ANY POWER) 1,250 CU. FT. AND OVER, TOTAL CAPACITY; CONCRETE, BATCH PLANT QUALITY CONTROL; CONCRETE, COMBINATION MIXER AND COMPRESSOR OPERATOR, GUNITE WORK; CONCRETE, CURB MACHINE, MECHANICAL BERM, CURB AND/OR CURB AND GUTTER; CONCRETE, FINISHING MACHINE; CONCRETE, GROUTING MACHINE; CONCRETE, INTERNAL FULL SLAB VIBRATOR OPERATOR; CONCRETE, JOINT MACHINE; CONCRETE, MIXER SINGLE DRUM, ANDY CAPACITY; CONCRETE, PAVING MACHINE 8' OR LESS; CONCRETE, PLANER; CONCRETE, PUMP; CONCRETE, PUMP TRUCK; CONCRETE, PUMPCRETE OPERATOR (ANY TYPE); CONCRETE, SLIP FORM PUMPS, POWER DRIVEN HYDRAULIC LIFTING DEVICE FOR CONCRETE FORMS; CONVEYORED MATERIAL HANDLER; CRANE, BOOM TRUCK UNDER 20 TONS; CRANE, BOOM TYPE LIFTING DEVICE, 5 TON CAPACITY OR LESS; DRILL, DIRECTIONAL TYPE LESS THAN 20,000 LBS. PULLBACK; FORM LIFT, OVER 10 TON OR ROBOTIC; HELICOPTER HOIST; HOIST OPERATOR, SINGLE DRUM; HYDRAULIC BACKHOE TRACK TYPE UP TO AND INCLUDING 20,000 LBS.; HYDRAUIC BACKHOE WHEEL TYPE (ANY MAKE); LASER SCREED; LOADERS, RUBBER-TIRED TYPE, LESS THAN 25,000 LBS.; PAVEMENT GRINDER AND/OR GROOVING MACHINE (RIDING TYPE); PIPE, CAST IN PLACE PIPE LAYING MACHINE; PULVA-MIXER OR SIMILAR TYPES; PUMP OPERATOR, MORE THAN 5 PUMPS (ANY SIZE); RAIL, BALLAST COMPACTOR, REGULATOR, OR TAMPER MACHINES; SERVICE OILER (GREASER); SWEEPER SELF-PROPELLED; TRACTOR, RUBBER-TIRED, 50 HP FLYWHEEL AND UNDER; TRENCHING MACHINE OPERATOR, MAXIMUM DIGGING CAPACITY 3' DEPTH; TUNNEL, LOCOMOTIVE, DINKEY; TUNNEL, POWER JUMBO SETTING SLIP FORMS, ETC. (CLARK, COWLITX, KLICKITAT, PACIFIC (SOUTH), SKAMANIA, AND WAHKIAKUM COUNTIES). ZONE DIFFERENTIALS (ADD TO ZONE 1 RATES). ZONE 1: BASE RATE. ZONE 2: $3.00. ZONE 3: $6.00. FOR THE FOLLOWING METROPOLITAN COUNTIES: MULTNOMAH; CLACKAMAS; MARION; WASHINGTON; YAMHILL; AND COLUMBIA; CLARK; AND COWLITZ COUNTY, WASHINGTON WITH MODIFICATIONS AS INDICATED: ALL JOBS OR PROJECTS LOCATED IN MULTNOMAH, CLACKAMAS, AND MARION COUNTIES, WEST OF THE WESTERN OBUNDARY OF MT. HOOD NATIONAL FOREST AND WEST OF MILE POST 30 ON I-84 AND WEST OF MILE POST 30 ON STATE HIGHWAY 26 AND WEST OF MILE POST 30 ON HIGHWAY 22 AND ALL JOBS OR PROJECTS LOCATED IN YAMHILL COUNTY, WASHINGTON COUNTY, AND COLUMBIA COUNTY AND ALL JOBS OR PROJECTS LOCATED IN CLARK & COWLITZ COUNTY IN THE MT. ST. HELENS ""BLAST ZONE"" SHALL RECEIVE ZONE 1 PAY FOR ALL CLASSIFICATIONS. ALL JOBS OR PROJECTS LOCATED IN THE AREA OUTSIDE THE IDENTIFIED BOUNDARY ABOVE, BUT LESS THAN 50 MILES FROM THE PORTLAND CITY HALL SHALL RECEIVE ZONE II PAY FOR ALL CLASSIFICATIONS. ALL JOBS OR PROJECTS LOCATED MORE THAN 50 MILES FROM THE PORTLAND CITY HALL, BUT OUTSIDE THE IDENTIFIED BORDER ABOVE, SHALL RECEIVE

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

ZONE III PAY FOR ALL CLASSIFICATION. FOR THE FOLLOWING CITIES: ALBANY, BEND , COOS BAY, EUGENE, GRANTS PASS, KLAMATH FALLS, MEDFORD, AND ROSEBURG- ALL JOBS OR PROJECTS LOCATED WITHIN 30 MILES OF THE RESPECTIVE CITY HALL OF THE AFOREMENTIONED CITIES SHALL RECEIVE ZONE 1 PAY FOR ALL CLASSIFICATIONS. ALL JOBS OR PROJECTS LOCATED MORE THAN 30 MILES AND LESS THAN 50 MILES FROM THE RESPECTIVE CITY HALL OF THE AFOREMENTIONED CITIES SHALL RECEIVE ZONE II PAY FOR ALL CLASSIFICATIONS. ALL JOBS OR PROJECTS LOCATED MORE THAN 50 MILES FROM THE RESPECTIVE CITY HALL OF THE AFOREMENTIONED CITIES SHALL RECEIVE ZONE III PAY FOR ALL CLASSIFICATIONS.....$ 51.31 17.15

POWER EQUIPMENT OPERATOR: GROUP 6- ASPHALT, PUGMILL (ANY TYPES); ASPHALT, RAKER; ASPHALT, TRUCK MOUNTED ASPHALT SPREADER, WITH SCREED; SUGER OILER; BOATMAN; BOBCAT, SKID STEER (LESS THAN 1 YRD); BROOM, SELF-PROPELLED; COMPRESSOR OPERATOR (ANY POWER) UNDER 1,250 CU. FT. TOTAL CAPACITY; CONCRETE CURING MACHINE (RIDING TYPE); CONCRETE SAW; CONVEYOR OPERATOR OR ASSISTANT; CRANE, TUGGER; CRUSHER FEEDERMAN; CRUSHER OILER; DECKHAND; DRILL, DIRECTIONAL LOCATOR; FORK LIFT; GRADE CHECKER; GUARDRAIL PUNCHOILER; HUDROGRAPHIC SEEDER MACHINE, STRAW, PULP OR SEED; HYDROSTATIC PUMP OPERATOR; MIXER BOX (CTB, DRY BATCH, ETC.); OILER; PLANT OILER; PUMP (ANY POWER); RAIL, BRAKEMAN, SWITCHMAN, MOTORMAN; RAIL, TAMPING MACHINE, MECHANICAL, SELF-PROPELLED; RIGGER; ROLLER GRADING (NOT ASPHALT); TRUCK, CRANE OILER-DRIVER. (CLARK, COWLITX, KLICKITAT, PACIFIC (SOUTH), SKAMANIA, AND WAHKIAKUM COUNTIES). ZONE DIFFERENTIALS (ADD TO ZONE 1 RATES). ZONE 1: BASE RATE. ZONE 2: $3.00. ZONE 3: $6.00. FOR THE FOLLOWING METROPOLITAN COUNTIES: MULTNOMAH; CLACKAMAS; MARION; WASHINGTON; YAMHILL; AND COLUMBIA; CLARK; AND COWLITZ COUNTY, WASHINGTON WITH MODIFICATIONS AS INDICATED: ALL JOBS OR PROJECTS LOCATED IN MULTNOMAH, CLACKAMAS, AND MARION COUNTIES, WEST OF THE WESTERN OBUNDARY OF MT. HOOD NATIONAL FOREST AND WEST OF MILE POST 30 ON I-84 AND WEST OF MILE POST 30 ON STATE HIGHWAY 26 AND WEST OF MILE POST 30 ON HIGHWAY 22 AND ALL JOBS OR PROJECTS LOCATED IN YAMHILL COUNTY, WASHINGTON COUNTY, AND COLUMBIA COUNTY AND ALL JOBS OR PROJECTS LOCATED IN CLARK & COWLITZ COUNTY IN THE MT. ST. HELENS ""BLAST ZONE"" SHALL RECEIVE ZONE 1 PAY FOR ALL CLASSIFICATIONS. ALL JOBS OR PROJECTS LOCATED IN THE AREA OUTSIDE THE IDENTIFIED BOUNDARY ABOVE, BUT LESS THAN 50 MILES FROM THE PORTLAND CITY HALL SHALL RECEIVE ZONE II PAY FOR ALL CLASSIFICATIONS. ALL JOBS OR PROJECTS LOCATED MORE THAN 50 MILES FROM THE PORTLAND CITY HALL, BUT OUTSIDE THE IDENTIFIED BORDER ABOVE, SHALL RECEIVE ZONE III PAY FOR ALL CLASSIFICATION. FOR THE FOLLOWING CITIES: ALBANY, BEND , COOS BAY, EUGENE, GRANTS PASS, KLAMATH FALLS, MEDFORD, AND ROSEBURG-

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

ALL JOBS OR PROJECTS LOCATED WITHIN 30 MILES OF THE
RESPECTIVE CITY HALL OF THE AFOREMENTIONED CITIES
SHALL RECEIVE ZONE 1 PAY FOR ALL CLASSIFICATIONS.
ALL JOBS OR PROJECTS LOCATED MORE THAN 30 MILES AND
LESS THAN 50 MILES FROM THE RESPECTIVE CITY HALL OF
THE AFOREMENTIONED CITIES SHALL RECEIVE ZONE II PAY
FOR ALL CLASSIFICATIONS. ALL JOBS OR PROJECTS
LOCATED MORE THAN 50 MILES FROM THE RESPECTIVE CITY
HALL OF THE AFOREMENTIONED CITIES SHALL RECEIVE
ZONE III PAY FOR ALL CLASSIFICATIONS.....$ 48.09 17.15

IRON0014-005 07/07/2025

Rates	Fringes
IRONWORKER (ADAMS, ASOTIN, BENTON, COLUMBIA, DOUGLAS, FERRY, FRANKLIN, GARFIELD, GRANT, LINCOLN, OKANOGAN, PEND ORIELLE, SPOKANE, STEVENS, WALLA WALLA, AND WHITMAN COUNTIES).....$ 43.40	32.77

IRON0029-002 07/07/2025

Rates	Fringes
IRONWORKER (CLARK, COWLITZ, KLICKITAT, PACIFIC, SKAMANIA, AND WAHKAIKUM COUNTIES).....$ 48.31	34.52

IRON0086-002 07/07/2025

Rates	Fringes
IRONWORKER (YAKIMA, KITTITAS AND CHELAN COUNTIES)...$ 43.40	32.77

IRON0086-004 07/07/2025

Rates	Fringes
IRONWORKER (CLALLAM, GRAYS HARBOR, ISLAND, JEFFERSON, KING, KITSAP, LEWIS, MASON, PIERCE, SKAGIT, SNOHOMISH, THURSTON, AND WHATCOME COUNTIES).$ 57.94	34.52

LABO0238-004 06/01/2025

Rates	Fringes
LABORER: GROUP 1, AREA A-1 - FLAGMAN; LANDSCAPE LABORER; SCALEMAN; TRAFFIC CONTROL MAINTENANCE LABORER (TO INCLUDE ERECTION AND MAINTENANCE OF BARRICADES, SIGNS AND RELIEF OF FLAGPERSON); WINDOW WASHER/CLEANER (DETAIL CLEANUP, SUCH AS, BUT NOT LIMITED TO CLEANING FLOORS, CEILINGS, WALLS, WINDOWS, ETC. PRIOR TO FINAL ACCEPTANCE BY THE OWNER) (A-1 AREA: ASOTIN, BENTON, FRANKLIN, GARFIELD, LINCOLN, SPOKANE, WALLA WALLA, AND WHITMAN COUNTIES).....$ 34.03	16.90
LABORER: GROUP 2, AREA A-1 - ASBESTOS ABATEMENT WORKER; BRUSH HOG FEEDER; CARPENTER TENDER; CEMENT HANDLER; CLEAN-UP LABORER; CONCRETE CREWMAN (TO INCLUDE STRIPPING OF FORMS, HAND OPERATING JACKS ON SLIP FORM CONSTRUCTION, APPLICATION OF CONCRETE CURING COMPOUNDS, PUMPCRETE MACHINE, SIGNALING,	

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

HANDLIGN THE NOZZLE OF SQUEEZCRETE OR SIMILAR
MACHINE, 6 INCHES AND SMALLER); CONFINED SPACE
ATTENDANT; CONCRETE SIGNALMAN; CRUSHER FEEDER;
DEMOLITION (TO INCLUDE CLEAN-UP, CURNING, LOADING,
WRECKING AND SALVAGE OF ALL MATERIAL); DUMPMAN;
FENCE ERECTOR; FIREWATCH; FORM CLEANING MACHINE
FEEDER, STACKER, GENERAL LABORER; GROUT MACHINE
HEADER TENDER; GUARD RAIL (TO INCLUDE GUARD RAILS,
GUIDE AND REFERENCE POSTS, SIGN POSTS, AND
RIGHT-OF-WAY MARKERS); HAZARDOUS WASTE WORKER,
LEVEL D (NO RESPIRATOR IS USED AND SKIN PROTECTION
IS MINIMAL); MINER, CLASS ""A"" (TO INCLUDE ALL BULL
GANG, CONCRETE CREWMAN, DUMPAN AND PUMPCRETE
CREWMAN, INCLUDING DISTRIBUTING PIPE, ASSEMBLY &
DISMANTLE, AND NIPPER), NIPPER; RIPRAP MAN;
SANDBLAST TAILHOSEMAN; SCAFFOLD ERECTOR (WOOD OR
STEEL); STAKE JUMPER; STRUCTURAL MOVER (TO INCLUDE
SEPARATING FOUNDATION, PREPARATION, CRIBBING,
SHORING, JACKING AND UNLOADING OF STRUCTURES);
TAILHOSEMAN (WATER NOZZLE); TIMBER BUCKER AND
FALLER (BY HAND); TRACK LABORER (RR); TRUCK LOADER;
WELL-POINT MAN; ALL OTHER WORK CLASSIFICATIONS NOT
SPECIFICALLY LISTED SHALL BE CLASSIFIED AS GENERAL
LABORER. (A-1 AREA: ASOTIN, BENTON, FRANKLIN,
GARFIELD, LINCOLN, SPOKANE, WALLA WALLA, AND
WHITMAN COUNTIES).....$ 37.13 16.90
LABORER: GROUP 3, AREA A-1 - ASPHALT ROLLER,
WALKING; CEMENT FINISHER TENDER; CONCRETE SAW,
WALKING; DEMOLITION TORCH; DOPE POT FIREMEN,
NON-MECHANICAL; DRILLER TENDER (WHEN REQUIRED TO
MOVE AND POSITION MACHINE); FORM SETTER, PAVING;
GRADE CHECKER USING LEVEL; HAZARDOUS WASTE WORKER,
LEVEL C (USES A CHEMICAL ""SPLASH SUIT"" AND AIR
PURIFYING RESPIRATOR); JACKHAMMER OPERATOR; MINER,
CLASS ""B"" (TO INCLUDE BRAKEMAN, FINISHER, VIBRATOR,
FORM SETTER); NOZZLEMAN (TO INCLUDE SQUEEZE AND
FLO-CRETE NOAZZLE); NOZZLEMAN, WATER, AIR OR STEAM;
PAVEMENT BREAKER (UNDER 90 LBS.); PIPELAYER,
CORRUGATED METAL CULVERT; PIPELAYER, MULTI-PLATE;
POT TENDER; POWER BUGGY OPERATOR; POWER TOOL
OPERATOR, GAS, ELECTRIC, PNEUMATIC; RAILROAD
EQUIPMENT, POWER DRIVEN, EXCEPT DUAL MOBILE POWER
SPIKER OR PULLER; RAILROAD POWER SPIKER OR PULLER,
DUAL MOBILE; RODDER AND SPREADER; TAMPER (TO
INCLUDE OPERATION OF BARCO, ESSEX AND SIMILAR
TAMPERS); TRENCHER, SHAWNEE; TUGGER OPERATOR; WAGON
DRILLS; WATER PIPE LINER; WHEELBARROW (POWER
DRIVEN). (A-1 AREA: ASOTIN, BENTON, FRANKLIN,
GARFIELD, LINCOLN, SPOKANE, WALLA WALLA, AND
WHITMAN COUNTIES).....$ 37.46 16.90
LABORER: GROUP 4, AREA A-1 - AIR AND HYDRAULIC
TRACK DRILL; ASPHALT RAKER; BRUSH MACHINE (TO
INCLUDE HORIZONTAL CONSTRUCTION JOINT CLEANUP BRUSH
MACHINE, POWER PROPELLED); CAISSON WORKER, FREE
AIR; CHAIN SAW OPERATOR AND FALLER; CONCRETE STACK
(TO INCLUDE LABORERS WHEN LABORERS WORKING ON FREE

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

STANDING CONCRETE STACKS FOR SMOKE OR FUME CONTROL
ABOVE 40 FEET HIGH); GUNITE (TO INCLUDE OPERATION
OF MACHINE AND NOZZLE); HAZARDOUS WASTE WORKER,
LEVEL B (USES SAME RESPIRATOR PROTECTION AS LEVEL
A. A SUPPLIED AIR LINE IS PROVIDED IN CONJUNCTION
WITH A CHEMICAL ""SPLASH SUIT""); HIGH SCALER; LASER
BEAM OPERATOR (TO INLCUDE GRADE CHECKER AND
ELEVATION CONTROL); MINER, CLASS C (TO INCLUDE
MINER, NOZZLEMAN FOR CONCRETE, LASER BEAM OPERATOR
AND RIGGER ON TUNNELS); MONITOR OPERATOR (AIR TRACK
OR SIMILAR MOUNTING); MORTAR MIXER; NOZZLEMAN (TO
INCLUDE JET BLASTING NOZZLEMAN, OVER 1,200 LBS.,
JET BLAST MACHINE POWER PROPELLED, SANDBLAST
NOZZLE); PAVEMENT BREAKER (90 LBS. AND OVER);
PIPELAYER (TO INCLUDE WORKING TOPMAN, CAULKER,
COLLARMAN, JOINTER, MORTARMAN, RIGGER, JACKER,
SHORER, VALVE OR METER INSTALLER); PIPEWRAPPER;
PLASTERER TENDER; VIBRATORS (ALL). (A-1 AREA:
ASOTIN, BENTON, FRANKLIN, GARFIELD, LINCOLN,
SPOKANE, WALLA WALLA, AND WHITMAN COUNTIES).....$ 37.80 16.90
LABORER: GROUP 5, AREA A-1 - DRILLS WITH DUAL
MASTS: HAZARDOUS WASTE WORKER, LEVEL A (UTILIZES A
FULLY ENCAPSULATED SUIT WITH A SELF-CONTAINED
BREATHING APPARATUS OR A SUPPLIED AIR LINE); MINER
CLASS ""D"", TO INCLUDE RAISE AND SHAFT MINER, LASER
BEAM OPERATOR ON RAISES AND SHAFTS). (A-1 AREA:
ASOTIN, BENTON, FRANKLIN, GARFIELD, LINCOLN,
SPOKANE, WALLA WALLA, AND WHITMAN COUNTIES A-2
AREA: ADAMS,COLUMBIA,DOUGLAS (EAST OF 120TH
MERIDIAN), FERRY, GRANT, OKANOGAN, PEND OREILLE,
AND STEVENS COUNTIES).....$ 38.14 16.90
LABORER: GROUP 1, AREA A-2 - FLAGMAN; LANDSCAPE
LABORER; SCALEMAN; TRAFFIC CONTROL MAINTENANCE
LABORER (TO INCLUDE ERECTION AND MAINTENANCE OF
BARRICADES, SIGNS AND RELIEF OF FLAGPERSON); WINDOW
WASHER/CLEANER (DETAIL CLEANUP, SUCH AS, BUT NOT
LIMITED TO CLEANING FLOORS, CEILINGS, WALLS,
WINDOWS, ETC. PRIOR TO FINAL ACCEPTANCE BY THE
OWNER) (A-2 AREA: ADAMS, COLUMBIA, DOUGLAS (EAST OF
120TH MERIDIAN), FERRY, GRANT, OKANOGAN, PEND
OREILLE, AND STEVENS COUNTIES).....$ 37.03 16.90
LABORER: GROUP 2, AREA A-2 - ASBESTOS ABATEMENT
WORKER; BRUSH HOG FEEDER; CARPENTER TENDER; CEMENT
HANDLER; CLEAN-UP LABORER; CONCRETE CREWMAN (TO
INCLUDE STRIPPING OF FORMS, HAND OPERATING JACKS ON
SLIP FORM CONSTRUCTION, APPLICATION OF CONCRETE
CURING COMPOUNDS, PUMPCRETE MACHINE, SIGNALING,
HANDLIGN THE NOZZLE OF SQUEEZCRETE OR SIMILAR
MACHINE, 6 INCHES AND SMALLER); CONFINED SPACE
ATTENDANT; CONCRETE SIGNALMAN; CRUSHER FEEDER;
DEMOLITION (TO INCLUDE CLEAN-UP, CURNING, LOADING,
WRECKING AND SALVAGE OF ALL MATERIAL); DUMPMAN;
FENCE ERECTOR; FIREWATCH; FORM CLEANING MACHINE
FEEDER, STACKER, GENERAL LABORER; GROUT MACHINE
HEADER TENDER; GUARD RAIL (TO INCLUDE GUARD RAILS,
GUIDE AND REFERENCE POSTS, SIGN POSTS, AND

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

RIGHT-OF-WAY MARKERS); HAZARDOUS WASTE WORKER,
LEVEL D (NO RESPIRATOR IS USED AND SKIN PROTECTION
IS MINIMAL); MINER, CLASS ""A"" (TO INCLUDE ALL BULL
GANG, CONCRETE CREWMAN, DUMPAN AND PUMPCRETE
CREWMAN, INCLUDING DISTRIBUTING PIPE, ASSEMBLY &
DISMANTLE, AND NIPPER), NIPPER; RIPRAP MAN;
SANDBLAST TAILHOSEMAN; SCAFFOLD ERECTOR (WOOD OR
STEEL); STAKE JUMPER; STRUCTURAL MOVER (TO INCLUDE
SEPARATING FOUNDATION, PREPARATION, CRIBBING,
SHORING, JACKING AND UNLOADING OF STRUCTURES);
TAILHOSEMAN (WATER NOZZLE); TIMBER BUCKER AND
FALLER (BY HAND); TRACK LABORER (RR); TRUCK LOADER;
WELL-POINT MAN; ALL OTHER WORK CLASSIFICATIONS NOT
SPECIFICALLY LISTED SHALL BE CLASSIFIED AS GENERAL
LABORER.(A-2 AREA: ADAMS,COLUMBIA,DOUGLAS (EAST OF
120TH MERIDIAN), FERRY, GRANT, OKANOGAN, PEND
OREILLE, AND STEVENS COUNTIES).....$ 40.13 16.90
LABORER: GROUP 3, AREA A-2 - ASPHALT ROLLER,
WALKING; CEMENT FINISHER TENDER; CONCRETE SAW,
WALKING; DEMOLITION TORCH; DOPE POT FIREMEN,
NON-MECHANICAL; DRILLER TENDER (WHEN REQUIRED TO
MOVE AND POSITION MACHINE); FORM SETTER, PAVING;
GRADE CHECKER USING LEVEL; HAZARDOUS WASTE WORKER,
LEVEL C (USES A CHEMICAL ""SPLASH SUIT"" AND AIR
PURIFYING RESPIRATOR); JACKHAMMER OPERATOR; MINER,
CLASS ""B"" (TO INCLUDE BRAKEMAN, FINISHER, VIBRATOR,
FORM SETTER); NOZZLEMAN (TO INCLUDE SQUEEZE AND
FLO-CRETE NOAZZLE); NOZZLEMAN, WATER, AIR OR STEAM;
PAVEMENT BREAKER (UNDER 90 LBS.); PIPELAYER,
CORRUGATED METAL CULVERT; PIPELAYER, MULTI-PLATE;
POT TENDER; POWER BUGGY OPERATOR; POWER TOOL
OPERATOR, GAS, ELECTRIC, PNEUMATIC; RAILROAD
EQUIPMENT, POWER DRIVEN, EXCEPT DUAL MOBILE POWER
SPIKER OR PULLER; RAILROAD POWER SPIKER OR PULLER,
DUAL MOBILE; RODDER AND SPREADER; TAMPER (TO
INCLUDE OPERATION OF BARCO, ESSEX AND SIMILAR
TAMPERS); TRENCHER, SHAWNEE; TUGGER OPERATOR; WAGON
DRILLS; WATER PIPE LINER; WHEELBARROW (POWER
DRIVEN).(A-2 AREA: ADAMS,COLUMBIA,DOUGLAS (EAST OF
120TH MERIDIAN), FERRY, GRANT, OKANOGAN, PEND
OREILLE, AND STEVENS COUNTIES).....$ 40.46 16.90
LABORER: GROUP 4, AREA A-2 - AIR AND HYDRAULIC
TRACK DRILL; ASPHALT RAKER; BRUSH MACHINE (TO
INCLUDE HORIZONTAL CONSTRUCTION JOINT CLEANUP BRUSH
MACHINE, POWER PROPELLED); CAISSON WORKER, FREE
AIR; CHAIN SAW OPERATOR AND FALLER; CONCRETE STACK
(TO INCLUDE LABORERS WHEN LABORERS WORKING ON FREE
STANDING CONCRETE STACKS FOR SMOKE OR FUME CONTROL
ABOVE 40 FEET HIGH); GUNITE (TO INCLUDE OPERATION
OF MACHINE AND NOZZLE); HAZARDOUS WASTE WORKER,
LEVEL B (USES SAME RESPIRATOR PROTECTION AS LEVEL
A. A SUPPLIED AIR LINE IS PROVIDED IN CONJUNCTION
WITH A CHEMICAL ""SPLASH SUIT""); HIGH SCALER; LASER
BEAM OPERATOR (TO INLCUDE GRADE CHECKER AND
ELEVATION CONTROL); MINER, CLASS C (TO INCLUDE
MINER, NOZZLEMAN FOR CONCRETE, LASER BEAM OPERATOR

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

AND RIGGER ON TUNNELS); MONITOR OPERATOR (AIR TRACK
OR SIMILAR MOUNTING); MORTAR MIXER; NOZZLEMAN (TO
INCLUDE JET BLASTING NOZZLEMAN, OVER 1,200 LBS.,
JET BLAST MACHINE POWER PROPELLED, SANDBLAST
NOZZLE); PAVEMENT BREAKER (90 LBS. AND OVER);
PIPELAYER (TO INCLUDE WORKING TOPMAN, CAULKER,
COLLARMAN, JOINTER, MORTARMAN, RIGGER, JACKER,
SHORER, VALVE OR METER INSTALLER); PIPEWRAPPER;
PLASTERER TENDER; VIBRATORS (ALL). (A-2 AREA:
ADAMS,COLUMBIA,DOUGLAS (EAST OF 120TH MERIDIAN),
FERRY, GRANT, OKANOGAN, PEND OREILLE, AND STEVENS
COUNTIES).....$ 40.80 16.90
LABORER: GROUP 5, AREA A-2 - DRILLS WITH DUAL
MASTS: HAZARDOUS WASTE WORKER, LEVEL A (UTILIZES A
FULLY ENCAPSULATED SUIT WITH A SELF-CONTAINED
BREATHING APPARATUS OR A SUPPLIED AIR LINE); MINER
CLASS ""D"", TO INCLUDE RAISE AND SHAFT MINER, LASER
BEAM OPERATOR ON RAISES AND SHAFTS). (A-2 AREA:
ADAMS,COLUMBIA,DOUGLAS (EAST OF 120TH MERIDIAN),
FERRY, GRANT, OKANOGAN, PEND OREILLE, AND STEVENS
COUNTIES).....$ 41.14 16.90

LABO0238-006 06/01/2025

Rates	Fringes
HOD CARRIER (COUNTIES EAST OF THE 120TH MERIDIAN: ADAMS, ASOTIN, BENTON, CHELAN, COLUMBIA, DOUGLAS, FERRY, FRANKLIN, GARFIELD, GRANT, LINCOLN, OKANOGAN, PEND OREILLE, STEVENS, SPOKANE, WALLA WALLA, WHITMAN).....$ 38.05	16.75

LABO0242-003 06/01/2025

Rates	Fringes
LABORER: ZONE 1: GROUP 1- LANDSCAPING AND PLANTING; WATCHMAN; WINDOW WASHER/CLEANER (DETAIL CLEAN-UP, SUCH AS BUT NOT LIMITED TO CLEANING FLOORS, CEILINGS, WALLS, WINDOWS, ETC., PRIOR TO FINAL ACCEPTANCE BY THE OWNER) (KING COUNTY) BASE POINTS: BELLINGHAM, MT. VERNON, EVERETT, SEATTLE, KENT, TACOMA, OLYMPIA, CENTRALIA, ABERDEEN, SHELTON, PT. TOWNSEND, PT. ANGELES, AND BREMERTON ZONE 1 - PROJECTS WITHIN 25 RADIUS MILES OF THE RESPECTIVE CITY HALL ZONE 2 - MORE THAN 25 BUT LESS THAN 45 RADIUS MILES FROM THE RESPECTIVE CITY HALL ZONE 3 - MORE THAN 45 RADIUS MILES FROM THE RESPECTIVE CITY HALL ZONE DIFFERENTIAL (ADD TO ZONE 1 RATES): ZONE 2 - $1.00 ZONE 3 - $1.30. BASE POINTS: CHELAN, SUNNYSIDE, WENATCHEE, AND YAKIMA ZONE 1 - PROJECTS WITHIN 25 RADIUS MILES OF THE RESPECTIVE CITY HALL ZONE 2 - MORE THAN 25 RADIUS MILES FROM THE RESPECTIVE CITY HALL ZONE DIFFERENTIAL (ADD TO ZONE 1 RATES): ZONE 2 - $2.25.....$ 36.07	15.79

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

LABORER: ZONE 1: GROUP 2A- BATCH WEIGHMAN; CRUSHER FEEDER; FENCE LABORER; FLAGMAN; PILOT CAR
(KING COUNTY)
BASE POINTS: BELLINGHAM, MT. VERNON, EVERETT, SEATTLE, KENT, TACOMA, OLYMPIA, CENTRALIA, ABERDEEN, SHELTON, PT. TOWNSEND, PT. ANGELES, AND BREMERTON ZONE 1 - PROJECTS WITHIN 25 RADIUS MILES OF THE RESPECTIVE CITY HALL ZONE 2 - MORE THAN 25 BUT LESS THAN 45 RADIUS MILES FROM THE RESPECTIVE CITY HALL ZONE 3 - MORE THAN 45 RADIUS MILES FROM THE RESPECTIVE CITY HALL ZONE DIFFERENTIAL (ADD TO ZONE 1 RATES): ZONE 2 - $1.00 ZONE 3 - $1.30. BASE POINTS: CHELAN, SUNNYSIDE, WENATCHEE, AND YAKIMA ZONE 1 - PROJECTS WITHIN 25 RADIUS MILES OF THE RESPECTIVE CITY HALL ZONE 2 - MORE THAN 25 RADIUS MILES FROM THE RESPECTIVE CITY HALL ZONE DIFFERENTIAL (ADD TO ZONE 1 RATES): ZONE 2 - $2.25.....$ 40.88 16.72

LABORER: ZONE 1: GROUP 3- GENERAL LABORER; AIR, GAS, OR ELECTRIC VIBRATING SCREED; ASBESTOS ABATEMENT LABORER; BALLAST REGULATOR MACHINE; BRUSH CUTTER; BRUSH HOG FEEDER; BURNER; CARPENTER TENDER; CEMENT FINISHER TENDER; CHANGE HOUSE OR DRY SHACK; CHIPPING GUN (UNDER 30 LBS.); CHOKER SETTER; CHUCK TENDER; CLEAN-UP LABORER; CONCRETE FORM STRIPPER; CURING LABORER; DEMOLITION (WRECKING AND MOVING INCLUDING CHARRED MATERIAL); DITCH DIGGER; DUMP PERSON; FINE GRADERS; FIREWATCH; FORM SETTER; GABIAN BASKET BUILDERS; GROUT MACHINE TENDER; GRINDERS; GUARDRAIL ERECTOR; HAZARDOUS WASTE WORKER (LEVEL C: USES A CHEMICAL ""SPLASH SUIT"" AND AIR PURIFYING RESPIRATOR); MAINTENANCE PERSON; MATERIAL YARD PERSON; POT TENDER; RIP RAP PERSON; RIGGERS; SCALE PERSON; SLOPER SPRAYER; SIGNAL PERSON; STOCK PILER; STAKE HOPPER; TOOLROOM MAN (AT JOB SITE); TOPPER-TAILER; TRACK LABORER; TRUCK SPOTTER; VINYL SEAMER
(KING COUNTY)
BASE POINTS: BELLINGHAM, MT. VERNON, EVERETT, SEATTLE, KENT, TACOMA, OLYMPIA, CENTRALIA, ABERDEEN, SHELTON, PT. TOWNSEND, PT. ANGELES, AND BREMERTON ZONE 1 - PROJECTS WITHIN 25 RADIUS MILES OF THE RESPECTIVE CITY HALL ZONE 2 - MORE THAN 25 BUT LESS THAN 45 RADIUS MILES FROM THE RESPECTIVE CITY HALL ZONE 3 - MORE THAN 45 RADIUS MILES FROM THE RESPECTIVE CITY HALL ZONE DIFFERENTIAL (ADD TO ZONE 1 RATES): ZONE 2 - $1.00 ZONE 3 - $1.30 BASE POINTS: CHELAN, SUNNYSIDE, WENATCHEE, AND YAKIMA ZONE 1 - PROJECTS WITHIN 25 RADIUS MILES OF THE RESPECTIVE CITY HALL ZONE 2 - MORE THAN 25 RADIUS MILES FROM THE RESPECTIVE CITY HALL ZONE DIFFERENTIAL (ADD TO ZONE 1 RATES): ZONE 2 - $2.25.....$ 50.38 16.96

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

LABORER: ZONE 1: GROUP 4- CEMENT DUMPER-PAVING; CHIPPING GUN (OVER 30 LBS.); CLARY POWER SPREADER; CONCRETE DUMPER/CHUTE OPERATOR; CONCRETE SAW OPERATOR; DRILL OPERATOR (HYDRAULIC, DIAMOND, AIARTRAC); FALLER AND BUCKER CHAIN SAW; GRADE CHECKER AND TRANSIT PERSON; GROUTMEN (PRESSURE) INCLUDING POST TENSION BEAMS; HAZARDOUS WASTE WORKER (LEVEL B: USES SAME RESPIRATOR PROTECTION AS LEVEL A. A SUPPLIED AIR LINE IS PROVIDED IN CONJUNCTION WITH A CHEMICAL ""SPLASH SUIT""); HIGH SCALER; JACKHAMMER; LASERBEAM OPERATOR; MANHOLE BUILDER-MUDMAN; NOZZLEMAN (CONCRETE PUMP, GREEN CUTTER WHEN USING COMBINATION OF HIGH PRESSURE AIR AND WATER ON CONCRETE AND ROCK, SANDBLAST, GUNITE, SHOTCRETE, WATER BLASTER, VACUUM BLASTER); PAVEMENT BREAKER; PIPE LAYER AND CAULKER; PIPE POT TENDER; PIPE RELINER (NOT INSERT TYPE); PIPE WRAPPER; POWER JACKS; RAILROAD SPIKE PULLER-POWER; RAKER-ASPHALT; RIVET BUSTER; RODDER; SLOPER (OVER 20 FT); SPREADER (CONCRETE); TAMPER AND SIMILAR ELECTRIC, AIR AND GLAS OPERATED TOOL; TIMBER PERSON-SEWER (LAGGER SHORER AND CRIBBER); TRACK LINER POWER; TUGGER OPERATOR; VIBRATOR; WELL POINT LABORER
(KING COUNTY)
BASE POINTS: BELLINGHAM, MT. VERNON, EVERETT, SEATTLE, KENT, TACOMA, OLYMPIA, CENTRALIA, ABERDEEN, SHELTON, PT. TOWNSEND, PT. ANGELES, AND BREMERTON ZONE 1 - PROJECTS WITHIN 25 RADIUS MILES OF THE RESPECTIVE CITY HALL ZONE 2 - MORE THAN 25 BUT LESS THAN 45 RADIUS MILES FROM THE RESPECTIVE CITY HALL ZONE 3 - MORE THAN 45 RADIUS MILES FROM THE RESPECTIVE CITY HALL ZONE DIFFERENTIAL (ADD TO ZONE 1 RATES): ZONE 2 - $1.00 ZONE 3 - $1.30 BASE POINTS: CHELAN, SUNNYSIDE, WENATCHEE, AND YAKIMA ZONE 1 - PROJECTS WITHIN 25 RADIUS MILES OF THE RESPECTIVE CITY HALL ZONE 2 - MORE THAN 25 RADIUS MILES FROM THE RESPECTIVE CITY HALL ZONE DIFFERENTIAL (ADD TO ZONE 1 RATES): ZONE 2 - $2.25.$ 51.52 16.99
LABORER: ZONE 1: GROUP 5- CAISSON WORKER; MORTARMAN AND HODCARRIER; POWDERMAN; RE-TIMBERMAN; HAZARDOUS WASTE WORKER (LEVEL A: UTILIZES A FULLY ENCAPSULATED SUIT WITH A SELF-CONTAINED BREATHING APPARATUS OR A SUPPLIED AIR LINE).
(KING COUNTY)
BASE POINTS: BELLINGHAM, MT. VERNON, EVERETT, SEATTLE, KENT, TACOMA, OLYMPIA, CENTRALIA, ABERDEEN, SHELTON, PT. TOWNSEND, PT. ANGELES, AND BREMERTON ZONE 1 - PROJECTS WITHIN 25 RADIUS MILES OF THE RESPECTIVE CITY HALL ZONE 2 - MORE THAN 25 BUT LESS THAN 45 RADIUS MILES FROM THE RESPECTIVE CITY HALL ZONE 3 - MORE THAN 45 RADIUS MILES FROM THE RESPECTIVE CITY HALL ZONE DIFFERENTIAL (ADD TO ZONE 1 RATES): ZONE 2 - $1.00 ZONE 3 - $1.30 BASE POINTS: CHELAN, SUNNYSIDE, WENATCHEE, AND YAKIMA ZONE 1 - PROJECTS WITHIN

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

25 RADIUS MILES OF THE RESPECTIVE CITY HALL ZONE 2 - MORE THAN 25 RADIUS MILES FROM THE RESPECTIVE CITY HALL ZONE DIFFERENTIAL (ADD TO ZONE 1 RATES): ZONE 2 - $2.25.....$ 52.31 17.01
LABORER: ZONE 1: GROUP 6- MINER
(KING COUNTY)
BASE POINTS: BELLINGHAM, MT. VERNON, EVERETT, SEATTLE, KENT, TACOMA, OLYMPIA, CENTRALIA, ABERDEEN, SHELTON, PT. TOWNSEND, PT. ANGELES, AND BREMERTON ZONE 1 - PROJECTS WITHIN 25 RADIUS MILES OF THE RESPECTIVE CITY HALL ZONE 2 - MORE THAN 25 BUT LESS THAN 45 RADIUS MILES FROM THE RESPECTIVE CITY HALL ZONE 3 - MORE THAN 45 RADIUS MILES FROM THE RESPECTIVE CITY HALL ZONE DIFFERENTIAL (ADD TO ZONE 1 RATES): ZONE 2 - $1.00 ZONE 3 - $1.30 BASE POINTS: CHELAN, SUNNYSIDE, WENATCHEE, AND YAKIMA ZONE 1 - PROJECTS WITHIN 25 RADIUS MILES OF THE RESPECTIVE CITY HALL ZONE 2 - MORE THAN 25 RADIUS MILES FROM THE RESPECTIVE CITY HALL ZONE DIFFERENTIAL (ADD TO ZONE 1 RATES): ZONE 2 - $2.25.....$ 53.99 17.05

LABO0252-010 06/01/2025

	Rates	Fringes
LABORER: ZONE 1: GROUP 1 LANDSCAPING AND PLANTING; WATCHMAN; WINDOW WASHER/CLEANER (DETAIL CLEAN-UP, SUCH AS BUT NOT LIMITED TO CLEANING FLOORS, CEILINGS, WALLS, WINDOWS, ETC., PRIOR TO FINAL ACCEPTANCE BY THE OWNER) (CLALLAM, GRAYS HARBOR, JEFFERSON, KITSAP, LEWIS, MASON, PACIFIC (EXCLUDING SOUTHWEST), PIERCE, AND THURSTON COUNTIES) BASE POINTS: BELLINGHAM, MT. VERNON, EVERETT, SEATTLE, KENT, TACOMA, OLYMPIA, CENTRALIA, ABERDEEN, SHELTON, PT. TOWNSEND, PT. ANGELES, AND BREMERTON ZONE 1 - PROJECTS WITHIN 25 RADIUS MILES OF THE RESPECTIVE CITY HALL ZONE 2 - MORE THAN 25 BUT LESS THAN 45 RADIUS MILES FROM THE RESPECTIVE CITY HALL ZONE 3 - MORE THAN 45 RADIUS MILES FROM THE RESPECTIVE CITY HALL ZONE DIFFERENTIAL (ADD TO ZONE 1 RATES): ZONE 2 - $1.00 ZONE 3 - $1.30 BASE POINTS: CHELAN, SUNNYSIDE, WENATCHEE, AND YAKIMA ZONE 1 - PROJECTS WITHIN 25 RADIUS MILES OF THE RESPECTIVE CITY HALL ZONE 2 - MORE THAN 25 RADIUS MILES FROM THE RESPECTIVE CITY HALL ZONE DIFFERENTIAL (ADD TO ZONE 1 RATES): ZONE 2 - $2.25.....	$ 36.07	15.79
LABORER: ZONE 1: GROUP 2 BATCH WEIGHMAN; CRUSHER FEEDER; FENCE LABORER; FLAGMAN; PILOT CAR (CLALLAM, GRAYS HARBOR, JEFFERSON, KITSAP, LEWIS, MASON, PACIFIC (EXCLUDING SOUTHWEST), PIERCE, AND THURSTON COUNTIES) BASE POINTS: BELLINGHAM, MT. VERNON, EVERETT, SEATTLE, KENT, TACOMA, OLYMPIA, CENTRALIA, ABERDEEN, SHELTON, PT. TOWNSEND, PT. ANGELES, AND		

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

BREMERTON ZONE 1 - PROJECTS WITHIN 25 RADIUS MILES OF THE RESPECTIVE CITY HALL ZONE 2 - MORE THAN 25 BUT LESS THAN 45 RADIUS MILES FROM THE RESPECTIVE CITY HALL ZONE 3 - MORE THAN 45 RADIUS MILES FROM THE RESPECTIVE CITY HALL ZONE DIFFERENTIAL (ADD TO ZONE 1 RATES): ZONE 2 - $1.00 ZONE 3 - $1.30 BASE POINTS: CHELAN, SUNNYSIDE, WENATCHEE, AND YAKIMA ZONE 1 - PROJECTS WITHIN 25 RADIUS MILES OF THE RESPECTIVE CITY HALL ZONE 2 - MORE THAN 25 RADIUS MILES FROM THE RESPECTIVE CITY HALL ZONE DIFFERENTIAL (ADD TO ZONE 1 RATES): ZONE 2 - $2.25.....$ 40.88 16.72

LABORER: ZONE 1: GROUP 3 GENERAL LABORER; AIR, GAS, OR ELECTRIC VIBRATING SCREED; ASBESTOS ABATEMENT LABORER; BALLAST REGULATOR MACHINE; BRUSH CUTTER; BRUSH HOG FEEDER; BURNER; CARPENTER TENDER; CEMENT FINISHER TENDER; CHANGE HOUSE OR DRY SHACK; CHIPPING GUN (UNDER 30 LBS.); CHOKER SETTER; CHUCK TENDER; CLEAN-UP LABORER; CONCRETE FORM STRIPPER; CURING LABORER; DEMOLITION (WRECKING AND MOVING INCLUDING CHARRED MATERIAL); DITCH DIGGER; DUMP PERSON; FINE GRADERS; FIREWATCH; FORM SETTER; GABIAN BASKET BUILDERS; GROUT MACHINE TENDER; GRINDERS; GUARDRAIL ERECTOR; HAZARDOUS WASTE WORKER (LEVEL C: USES A CHEMICAL ""SPLASH SUIT"" AND AIR PURIFYING RESPIRATOR); MAINTENANCE PERSON; MATERIAL YARD PERSON; POT TENDER; RIP RAP PERSON; RIGGERS; SCALE PERSON; SLOPER SPRAYER; SIGNAL PERSON; STOCK PILER; STAKE HOPPER; TOOLROOM MAN (AT JOB SITE); TOPPER-TAILER; TRACK LABORER; TRUCK SPOTTER; VINYL SEAMER
(CLALLAM, GRAYS HARBOR, JEFFERSON, KITSAP, LEWIS, MASON, PACIFIC (EXCLUDING SOUTHWEST), PIERCE, AND THURSTON COUNTIES)
BASE POINTS: BELLINGHAM, MT. VERNON, EVERETT, SEATTLE, KENT, TACOMA, OLYMPIA, CENTRALIA, ABERDEEN, SHELTON, PT. TOWNSEND, PT. ANGELES, AND BREMERTON ZONE 1 - PROJECTS WITHIN 25 RADIUS MILES OF THE RESPECTIVE CITY HALL ZONE 2 - MORE THAN 25 BUT LESS THAN 45 RADIUS MILES FROM THE RESPECTIVE CITY HALL ZONE 3 - MORE THAN 45 RADIUS MILES FROM THE RESPECTIVE CITY HALL ZONE DIFFERENTIAL (ADD TO ZONE 1 RATES): ZONE 2 - $1.00 ZONE 3 - $1.30 BASE POINTS: CHELAN, SUNNYSIDE, WENATCHEE, AND YAKIMA ZONE 1 - PROJECTS WITHIN 25 RADIUS MILES OF THE RESPECTIVE CITY HALL ZONE 2 - MORE THAN 25 RADIUS MILES FROM THE RESPECTIVE CITY HALL ZONE DIFFERENTIAL (ADD TO ZONE 1 RATES): ZONE 2 - $2.25.....$ 50.38 16.96

LABORER: ZONE 1: GROUP 4 CEMENT DUMPER-PAVING; CHIPPING GUN (OVER 30 LBS.); CLARY POWER SPREADER; CONCRETE DUMPER/CHUTE OPERATOR; CONCRETE SAW OPERATOR; DRILL OPERATOR (HYDRAULIC, DIAMOND, AIARTRAC); FALLER AND BUCKER CHAIN SAW; GROUTMEN (PRESSURE) INCLUDING POST TENSION BEAMS; HAZARDOUS WASTE WORKER (LEVEL B: USES SAME RESPIRATOR

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

PROTECTION AS LEVEL A. A SUPPLIED AIR LINE IS PROVIDED IN CONJUNCTION WITH A CHEMICAL ""SPLASH SUIT""); JACKHAMMER; LASERBEAM OPERATOR; MANHOLE BUILDER-MUDMAN; NOZZLEMAN (CONCRETE PUMP, GREEN CUTTER WHEN USING COMBINATION OF HIGH PRESSURE AIR AND WATER ON CONCRETE AND ROCK, SANDBLAST, GUNITE, SHOTCRETE, WATER BLASTER, VACUUM BLASTER); PAVEMENT BREAKER; PIPE LAYER AND CAULKER; PIPE POT TENDER; PIPE RELINER (NOT INSERT TYPE); PIPE WRAPPER; POWER JACKS; RAILROAD SPIKE PULLER-POWER; RAKER-ASPHALT; RIVET BUSTER; RODDER; SLOPER (OVER 20 FT); SPREADER (CONCRETE); TAMPER AND SIMILAR ELECTRIC, AIR AND GLAS OPERATED TOOL; TIMBER PERSON-SEWER (LAGGER SHORER AND CRIBBER); TRACK LINER POWER; TUGGER OPERATOR; VIBRATOR; WELL POINT LABORER
(CLALLAM, GRAYS HARBOR, JEFFERSON, KITSAP, LEWIS, MASON, PACIFIC (EXCLUDING SOUTHWEST), PIERCE, AND THURSTON COUNTIES)
BASE POINTS: BELLINGHAM, MT. VERNON, EVERETT, SEATTLE, KENT, TACOMA, OLYMPIA, CENTRALIA, ABERDEEN, SHELTON, PT. TOWNSEND, PT. ANGELES, AND BREMERTON ZONE 1 - PROJECTS WITHIN 25 RADIUS MILES OF THE RESPECTIVE CITY HALL ZONE 2 - MORE THAN 25 BUT LESS THAN 45 RADIUS MILES FROM THE RESPECTIVE CITY HALL ZONE 3 - MORE THAN 45 RADIUS MILES FROM THE RESPECTIVE CITY HALL ZONE DIFFERENTIAL (ADD TO ZONE 1 RATES): ZONE 2 - $1.00 ZONE 3 - $1.30 BASE POINTS: CHELAN, SUNNYSIDE, WENATCHEE, AND YAKIMA ZONE 1 - PROJECTS WITHIN 25 RADIUS MILES OF THE RESPECTIVE CITY HALL ZONE 2 - MORE THAN 25 RADIUS MILES FROM THE RESPECTIVE CITY HALL ZONE DIFFERENTIAL (ADD TO ZONE 1 RATES): ZONE 2 - $2.25.....$ 51.52 16.99
LABORER: ZONE 1: GROUP 5 CAISSON WORKER; MINER; MORTARMAN AND HODCARRIER; GRADE CHECKER AND TRANSIT PERSON; HIGH SCALER; POWDERMAN; RE-TIMBERMAN; HAZARDOUS WASTE WORKER (LEVEL A: UTILIZES A FULLY ENCAPSULATED SUIT WITH A SELF-CONTAINED BREATHING APPARATUS OR A SUPPLIED AIR LINE).
(CLALLAM, GRAYS HARBOR, JEFFERSON, KITSAP, LEWIS, MASON, PACIFIC (EXCLUDING SOUTHWEST), PIERCE, AND THURSTON COUNTIES)
BASE POINTS: BELLINGHAM, MT. VERNON, EVERETT, SEATTLE, KENT, TACOMA, OLYMPIA, CENTRALIA, ABERDEEN, SHELTON, PT. TOWNSEND, PT. ANGELES, AND BREMERTON ZONE 1 - PROJECTS WITHIN 25 RADIUS MILES OF THE RESPECTIVE CITY HALL ZONE 2 - MORE THAN 25 BUT LESS THAN 45 RADIUS MILES FROM THE RESPECTIVE CITY HALL ZONE 3 - MORE THAN 45 RADIUS MILES FROM THE RESPECTIVE CITY HALL ZONE DIFFERENTIAL (ADD TO ZONE 1 RATES): ZONE 2 - $1.00 ZONE 3 - $1.30 BASE POINTS: CHELAN, SUNNYSIDE, WENATCHEE, AND YAKIMA ZONE 1 - PROJECTS WITHIN 25 RADIUS MILES OF THE RESPECTIVE CITY HALL ZONE 2 - MORE THAN 25 RADIUS MILES FROM THE RESPECTIVE CITY HALL ZONE DIFFERENTIAL (ADD TO ZONE 1

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

RATES): ZONE 2 - $2.25.....$ 52.31 17.01

LABO0292-008 06/01/2025
Rates Fringes
LABORER: ZONE 1: GROUP 1 LANDSCAPING AND PLANTING; WATCHMAN; WINDOW WASHER/CLEANER (DETAIL CLEAN-UP, SUCH AS BUT NOT LIMITED TO CLEANING FLOORS, CEILINGS, WALLS, WINDOWS, ETC., PRIOR TO FINAL ACCEPTANCE BY THE OWNER)
(ISLAND, SAN JUAN, SKAGIT, SNOHOMISH, AND WHATCOM COUNTIES)
BASE POINTS: BELLINGHAM, MT. VERNON, EVERETT, SEATTLE, KENT, TACOMA, OLYMPIA, CENTRALIA, ABERDEEN, SHELTON, PT. TOWNSEND, PT. ANGELES, AND BREMERTON ZONE 1 - PROJECTS WITHIN 25 RADIUS MILES OF THE RESPECTIVE CITY HALL ZONE 2 - MORE THAN 25 BUT LESS THAN 45 RADIUS MILES FROM THE RESPECTIVE CITY HALL ZONE 3 - MORE THAN 45 RADIUS MILES FROM THE RESPECTIVE CITY HALL ZONE DIFFERENTIAL (ADD TO ZONE 1 RATES): ZONE 2 - $1.00 ZONE 3 - $1.30 BASE POINTS: CHELAN, SUNNYSIDE, WENATCHEE, AND YAKIMA ZONE 1 - PROJECTS WITHIN 25 RADIUS MILES OF THE RESPECTIVE CITY HALL ZONE 2 - MORE THAN 25 RADIUS MILES FROM THE RESPECTIVE CITY HALL ZONE DIFFERENTIAL (ADD TO ZONE 1 RATES): ZONE 2 - $2.25.....$ 36.07 15.79
LABORER: ZONE 1: GROUP 2 BATCH WEIGHMAN; CRUSHER FEEDER; FENCE LABORER; FLAGMAN; PILOT CAR
(ISLAND, SAN JUAN, SKAGIT, SNOHOMISH, AND WHATCOM COUNTIES)
BASE POINTS: BELLINGHAM, MT. VERNON, EVERETT, SEATTLE, KENT, TACOMA, OLYMPIA, CENTRALIA, ABERDEEN, SHELTON, PT. TOWNSEND, PT. ANGELES, AND BREMERTON ZONE 1 - PROJECTS WITHIN 25 RADIUS MILES OF THE RESPECTIVE CITY HALL ZONE 2 - MORE THAN 25 BUT LESS THAN 45 RADIUS MILES FROM THE RESPECTIVE CITY HALL ZONE 3 - MORE THAN 45 RADIUS MILES FROM THE RESPECTIVE CITY HALL ZONE DIFFERENTIAL (ADD TO ZONE 1 RATES): ZONE 2 - $1.00 ZONE 3 - $1.30 BASE POINTS: CHELAN, SUNNYSIDE, WENATCHEE, AND YAKIMA ZONE 1 - PROJECTS WITHIN 25 RADIUS MILES OF THE RESPECTIVE CITY HALL ZONE 2 - MORE THAN 25 RADIUS MILES FROM THE RESPECTIVE CITY HALL ZONE DIFFERENTIAL (ADD TO ZONE 1 RATES): ZONE 2 - $2.25.$ 40.88 16.72
LABORER: ZONE 1: GROUP 3 GENERAL LABORER; AIR, GAS, OR ELECTRIC VIBRATING SCREED; ASBESTOS ABATEMENT LABORER; BALLAST REGULATOR MACHINE; BRUSH CUTTER; BRUSH HOG FEEDER; BURNER; CARPENTER TENDER; CEMENT FINISHER TENDER; CHANGE HOUSE OR DRY SHACK; CHIPPING GUN (UNDER 30 LBS.); CHOKER SETTER; CHUCK TENDER; CLEAN-UP LABORER; CONCRETE FORM STRIPPER; CURING LABORER; DEMOLITION (WRECKING AND MOVING INCLUDING CHARRED MATERIAL); DITCH DIGGER; DUMP PERSON; FINE GRADERS; FIREWATCH; FORM SETTER;

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

GABIAN BASKET BUILDERS; GROUT MACHINE TENDER; GRINDERS; GUARDRAIL ERECTOR; HAZARDOUS WASTE WORKER (LEVEL C: USES A CHEMICAL ""SPLASH SUIT"" AND AIR PURIFYING RESPIRATOR); MAINTENANCE PERSON; MATERIAL YARD PERSON; POT TENDER; RIP RAP PERSON; RIGGERS; SCALE PERSON; SLOPER SPRAYER; SIGNAL PERSON; STOCK PILER; STAKE HOPPER; TOOLROOM MAN (AT JOB SITE); TOPPER-TAILER; TRACK LABORER; TRUCK SPOTTER; VINYL SEAMER

(ISLAND, SAN JUAN, SKAGIT, SNOHOMISH, AND WHATCOM COUNTIES)

BASE POINTS: BELLINGHAM, MT. VERNON, EVERETT, SEATTLE, KENT, TACOMA, OLYMPIA, CENTRALIA, ABERDEEN, SHELTON, PT. TOWNSEND, PT. ANGELES, AND BREMERTON ZONE 1 - PROJECTS WITHIN 25 RADIUS MILES OF THE RESPECTIVE CITY HALL ZONE 2 - MORE THAN 25 BUT LESS THAN 45 RADIUS MILES FROM THE RESPECTIVE CITY HALL ZONE 3 - MORE THAN 45 RADIUS MILES FROM THE RESPECTIVE CITY HALL ZONE DIFFERENTIAL (ADD TO ZONE 1 RATES): ZONE 2 - $1.00 ZONE 3 - $1.30 BASE POINTS: CHELAN, SUNNYSIDE, WENATCHEE, AND YAKIMA ZONE 1 - PROJECTS WITHIN 25 RADIUS MILES OF THE RESPECTIVE CITY HALL ZONE 2 - MORE THAN 25 RADIUS MILES FROM THE RESPECTIVE CITY HALL ZONE DIFFERENTIAL (ADD TO ZONE 1 RATES): ZONE 2 - $2.25.....$ 50.38 16.96

LABORER: ZONE 1: GROUP 4 CEMENT DUMPER-PAVING; CHIPPING GUN (OVER 30 LBS.); CLARY POWER SPREADER; CONCRETE DUMPER/CHUTE OPERATOR; CONCRETE SAW OPERATOR; DRILL OPERATOR (HYDRAULIC, DIAMOND, AIARTRAC); FALLER AND BUCKER CHAIN SAW; GRADE CHECKER AND TRANSIT PERSON; GROUTMEN (PRESSURE) INCLUDING POST TENSION BEAMS; HAZARDOUS WASTE WORKER (LEVEL B: USES SAME RESPIRATOR PROTECTION AS LEVEL A. A SUPPLIED AIR LINE IS PROVIDED IN CONJUNCTION WITH A CHEMICAL ""SPLASH SUIT""); HIGH SCALER; JACKHAMMER; LASERBEAM OPERATOR; MANHOLE BUILDER-MUDMAN; NOZZLEMAN (CONCRETE PUMP, GREEN CUTTER WHEN USING COMBINATION OF HIGH PRESSURE AIR AND WATER ON CONCRETE AND ROCK, SANDBLAST, GUNITE, SHOTCRETE, WATER BLASTER, VACUUM BLASTER); PAVEMENT BREAKER; PIPE LAYER AND CAULKER; PIPE POT TENDER; PIPE RELINER (NOT INSERT TYPE); PIPE WRAPPER; POWER JACKS; RAILROAD SPIKE PULLER-POWER; RAKER-ASPHALT; RIVET BUSTER; RODDER; SLOPER (OVER 20 FT); SPREADER (CONCRETE); TAMPER AND SIMILAR ELECTRIC, AIR AND GLAS OPERATED TOOL; TIMBER PERSON-SEWER (LAGGER SHORER AND CRIBBER); TRACK LINER POWER; TUGGER OPERATOR; VIBRATOR; WELL POINT LABORER

(ISLAND, SAN JUAN, SKAGIT, SNOHOMISH, AND WHATCOM COUNTIES)

BASE POINTS: BELLINGHAM, MT. VERNON, EVERETT, SEATTLE, KENT, TACOMA, OLYMPIA, CENTRALIA, ABERDEEN, SHELTON, PT. TOWNSEND, PT. ANGELES, AND BREMERTON ZONE 1 - PROJECTS WITHIN 25 RADIUS MILES OF THE RESPECTIVE

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

CITY HALL ZONE 2 - MORE THAN 25 BUT LESS THAN 45
RADIUS MILES FROM THE RESPECTIVE CITY HALL ZONE 3
- MORE THAN 45 RADIUS MILES FROM THE RESPECTIVE
CITY HALL ZONE DIFFERENTIAL (ADD TO ZONE 1
RATES): ZONE 2 - $1.00 ZONE 3 - $1.30 BASE
POINTS: CHELAN, SUNNYSIDE, WENATCHEE, AND YAKIMA
ZONE 1 - PROJECTS WITHIN 25 RADIUS MILES OF THE
RESPECTIVE CITY HALL ZONE 2 - MORE THAN 25 RADIUS
MILES FROM THE RESPECTIVE CITY HALL ZONE
DIFFERENTIAL (ADD TO ZONE 1 RATES): ZONE 2 - $2.25.$ 51.52 16.99
LABORER: ZONE 1: GROUP 5 CAISSON WORKER; MINER;
MORTARMAN AND HODCARRIER; POWDERMAN; RE-TIMBERMAN;
HAZARDOUS WASTE WORKER (LEVEL A: UTILIZES A FULLY
ENCAPSULATED SUIT WITH A SELF-CONTAINED BREATHING
APPARATUS OR A SUPPLIED AIR LINE).
(ISLAND, SAN JUAN, SKAGIT,
SNOHOMISH, AND WHATCOM COUNTIES)
BASE POINTS: BELLINGHAM, MT. VERNON, EVERETT,
SEATTLE, KENT, TACOMA, OLYMPIA, CENTRALIA,
ABERDEEN, SHELTON, PT. TOWNSEND, PT. ANGELES, AND
BREMERTON ZONE 1 - PROJECTS WITHIN 25 RADIUS
MILES OF THE RESPECTIVE CITY HALL ZONE 2 - MORE
THAN 25 BUT LESS THAN 45 RADIUS MILES FROM THE
RESPECTIVE CITY HALL ZONE 3 - MORE THAN 45 RADIUS
MILES FROM THE RESPECTIVE CITY HALL ZONE
DIFFERENTIAL (ADD TO ZONE 1 RATES): ZONE 2 - $1.00
ZONE 3 - $1.30 BASE POINTS: CHELAN, SUNNYSIDE,
WENATCHEE, AND YAKIMA ZONE 1 - PROJECTS WITHIN
25 RADIUS MILES OF THE RESPECTIVE CITY HALL ZONE
2 - MORE THAN 25 RADIUS MILES FROM THE RESPECTIVE
CITY HALL ZONE DIFFERENTIAL (ADD TO ZONE 1
RATES): ZONE 2 - $2.25.....$ 52.31 17.01

LABO0335-022 06/01/2025

Rates	Fringes
LABORER: GROUP 1 LANDSCAPING, AND/OR PLANTING LABORERS (CLARK, COWLITZ, KLICKITAT, PACIFIC (SOUTH OF A STRAIGHT LINE MADE BY EXTENDING THE NORTH BOUNDARY LINE OF WAHKIAKUM COUNTY WEST TO THE PACIFIC OCEAN), SKAMANIA AND WAHKIAKUM COUNTIES).....$ 32.67	15.60
LABORER: GROUP 2 FENCE BUILDERS AND TRAFFIC FLAGGERS (CLARK, COWLITZ, KLICKITAT, PACIFIC (SOUTH OF A STRAIGHT LINE MADE BY EXTENDING THE NORTH BOUNDARY LINE OF WAHKIAKUM COUNTY WEST TO THE PACIFIC OCEAN), SKAMANIA AND WAHKIAKUM COUNTIES).....$ 40.56	15.60
LABORER: GROUP 3 ASPHALT PLANT LABORERS; ASPHALT SPREADERS; BATCH WEIGHMAN; BROOMERS; BRUSH BURNERS AND CUTTERS; CAR AND TRUCK LOADERS; CARPENTER TENDER; CHANGE-HOUSE MAN OR DRY SHACK MAN; CHOKER SETTER; CLEAN-UP LABORERS; CURING, CONCRETE; DEMOLITION, WRECKING AND MOVING LABORERS; DUMPERS, ROAD OILING CREW; DUMPMEN (FOR GRADING CREW);	

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

ELEVATOR FEEDERS; MEDIAN RAIL REFERENCE POST, GUIDE POST, RIGHT OF WAY MARKER; FINE GRADERS; FIRE WATCH; FORM STRIPPERS (NOT SWINGING STAGES); GENERAL LABORERS; HAZARDOUS WASTE WORKER; HOD CARRIER; LEVERMAN OR AGGREGATE SPREADER (FLAHERTY AND SIMILAR TYPES); LOADING SPOTTERS; MATERIAL YARD MAN (INCLUDING ELECTRICAL); PITTSBURGH CHIPPER OPERATOR OR SIMILAR TYPES; RAILROAD TRACK LABORERS; RIBBON SETTERS (INCLUDING STEEL FORMS); RIP RAP MAN (HAND PLACED); ROAD PUMP TENDER; SEWER LABOR; SIGNALMAN; SKIPMAN; SLOPERS; SPRAYMEN; STAKE CHASER; STOCKPILER; TIE BACK SHORING; TIMBER FALLER AND BUCKER (HAND LABOR); TOOLROOM MAN (AT JOB SITE); TUNNEL BULLGANG (ABOVE GROUND); WEIGHT-MAN-CRUSHER (AGGREGATE WHEN USED)

(CLARK, COWLITZ, KLICKITAT, PACIFIC (SOUTH OF A STRAIGHT LINE MADE BY EXTENDING THE NORTH BOUNDARY LINE OF WAHKIAKUM COUNTY WEST TO THE PACIFIC OCEAN), SKAMANIA AND WAHKIAKUM COUNTIES)....$ 44.06 15.60

LABORER: GROUP 4 APPLICATOR (INCLUDING POT POWER TENDER FOR SAME), APPLYING PROTECTIVE MATERIAL BY HAND OR NOZZLE ON UTILITY LINES OR STORAGE TANKS ON PROJECT; BRUSH CUTTERS (POWER SAW); BURNERS; CHOKER SPLICER; CLARY POWER SPREADER AND SIMILAR TYPES; CLEAN- UP NOZZLEMAN-GREEN CUTTER (CONCRETE, ROCK, ETC.); CONCRETE POWER BUGGYMAN; CONCRETE LABORER; CRUSHER FEEDER; DEMOLITION AND WRECKING CHARRED MATERIALS; GUNITE NOZZLEMAN TENDER; GUNITE OR SAND BLASTING POT TENDER; HANDLERS OR MIXERS OF ALL MATERIALS OF AN IRRITATING NATURE (INCLUDING CEMENT AND LIME); TOOL OPERATORS (INCLUDES BUT NOT LIMITED TO: DRY PACK MACHINE; JACKHAMMER; CHIPPING GUNS; PAVING BREAKERS); PIPE DOPING AND WRAPPING; POST HOLE DIGGER, AIR, GAS OR ELECTRIC; VIBRATING SCREED; TAMPERS; SAND BLASTING (WET); STAKE-SETTER; TUNNEL-MUCKERS, BRAKEMEN, CONCRETE CREW, BULLGANG (UNDERGROUND)

(CLARK, COWLITZ, KLICKITAT, PACIFIC (SOUTH OF A STRAIGHT LINE MADE BY EXTENDING THE NORTH BOUNDARY LINE OF WAHKIAKUM COUNTY WEST TO THE PACIFIC OCEAN), SKAMANIA AND WAHKIAKUM COUNTIES)....$ 44.90 15.60

LABORER: GROUP 5 ASBESTOS REMOVAL; BIT GRINDER; DRILL DOCTOR; DRILL OPERATORS, AIR TRACKS, CAT DRILLS, WAGON DRILLS, RUBBER-MOUNTED DRILLS, AND OTHER SIMILAR TYPES INCLUDING AT CRUSHER PLANTS; GUNITE NOZZLEMAN; HIGH SCALERS, STRIPPERS AND DRILLERS (COVERS WORK IN SWINGING STAGES, CHAIRS OR BELTS, UNDER EXTREME CONDITIONS UNUSUAL TO NORMAL DRILLING, BLASTING, BARRING-DOWN, OR SLOPING AND STRIPPING); MANHOLE BUILDER; POWDERMEN; CONCRETE SAW OPERATOR; PWDERMEN; POWER SAW OPERATORS (BUCKING AND FALLING); PUMPCRETE NOZZLEMEN; SAND BLASTING (DRY); SEWER TIMBERMAN; TRACK LINERS, ANCHOR MACHINES, BALLAST REGULATORS, MULTIPLE TAMPERS, POWER JACKS, TUGGER OPERATOR; TUNNEL-CHUCK TENDERS, NIPPERS AND TIMBERMEN; VIBRATOR; WATER

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

BLASTER
(CLARK, COWLITZ, KLICKITAT, PACIFIC (SOUTH OF A STRAIGHT LINE MADE BY EXTENDING THE NORTH BOUNDARY LINE OF WAHKIAKUM COUNTY WEST TO THE PACIFIC OCEAN), SKAMANIA AND WAHKIAKUM COUNTIES).....$ 45.54 15.60
LABORER: GROUP 6 ASPHALT RAKER; CONCRETE SAW OPERATOR (WALLS); CONCRETE NOZZELMAN; GRADE CHECKER; PIPELAYER; LASER BEAM (PIPELAYING)-APPLICABLE WHEN EMPLOYEE ASSIGNED TO MOVE, SET UP, ALIGN; LASER BEAM; TUNNEL MINERS; MOTORMAN-DINKY LOCOMOTIVE-TUNNEL; POWDERMAN-TUNNEL; SHIELD OPERATOR-TUNNEL
(CLARK, COWLITZ, KLICKITAT, PACIFIC (SOUTH OF A STRAIGHT LINE MADE BY EXTENDING THE NORTH BOUNDARY LINE OF WAHKIAKUM COUNTY WEST TO THE PACIFIC OCEAN), SKAMANIA AND WAHKIAKUM COUNTIES).....$ 46.08 15.60

LABO0348-003 06/01/2025

	Rates	Fringes
LABORER: ZONE 1: GROUP 1 LANDSCAPING AND PLANTING; WATCHMAN; WINDOW WASHER/CLEANER (DETAIL CLEAN-UP, SUCH AS BUT NOT LIMITED TO CLEANING FLOORS, CEILINGS, WALLS, WINDOWS, ETC., PRIOR TO FINAL ACCEPTANCE BY THE OWNER) (CHELAN, DOUGLAS (W OF 12TH MERIDIAN), KITTITAS, AND YAKIMA COUNTIES) BASE POINTS: BELLINGHAM, MT. VERNON, EVERETT, SEATTLE, KENT, TACOMA, OLYMPIA, CENTRALIA, ABERDEEN, SHELTON, PT. TOWNSEND, PT. ANGELES, AND BREMERTON ZONE 1 - PROJECTS WITHIN 25 RADIUS MILES OF THE RESPECTIVE CITY HALL ZONE 2 - MORE THAN 25 BUT LESS THAN 45 RADIUS MILES FROM THE RESPECTIVE CITY HALL ZONE 3 - MORE THAN 45 RADIUS MILES FROM THE RESPECTIVE CITY HALL ZONE DIFFERENTIAL (ADD TO ZONE 1 RATES): ZONE 2 - $1.00 ZONE 3 - $1.30. BASE POINTS: CHELAN, SUNNYSIDE, WENATCHEE, AND YAKIMA ZONE 1 - PROJECTS WITHIN 25 RADIUS MILES OF THE RESPECTIVE CITY HALL ZONE 2 - MORE THAN 25 RADIUS MILES FROM THE RESPECTIVE CITY HALL ZONE DIFFERENTIAL (ADD TO ZONE 1 RATES): ZONE 2 - $2.25.....	$ 31.19	16.48
LABORER: ZONE 1: GROUP 2 BATCH WEIGHMAN; CRUSHER FEEDER; FENCE LABORER; FLAGMAN; PILOT CAR (CHELAN, DOUGLAS (W OF 12TH MERIDIAN), KITTITAS, AND YAKIMA COUNTIES) BASE POINTS: BELLINGHAM, MT. VERNON, EVERETT, SEATTLE, KENT, TACOMA, OLYMPIA, CENTRALIA, ABERDEEN, SHELTON, PT. TOWNSEND, PT. ANGELES, AND BREMERTON ZONE 1 - PROJECTS WITHIN 25 RADIUS MILES OF THE RESPECTIVE CITY HALL ZONE 2 - MORE THAN 25 BUT LESS THAN 45 RADIUS MILES FROM THE RESPECTIVE CITY HALL ZONE 3 - MORE THAN 45 RADIUS MILES FROM THE RESPECTIVE		

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

CITY HALL ZONE DIFFERENTIAL (ADD TO ZONE 1 RATES): ZONE 2 - $1.00 ZONE 3 - $1.30. BASE POINTS: CHELAN, SUNNYSIDE, WENATCHEE, AND YAKIMA ZONE 1 - PROJECTS WITHIN 25 RADIUS MILES OF THE RESPECTIVE CITY HALL ZONE 2 - MORE THAN 25 RADIUS MILES FROM THE RESPECTIVE CITY HALL ZONE DIFFERENTIAL (ADD TO ZONE 1 RATES): ZONE 2 - $2.25.$ 35.34 16.59

LABORER: ZONE 1: GROUP 3 GENERAL LABORER; AIR, GAS, OR ELECTRIC VIBRATING SCREED; ASBESTOS ABATEMENT LABORER; BALLAST REGULATOR MACHINE; BRUSH CUTTER; BRUSH HOG FEEDER; BURNER; CARPENTER TENDER; CEMENT FINISHER TENDER; CHANGE HOUSE OR DRY SHACK; CHIPPING GUN (UNDER 30 LBS.); CHOKER SETTER; CHUCK TENDER; CLEAN-UP LABORER; CONCRETE FORM STRIPPER; CURING LABORER; DEMOLITION (WRECKING AND MOVING INCLUDING CHARRED MATERIAL); DITCH DIGGER; DUMP PERSON; FINE GRADERS; FIREWATCH; FORM SETTER; GABIAN BASKET BUILDERS; GROUT MACHINE TENDER; GRINDERS; GUARDRAIL ERECTOR; HAZARDOUS WASTE WORKER (LEVEL C: USES A CHEMICAL ""SPLASH SUIT"" AND AIR PURIFYING RESPIRATOR); MAINTENANCE PERSON; MATERIAL YARD PERSON; POT TENDER; RIP RAP PERSON; RIGGERS; SCALE PERSON; SLOPER SPRAYER; SIGNAL PERSON; STOCK PILER; STAKE HOPPER; TOOLROOM MAN (AT JOB SITE); TOPPER-TAILER; TRACK LABORER; TRUCK SPOTTER; VINYL SEAMER

(CHELAN,
DOUGLAS (W OF 12TH MERIDIAN), KITTITAS, AND YAKIMA COUNTIES)
BASE POINTS: BELLINGHAM, MT.
VERNON, EVERETT, SEATTLE, KENT, TACOMA, OLYMPIA, CENTRALIA, ABERDEEN, SHELTON, PT. TOWNSEND, PT. ANGELES, AND BREMERTON ZONE 1 - PROJECTS WITHIN 25 RADIUS MILES OF THE RESPECTIVE CITY HALL ZONE 2 - MORE THAN 25 BUT LESS THAN 45 RADIUS MILES FROM THE RESPECTIVE CITY HALL ZONE 3 - MORE THAN 45 RADIUS MILES FROM THE RESPECTIVE CITY HALL ZONE DIFFERENTIAL (ADD TO ZONE 1 RATES): ZONE 2 - $1.00 ZONE 3 - $1.30. BASE POINTS: CHELAN, SUNNYSIDE, WENATCHEE, AND YAKIMA ZONE 1 - PROJECTS WITHIN 25 RADIUS MILES OF THE RESPECTIVE CITY HALL ZONE 2 - MORE THAN 25 RADIUS MILES FROM THE RESPECTIVE CITY HALL ZONE DIFFERENTIAL (ADD TO ZONE 1 RATES): ZONE 2 - $2.25.....$ 38.40 16.66

LABORER: ZONE 1: GROUP 4 CEMENT DUMPER-PAVING; CHIPPING GUN (OVER 30 LBS.); CLARY POWER SPREADER; CONCRETE DUMPER/CHUTE OPERATOR; CONCRETE SAW OPERATOR; DRILL OPERATOR (HYDRAULIC, DIAMOND, AIARTRAC); FALLER AND BUCKER CHAIN SAW; GRADE CHECKER AND TRANSIT PERSON; GROUTMEN (PRESSURE) INCLUDING POST TENSION BEAMS; HAZARDOUS WASTE WORKER (LEVEL B: USES SAME RESPIRATOR PROTECTION AS LEVEL A. A SUPPLIED AIR LINE IS PROVIDED IN CONJUNCTION WITH A CHEMICAL ""SPLASH SUIT""); HIGH SCALER; JACKHAMMER; LASERBEAM OPERATOR; MANHOLE BUILDER-MUDMAN; NOZZLEMAN (CONCRETE PUMP, GREEN

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

CUTTER WHEN USING COMBINATION OF HIGH PRESSURE AIR AND WATER ON CONCRETE AND ROCK, SANDBLAST, GUNITE, SHOTCRETE, WATER BLASTER, VACUUM BLASTER); PAVEMENT BREAKER; PIPE LAYER AND CAULKER; PIPE POT TENDER; PIPE RELINER (NOT INSERT TYPE); PIPE WRAPPER; POWER JACKS; RAILROAD SPIKE PULLER-POWER; RAKER-ASPHALT; RIVET BUSTER; RODDER; SLOPER (OVER 20 FT); SPREADER (CONCRETE); TAMPER AND SIMILAR ELECTRIC, AIR AND GLAS OPERATED TOOL; TIMBER PERSON-SEWER (LAGGER SHORER AND CRIBBER); TRACK LINER POWER; TUGGER OPERATOR; VIBRATOR; WELL POINT LABORER
(CHELAN, DOUGLAS (W OF 12TH MERIDIAN), KITTITAS, AND YAKIMA COUNTIES)
BASE POINTS: BELLINGHAM, MT. VERNON, EVERETT, SEATTLE, KENT, TACOMA, OLYMPIA, CENTRALIA, ABERDEEN, SHELTON, PT. TOWNSEND, PT. ANGELES, AND BREMERTON ZONE 1 - PROJECTS WITHIN 25 RADIUS MILES OF THE RESPECTIVE CITY HALL ZONE 2 - MORE THAN 25 BUT LESS THAN 45 RADIUS MILES FROM THE RESPECTIVE CITY HALL ZONE 3 - MORE THAN 45 RADIUS MILES FROM THE RESPECTIVE CITY HALL ZONE DIFFERENTIAL (ADD TO ZONE 1 RATES): ZONE 2 - $1.00 ZONE 3 - $1.30. BASE POINTS: CHELAN, SUNNYSIDE, WENATCHEE, AND YAKIMA ZONE 1 - PROJECTS WITHIN 25 RADIUS MILES OF THE RESPECTIVE CITY HALL ZONE 2 - MORE THAN 25 RADIUS MILES FROM THE RESPECTIVE CITY HALL ZONE DIFFERENTIAL (ADD TO ZONE 1 RATES): ZONE 2 - $2.25.....$ 39.26 16.68

LABORER: ZONE 1: GROUP 5 CAISSON WORKER; MINER; MORTARMAN AND HODCARRIER; POWDERMAN; RE-TIMBERMAN; HAZARDOUS WASTE WORKER (LEVEL A: UTILIZES A FULLY ENCAPSULATED SUIT WITH A SELF-CONTAINED BREATHING APPARATUS OR A SUPPLIED AIR LINE).
(CHELAN, DOUGLAS (W OF 12TH MERIDIAN), KITTITAS, AND YAKIMA COUNTIES)
BASE POINTS: BELLINGHAM, MT. VERNON, EVERETT, SEATTLE, KENT, TACOMA, OLYMPIA, CENTRALIA, ABERDEEN, SHELTON, PT. TOWNSEND, PT. ANGELES, AND BREMERTON ZONE 1 - PROJECTS WITHIN 25 RADIUS MILES OF THE RESPECTIVE CITY HALL ZONE 2 - MORE THAN 25 BUT LESS THAN 45 RADIUS MILES FROM THE RESPECTIVE CITY HALL ZONE 3 - MORE THAN 45 RADIUS MILES FROM THE RESPECTIVE CITY HALL ZONE DIFFERENTIAL (ADD TO ZONE 1 RATES): ZONE 2 - $1.00 ZONE 3 - $1.30. BASE POINTS: CHELAN, SUNNYSIDE, WENATCHEE, AND YAKIMA ZONE 1 - PROJECTS WITHIN 25 RADIUS MILES OF THE RESPECTIVE CITY HALL ZONE 2 - MORE THAN 25 RADIUS MILES FROM THE RESPECTIVE CITY HALL ZONE DIFFERENTIAL (ADD TO ZONE 1 RATES): ZONE 2 - $2.25.....$ 39.89 16.70

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

PAIN0005-002 07/01/2025

	Rates	Fringes
PAINTERS: STRIPERS (STATEWIDE EXCEPT CLARK, COWLITZ, KLICKITAT, PACIFIC, SKAMANIA, AND WAHKIAKUM COUNTIES)	$ 41.80	20.85

PAIN0010-012 07/01/2025

	Rates	Fringes
PAINTER: BRUSH, ROLLER, SPRAY & SANDBLASTING (CLARK, COWLITZ, KLICKITAT, PACIFIC, SKAMANIA, AND WAHKIAKUM COUNTIES)	$ 39.94	16.68

PAIN0010-013 07/01/2025

	Rates	Fringes
PAINTERS: HIGHWAY & PARKING LOT STRIPER (CLARK, COWLITZ, KLICKITAT, PACIFIC, SKAMANIA AND WAHKIAKUM COUNTIES)	$ 41.19	17.09

PAIN0300-007 07/01/2025

	Rates	Fringes
PAINTER (CLALLAM, GRAYS HARBOR, ISLAND, JEFFERSON, KING, KITSAP, LEWIS, MASON, PIERCE, SAN JUAN, SKAGIT, SNOHOMISH, THURSTON, AND WHATCOM COUNTIES)..	$ 41.24	14.70

PAIN0427-005 07/01/2025

	Rates	Fringes
PAINTER (APPLICATION OF COLD TAR PRODUCTS, EPOXIES, POLYURETHANES, ACIDS, RADIATION RESISTANT MATERIAL, WATER, SANDBLASTING, OVER 30'/SWING STAGE WORK, BRUSH, ROLLER, STRIPING, STEAM-CLEANING, AND SPRAY). (ADAMS, ASOTIN; BENTON AND FRANKLIN (EXCEPT HANFORD SITE); CHELAN, COLUMBIA, DOUGLAS, FERRY, GARFIELD, GRANT, KITTITAS, LINCOLN, OKANOGAN, PEND OREILLE, SPOKANE, STEVENS, WALLA WALLA, WHITMAN, AND YAKIMA COUNTIES)	$ 36.26	17.01

PLAS0072-004 06/01/2025

	Rates	Fringes
CEMENT MASON/CONCRETE FINISHER (ADAMS, ASOTIN, BENTON, CHELAN, COLUMBIA, DOUGLAS, FERRY, FRANKLIN, GARFIELD, GRANT, KITTITAS, LINCOLN, OKANOGAN, PEND OREILLE, SPOKANE, STEVENS, WALLA WALLA, WHITMAN, AND YAKIMA COUNTIES) ZONE DIFFERENTIAL (ADD TO ZONE 1 RATE): ZONE 1- BASE RATE. ZONE 2 - $3.00 BASE POINTS: SPOKANE, PASCO, LEWISTON; WENATCHEE ZONE 1: 0 - 45 RADIUS MILES FROM THE MAIN POST OFFICE ZONE 2: OVER 45 RADIUS MILES FROM THE MAIN POST OFFICE	$ 40.89	18.64

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

PLAS0528-001 06/01/2024

	Rates	Fringes
CEMENT MASON: CEMENT MASON (CLALUM, COWLITZ, GRAYS HARBOR, ISLAND, JEFFERSON, KING, KITSAP, LEWIS, MASON, PACIFIC, PIERCE, SAN JUAN, SKAGIT, SNOHOMISH, THURSTON, WAHKIAKUM, AND WHATCOM COUNTIES)	$ 54.16	21.27
CEMENT MASON:COMPOSITION, TROWEL MACHINE, GRINDER, POWER TOOLS, GUNNITE NOZZLE (CLALUM, COWLITZ, GRAYS HARBOR, ISLAND, JEFFERSON, KING, KITSAP, LEWIS, MASON, PACIFIC, PIERCE, SAN JUAN, SKAGIT, SNOHOMISH, THURSTON, WAHKIAKUM, AND WHATCOM COUNTIES)	$ 54.66	21.27
CEMENT MASON: TROWELING MACHINE OPERATOR ON COMPOSITION (CLALUM, COWLITZ, GRAYS HARBOR, ISLAND, JEFFERSON, KING, KITSAP, LEWIS, MASON, PACIFIC, PIERCE, SAN JUAN, SKAGIT, SNOHOMISH, THURSTON, WAHKIAKUM, AND WHATCOM COUNTIES)	$ 54.66	21.27

PLAS0555-002 06/01/2025

	Rates	Fringes
CEMENT MASON: CEMENT MASONS (CLARK, KLICKITAT AND SKAMANIA COUNTIES) ZONE DIFFERENTIAL- ZONE 1: BASE RATE. ZONE 2 - $0.65 ZONE 3 - 1.15 ZONE 4 - 1.70 ZONE 5 - 3.00 BASE POINTS: BEND, CORVALLIS, EUGENE, MEDFORD, PORTLAND, SALEM, THE DALLES, VANCOUVER ZONE 1: PROJECTS WITHIN 30 MILES OF THE RESPECTIVE CITY HALL ZONE 2: MORE THAN 30 MILES BUT LESS THAN 40 MILES FROM THE RESPECTIVE CITY HALL. ZONE 3: MORE THAN 40 MILES BUT LESS THAN 50 MILES FROM THE RESPECTIVE CITY HALL. ZONE 4: MORE THAN 50 MILES BUT LESS THAN 80 MILES FROM THE RESPECTIVE CITY HALL. ZONE 5: MORE THAN 80 MILES FROM THE RESPECTIVE CITY HALL	$ 46.13	20.31
CEMENT MASON: CEMENT MASONS DOING BOTH COMPOSITION/POWER MACHINERY AND SUSPENDED/HANGING SCAFFOLD (CLARK, KLICKITAT AND SKAMANIA COUNTIES) ZONE DIFFERENTIAL- ZONE 1: BASE RATE. ZONE 2 - $0.65 ZONE 3 - 1.15 ZONE 4 - 1.70 ZONE 5 - 3.00 BASE POINTS: BEND, CORVALLIS, EUGENE, MEDFORD, PORTLAND, SALEM, THE DALLES, VANCOUVER ZONE 1: PROJECTS WITHIN 30 MILES OF THE RESPECTIVE CITY HALL ZONE 2: MORE THAN 30 MILES BUT LESS THAN 40 MILES FROM THE RESPECTIVE CITY HALL. ZONE 3: MORE THAN 40 MILES BUT LESS THAN 50 MILES FROM THE RESPECTIVE CITY HALL. ZONE 4: MORE THAN 50 MILES BUT LESS THAN 80 MILES FROM THE RESPECTIVE CITY HALL. ZONE 5: MORE THAN 80 MILES FROM THE RESPECTIVE CITY HALL	$ 48.05	20.31
CEMENT MASON: CEMENT MASONS ON SUSPENDED, SWINGING AND/OR HANGING SCAFFOLD (CLARK, KLICKITAT AND SKAMANIA COUNTIES) ZONE DIFFERENTIAL- ZONE 1: BASE RATE. ZONE 2 - $0.65 ZONE 3 - 1.15 ZONE 4 - 1.70 ZONE 5 - 3.00 BASE POINTS: BEND, CORVALLIS, EUGENE, MEDFORD, PORTLAND, SALEM, THE		

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

DALLES, VANCOUVER ZONE 1: PROJECTS WITHIN 30 MILES OF THE RESPECTIVE CITY HALL ZONE 2: MORE THAN 30 MILES BUT LESS THAN 40 MILES FROM THE RESPECTIVE CITY HALL. ZONE 3: MORE THAN 40 MILES BUT LESS THAN 50 MILES FROM THE RESPECTIVE CITY HALL. ZONE 4: MORE THAN 50 MILES BUT LESS THAN 80 MILES FROM THE RESPECTIVE CITY HALL. ZONE 5: MORE THAN 80 MILES FROM THE RESPECTIVE CITY HALL....$ 47.09 20.31

CEMENT MASON: COMPOSITION WORKERS AND POWER MACHINERY OPERATORS (CLARK, KLICKITAT AND SKAMANIA COUNTIES) ZONE DIFFERENTIAL- ZONE 1: BASE RATE. ZONE 2 -$0.65 ZONE 3 - 1.15 ZONE 4 - 1.70 ZONE 5 -3.00 BASE POINTS: BEND, CORVALLIS, EUGENE, MEDFORD, PORTLAND, SALEM, THE DALLES, VANCOUVER ZONE 1: PROJECTS WITHIN 30 MILES OF THE RESPECTIVE CITY HALL ZONE 2: MORE THAN 30 MILES BUT LESS THAN 40 MILES FROM THE RESPECTIVE CITY HALL. ZONE 3: MORE THAN 40 MILES BUT LESS THAN 50 MILES FROM THE RESPECTIVE CITY HALL. ZONE 4: MORE THAN 50 MILES BUT LESS THAN 80 MILES FROM THE RESPECTIVE CITY HALL. ZONE 5: MORE THAN 80 MILES FROM THE RESPECTIVE CITY HALL.....$ 47.09 20.31

TEAM0037-002 06/01/2024

Rates	Fringes

TRUCK DRIVER: GROUP 1- A FRAME OR HYDRA LIFRT TRUCK W/LOAD BEARING SURFACE; ARTICULATED DUMP TRUCK; BATTERY REBUILDERS; BUS OR MANHAUL DRIVER; CONCRETE BUGGIES (POWER OPERATED); CONCRETE PUMP TRUCK; DUMP TRUCKS, SIDE, END AND BOTTOM DUMPS, INCLUDING SEMI TRUCKS AND TRAINS OR COMBINATIONS THERE OF: UP TO AND INCLUDING 10 CU. YDS.; LIFT JITNEYS, FORK LIFTS (ALL SIZES IN LOADING, UNLOADING AND TRANSPORTING MATERIAL ON JOB SITE); LOADER AND/OR LEVERMAN ON CONCRETE DRY BATCH PLANT (MANUALLY OPERATED); PILOT CAR; PICKUP TRUCK; SOLO FLAT BED AND MISC. BODY TRUCKS, 0-10 TONS; TRUCK TENDER; TRUCK MECHANIC TENDER; WATER WAGONS (RATED CAPACITY) UP TO 3,000 GALLONS; TRANSIT MIX AND WET OR DRY MIX - 5 CU. YDS. AND UNDER; LUBRICATION MAN, FUEL TRUCK DRIVER, TIREMAN, WASH RACK, STEAM CLEANER OR COMBINATIONS; TEAM DRIVER; SLURRY TRUCK DRIVER OR LEVERMAN; TIREMAN
(CLARK, COWLITZ,
KLICKITAT, PACIFIC (SOUTH OF A STRAIGHT LINE MADE BY EXTENDING THE NORTH BOUNDARY LINE OF WAHKIAKUM COUNTY WEST TO THE PACIFIC OCEAN), SKAMANIA, AND WAHKIAKUM COUNTIES)
ZONE
DIFFERENTIAL- ZONE 1: BASE RATE. ZONE 2 - $0.65 ZONE 3 -$1.15 ZONE 4 - $1.70 ZONE 5 - $2.75. BASE POINTS: ASTORIA, THE DALLES, LONGVIEW AND VANCOUVER. ZONE 1: PROJECTS WITHIN 30 MILES OF THE RESPECTIVE CITY HALL. ZONE 2: MORE THAN 30 MILES BUT LESS THAN 40 MILES FROM THE RESPECTIVE

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

CITY HALL. ZONE 3: MORE THAN 40 MILES BUT LESS THAN 50 MILES FROM THE RESPECTIVE CITY HALL. ZONE 4: MORE THAN 50 MILES BUT LESS THAN 80 MILES FROM THE RESPECTIVE CITY HALL. ZONE 5: MORE THAN 80 MILES FROM THE RESPECTIVE CITY HALL.....$ 33.09 17.63

TRUCK DRIVER: GROUP 2- BOOM TRUCK/HYDRA-LIFT OR RETRACTING CRANE; CHALLENGER; DUMPSTERS OR SIMILAR EQUIPMENT ALL SIZES; DUMP TRUCKS/ARTICULATED DUMPS 6 CU TO 10 CU.; FLAHERTY SPREADER DRIVER OR LEVERMAN; LOWBED EQUIPMENT, FLAT BED SEMI-TRAILER OR DOUBLES TRANSPORTING EQUIPMENT OR WET OR DRY MATERIALS; LUMBER CARRIER, DRIVER-STRADDLE CARRIER (USED IN LOADING, UNLOADING AND TRANSPORTING OF MATERIALS ON JOB SITE); OIL DISTRIBUTOR DRIVER OR LEVERMAN; TRANSIT MIX AND WET OR DRY MIX TRCUKS: OVER 5 CU. YDS. AND INCLUDING 7 CU. YDS.; VACUUM TRUCKS; WATER TRUCK/WAGONS (RATED CAPACITY) OVER 3,000 TO 5,000 GALLONS

(CLARK, COWLITZ, KLICKITAT, PACIFIC (SOUTH OF A STRAIGHT LINE MADE BY EXTENDING THE NORTH BOUNDARY LINE OF WAHKIAKUM COUNTY WEST TO THE PACIFIC OCEAN), SKAMANIA, AND WAHKIAKUM COUNTIES)

ZONE DIFFERENTIAL- ZONE 1: BASE RATE. ZONE 2 - $0.65 ZONE 3 - $1.15 ZONE 4 - $1.70 ZONE 5 - $2.75. BASE POINTS: ASTORIA, THE DALLES, LONGVIEW AND VANCOUVER. ZONE 1: PROJECTS WITHIN 30 MILES OF THE RESPECTIVE CITY HALL. ZONE 2: MORE THAN 30 MILES BUT LESS THAN 40 MILES FROM THE RESPECTIVE CITY HALL. ZONE 3: MORE THAN 40 MILES BUT LESS THAN 50 MILES FROM THE RESPECTIVE CITY HALL. ZONE 4: MORE THAN 50 MILES BUT LESS THAN 80 MILES FROM THE RESPECTIVE CITY HALL. ZONE 5: MORE THAN 80 MILES FROM THE RESPECTIVE CITY HALL....$ 33.24 17.63

TRUCK DRIVER: GROUP 3- AMMONIA NITRATE DISTRIBUTOR DRIVER; DUMP TRUCKS, SIDE, END AND BOTTOM DUMPS, INCLUDING SEMI TRUCKS AND TRAINS OR COMBINATIONS THEREOF: OVER 10 CU. YDS. AND INCLUDING 30 CU. YDS. INCLUDES ARTICULATED DUMP TRUCKS; SELF-PROPELLED STREET SWEEPER; TRANSIT MIX AND WET OR DRY MIX TRUCK: OVER 7 CU YDS. AND INCLUDING 11 CU YDS.; TRUCK MECHANIC-WELDER-BODY REPAIRMAN; UTILITY AND CLEAN-UP TRUCK; WATER WAGONS (RATED CAPACITY) OVER 5,000 TO 10,000 GALLONS

(CLARK, COWLITZ, KLICKITAT, PACIFIC (SOUTH OF A STRAIGHT LINE MADE BY EXTENDING THE NORTH BOUNDARY LINE OF WAHKIAKUM COUNTY WEST TO THE PACIFIC OCEAN), SKAMANIA, AND WAHKIAKUM COUNTIES)

ZONE DIFFERENTIAL- ZONE 1: BASE RATE. ZONE 2 - $0.65 ZONE 3 - $1.15 ZONE 4 - $1.70 ZONE 5 - $2.75. BASE POINTS: ASTORIA, THE DALLES, LONGVIEW AND VANCOUVER. ZONE 1: PROJECTS WITHIN 30 MILES OF THE RESPECTIVE CITY HALL. ZONE 2: MORE THAN 30 MILES BUT LESS THAN 40 MILES FROM THE RESPECTIVE CITY HALL. ZONE 3: MORE THAN 40 MILES BUT LESS

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

THAN 50 MILES FROM THE RESPECTIVE CITY HALL. ZONE 4: MORE THAN 50 MILES BUT LESS THAN 80 MILES FROM THE RESPECTIVE CITY HALL. ZONE 5: MORE THAN 80 MILES FROM THE RESPECTIVE CITY HALL.....$ 33.40 17.63

TRUCK DRIVER: GROUP 4- ASPHALT BURNER; DUMP TRUCKS, SIDE, END AND BOTTOM CUMPS, INCLUDING SEMI-TRUCKS AND TRAINS OR COMBINATIONS THEREOF: OVER 30 CU. YDS. AND INCLUDING 50 CU. YDS. INCLUDES ARTICULATED DUMP TRUCKS; FIRE GUARD; TRANSIT MIX AND WET OR DRY MIX TRUCKS, OVER 11 CU. YDS. AND INCLUDING 15 CU. YDS.; WATER WAGON (RATED CAPACITY) OVER 10,000 GALLONS TO 15,000 GALLONS

(CLARK, COWLITZ, KLICKITAT, PACIFIC (SOUTH OF A STRAIGHT LINE MADE BY EXTENDING THE NORTH BOUNDARY LINE OF WAHKIAKUM COUNTY WEST TO THE PACIFIC OCEAN), SKAMANIA, AND WAHKIAKUM COUNTIES)

ZONE DIFFERENTIAL- ZONE 1: BASE RATE. ZONE 2 - $0.65 ZONE 3 - $1.15 ZONE 4 - $1.70 ZONE 5 - $2.75. BASE POINTS: ASTORIA, THE DALLES, LONGVIEW AND VANCOUVER. ZONE 1: PROJECTS WITHIN 30 MILES OF THE RESPECTIVE CITY HALL. ZONE 2: MORE THAN 30 MILES BUT LESS THAN 40 MILES FROM THE RESPECTIVE CITY HALL. ZONE 3: MORE THAN 40 MILES BUT LESS THAN 50 MILES FROM THE RESPECTIVE CITY HALL. ZONE 4: MORE THAN 50 MILES BUT LESS THAN 80 MILES FROM THE RESPECTIVE CITY HALL. ZONE 5: MORE THAN 80 MILES FROM THE RESPECTIVE CITY HALL.....$ 33.72 17.63

TRUCK DRIVER: GROUP 5- COMPOSITE CREWMAN; DUMP TRUCKS, SIDE, END AND BOTTOM DUMPS, INCLUDING SEMI TRUCKS AND TRAINS OR COMBINATIONS THEREOF: OVER 50 CU. YDS. AND INCLUDING 60 CU. YDS. INCLUDES ARTICULATED DUMP TRUCKS

(CLARK, COWLITZ, KLICKITAT, PACIFIC (SOUTH OF A STRAIGHT LINE MADE BY EXTENDING THE NORTH BOUNDARY LINE OF WAHKIAKUM COUNTY WEST TO THE PACIFIC OCEAN), SKAMANIA, AND WAHKIAKUM COUNTIES)

ZONE DIFFERENTIAL- ZONE 1: BASE RATE. ZONE 2 - $0.65 ZONE 3 - $1.15 ZONE 4 - $1.70 ZONE 5 - $2.75. BASE POINTS: ASTORIA, THE DALLES, LONGVIEW AND VANCOUVER. ZONE 1: PROJECTS WITHIN 30 MILES OF THE RESPECTIVE CITY HALL. ZONE 2: MORE THAN 30 MILES BUT LESS THAN 40 MILES FROM THE RESPECTIVE CITY HALL. ZONE 3: MORE THAN 40 MILES BUT LESS THAN 50 MILES FROM THE RESPECTIVE CITY HALL. ZONE 4: MORE THAN 50 MILES BUT LESS THAN 80 MILES FROM THE RESPECTIVE CITY HALL. ZONE 5: MORE THAN 80 MILES FROM THE RESPECTIVE CITY HALL.....$ 33.97 17.63

TRUCK DRIVER:GROUP 6- BULK CEMENT SPREADER W/O AUGER; DRY PRE-BATCH CONCRETE MIX TRUCKS; DUMP TRUCKS, SIDE, END AND BOTTOM DUMPS, INCLUDING SEMI TRUCKS AND TRAINS OF COMBINATIONS THEREOF: OVER 60 CU. YDS. AND INCLUDING 80 CU. YDS., AND INCLUDES

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

ARTICULATED DUMP TRUCKS; SKID TRUCK
(CLARK,
COWLITZ, KLICKITAT, PACIFIC (SOUTH OF A STRAIGHT
LINE MADE BY EXTENDING THE NORTH BOUNDARY LINE OF
WAHKIAKUM COUNTY WEST TO THE PACIFIC OCEAN),
SKAMANIA, AND WAHKIAKUM COUNTIES)
ZONE DIFFERENTIAL- ZONE 1: BASE RATE. ZONE 2 -
$0.65 ZONE 3 - $1.15 ZONE 4 - $1.70 ZONE 5 -
$2.75. BASE POINTS: ASTORIA, THE DALLES, LONGVIEW
AND VANCOUVER. ZONE 1: PROJECTS WITHIN 30 MILES
OF THE RESPECTIVE CITY HALL. ZONE 2: MORE THAN
30 MILES BUT LESS THAN 40 MILES FROM THE RESPECTIVE
CITY HALL. ZONE 3: MORE THAN 40 MILES BUT LESS
THAN 50 MILES FROM THE RESPECTIVE CITY HALL. ZONE
4: MORE THAN 50 MILES BUT LESS THAN 80 MILES FROM
THE RESPECTIVE CITY HALL. ZONE 5: MORE THAN 80
MILES FROM THE RESPECTIVE CITY HALL.....$ 34.18 17.63
TRUCK DRIVER: GROUP 7- DUMP TRUCKS, SIDE, END AND
BOTTOM DUMPS, INCLUDING SEMI TRUCKS AND TRAINS OR
COMBINATIONS THEREOF: OVER 80 CU. YDS. AND
INCLUDING 100 CU. YDS., INCLUDES ARTICULATED DUMP
TRUCKS; INDUSTRIAL LIFT TRUCK (MECHANICAL TAILGATE)
(CLARK, COWLITZ, KLICKITAT, PACIFIC (SOUTH
OF A STRAIGHT LINE MADE BY EXTENDING THE NORTH
BOUNDARY LINE OF WAHKIAKUM COUNTY WEST TO THE
PACIFIC OCEAN), SKAMANIA, AND WAHKIAKUM COUNTIES)
ZONE DIFFERENTIAL- ZONE 1: BASE
RATE. ZONE 2 - $0.65 ZONE 3 - $1.15 ZONE 4 -
$1.70 ZONE 5 - $2.75. BASE POINTS: ASTORIA, THE
DALLES, LONGVIEW AND VANCOUVER. ZONE 1:
PROJECTS WITHIN 30 MILES OF THE RESPECTIVE CITY
HALL. ZONE 2: MORE THAN 30 MILES BUT LESS THAN
40 MILES FROM THE RESPECTIVE CITY HALL. ZONE 3:
MORE THAN 40 MILES BUT LESS THAN 50 MILES FROM THE
RESPECTIVE CITY HALL. ZONE 4: MORE THAN 50 MILES
BUT LESS THAN 80 MILES FROM THE RESPECTIVE CITY
HALL. ZONE 5: MORE THAN 80 MILES FROM THE
RESPECTIVE CITY HALL.....$ 34.42 17.63

TEAM0174-001 06/01/2025

Rates Fringes

TRUCK DRIVER: GROUP 1- ""A-FRAME OR HYDRALIFT""
TRUCKS AND BOOM TRUCKS OR SIMILAR EQUIPMENT WHEN
""A"" FRAME OR ""HYDRALIFT"" AND BOOM TRUCK OR SIMILAR
EQUIPMENT IS USED; BUGGYMOBILE; BULK CEMENT TANKER;
DUMPSTERS AND SIMILAR EQUIPMENT, TOURNOROCKERS,
TOURNOWAGON, TOURNOTRAILER, CAT DW SERIES, TERRA
COBRA, LE TOURNEAU, WESTINGHOUSE, ATHYE WAGON,
EUCLID TWO AND FOUR-WHEELED POWER TRACTOR WITH
TRAILER AND SIMILAR TOP-LOADED EQUIPMENT
TRANSPORTING MATERIAL: DUMP TRUCKS, SIDE, END AND
BOTTOM DUMP, INCLUDING SEMI-TRUCKS AND TRAINS OR
COMBINATIONS THEREOF WITH 16 YARDS TO 30 YARDS
CAPACITY: OVER 30 YARDS $.15 PER HOUR ADDITIONAL
FOR EACH 10 YARD INCREMENT; EXPLOSIVE TRUCK (FIELD

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

MIX) AND SIMILAR EQUIPMENT; HYSTER OPERATORS (HANDLING BULK LOOSE AGGREGATES); LOWBED AND HEAVY DUTY TRAILER; ROAD OIL DISTRIBUTOR DRIVER; SPREADER, FLAHERTY TRANSIT MIX USED EXCLUSIVELY IN HEAVY CONSTRUCTION; WATER WAGON AND TANK TRUCK-3,000 GALLONS AND OVER CAPACITY (HAZMAT PROJECTS ANYONE WORKING ON A HAZMAT JOB, WHERE HAZMAT CERTIFICATION IS REQUIRED, SHALL BE COMPENSATED AS A PREMIUM, IN ADDITION TO THE CLASSIFICATION WORKING IN AS FOLLOWS: LEVEL C: +$0.25 PER HOUR - THIS LEVEL USES AN AIR PURIFYING RESPIRATOR OR ADDITIONAL PROTECTIVE CLOTHING. LEVEL B: +$0.50 PER HOUR - USES SAME RESPIRATOR PROTECTION AS LEVEL A. SUPPLIED AIR LINE IS PROVIDED IN CONJUNCTION WITH A CHEMICAL ""SPLASH SUIT."" LEVEL A: +$0.75 PER HOUR - THIS LEVEL UTILIZES A FULLY- ENCAPSULATED SUIT WITH A SELF-CONTAINED BREATHING APPARATUS OR A SUPPLIED AIR LINE.)

(CLALLAM, GRAYS HARBOR, ISLAND, JEFFERSON, KING, KITSAP, LEWIS, MASON, PACIFIC (NORTH OF A STRAIGHT LINE MADE BY EXTENDING THE NORTH BOUNDARY LINE OF WAHKIAKUM COUNTY WEST TO THE PACIFIC OCEAN), PIERCE, SAN JUAN, SKAGIT, SNOHOMISH, THURSTON AND WHATCOM COUNTIES)

ZONE A: (LESS THAN 25 MILES FROM CENTER OF LISTED CITIES*). BASE RATE. ZONE B: (25-45 MILES FROM CENTER OF LISTED CITIES*): $0.70. ZONE C (OVER 45 MILES FROM CENTR OF LISTED CITIES*): $1.00. *ZONE PAY WILL BE CALCULATED FROM THE CITY CENTER OF THE FOLLOWING LISTED CITIES: BELLINGHAM, CENTRALIA, RAYMOND, OLYMPIA EVERETT, SHELTON, ANACORTES, BELLEVUE, SEATTLE, PORT ANGELES, MT. VERNON, KENT, TACOMA, PORT TOWNSEND, ABERDEEN, BREMERTON. .....$ 55.43 27.52

TRUCK DRIVER: GROUP 2- BULLLIFTS, OR SIMILAR EQUIPMENT USED IN LOADING OR UNLOADING TRUCKS, TRANSPORTING MATERIALS ON JOB SITE; DUMPSTERS, AND SIMILAR EQUIPMENT, TOURNOROCKERS, TOURNOWAGON, TURNOTRAILER, CAT. D.W. SERIES, TERRA COBRA, LE TOURNEAU, WESTINGHOUSE, ATHYE WAGON, EUCLID TWO AND FOUR-WHEELED POWER TRACTOR WITH TRAILER AND SIMILAR TOP-LOADED EQUIPMENT TRANSPORTING MATERIAL: DUMP TRUCKS, SIDE, END AND BOTTOM DUMP, INCLUDING SEMI-TRUCKS AND TRAINS OR COMBINATIONS THEREOF WITH LESS THAN 16 YARDS CAPACITY; FLATBED (DUAL REAR AXLE); GREASE TRUCK, FUEL TRUCK, GREASER, BATTERY SERVICE MAN AND/OR TIRE SERVICE MAN; LEVERMAN AND LOADER AT BUNKERS AND BATCH PLANTS; OIL TANK TRANSPORT; SCISSOR TRUCK; SLURRY TRUCK; SNO-GO AND SIMILAR EQUIPMENT; SWAMPERS; STRADDLER CARRIER (ROSS, HYSTER) AND SIMILAR EQUIPMENT; TEAM DRIVER; TRACTOR (SMALL, RUBBER-TIRED)(WHEN USED WITHIN TEAMSTER JURISDICTION); VACUUM TRUCK; WATER WAGON AND TANK TRUCKS-LESS THAN 3,000 GALLONS CAPACITY; WINCH TRUCK; WRECKER, TOW TRUCK AND SIMILAR

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

EQUIPMENT
(HAZMAT PROJECTS ANYONE WORKING ON A HAZMAT JOB, WHERE HAZMAT CERTIFICATION IS REQUIRED, SHALL BE COMPENSATED AS A PREMIUM, IN ADDITION TO THE CLASSIFICATION WORKING IN AS FOLLOWS: LEVEL C: +$0.25 PER HOUR - THIS LEVEL USES AN AIR PURIFYING RESPIRATOR OR ADDITIONAL PROTECTIVE CLOTHING. LEVEL B: +$0.50 PER HOUR - USES SAME RESPIRATOR PROTECTION AS LEVEL A. SUPPLIED AIR LINE IS PROVIDED IN CONJUNCTION WITH A CHEMICAL ""SPLASH SUIT."" LEVEL A: +$0.75 PER HOUR - THIS LEVEL UTILIZES A FULLY- ENCAPSULATED SUIT WITH A SELF-CONTAINED BREATHING APPARATUS OR A SUPPLIED AIR LINE.)
(CLALLAM, GRAYS HARBOR, ISLAND, JEFFERSON, KING, KITSAP, LEWIS, MASON, PACIFIC (NORTH OF A STRAIGHT LINE MADE BY EXTENDING THE NORTH BOUNDARY LINE OF WAHKIAKUM COUNTY WEST TO THE PACIFIC OCEAN), PIERCE, SAN JUAN, SKAGIT, SNOHOMISH, THURSTON AND WHATCOM COUNTIES)
ZONE A: (LESS THAN 25 MILES FROM CENTER OF LISTED CITIES*). BASE RATE. ZONE B: (25-45 MILES FROM CENTER OF LISTED CITIES*): $0.70. ZONE C (OVER 45 MILES FROM CENTR OF LISTED CITIES*): $1.00. *ZONE PAY WILL BE CALCULATED FROM THE CITY CENTER OF THE FOLLOWING LISTED CITIES: BELLINGHAM, CENTRALIA, RAYMOND, OLYMPIA EVERETT, SHELTON, ANACORTES, BELLEVUE, SEATTLE, PORT ANGELES, MT. VERNON, KENT, TACOMA, PORT TOWNSEND, ABERDEEN, BREMERTON. .....$ 54.59 27.52
TRUCK DRIVER: GROUP 3- FLATBED (SINGLE REAR AXLE); PICKUP SWEEPER; PICKUP TRUCK. (ADJUST GROUP 3 UPWARD BY $2.00 PER HOUR FOR ONSITE WORK ONLY)
(HAZMAT PROJECTS ANYONE WORKING ON A HAZMAT JOB, WHERE HAZMAT CERTIFICATION IS REQUIRED, SHALL BE COMPENSATED AS A PREMIUM, IN ADDITION TO THE CLASSIFICATION WORKING IN AS FOLLOWS: LEVEL C: +$0.25 PER HOUR - THIS LEVEL USES AN AIR PURIFYING RESPIRATOR OR ADDITIONAL PROTECTIVE CLOTHING. LEVEL B: +$0.50 PER HOUR - USES SAME RESPIRATOR PROTECTION AS LEVEL A. SUPPLIED AIR LINE IS PROVIDED IN CONJUNCTION WITH A CHEMICAL ""SPLASH SUIT."" LEVEL A: +$0.75 PER HOUR - THIS LEVEL UTILIZES A FULLY- ENCAPSULATED SUIT WITH A SELF-CONTAINED BREATHING APPARATUS OR A SUPPLIED AIR LINE.)
(CLALLAM, GRAYS HARBOR, ISLAND, JEFFERSON, KING, KITSAP, LEWIS, MASON, PACIFIC (NORTH OF A STRAIGHT LINE MADE BY EXTENDING THE NORTH BOUNDARY LINE OF WAHKIAKUM COUNTY WEST TO THE PACIFIC OCEAN), PIERCE, SAN JUAN, SKAGIT, SNOHOMISH, THURSTON AND WHATCOM COUNTIES)
ZONE A: (LESS THAN 25 MILES FROM CENTER OF LISTED CITIES*). BASE RATE. ZONE B: (25-45 MILES FROM CENTER OF LISTED CITIES*): $0.70. ZONE C (OVER 45 MILES FROM CENTR OF LISTED

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

CITIES*): $1.00. *ZONE PAY WILL BE CALCULATED FROM THE CITY CENTER OF THE FOLLOWING LISTED CITIES: BELLINGHAM, CENTRALIA, RAYMOND, OLYMPIA EVERETT, SHELTON, ANACORTES, BELLEVUE, SEATTLE, PORT ANGELES, MT. VERNON, KENT, TACOMA, PORT TOWNSEND, ABERDEEN, BREMERTON. .....$ 51.78 27.52

TRUCK DRIVER: GROUP 4- ESCORT OR PILOT CAR (HAZMAT PROJECTS ANYONE WORKING ON A HAZMAT JOB, WHERE HAZMAT CERTIFICATION IS REQUIRED, SHALL BE COMPENSATED AS A PREMIUM, IN ADDITION TO THE CLASSIFICATION WORKING IN AS FOLLOWS: LEVEL C: +$0.25 PER HOUR - THIS LEVEL USES AN AIR PURIFYING RESPIRATOR OR ADDITIONAL PROTECTIVE CLOTHING. LEVEL B: +$0.50 PER HOUR - USES SAME RESPIRATOR PROTECTION AS LEVEL A. SUPPLIED AIR LINE IS PROVIDED IN CONJUNCTION WITH A CHEMICAL ""SPLASH SUIT."" LEVEL A: +$0.75 PER HOUR - THIS LEVEL UTILIZES A FULLY- ENCAPSULATED SUIT WITH A SELF-CONTAINED BREATHING APPARATUS OR A SUPPLIED AIR LINE.)

(CLALLAM, GRAYS HARBOR, ISLAND, JEFFERSON, KING, KITSAP, LEWIS, MASON, PACIFIC (NORTH OF A STRAIGHT LINE MADE BY EXTENDING THE NORTH BOUNDARY LINE OF WAHKIAKUM COUNTY WEST TO THE PACIFIC OCEAN), PIERCE, SAN JUAN, SKAGIT, SNOHOMISH, THURSTON AND WHATCOM COUNTIES)

ZONE A: (LESS THAN 25 MILES FROM CENTER OF LISTED CITIES*). BASE RATE. ZONE B: (25-45 MILES FROM CENTER OF LISTED CITIES*): $0.70. ZONE C (OVER 45 MILES FROM CENTR OF LISTED CITIES*): $1.00. *ZONE PAY WILL BE CALCULATED FROM THE CITY CENTER OF THE FOLLOWING LISTED CITIES: BELLINGHAM, CENTRALIA, RAYMOND, OLYMPIA EVERETT, SHELTON, ANACORTES, BELLEVUE, SEATTLE, PORT ANGELES, MT. VERNON, KENT, TACOMA, PORT TOWNSEND, ABERDEEN, BREMERTON. .....$ 46.81 27.52

TRUCK DRIVER: GROUP 5- MECHANIC (HAZMAT PROJECTS ANYONE WORKING ON A HAZMAT JOB, WHERE HAZMAT CERTIFICATION IS REQUIRED, SHALL BE COMPENSATED AS A PREMIUM, IN ADDITION TO THE CLASSIFICATION WORKING IN AS FOLLOWS: LEVEL C: +$0.25 PER HOUR - THIS LEVEL USES AN AIR PURIFYING RESPIRATOR OR ADDITIONAL PROTECTIVE CLOTHING. LEVEL B: +$0.50 PER HOUR - USES SAME RESPIRATOR PROTECTION AS LEVEL A. SUPPLIED AIR LINE IS PROVIDED IN CONJUNCTION WITH A CHEMICAL ""SPLASH SUIT."" LEVEL A: +$0.75 PER HOUR - THIS LEVEL UTILIZES A FULLY- ENCAPSULATED SUIT WITH A SELF-CONTAINED BREATHING APPARATUS OR A SUPPLIED AIR LINE.)

(CLALLAM, GRAYS HARBOR, ISLAND, JEFFERSON, KING, KITSAP, LEWIS, MASON, PACIFIC (NORTH OF A STRAIGHT LINE MADE BY EXTENDING THE NORTH BOUNDARY LINE OF WAHKIAKUM COUNTY WEST TO THE

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

PACIFIC OCEAN), PIERCE, SAN JUAN, SKAGIT,
SNOHOMISH, THURSTON AND WHATCOM COUNTIES)
ZONE A: (LESS THAN 25 MILES FROM
CENTER OF LISTED CITIES*). BASE RATE. ZONE B:
(25-45 MILES FROM CENTER OF LISTED CITIES*): $0.70.
ZONE C (OVER 45 MILES FROM CENTR OF LISTED
CITIES*): $1.00. *ZONE PAY WILL BE CALCULATED
FROM THE CITY CENTER OF THE FOLLOWING LISTED
CITIES: BELLINGHAM, CENTRALIA, RAYMOND, OLYMPIA
EVERETT, SHELTON, ANACORTES, BELLEVUE, SEATTLE,
PORT ANGELES, MT. VERNON, KENT, TACOMA, PORT
TOWNSEND, ABERDEEN, BREMERTON. .....$ 54.98 27.52

TEAM0690-004 06/01/2024

Rates	Fringes
TRUCK DRIVERS: GROUP 1- ESCORT DRIVER OR PILOT CAR; EMPLOYEE HAUL; POWER BOAT HAULING EMPLOYEES OR MATERIAL. (ADAMS, ASOTIN, BENTON, CHELAN, COLUMBIA, DOUGLAS, FERRY, FRANKLIN, GARFIELD, GRANT KITTITAS, LINCOLN, OKANOGAN, PEND OREILLE, SPOKANE, STEVENS, WALLA WALLA, WHITMAN AND YAKIMA COUNTIES) (AREA 1: LEWISTON ZONE CENTER: ASOTIN, COLUMBIA, AND GARFIELD COUNTIES; SPOKANE ZONE CENTER: ADAMS, CHELAN, DOUGLAS, FERRY, GRANT, KITTITAS, LINCOLN, OKANOGAN, PEND OREILLE, SPOKANE, STEVENS, AND WHITMAN COUNTIES) ZONE DIFFERENTIAL: ZONE 1- BASE RATE. ZONE 2: $2.00. BASE POINTS: SPOKANE, PASCO, LEWISTON. ZONE 1: 0-45 RADIUS MILES FROM THE MAIN POST OFFICE. ZONE 2: OUTSIDE 45 RADIUS MILES FROM THE MAIN POST OFFICE. FOOTNOTE A - ANYONE WORKING ON A HAZMAT JOB, WHERE HAZMAT CERTIFICATION IS REQUIRED, SHALL BE COMPENSATED AS A PREMIUM, IN ADDITON TO THE CLASSIFICATION WORKING IN AS FOLLOWS: LEVEL C-D: -$0.50 PER HOUR (THIS IS THE LOWEST LEVEL OF PROTECTION. THIS LEVEL MAY USE AN AIR PURIFYING RESPIRATOR OR ADDITIONAL PROTECTIVE CLOTHING. LEVEL A-B: $1.00 PER HOUR (USES SUPPLIED AIR IS CONJUNCTION WITH A CHEMICAL SPASH SUIT OR FULLY ENCAPSULATED SUIT WITH A SELF-CONTAINED BREATHING APPARATUS. EMPLOYEES SHALL BE PAID HAZMAT PAY IN INCREMENTS OF FOUR(4) AND EIGHT(8) HOURS. NOTE: TRUCKS PULLING EQUIPMENT TRAILERS: SHALL RECEIVE $0.15/HOUR OVER APPLICABLE TRUCK RATE. .....$ 36.83	20.93
TRUCK DRIVERS: GROUP 2- FISH TRUCK; FLAT BED TRUCK; FORK LIFT (3,000 LBS. AND UNDER); LEVERPERSON (LOADING TRUCKS AT BUNKERS); TRAILER MOUNTED HYDRO SEEDER AND MULCHER; SEEDER & MULCHER; STATIONARY FUEL OPERATOR; TRACTOR (SMALL, RUBBER-TIRED, PULLING TRAILER OR SIMILAR (ADAMS, ASOTIN, BENTON, CHELAN, COLUMBIA, DOUGLAS, FERRY, FRANKLIN, GARFIELD, GRANT KITTITAS, LINCOLN, OKANOGAN, PEND OREILLE, SPOKANE, STEVENS, WALLA WALLA, WHITMAN AND YAKIMA COUNTIES) (AREA 1:	

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

LEWISTON ZONE CENTER: ASOTIN, COLUMBIA, AND GARFIELD COUNTIES; SPOKANE ZONE CENTER: ADAMS, CHELAN, DOUGLAS, FERRY, GRANT, KITTITAS, LINCOLN, OKANOGAN, PEND OREILLE, SPOKANE, STEVENS, AND WHITMAN COUNTIES) ZONE DIFFERENTIAL: ZONE 1- BASE RATE. ZONE 2: $2.00. BASE POINTS: SPOKANE, PASCO, LEWISTON. ZONE 1: 0-45 RADIUS MILES FROM THE MAIN POST OFFICE. ZONE 2: OUTSIDE 45 RADIUS MILES FROM THE MAIN POST OFFICE. FOOTNOTE A - ANYONE WORKING ON A HAZMAT JOB, WHERE HAZMAT CERTIFICATION IS REQUIRED, SHALL BE COMPENSATED AS A PREMIUM, IN ADDITON TO THE CLASSIFICATION WORKING IN AS FOLLOWS: LEVEL C-D: -$0.50 PER HOUR (THIS IS THE LOWEST LEVEL OF PROTECTION. THIS LEVEL MAY USE AN AIR PURIFYING RESPIRATOR OR ADDITIONAL PROTECTIVE CLOTHING. LEVEL A-B: $1.00 PER HOUR (USES SUPPLIED AIR IS CONJUNCTION WITH A CHEMICAL SPASH SUIT OR FULLY ENCAPSULATED SUIT WITH A SELF-CONTAINED BREATHING APPARATUS. EMPLOYEES SHALL BE PAID HAZMAT PAY IN INCREMENTS OF FOUR(4) AND EIGHT(8) HOURS. NOTE: TRUCKS PULLING EQUIPMENT TRAILERS: SHALL RECEIVE $0.15/HOUR OVER APPLICABLE TRUCK RATE. .....$ 39.47 20.93

TRUCK DRIVERS: GROUP 3- AUTO CRANE (2,000 LBS. CAPACITY); BUGGY MOBILE & SIMILAR; BULK CEMENT TANKS & SPREADER; DUMPTOR (6 YDS. & UNDER); FLAT BED TRUCK WITH HYDRAULLIC SYSTEM; FORK LIFT (3,001-16,000 LBS.); FUEL TRUCK DRIVER, STEAMCLEANER & WASHER; POWER OPERATED SWEEPER; RUBBER-TIRED TUNNEL JUMBO; SCISSORS TRUCK; SLURRY TRUCK DRIVER; STRADDLE CARRIER (ROSS, HYSTER, & SIMILAR); TIREPERSON; TRANSIT MIXERS & TRUCK HAULING CONCRETE (3 YD. TO & INCLUDING 6 YDS.); TRUCKS, SIDE, END, BOTTOM & ARTICULATD END DUMP (3 YARDS TO AND INCLUDING 6 YDS.); WAREHOUSEPERSON (TO INCLUDE SHIPPING & RECEIVING); WRECKER & TOW (ADAMS, ASOTIN, BENTON, CHELAN, COLUMBIA, DOUGLAS, FERRY, FRANKLIN, GARFIELD, GRANT KITTITAS, LINCOLN, OKANOGAN, PEND OREILLE, SPOKANE, STEVENS, WALLA WALLA, WHITMAN AND YAKIMA COUNTIES) (AREA 1: LEWISTON ZONE CENTER: ASOTIN, COLUMBIA, AND GARFIELD COUNTIES; SPOKANE ZONE CENTER: ADAMS, CHELAN, DOUGLAS, FERRY, GRANT, KITTITAS, LINCOLN, OKANOGAN, PEND OREILLE, SPOKANE, STEVENS, AND WHITMAN COUNTIES) ZONE DIFFERENTIAL: ZONE 1- BASE RATE. ZONE 2: $2.00. BASE POINTS: SPOKANE, PASCO, LEWISTON. ZONE 1: 0-45 RADIUS MILES FROM THE MAIN POST OFFICE. ZONE 2: OUTSIDE 45 RADIUS MILES FROM THE MAIN POST OFFICE.
FOOTNOTE A - ANYONE WORKING ON A HAZMAT JOB, WHERE HAZMAT CERTIFICATION IS REQUIRED, SHALL BE COMPENSATED AS A PREMIUM, IN ADDITON TO THE CLASSIFICATION WORKING IN AS FOLLOWS: LEVEL C-D: -$0.50 PER HOUR (THIS IS THE LOWEST LEVEL OF PROTECTION. THIS LEVEL MAY USE AN AIR PURIFYING RESPIRATOR OR ADDITIONAL PROTECTIVE CLOTHING. LEVEL A-B: $1.00 PER HOUR (USES SUPPLIED AIR IS

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

CONJUNCTION WITH A CHEMICAL SPASH SUIT OR FULLY ENCAPSULATED SUIT WITH A SELF-CONTAINED BREATHING APPARATUS. EMPLOYEES SHALL BE PAID HAZMAT PAY IN INCREMENTS OF FOUR(4) AND EIGHT(8) HOURS. NOTE: TRUCKS PULLING EQUIPMENT TRAILERS: SHALL RECEIVE $0.15/HOUR OVER APPLICABLE TRUCK RATE. .....$ 39.58 20.93

TRUCK DRIVERS: GROUP 4- A-FRAME; BURNER, CUTTER, & WELDER; SERVICE GRASER; TRUCKS, SIDE, END, BOTTOM & ARTICULATED END DUMP (OVER 6 YARDS TO AND INCLUDING 12 YDS.); TRUCK MOUNTED HYDRO SEEDER; WAREHOUSEPERSON; WATER TANK TRUCK (0-8,000 (ADAMS, ASOTIN, BENTON, CHELAN, COLUMBIA, DOUGLAS, FERRY, FRANKLIN, GARFIELD, GRANT KITTITAS, LINCOLN, OKANOGAN, PEND OREILLE, SPOKANE, STEVENS, WALLA WALLA, WHITMAN AND YAKIMA COUNTIES) (AREA 1: LEWISTON ZONE CENTER: ASOTIN, COLUMBIA, AND GARFIELD COUNTIES; SPOKANE ZONE CENTER: ADAMS, CHELAN, DOUGLAS, FERRY, GRANT, KITTITAS, LINCOLN, OKANOGAN, PEND OREILLE, SPOKANE, STEVENS, AND WHITMAN COUNTIES) ZONE DIFFERENTIAL: ZONE 1- BASE RATE. ZONE 2: $2.00. BASE POINTS: SPOKANE, PASCO, LEWISTON. ZONE 1: 0-45 RADIUS MILES FROM THE MAIN POST OFFICE. ZONE 2: OUTSIDE 45 RADIUS MILES FROM THE MAIN POST OFFICE. FOOTNOTE A - ANYONE WORKING ON A HAZMAT JOB, WHERE HAZMAT CERTIFICATION IS REQUIRED, SHALL BE COMPENSATED AS A PREMIUM, IN ADDITON TO THE CLASSIFICATION WORKING IN AS FOLLOWS: LEVEL C-D: -$0.50 PER HOUR (THIS IS THE LOWEST LEVEL OF PROTECTION. THIS LEVEL MAY USE AN AIR PURIFYING RESPIRATOR OR ADDITIONAL PROTECTIVE CLOTHING. LEVEL A-B: $1.00 PER HOUR (USES SUPPLIED AIR IS CONJUNCTION WITH A CHEMICAL SPASH SUIT OR FULLY ENCAPSULATED SUIT WITH A SELF-CONTAINED BREATHING APPARATUS. EMPLOYEES SHALL BE PAID HAZMAT PAY IN INCREMENTS OF FOUR(4) AND EIGHT(8) HOURS. NOTE: TRUCKS PULLING EQUIPMENT TRAILERS: SHALL RECEIVE $0.15/HOUR OVER APPLICABLE TRUCK RATE. .....$ 39.91 20.93

TRUCK DRIVERS: GROUP 5- DUMPTOR (OVER 6 YDS.); LOWBOY (50 TONS & UNDER); SELF-LOADING ROLL OFF; SEMI-TRUCK & TRAILER; TRACTOR WITH STEER TRAILER; TRANSIT MIXERS AND TRUCKS HAULING CONCRETE (OVER 6 YDS. TO AN INCLUDING 10 YDS.); TRUCKS, SIDE, END, BOTTOM AND END DUMP (OVER 12 YDS. TO & INCLUDING 20 YDS.); TRUCK-MOUNTED CRANE (WITH LOAD BEARING SURFACE EITHER MOUNTED OR PULLED, UP TO 14 TON); VACUUM TRUCK (SUPER SUCKER, GUZZLER, (ADAMS, ASOTIN, BENTON, CHELAN, COLUMBIA, DOUGLAS, FERRY, FRANKLIN, GARFIELD, GRANT KITTITAS, LINCOLN, OKANOGAN, PEND OREILLE, SPOKANE, STEVENS, WALLA WALLA, WHITMAN AND YAKIMA COUNTIES) (AREA 1: LEWISTON ZONE CENTER: ASOTIN, COLUMBIA, AND GARFIELD COUNTIES; SPOKANE ZONE CENTER: ADAMS, CHELAN, DOUGLAS, FERRY, GRANT, KITTITAS, LINCOLN, OKANOGAN, PEND OREILLE, SPOKANE, STEVENS, AND WHITMAN COUNTIES) ZONE DIFFERENTIAL: ZONE 1- BASE RATE. ZONE 2: $2.00. BASE POINTS: SPOKANE, PASCO,

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

LEWISTON. ZONE 1: 0-45 RADIUS MILES FROM THE MAIN POST OFFICE. ZONE 2: OUTSIDE 45 RADIUS MILES FROM THE MAIN POST OFFICE. FOOTNOTE A - ANYONE WORKING ON A HAZMAT JOB, WHERE HAZMAT CERTIFICATION IS REQUIRED, SHALL BE COMPENSATED AS A PREMIUM, IN ADDITON TO THE CLASSIFICATION WORKING IN AS FOLLOWS: LEVEL C-D: -$0.50 PER HOUR (THIS IS THE LOWEST LEVEL OF PROTECTION. THIS LEVEL MAY USE AN AIR PURIFYING RESPIRATOR OR ADDITIONAL PROTECTIVE CLOTHING. LEVEL A-B: $1.00 PER HOUR (USES SUPPLIED AIR IS CONJUNCTION WITH A CHEMICAL SPASH SUIT OR FULLY ENCAPSULATED SUIT WITH A SELF-CONTAINED BREATHING APPARATUS. EMPLOYEES SHALL BE PAID HAZMAT PAY IN INCREMENTS OF FOUR(4) AND EIGHT(8) HOURS. NOTE: TRUCKS PULLING EQUIPMENT TRAILERS: SHALL RECEIVE $0.15/HOUR OVER APPLICABLE TRUCK RATE. .....$ 40.02 20.93
TRUCK DRIVERS: GROUP 6- FLAHERTY SPREADER BOX DRIVER; FLOWBOYS; FORK LIFT (OVER 16,000 LBS.); DUMPS (SEMI-END); MECHANIC (FIELD); SEMI-END DUMPS; TRANSFER TRUCK & TRAILER; TRANSIT MIXERS & TRUCKS HAULING CONCRETE (OVER 10 YDS. TO & INCLUDING 20 YDS.); TRUCKS, SIDE, END, BOTTOM AND ARTICULATED END DUMP (OVER 20 YDS. TO & INCLUDING 40 YDS.); TRUCK AND PUP; TOURNAROCKER, DWS & SIMILAR WITH 2 OR MORE 4 WHEEL-POWER TRACKTOR WITH TRAILER, GALLONAGE OR YARDAGE SCALE, WHICHEVER IS GREATER WATER TANK TRUCK (8,001- 14,000 GALLONS); LOWBOY (OVER 50
(ADAMS, ASOTIN, BENTON, CHELAN, COLUMBIA, DOUGLAS, FERRY, FRANKLIN, GARFIELD, GRANT KITTITAS, LINCOLN, OKANOGAN, PEND OREILLE, SPOKANE, STEVENS, WALLA WALLA, WHITMAN AND YAKIMA COUNTIES) (AREA 1: LEWISTON ZONE CENTER: ASOTIN, COLUMBIA, AND GARFIELD COUNTIES; SPOKANE ZONE CENTER: ADAMS, CHELAN, DOUGLAS, FERRY, GRANT, KITTITAS, LINCOLN, OKANOGAN, PEND OREILLE, SPOKANE, STEVENS, AND WHITMAN COUNTIES) ZONE DIFFERENTIAL: ZONE 1- BASE RATE. ZONE 2: $2.00. BASE POINTS: SPOKANE, PASCO, LEWISTON. ZONE 1: 0-45 RADIUS MILES FROM THE MAIN POST OFFICE. ZONE 2: OUTSIDE 45 RADIUS MILES FROM THE MAIN POST OFFICE. FOOTNOTE A - ANYONE WORKING ON A HAZMAT JOB, WHERE HAZMAT CERTIFICATION IS REQUIRED, SHALL BE COMPENSATED AS A PREMIUM, IN ADDITON TO THE CLASSIFICATION WORKING IN AS FOLLOWS: LEVEL C-D: -$0.50 PER HOUR (THIS IS THE LOWEST LEVEL OF PROTECTION. THIS LEVEL MAY USE AN AIR PURIFYING RESPIRATOR OR ADDITIONAL PROTECTIVE CLOTHING. LEVEL A-B: $1.00 PER HOUR (USES SUPPLIED AIR IS CONJUNCTION WITH A CHEMICAL SPASH SUIT OR FULLY ENCAPSULATED SUIT WITH A SELF-CONTAINED BREATHING APPARATUS. EMPLOYEES SHALL BE PAID HAZMAT PAY IN INCREMENTS OF FOUR(4) AND EIGHT(8) HOURS. NOTE: TRUCKS PULLING EQUIPMENT TRAILERS: SHALL RECEIVE $0.15/HOUR OVER APPLICABLE TRUCK RATE. .....$ 40.22 20.93
TRUCK DRIVERS: GROUP 7- OIL DISTRIBUTOR DRIVER; STRINGER TRUCK (CABLE OPERATED TRAILER); TRANSIT

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

MIXERS & TRUCKS HAULING CONCRETE (OVER 20 YDS.); TRUCK, SIDE, END, BOTTOM END DUMP (OVER 40 YDS. TO & INCLUDING 100 YDS.); TRUCK MOUNTED CRANE (WITH LOAD BEARING SURFACE EITHER MOUNTED OR PULLED (16 THROUGH 25
(ADAMS, ASOTIN, BENTON, CHELAN, COLUMBIA, DOUGLAS, FERRY, FRANKLIN, GARFIELD, GRANT KITTITAS, LINCOLN, OKANOGAN, PEND OREILLE, SPOKANE, STEVENS, WALLA WALLA, WHITMAN AND YAKIMA COUNTIES) (AREA 1: LEWISTON ZONE CENTER: ASOTIN, COLUMBIA, AND GARFIELD COUNTIES; SPOKANE ZONE CENTER: ADAMS, CHELAN, DOUGLAS, FERRY, GRANT, KITTITAS, LINCOLN, OKANOGAN, PEND OREILLE, SPOKANE, STEVENS, AND WHITMAN COUNTIES) ZONE DIFFERENTIAL: ZONE 1- BASE RATE. ZONE 2: $2.00. BASE POINTS: SPOKANE, PASCO, LEWISTON. ZONE 1: 0-45 RADIUS MILES FROM THE MAIN POST OFFICE. ZONE 2: OUTSIDE 45 RADIUS MILES FROM THE MAIN POST OFFICE. FOOTNOTE A - ANYONE WORKING ON A HAZMAT JOB, WHERE HAZMAT CERTIFICATION IS REQUIRED, SHALL BE COMPENSATED AS A PREMIUM, IN ADDITON TO THE CLASSIFICATION WORKING IN AS FOLLOWS: LEVEL C-D: -$0.50 PER HOUR (THIS IS THE LOWEST LEVEL OF PROTECTION. THIS LEVEL MAY USE AN AIR PURIFYING RESPIRATOR OR ADDITIONAL PROTECTIVE CLOTHING. LEVEL A-B: $1.00 PER HOUR (USES SUPPLIED AIR IS CONJUNCTION WITH A CHEMICAL SPASH SUIT OR FULLY ENCAPSULATED SUIT WITH A SELF-CONTAINED BREATHING APPARATUS. EMPLOYEES SHALL BE PAID HAZMAT PAY IN INCREMENTS OF FOUR(4) AND EIGHT(8) HOURS. NOTE: TRUCKS PULLING EQUIPMENT TRAILERS: SHALL RECEIVE $0.15/HOUR OVER APPLICABLE TRUCK RATE. .....$ 40.56 20.93
TRUCK DRIVERS: GROUP 8- PRIME MOVERS AND STINGER TRUCK; TRUCKS, SIDE, END, BOTTOM AND ARTICULATED END DUMP (OVER 100 YDS.); HELICOPTER PILOT HAULING EMPLOYEES OR
(ADAMS, ASOTIN, BENTON, CHELAN, COLUMBIA, DOUGLAS, FERRY, FRANKLIN, GARFIELD, GRANT KITTITAS, LINCOLN, OKANOGAN, PEND OREILLE, SPOKANE, STEVENS, WALLA WALLA, WHITMAN AND YAKIMA COUNTIES) (AREA 1: LEWISTON ZONE CENTER: ASOTIN, COLUMBIA, AND GARFIELD COUNTIES; SPOKANE ZONE CENTER: ADAMS, CHELAN, DOUGLAS, FERRY, GRANT, KITTITAS, LINCOLN, OKANOGAN, PEND OREILLE, SPOKANE, STEVENS, AND WHITMAN COUNTIES) ZONE DIFFERENTIAL: ZONE 1- BASE RATE. ZONE 2: $2.00. BASE POINTS: SPOKANE, PASCO, LEWISTON. ZONE 1: 0-45 RADIUS MILES FROM THE MAIN POST OFFICE. ZONE 2: OUTSIDE 45 RADIUS MILES FROM THE MAIN POST OFFICE. FOOTNOTE A - ANYONE WORKING ON A HAZMAT JOB, WHERE HAZMAT CERTIFICATION IS REQUIRED, SHALL BE COMPENSATED AS A PREMIUM, IN ADDITON TO THE CLASSIFICATION WORKING IN AS FOLLOWS: LEVEL C-D: -$0.50 PER HOUR (THIS IS THE LOWEST LEVEL OF PROTECTION. THIS LEVEL MAY USE AN AIR PURIFYING RESPIRATOR OR ADDITIONAL PROTECTIVE CLOTHING. LEVEL A-B: $1.00 PER HOUR (USES SUPPLIED AIR IS CONJUNCTION WITH A CHEMICAL SPASH SUIT OR

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

FULLY ENCAPSULATED SUIT WITH A SELF-CONTAINED
BREATHING APPARATUS. EMPLOYEES SHALL BE PAID HAZMAT
PAY IN INCREMENTS OF FOUR(4) AND EIGHT(8) HOURS.
NOTE: TRUCKS PULLING EQUIPMENT TRAILERS: SHALL
RECEIVE $0.15/HOUR OVER APPLICABLE TRUCK RATE. .....$ 40.88 20.93
TRUCK DRIVERS: GROUP 1- ESCORT DRIVER OR PILOT CAR;
EMPLOYEE HAUL; POWER BOAT HAULING EMPLOYEES OR
MATERIAL. (ADAMS, ASOTIN, BENTON, CHELAN, COLUMBIA,
DOUGLAS, FERRY, FRANKLIN, GARFIELD, GRANT KITTITAS,
LINCOLN, OKANOGAN, PEND OREILLE, SPOKANE, STEVENS,
WALLA WALLA, WHITMAN AND YAKIMA COUNTIES) (AREA 2:
PASCO ZONE CENTER: BENTON, FRANKLIN, WALLA WALLA
AND YAKIMA COUNTIES). ZONE DIFFERENTIAL: ZONE 1-
BASE RATE. ZONE 2: $2.00. BASE POINTS: SPOKANE,
PASCO, LEWISTON. ZONE 1: 0-45 RADIUS MILES FROM THE
MAIN POST OFFICE. ZONE 2: OUTSIDE 45 RADIUS MILES
FROM THE MAIN POST OFFICE. FOOTNOTE A - ANYONE
WORKING ON A HAZMAT JOB, WHERE HAZMAT CERTIFICATION
IS REQUIRED, SHALL BE COMPENSATED AS A PREMIUM, IN
ADDITON TO THE CLASSIFICATION WORKING IN AS
FOLLOWS: LEVEL C-D: -$0.50 PER HOUR (THIS IS THE
LOWEST LEVEL OF PROTECTION. THIS LEVEL MAY USE AN
AIR PURIFYING RESPIRATOR OR ADDITIONAL PROTECTIVE
CLOTHING. LEVEL A-B: $1.00 PER HOUR (USES SUPPLIED
AIR IS CONJUNCTION WITH A CHEMICAL SPASH SUIT OR
FULLY ENCAPSULATED SUIT WITH A SELF-CONTAINED
BREATHING APPARATUS. EMPLOYEES SHALL BE PAID HAZMAT
PAY IN INCREMENTS OF FOUR(4) AND EIGHT(8) HOURS.
NOTE: TRUCKS PULLING EQUIPMENT TRAILERS: SHALL
RECEIVE $0.15/HOUR OVER APPLICABLE TRUCK RATE. .....$ 33.83 20.93
TRUCK DRIVERS: GROUP 2- FISH TRUCK; FLAT BED TRUCK;
FORK LIFT (3,000 LBS. AND UNDER); LEVERPERSON
(LOADING TRUCKS AT BUNKERS); TRAILER MOUNTED HYDRO
SEEDER AND MULCHER; SEEDER & MULCHER; STATIONARY
FUEL OPERATOR; TRACTOR (SMALL, RUBBER-TIRED,
PULLING TRAILER OR SIMILAR
(ADAMS, ASOTIN, BENTON, CHELAN, COLUMBIA, DOUGLAS,
FERRY, FRANKLIN, GARFIELD, GRANT KITTITAS, LINCOLN,
OKANOGAN, PEND OREILLE, SPOKANE, STEVENS, WALLA
WALLA, WHITMAN AND YAKIMA COUNTIES) (AREA 2: PASCO
ZONE CENTER: BENTON, FRANKLIN, WALLA WALLA AND
YAKIMA COUNTIES). ZONE DIFFERENTIAL: ZONE 1- BASE
RATE. ZONE 2: $2.00. BASE POINTS: SPOKANE, PASCO,
LEWISTON. ZONE 1: 0-45 RADIUS MILES FROM THE MAIN
POST OFFICE. ZONE 2: OUTSIDE 45 RADIUS MILES FROM
THE MAIN POST OFFICE. FOOTNOTE A - ANYONE WORKING
ON A HAZMAT JOB, WHERE HAZMAT CERTIFICATION IS
REQUIRED, SHALL BE COMPENSATED AS A PREMIUM, IN
ADDITON TO THE CLASSIFICATION WORKING IN AS
FOLLOWS: LEVEL C-D: -$0.50 PER HOUR (THIS IS THE
LOWEST LEVEL OF PROTECTION. THIS LEVEL MAY USE AN
AIR PURIFYING RESPIRATOR OR ADDITIONAL PROTECTIVE
CLOTHING. LEVEL A-B: $1.00 PER HOUR (USES SUPPLIED
AIR IS CONJUNCTION WITH A CHEMICAL SPASH SUIT OR
FULLY ENCAPSULATED SUIT WITH A SELF-CONTAINED
BREATHING APPARATUS. EMPLOYEES SHALL BE PAID HAZMAT

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

PAY IN INCREMENTS OF FOUR(4) AND EIGHT(8) HOURS.
NOTE: TRUCKS PULLING EQUIPMENT TRAILERS: SHALL
RECEIVE $0.15/HOUR OVER APPLICABLE TRUCK RATE. .....$ 36.47 20.93
TRUCK DRIVERS: GROUP 3- AUTO CRANE (2,000 LBS.
CAPACITY); BUGGY MOBILE & SIMILAR; BULK CEMENT
TANKS & SPREADER; DUMPTOR (6 YDS. & UNDER); FLAT
BED TRUCK WITH HYDRAULLIC SYSTEM; FORK LIFT
(3,001-16,000 LBS.); FUEL TRUCK DRIVER,
STEAMCLEANER & WASHER; POWER OPERATED SWEEPER;
RUBBER-TIRED TUNNEL JUMBO; SCISSORS TRUCK; SLURRY
TRUCK DRIVER; STRADDLE CARRIER (ROSS, HYSTER, &
SIMILAR); TIREPERSON; TRANSIT MIXERS & TRUCK
HAULING CONCRETE (3 YD. TO & INCLUDING 6 YDS.);
TRUCKS, SIDE, END, BOTTOM & ARTICULATD END DUMP (3
YARDS TO AND INCLUDING 6 YDS.); WAREHOUSEPERSON (TO
INCLUDE SHIPPING & RECEIVING); WRECKER & TOW
(ADAMS, ASOTIN, BENTON, CHELAN, COLUMBIA, DOUGLAS,
FERRY, FRANKLIN, GARFIELD, GRANT KITTITAS, LINCOLN,
OKANOGAN, PEND OREILLE, SPOKANE, STEVENS, WALLA
WALLA, WHITMAN AND YAKIMA COUNTIES) (AREA 2: PASCO
ZONE CENTER: BENTON, FRANKLIN, WALLA WALLA AND
YAKIMA COUNTIES). ZONE DIFFERENTIAL: ZONE 1- BASE
RATE. ZONE 2: $2.00. BASE POINTS: SPOKANE, PASCO,
LEWISTON. ZONE 1: 0-45 RADIUS MILES FROM THE MAIN
POST OFFICE. ZONE 2: OUTSIDE 45 RADIUS MILES FROM
THE MAIN POST OFFICE. FOOTNOTE A - ANYONE WORKING
ON A HAZMAT JOB, WHERE HAZMAT CERTIFICATION IS
REQUIRED, SHALL BE COMPENSATED AS A PREMIUM, IN
ADDITON TO THE CLASSIFICATION WORKING IN AS
FOLLOWS: LEVEL C-D: -$0.50 PER HOUR (THIS IS THE
LOWEST LEVEL OF PROTECTION. THIS LEVEL MAY USE AN
AIR PURIFYING RESPIRATOR OR ADDITIONAL PROTECTIVE
CLOTHING. LEVEL A-B: $1.00 PER HOUR (USES SUPPLIED
AIR IS CONJUNCTION WITH A CHEMICAL SPASH SUIT OR
FULLY ENCAPSULATED SUIT WITH A SELF-CONTAINED
BREATHING APPARATUS. EMPLOYEES SHALL BE PAID HAZMAT
PAY IN INCREMENTS OF FOUR(4) AND EIGHT(8) HOURS.
NOTE: TRUCKS PULLING EQUIPMENT TRAILERS: SHALL
RECEIVE $0.15/HOUR OVER APPLICABLE TRUCK RATE. .....$ 36.58 20.93
TRUCK DRIVERS: GROUP 4- A-FRAME; BURNER, CUTTER, &
WELDER; SERVICE GRASER; TRUCKS, SIDE, END, BOTTOM &
ARTICULATED END DUMP (OVER 6 YARDS TO AND INCLUDING
12 YDS.); TRUCK MOUNTED HYDRO SEEDER;
WAREHOUSEPERSON; WATER TANK TRUCK (0-8,000
(ADAMS, ASOTIN, BENTON, CHELAN, COLUMBIA, DOUGLAS,
FERRY, FRANKLIN, GARFIELD, GRANT KITTITAS, LINCOLN,
OKANOGAN, PEND OREILLE, SPOKANE, STEVENS, WALLA
WALLA, WHITMAN AND YAKIMA COUNTIES) (AREA 2: PASCO
ZONE CENTER: BENTON, FRANKLIN, WALLA WALLA AND
YAKIMA COUNTIES). ZONE DIFFERENTIAL: ZONE 1- BASE
RATE. ZONE 2: $2.00. BASE POINTS: SPOKANE, PASCO,
LEWISTON. ZONE 1: 0-45 RADIUS MILES FROM THE MAIN
POST OFFICE. ZONE 2: OUTSIDE 45 RADIUS MILES FROM
THE MAIN POST OFFICE. FOOTNOTE A - ANYONE WORKING
ON A HAZMAT JOB, WHERE HAZMAT CERTIFICATION IS
REQUIRED, SHALL BE COMPENSATED AS A PREMIUM, IN

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

ADDITON TO THE CLASSIFICATION WORKING IN AS
FOLLOWS: LEVEL C-D: -$0.50 PER HOUR (THIS IS THE
LOWEST LEVEL OF PROTECTION. THIS LEVEL MAY USE AN
AIR PURIFYING RESPIRATOR OR ADDITIONAL PROTECTIVE
CLOTHING. LEVEL A-B: $1.00 PER HOUR (USES SUPPLIED
AIR IS CONJUNCTION WITH A CHEMICAL SPASH SUIT OR
FULLY ENCAPSULATED SUIT WITH A SELF-CONTAINED
BREATHING APPARATUS. EMPLOYEES SHALL BE PAID HAZMAT
PAY IN INCREMENTS OF FOUR(4) AND EIGHT(8) HOURS.
NOTE: TRUCKS PULLING EQUIPMENT TRAILERS: SHALL
RECEIVE $0.15/HOUR OVER APPLICABLE TRUCK RATE. .....$ 36.91 20.93
TRUCK DRIVERS: GROUP 5- DUMPTOR (OVER 6 YDS.);
LOWBOY (50 TONS & UNDER); SELF-LOADING ROLL OFF;
SEMI-TRUCK & TRAILER; TRACTOR WITH STEER TRAILER;
TRANSIT MIXERS AND TRUCKS HAULING CONCRETE (OVER 6
YDS. TO AN INCLUDING 10 YDS.); TRUCKS, SIDE, END,
BOTTOM AND END DUMP (OVER 12 YDS. TO & INCLUDING 20
YDS.); TRUCK-MOUNTED CRANE (WITH LOAD BEARING
SURFACE EITHER MOUNTED OR PULLED, UP TO 14 TON);
VACUUM TRUCK (SUPER SUCKER, GUZZLER,
(ADAMS, ASOTIN, BENTON, CHELAN, COLUMBIA, DOUGLAS,
FERRY, FRANKLIN, GARFIELD, GRANT KITTITAS, LINCOLN,
OKANOGAN, PEND OREILLE, SPOKANE, STEVENS, WALLA
WALLA, WHITMAN AND YAKIMA COUNTIES) (AREA 2: PASCO
ZONE CENTER: BENTON, FRANKLIN, WALLA WALLA AND
YAKIMA COUNTIES). ZONE DIFFERENTIAL: ZONE 1- BASE
RATE. ZONE 2: $2.00. BASE POINTS: SPOKANE, PASCO,
LEWISTON. ZONE 1: 0-45 RADIUS MILES FROM THE MAIN
POST OFFICE. ZONE 2: OUTSIDE 45 RADIUS MILES FROM
THE MAIN POST OFFICE. FOOTNOTE A - ANYONE WORKING
ON A HAZMAT JOB, WHERE HAZMAT CERTIFICATION IS
REQUIRED, SHALL BE COMPENSATED AS A PREMIUM, IN
ADDITON TO THE CLASSIFICATION WORKING IN AS
FOLLOWS: LEVEL C-D: -$0.50 PER HOUR (THIS IS THE
LOWEST LEVEL OF PROTECTION. THIS LEVEL MAY USE AN
AIR PURIFYING RESPIRATOR OR ADDITIONAL PROTECTIVE
CLOTHING. LEVEL A-B: $1.00 PER HOUR (USES SUPPLIED
AIR IS CONJUNCTION WITH A CHEMICAL SPASH SUIT OR
FULLY ENCAPSULATED SUIT WITH A SELF-CONTAINED
BREATHING APPARATUS. EMPLOYEES SHALL BE PAID HAZMAT
PAY IN INCREMENTS OF FOUR(4) AND EIGHT(8) HOURS.
NOTE: TRUCKS PULLING EQUIPMENT TRAILERS: SHALL
RECEIVE $0.15/HOUR OVER APPLICABLE TRUCK RATE. .....$ 37.02 20.93
TRUCK DRIVERS: GROUP 6- FLAHERTY SPREADER BOX
DRIVER; FLOWBOYS; FORK LIFT (OVER 16,000 LBS.);
DUMPS (SEMI-END); MECHANIC (FIELD); SEMI-END DUMPS;
TRANSFER TRUCK & TRAILER; TRANSIT MIXERS & TRUCKS
HAULING CONCRETE (OVER 10 YDS. TO & INCLUDING 20
YDS.); TRUCKS, SIDE, END, BOTTOM AND ARTICULATED
END DUMP (OVER 20 YDS. TO & INCLUDING 40 YDS.);
TRUCK AND PUP; TOURNAROCKER, DWS & SIMILAR WITH 2
OR MORE 4 WHEEL-POWER TRACKTOR WITH TRAILER,
GALLONAGE OR YARDAGE SCALE, WHICHEVER IS GREATER
WATER TANK TRUCK (8,001- 14,000 GALLONS); LOWBOY
(OVER 50
(ADAMS, ASOTIN, BENTON, CHELAN, COLUMBIA, DOUGLAS,

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

FERRY, FRANKLIN, GARFIELD, GRANT KITTITAS, LINCOLN, OKANOGAN, PEND OREILLE, SPOKANE, STEVENS, WALLA WALLA, WHITMAN AND YAKIMA COUNTIES) (AREA 2: PASCO ZONE CENTER: BENTON, FRANKLIN, WALLA WALLA AND YAKIMA COUNTIES). ZONE DIFFERENTIAL: ZONE 1- BASE RATE. ZONE 2: $2.00. BASE POINTS: SPOKANE, PASCO, LEWISTON. ZONE 1: 0-45 RADIUS MILES FROM THE MAIN POST OFFICE. ZONE 2: OUTSIDE 45 RADIUS MILES FROM THE MAIN POST OFFICE. FOOTNOTE A - ANYONE WORKING ON A HAZMAT JOB, WHERE HAZMAT CERTIFICATION IS REQUIRED, SHALL BE COMPENSATED AS A PREMIUM, IN ADDITON TO THE CLASSIFICATION WORKING IN AS FOLLOWS: LEVEL C-D: -$0.50 PER HOUR (THIS IS THE LOWEST LEVEL OF PROTECTION. THIS LEVEL MAY USE AN AIR PURIFYING RESPIRATOR OR ADDITIONAL PROTECTIVE CLOTHING. LEVEL A-B: $1.00 PER HOUR (USES SUPPLIED AIR IS CONJUNCTION WITH A CHEMICAL SPASH SUIT OR FULLY ENCAPSULATED SUIT WITH A SELF-CONTAINED BREATHING APPARATUS. EMPLOYEES SHALL BE PAID HAZMAT PAY IN INCREMENTS OF FOUR(4) AND EIGHT(8) HOURS. NOTE: TRUCKS PULLING EQUIPMENT TRAILERS: SHALL RECEIVE $0.15/HOUR OVER APPLICABLE TRUCK RATE. .....$ 37.22 20.93

TRUCK DRIVERS: GROUP 7- OIL DISTRIBUTOR DRIVER; STRINGER TRUCK (CABLE OPERATED TRAILER); TRANSIT MIXERS & TRUCKS HAULING CONCRETE (OVER 20 YDS.); TRUCK, SIDE, END, BOTTOM END DUMP (OVER 40 YDS. TO & INCLUDING 100 YDS.); TRUCK MOUNTED CRANE (WITH LOAD BEARING SURFACE EITHER MOUNTED OR PULLED (16 THROUGH 25
(ADAMS, ASOTIN, BENTON, CHELAN, COLUMBIA, DOUGLAS, FERRY, FRANKLIN, GARFIELD, GRANT KITTITAS, LINCOLN, OKANOGAN, PEND OREILLE, SPOKANE, STEVENS, WALLA WALLA, WHITMAN AND YAKIMA COUNTIES) (AREA 2: PASCO ZONE CENTER: BENTON, FRANKLIN, WALLA WALLA AND YAKIMA COUNTIES). ZONE DIFFERENTIAL: ZONE 1- BASE RATE. ZONE 2: $2.00. BASE POINTS: SPOKANE, PASCO, LEWISTON. ZONE 1: 0-45 RADIUS MILES FROM THE MAIN POST OFFICE. ZONE 2: OUTSIDE 45 RADIUS MILES FROM THE MAIN POST OFFICE. FOOTNOTE A - ANYONE WORKING ON A HAZMAT JOB, WHERE HAZMAT CERTIFICATION IS REQUIRED, SHALL BE COMPENSATED AS A PREMIUM, IN ADDITON TO THE CLASSIFICATION WORKING IN AS FOLLOWS: LEVEL C-D: -$0.50 PER HOUR (THIS IS THE LOWEST LEVEL OF PROTECTION. THIS LEVEL MAY USE AN AIR PURIFYING RESPIRATOR OR ADDITIONAL PROTECTIVE CLOTHING. LEVEL A-B: $1.00 PER HOUR (USES SUPPLIED AIR IS CONJUNCTION WITH A CHEMICAL SPASH SUIT OR FULLY ENCAPSULATED SUIT WITH A SELF-CONTAINED BREATHING APPARATUS. EMPLOYEES SHALL BE PAID HAZMAT PAY IN INCREMENTS OF FOUR(4) AND EIGHT(8) HOURS. NOTE: TRUCKS PULLING EQUIPMENT TRAILERS: SHALL RECEIVE $0.15/HOUR OVER APPLICABLE TRUCK RATE. .....$ 37.56 20.93

TRUCK DRIVERS: GROUP 8- PRIME MOVERS AND STINGER TRUCK; TRUCKS, SIDE, END, BOTTOM AND ARTICULATED END DUMP (OVER 100 YDS.); HELICOPTER PILOT HAULING EMPLOYEES OR

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

(ADAMS, ASOTIN, BENTON, CHELAN, COLUMBIA, DOUGLAS,
FERRY, FRANKLIN, GARFIELD, GRANT KITTITAS, LINCOLN,
OKANOGAN, PEND OREILLE, SPOKANE, STEVENS, WALLA
WALLA, WHITMAN AND YAKIMA COUNTIES) (AREA 2: PASCO
ZONE CENTER: BENTON, FRANKLIN, WALLA WALLA AND
YAKIMA COUNTIES). ZONE DIFFERENTIAL: ZONE 1- BASE
RATE. ZONE 2: $2.00. BASE POINTS: SPOKANE, PASCO,
LEWISTON. ZONE 1: 0-45 RADIUS MILES FROM THE MAIN
POST OFFICE. ZONE 2: OUTSIDE 45 RADIUS MILES FROM
THE MAIN POST OFFICE. FOOTNOTE A - ANYONE WORKING
ON A HAZMAT JOB, WHERE HAZMAT CERTIFICATION IS
REQUIRED, SHALL BE COMPENSATED AS A PREMIUM, IN
ADDITON TO THE CLASSIFICATION WORKING IN AS
FOLLOWS: LEVEL C-D: -$0.50 PER HOUR (THIS IS THE
LOWEST LEVEL OF PROTECTION. THIS LEVEL MAY USE AN
AIR PURIFYING RESPIRATOR OR ADDITIONAL PROTECTIVE
CLOTHING. LEVEL A-B: $1.00 PER HOUR (USES SUPPLIED
AIR IS CONJUNCTION WITH A CHEMICAL SPASH SUIT OR
FULLY ENCAPSULATED SUIT WITH A SELF-CONTAINED
BREATHING APPARATUS. EMPLOYEES SHALL BE PAID HAZMAT
PAY IN INCREMENTS OF FOUR(4) AND EIGHT(8) HOURS.
NOTE: TRUCKS PULLING EQUIPMENT TRAILERS: SHALL
RECEIVE $0.15/HOUR OVER APPLICABLE TRUCK RATE. .....$ 37.88 20.93

WELDERS - Receive rate prescribed for craft performing
operation to which welding is incidental.
==========
Note: Executive Order (EO) 13706, Establishing Paid Sick Leave
for Federal Contractors applies to all contracts subject to the
Davis-Bacon Act for which the contract is awarded (and any
solicitation was issued) on or after January 1, 2017. If this
contract is covered by the EO, the contractor must provide
employees with 1 hour of paid sick leave for every 30 hours
they work, up to 56 hours of paid sick leave each year.
Employees must be permitted to use paid sick leave for their
own illness, injury or other health-related needs, including
preventive care; to assist a family member (or person who is
like family to the employee) who is ill, injured, or has other
health-related needs, including preventive care; or for reasons
resulting from, or to assist a family member (or person who is
like family to the employee) who is a victim of, domestic
violence, sexual assault, or stalking. Additional information
on contractor requirements and worker protections under the EO
is available at https://www.dol.gov/agencies/whd/government-contracts.

Note: Executive Order 13658 generally applies to contracts subject
to the Davis-Bacon Act that were awarded on or between January 1,
2015 and January 29, 2022, and that have not been renewed or
extended on or after January 30, 2022. Executive Order 13658 does
not apply to contracts subject only to the Davis-Bacon Related Acts
regardless of when they were awarded. If a contract is subject to
Executive Order 13658, the contractor must pay all covered workers
at least $13.65 per hour (or the applicable wage rate listed on this

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

wage determination, if it is higher) for all hours spent performing on the contract from May 11, 2026, through December 31, 2026. The applicable Executive Order minimum wage rate will be adjusted annually. Additional information on contractor requirements and worker protections under Executive Order 13658 is available at www.dol.gov/whd/govcontracts.

Unlisted classifications needed for work not included within the scope of the classifications listed may be added after award only as provided in the labor standards contract clauses (29CFR 5.5 (a) (1) (iii)).

The body of each wage determination lists the classifications and wage rates that have been found to be prevailing for the type(s) of construction and geographic area covered by the wage determination. The classifications are listed in alphabetical order under rate identifiers indicating whether the particular rate is a union rate (current union negotiated rate), a survey rate, a weighted union average rate, a state adopted rate, or a supplemental classification rate.

Union Rate Identifiers

A four-letter identifier beginning with characters other than "SU", "UAVG", "SA", or "SC" denotes that a union rate was prevailing for that classification in the survey. Example: PLUM0198-005 07/01/2024. PLUM is an identifier of the union whose collectively bargained rate prevailed in the survey for this classification, which in this example would be Plumbers. 0198 indicates the local union number or district council number where applicable, i.e., Plumbers Local 0198. The next number, 005 in the example, is an internal number used in processing the wage determination. The date, 07/01/2024 in the example, is the effective date of the most current negotiated rate.

Union prevailing wage rates are updated to reflect all changes over time that are reported to WHD in the rates in the collective bargaining agreement (CBA) governing the classification.

Union Average Rate Identifiers

The UAVG identifier indicates that no single rate prevailed for those classifications, but that 100% of the data reported for the classifications reflected union rates. EXAMPLE: UAVG-OH-0010 01/01/2024. UAVG indicates that the rate is a weighted union average rate. OH indicates the State of Ohio. The next number, 0010 in the example, is an internal number used in producing the wage determination. The date, 01/01/2024 in the example, indicates the date the wage determination was updated to reflect the most current union average rate.

A UAVG rate will be updated once a year, usually in January, to reflect a weighted average of the current rates in the

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

collective bargaining agreements on which the rate is based.

Survey Rate Identifiers

The "SU" identifier indicates that either a single non-union rate prevailed (as defined in 29 CFR 1.2) for this classification in the survey or that the rate was derived by computing a weighted average rate based on all the rates reported in the survey for that classification. As a weighted average rate includes all rates reported in the survey, it may include both union and non-union rates. Example: SUFL2022-007 6/27/2024. SU indicates the rate is a single non-union prevailing rate or a weighted average of survey data for that classification. FL indicates the State of Florida. 2022 is the year of the survey on which these classifications and rates are based. The next number, 007 in the example, is an internal number used in producing the wage determination. The date, 6/27/2024 in the example, indicates the survey completion date for the classifications and rates under that identifier.

"SU" wage rates typically remain in effect until a new survey is conducted. However, the Wage and Hour Division (WHD) has the discretion to update such rates under 29 CFR 1.6(c)(1).

State Adopted Rate Identifiers

The "SA" identifier indicates that the classifications and prevailing wage rates set by a state (or local) government were adopted under 29 C.F.R 1.3(g)-(h). Example: SAME2023-007 01/03/2024. SA reflects that the rates are state adopted. ME refers to the State of Maine. 2023 is the year during which the state completed the survey on which the listed classifications and rates are based. The next number, 007 in the example, is an internal number used in producing the wage determination. The date, 01/03/2024 in the example, reflects the date on which the classifications and rates under the "SA" identifier took effect under state law in the state from which the rates were adopted.

WAGE DETERMINATION APPEALS PROCESS

1) Has there been an initial decision in the matter? This can be:

a) a survey underlying a wage determination
b) an existing published wage determination
c) an initial WHD letter setting forth a position on a wage determination matter
d) an initial conformance (additional classification and rate) determination

On survey related matters, initial contact, including requests for summaries of surveys, should be directed to the WHD Branch of Wage Surveys. Requests can be submitted via email to davisbaconinfo@dol.gov or by mail to:

Branch of Wage Surveys
Wage and Hour Division
U.S. Department of Labor

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

200 Constitution Avenue, N.W.
Washington, DC 20210
Regarding any other wage determination matter such as conformance decisions, requests for initial decisions should be directed to the WHD Branch of Construction Wage Determinations. Requests can be submitted via email to BCWD-Office@dol.gov or by mail to:
Branch of Construction Wage Determinations
Wage and Hour Division
U.S. Department of Labor
200 Constitution Avenue, N.W.
Washington, DC 20210
2) If an initial decision has been issued, then any interested party (those affected by the action) that disagrees with the decision can request review and reconsideration from the Wage and Hour Administrator (See 29 CFR Part 1.8 and 29 CFR Part 7). Requests for review and reconsideration can be submitted via email to dba.reconsideration@dol.gov or by mail to:
Wage and Hour Administrator
U.S. Department of Labor
200 Constitution Avenue, N.W.
Washington, DC 20210
The request should be accompanied by a full statement of the interested party's position and any information (wage payment data, project description, area practice material, etc.) that the requestor considers relevant to the issue.

3) If the decision of the Administrator is not favorable, an interested party may appeal directly to the Administrative Review Board (formerly the Wage Appeals Board). Write to:
Administrative Review Board
U.S. Department of Labor
200 Constitution Avenue, N.W.
Washington, DC 20210.
==
END OF GENERAL DECISION
"

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

State of Washington
Department of Labor & Industries
Prevailing Wage Section - Telephone 360-902-5335
PO Box 44540, Olympia, WA 98504-4540

Washington State Prevailing Wage

The PREVAILING WAGES listed here include both the hourly wage rate and the hourly rate of fringe benefits. On public works projects, worker's wage and benefit rates must add to not less than this total. A brief description of overtime calculation requirements are provided on the Benefit Code Key.

Journey Level Prevailing Wage Rates for the Effective Date: 10/06/2026

Clark County

Trade	Job Classification	Wage	Holiday	Overtime	Note	Risk Class
Asbestos Abatement Workers	Journey Level	$65.48	**6Z**	**11Z**		**View**
Boilermakers	Journey Level	$77.39	**5N**	**1C**		**View**
Brick Mason	Brick Finisher	$51.13	**5A**	**1B**		**View**
Brick Mason	Caulker-Pointer-Cleaner	$79.19	**5A**	**1B**		**View**
Brick Mason	Journey Level	$79.19	**5A**	**1B**		**View**
Building Service Employees	Janitor	$24.14	**6G**	**1**		**View**
Building Service Employees	Shampooer	$24.14	**6G**	**1**		**View**
Building Service Employees	Waxer	$24.14	**6G**	**1**		**View**
Building Service Employees	Window Cleaner	$31.56	**6G**	**1**		**View**

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Cabinet Makers (In Shop)	Journey Level	$17.13		1		View
Carpenters	Acoustical Worker	$74.70	15J	11U	9L	View
Carpenters	Bridge & Highway Carpenter	$76.07	15J	11U	9L	View
Carpenters	Floor Layer And Floor Finishers	$74.87	15J	11U	9L	View
Carpenters	General Carpenter	$74.70	15J	11U	9L	View
Carpenters	Scaffold/Shoring Erecting & Dismantling	$74.70	15J	11U	9L	View
Carpenters	Stationary Power Saw	$74.87	15J	11U	9L	View
Cement Masons	Journey Level	$71.52	7E	1H		View
Divers & Tenders	Assistant Tender	$82.35	15J	11T	9I	View
Divers & Tenders	Bell/Vehicle or Submersible Operator Not Under Pressure	$131.93	15J	11T	9I	View
Divers & Tenders	Dive Master	$101.29	15J	11T	9I	View
Divers & Tenders	Dive Supervisor	$133.43	15J	11T	9I	View
Divers & Tenders	Diver Diving	$131.93	15J	11T	9I	View
Divers & Tenders	Diver Tender	$87.92	15J	11T	9I	View
Divers & Tenders	Divers Including Stand-By Diver	$96.29	15J	11T	9I	View
Divers & Tenders	Manifold Operator	$92.92	15J	11T	9I	View

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Divers & Tenders	Manifold Operator Mixed Gas	$90.92	**15J**	**11T**	**9I**	**View**
Divers & Tenders	ROV Operator	$87.92	**15J**	**11T**	**9I**	**View**
Divers & Tenders	ROV Tender/Technician	$82.35	**15J**	**11T**	**9I**	**View**
Dredge Workers	Assistant Engineer	$76.19	**5D**	**1N**	**8D**	**View**
Dredge Workers	Assistant Mate (deckhand)	$70.83	**5D**	**1N**	**8D**	**View**
Dredge Workers	Boatman (licensed)	$76.19	**5D**	**1N**	**8D**	**View**
Dredge Workers	Fill Equipment Operator	$73.53	**5D**	**1N**	**8D**	**View**
Dredge Workers	Fireman	$74.70	**5D**	**1N**	**8D**	**View**
Dredge Workers	Leverman (hydraulic & Clamshell)	$79.35	**5D**	**1N**	**8D**	**View**
Dredge Workers	Mate	$76.19	**5D**	**1N**	**8D**	**View**
Dredge Workers	Oiler	$70.83	**5D**	**1N**	**8D**	**View**
Dredge Workers	Tenderman (boatman Attending Dredge Plant)	$74.70	**5D**	**1N**	**8D**	**View**
Dredge Workers	Welder	$76.19	**5D**	**1N**	**8D**	**View**
Drywall Applicator	Journey Level	$74.80	**5A**	**1B**		**View**
Drywall Tapers	Journey Level	$72.95	**7E**	**1E**		**View**
Electrical Fixture Maintenance Workers	Journey Level	$26.96		**1**		**View**

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Electricians - Inside	Journey Level	$99.74	5A	1B		View
Electricians - Inside	Journeyman, Welder	$106.48	5A	1B		View
Electricians - Motor Shop	Craftsman	$17.13		1		View
Electricians - Motor Shop	Journey Level	$17.13		1		View
Electricians - Powerline Construction	Cable Splicer	$107.31	5A	4D		View
Electricians - Powerline Construction	Certified Line Welder	$98.45	5A	4D		View
Electricians - Powerline Construction	Groundperson	$61.75	5A	4D		View
Electricians - Powerline Construction	Heavy Line Equipment Operator	$98.45	5A	4D		View
Electricians - Powerline Construction	Journey Level Lineperson	$98.45	5A	4D		View
Electricians - Powerline Construction	Line Equipment Operator	$84.94	5A	4D		View
Electricians - Powerline Construction	Meter Installer	$61.75	5A	4D	8W	View
Electricians - Powerline Construction	Pole Sprayer	$98.45	5A	4D		View
Electricians - Powerline Construction	Powderperson	$72.81	5A	4D		View
Electronic Technicians	Journey Level	$83.46	5A	1B		View
Elevator Constructors	Mechanic	$119.67	5N	4A		View
Elevator Constructors	Mechanic In Charge	$129.52	5N	4A		View

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Fabricated Precast Concrete Products	Journey Level	$17.13		1		View
Fabricated Precast Concrete Products	Journey Level - In-Factory Work Only	$17.13		1		View
Fence Erectors	Fence Erector	$60.14	6Z	11Z	90	View
Fence Erectors	Fence Laborer	$60.14	6Z	11Z	90	View
Flaggers	Journey Level	$60.14	6Z	11Z	90	View
Glaziers	Journey Level	$78.46	7I	11K		View
Heat & Frost Insulators And Asbestos Workers	Mechanic	$87.79	5N	1F		View
Heating Equipment Mechanics	Mechanic	$95.17	5A	1B		View
Hod Carriers & Mason Tenders	Journey Level	$68.02	5D	1B		View
Industrial Power Vacuum Cleaner	Journey Level	$18.50		1		View
Inland Boatmen	Boat Operator	$71.28	5B	1K		View
Inland Boatmen	Cook	$69.70	5B	1K		View
Inland Boatmen	Deckhand	$70.00	5B	1K		View
Inland Boatmen	Deckhand Engineer	$69.55	5B	1K		View
Inland Boatmen	Launch Operator	$71.23	5B	1K		View
Inland Boatmen	Mate	$89.12	5B	1K		View

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Inspection/Cleaning/Sealing Of Sewer & Water Systems By Remote Control	Cleaner Operator, Foamer Operator	$17.13	1	View
Inspection/Cleaning/Sealing Of Sewer & Water Systems By Remote Control	Cleaner Operator, Foamer Operator	$17.13	1	View
Inspection/Cleaning/Sealing Of Sewer & Water Systems By Remote Control	Grout Truck Operator	$17.13	1	View
Inspection/Cleaning/Sealing Of Sewer & Water Systems By Remote Control	Grout Truck Operator	$17.13	1	View
Inspection/Cleaning/Sealing Of Sewer & Water Systems By Remote Control	Head Operator	$17.13	1	View
Inspection/Cleaning/Sealing Of Sewer & Water Systems By Remote Control	Head Operator	$17.13	1	View
Inspection/Cleaning/Sealing Of Sewer & Water Systems By Remote Control	Technician	$17.39	1	View
Inspection/Cleaning/Sealing Of Sewer & Water Systems By Remote Control	Technician	$17.39	1	View
Inspection/Cleaning/Sealing Of Sewer & Water Systems By Remote Control	Tv Truck Operator	$17.13	1	View
Inspection/Cleaning/Sealing Of Sewer & Water Systems By Remote Control	Tv Truck Operator	$17.13	1	View

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Insulation Applicators	Journey Level	$74.87	**15J**	**11U**	**9L**	**View**
Ironworkers	Journey Level	$85.13	**15K**	**11N**		**View**
Laborers	Anchor Machines	$65.48	**6Z**	**11Z**		**View**
Laborers	Application (Including Pot Power Tender For Same), Applying Protective Material By Hand Or Nozzle On Utility Lines Or Storage Tanks On Project	$64.79	**6Z**	**11Z**		**View**
Laborers	Asbestos Removal	$65.48	**6Z**	**11Z**		**View**
Laborers	Asphalt Plant Laborers	$63.89	**6Z**	**11Z**		**View**
Laborers	Asphalt Raker	$66.05	**6Z**	**11Z**		**View**
Laborers	Asphalt Spreaders	$63.89	**6Z**	**11Z**		**View**
Laborers	Ballast Regulators	$65.48	**6Z**	**11Z**		**View**
Laborers	Batch Weighman	$63.89	**6Z**	**11Z**		**View**
Laborers	Bit Grinder	$65.48	**6Z**	**11Z**		**View**
Laborers	Brick Pavers (Dry)	$63.89	**6Z**	**11Z**		**View**
Laborers	Broomers	$63.89	**6Z**	**11Z**		**View**
Laborers	Brush (Power Saw)	$64.79	**6Z**	**11Z**		**View**
Laborers	Brush Burners And Cutters	$63.89	**6Z**	**11Z**		**View**
Laborers	Burners	$64.79	**6Z**	**11Z**		**View**

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Laborers	Car And Truck Loaders	$63.89	6Z	11Z	View
Laborers	Carpenter Tender	$63.89	6Z	11Z	View
Laborers	Change-house Man Or Dry Shack Man	$63.89	6Z	11Z	View
Laborers	Chipping Guns	$64.79	6Z	11Z	View
Laborers	Choker Setters	$63.89	6Z	11Z	View
Laborers	Choker Splicer	$64.79	6Z	11Z	View
Laborers	Chuck Tender	$64.79	6Z	11Z	View
Laborers	Clary Power Spreader And Similar Types	$64.79	6Z	11Z	View
Laborers	Clean Up Laborers	$63.89	6Z	11Z	View
Laborers	Clean-up Nozzleman-Green-Cutter (Concrete Rock, Etc.)	$64.79	6Z	11Z	View
Laborers	Concrete Crew, Bull Gang	$64.79	6Z	11Z	View
Laborers	Concrete Laborers	$64.79	6Z	11Z	View
Laborers	Concrete Nozzlemen	$66.05	6Z	11Z	View
Laborers	Concrete Power Buggyman	$64.79	6Z	11Z	View
Laborers	Concrete Saw Operator	$65.48	6Z	11Z	View
Laborers	Concrete Saw Operator (Walls)	$66.05	6Z	11Z	View

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Laborers	Confined Space / Hole Watch	$60.14	6Z	11Z	90	View
Laborers	Crusher Feeder	$64.79	6Z	11Z		View
Laborers	Curing, Concrete	$63.89	6Z	11Z		View
Laborers	Demolition And Wrecking Charred Materials	$64.79	6Z	11Z		View
Laborers	Demolition, Wrecking And Moving Laborers	$63.89	6Z	11Z		View
Laborers	Drill Doctor	$65.48	6Z	11Z		View
Laborers	Drill Operators, Air Tracks, Cat Drills, Wagon Drills, Rubber-mounted Drills And Other Similar Types, Including At Crusher Plants	$66.05	6Z	11Z		View
Laborers	Dry Pack Machine	$64.79	6Z	11Z		View
Laborers	Dry Stack Walls	$63.89	6Z	11Z		View
Laborers	Dumpers, Road Oiling Crew	$63.89	6Z	11Z		View
Laborers	Dumpmen (for Grading Crew)	$63.89	6Z	11Z		View
Laborers	Elevator Feeders	$63.89	6Z	11Z		View
Laborers	Erosion Control Specialist	$63.89	6Z	11Z		View

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Laborers	Final Clean-up	$60.14	6Z	11Z	90	View
Laborers	Fine Graders	$63.89	6Z	11Z		View
Laborers	Fire Watch	$60.14	6Z	11Z	90	View
Laborers	Form Strippers (Not Swinging Stages)	$63.89	6Z	11Z		View
Laborers	General Laborer	$63.89	6Z	11Z		View
Laborers	Grade Checker	$66.05	6Z	11Z		View
Laborers	Guard Rail, Median Rail, Reference Post Guide Post, Right-of-way Marker	$63.89	6Z	11Z		View
Laborers	Gunite Nozzleman	$66.05	6Z	11Z		View
Laborers	Gunite Nozzleman Tender	$64.79	6Z	11Z		View
Laborers	Gunite or Sand Blasting Pot Tender	$64.79	6Z	11Z		View
Laborers	Hand Placed Sand Blasting (Wet)	$64.79	6Z	11Z		View
Laborers	Handlers Or Mixers Of All Materials Of An Irritating Nature (Including Cement & Lime)	$64.79	6Z	11Z		View
Laborers	Hazardous Waste Worker	$65.48	6Z	11Z		View
Laborers	High Scalers, Strippers & Drillers (covers work	$66.05	6Z	11Z		View

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

	in swinging stages, chairs or belts under extreme conditions unusual to normal drilling, blasting, barring down or slopping and stripping				
Laborers	Laser Beam	$66.05	**6Z**	**11Z**	**View**
Laborers	Laser Beam (Pipe Laying) - Applicable When Employee Assigned To Move, Set Up, Align	$66.05	**6Z**	**11Z**	**View**
Laborers	Laser Beam (Tunnel) - Applicable When Employee Assigned To Move, Set Up, Align	$66.05	**6Z**	**11Z**	**View**
Laborers	Lead Abatement	$65.48	**6Z**	**11Z**	**View**
Laborers	Leverman Or Aggregate Spreaders (Flaherty And Similar Types)	$63.89	**6Z**	**11Z**	**View**
Laborers	Loading Spotters	$63.89	**6Z**	**11Z**	**View**
Laborers	Loop Installation	$66.05	**6Z**	**11Z**	**View**
Laborers	Manhole Building	$65.48	**6Z**	**11Z**	**View**
Laborers	Material Yard Man	$63.89	**6Z**	**11Z**	**View**
Laborers	Miner - Tunnel	$66.05	**6Z**	**11Z**	**View**

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Laborers	Mold Remediation Or Removal	$65.48	6Z	11Z		View
Laborers	Nippers And Timbermen	$65.48	6Z	11Z		View
Laborers	Nuclear Plant Workers - Lead Shield, Power Saw Operators (Bucking & Falling)	$65.48	6Z	11Z		View
Laborers	Pilot Car	$60.14	6Z	11Z	90	View
Laborers	Pipe Doping & Wrapping	$64.79	6Z	11Z		View
Laborers	Pipe Layer All Types	$66.05	6Z	11Z		View
Laborers	Pittsburgh Chipper Operator Or Similar Types	$63.89	6Z	11Z		View
Laborers	Post Hold Digger, Air, Gas Or Electric	$64.79	6Z	11Z		View
Laborers	Powderman - Tunnel	$66.05	6Z	11Z		View
Laborers	Powderman Tender	$63.89	6Z	11Z		View
Laborers	Power Jacks	$65.48	6Z	11Z		View
Laborers	Pressure Washer	$64.79	6Z	11Z		View
Laborers	Railroad Track Laborers	$63.89	6Z	11Z		View
Laborers	Ribbon Setter, Head	$64.79	6Z	11Z		View
Laborers	Ribbon Setters (Including Steel Forms)	$63.89	6Z	11Z		View

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Laborers	Rigger/Signalperson	$63.89	6Z	11Z	View
Laborers	Rip Rap Man (Hand Packed)	$63.89	6Z	11Z	View
Laborers	Rip Rap Man (Head)	$64.79	6Z	11Z	View
Laborers	Road Pump Tender	$63.89	6Z	11Z	View
Laborers	Sand Blasting (Dry)	$65.48	6Z	11Z	View
Laborers	Scaffold Tender	$63.89	6Z	11Z	View
Laborers	Sewer Labor	$63.89	6Z	11Z	View
Laborers	Sewer Timbermen	$65.48	6Z	11Z	View
Laborers	Signalman	$63.89	6Z	11Z	View
Laborers	Skipman	$63.89	6Z	11Z	View
Laborers	Slopers	$63.89	6Z	11Z	View
Laborers	Spraymen	$63.89	6Z	11Z	View
Laborers	Stake Chaser	$63.89	6Z	11Z	View
Laborers	Stake-setter	$64.79	6Z	11Z	View
Laborers	Stockpiler	$63.89	6Z	11Z	View
Laborers	Tampers	$64.79	6Z	11Z	View
Laborers	Tie Back Shoring	$64.79	6Z	11Z	View
Laborers	Timber Faller And Bucker (Hand Labor)	$63.89	6Z	11Z	View

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Laborers	Tool Operators - Jackhammer	$64.79	6Z	11Z	View
Laborers	Tool Operators - Paving Breakers	$64.79	6Z	11Z	View
Laborers	Toolroom Man (At Job Site)	$63.89	6Z	11Z	View
Laborers	Track Liners	$65.48	6Z	11Z	View
Laborers	Traffic Control Laborer	$63.89	6Z	11Z	View
Laborers	Traffic Control Supervisor	$64.79	6Z	11Z	View
Laborers	Traffic Control Supervisor	$64.79	6Z	11Z	View
Laborers	Truck Mounted Attenuator	$63.89	6Z	11Z	View
Laborers	Tugger Operator	$65.48	6Z	11Z	View
Laborers	Tunnel Bullgang (Above Ground)	$66.05	6Z	11Z	View
Laborers	Tunnel Chuck Tenders	$66.05	6Z	11Z	View
Laborers	Tunnel Motorman - Dinky Locomotive	$66.05	6Z	11Z	View
Laborers	Tunnel Muckers, Brakemen	$66.05	6Z	11Z	View
Laborers	Tunnel Shield Operator	$66.05	6Z	11Z	View
Laborers	Vibrating Screed	$66.05	6Z	11Z	View
Laborers	Vibrators (All Types)	$66.05	6Z	11Z	View

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Laborers	Water Blaster	$65.48	6Z	11Z		View
Laborers	Weight-Man-Crusher (Aggregate When Used)	$63.89	6Z	11Z		View
Laborers	Welder	$65.48	6Z	11Z		View
Laborers - Underground Sewer & Water	General Laborer and Topman	$66.05	6Z	11Z		View
Landscape Construction	Landscape Operator	$71.91	7B	4G	8U	View
Landscape Construction	Landscaping or Planting Laborer	$51.68	6Z	11Z	9O	View
Landscape Maintenance	Groundskeeper	$17.13		1		View
Lathers	Journey Level	$74.80	5A	1B		View
Marble Setters	Journey Level	$80.19	5A	1B		View
Metal Fabrication (In Shop)	Fitter	$43.03	6H	1E		View
Metal Fabrication (In Shop)	Laborer	$31.76	6H	1E		View
Metal Fabrication (In Shop)	Layerout	$47.96	6H	1E		View
Metal Fabrication (In Shop)	Machine Operator	$43.43	6H	1E		View
Metal Fabrication (In Shop)	Painter	$40.73	6H	1E		View
Metal Fabrication (In Shop)	Welder	$43.03	6H	1E		View
Millwright	Journey Level	$88.90	5A	1B		View
Modular Buildings	Journey Level	$17.13		1		View

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Painters	Bridge Painter	$65.29	7E	11L		View
Painters	Commercial Painter	$55.64	7E	11L		View
Painters	Industrial Painter	$57.86	7E	11L	9F	View
Pile Driver	Journey Level	$76.07	15J	11U	9L	View
Plasterers	Journey Level	$68.69	5H	1E		View
Playground & Park Equipment Installers	Journey Level	$17.13		1		View
Plumbers & Pipefitters	Journey Level	$99.52	5Z	10		View
Power Equipment Operators	Air Filtration Equipment(group 6)	$68.69	7B	4G	8U	View
Power Equipment Operators	Asphalt Plant (any Type) (assistant Engineer Required) (group 2)	$77.63	7B	4G	8U	View
Power Equipment Operators	Asphalt, Burner & Reconditioner (any Type), (asst To Engineer If Required) (group 5)	$71.91	7B	4G	8U	View
Power Equipment Operators	Asphalt, Extrusion Machine Operator(group 5)	$71.91	7B	4G	8U	View
Power Equipment Operators	Asphalt, Paver (screed Man Required)(group 4)	$73.15	7B	4G	8U	View
Power Equipment Operators	Asphalt, Pugmill (any Type)(group 6)	$68.69	7B	4G	8U	View

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Power Equipment Operators	Asphalt, Raker(group 6)	$68.69	7B	4G	8U	View
Power Equipment Operators	Asphalt, Roller (any Asphalt Mix)(group 5)	$71.91	7B	4G	8U	View
Power Equipment Operators	Asphalt, Roto-mill, Pavement Profiler Under 8 Ft Lateral Cut(group 4)	$73.15	7B	4G	8U	View
Power Equipment Operators	Asphalt, Roto-mill, Pavement Profiler, 8 Ft Lateral Cut & Over(group 2)	$77.63	7B	4G	8U	View
Power Equipment Operators	Asphalt, Roto-mill, Pavement Profiler, Groundman(group 5)	$71.91	7B	4G	8U	View
Power Equipment Operators	Asphalt, Screed(group 4)	$73.15	7B	4G	8U	View
Power Equipment Operators	Asphalt, Truck Mounted Spreader, With Screed(group 6)	$68.69	7B	4G	8U	View
Power Equipment Operators	Auger Oiler(group 6)	$68.69	7B	4G	8U	View
Power Equipment Operators	Auto Grader Or "trimmer" (grade Checker Required) (group 2)	$77.63	7B	4G	8U	View
Power Equipment Operators	Back Filling Machine (assistant To Engineer Required)(group 4)	$73.15	7B	4G	8U	View
Power Equipment Operators	Backhoe, Robotic, Track And Wheel Type	$73.15	7B	4G	8U	View

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

	Up To And Including 20,000 Lbs. With Any Attachments(group 4)					
Power Equipment Operators	Band Wagons (in Conjuction With Whell Excavator)(group 2)	$77.63	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Bell Man (any Type Of Comunication)(group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Blade Any Type(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Blade, Robotic(group 2)	$77.63	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Boatman(group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Boatman, Licensed(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Bobcat, Skid Steer (< 1yd)(group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Boom Type Lifting Device, 5 Ton Capacity Or Less(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Boring Machine (asst To Engineer Required) (group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Broom Self-propelled, Construction Job Site(group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Bulldozer Operator, 20,000 Lbs Or Less,	$71.91	**7B**	**4G**	**8U**	**View**

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

	Or 100 Horse Or Less(group 5)					
Power Equipment Operators	Bulldozer Operator, Over 20,000 Lbs And More Than 100 Horse Up To 70,000 Lbs(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Bulldozer Over 70,000 Lbs Up To And Including 120,000 Lbs(group 3)	$76.48	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Bulldozer Over 120,000 Lbs And Above(group 2)	$77.63	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Bulldozer Robotic Equipment(group 2)	$77.63	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Cable-plow (any Type) (group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Cableway 25 Ton & Over(group 2)	$77.63	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Cableway Up To 25 Ton(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Canal Trimmer (grade Oiler Required)(group 2)	$77.63	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Cat Drill (john Henry) (group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Cement Pump(group 5)	$71.91	**7B**	**4G**	**8U**	**View**

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Power Equipment Operators	Challenger(group 4)	$73.15	7B	4G	8U	View
Power Equipment Operators	Chip Spreading Machine(group 5)	$71.91	7B	4G	8U	View
Power Equipment Operators	Chippers (asst To Engineer If Required) (group 4)	$73.15	7B	4G	8U	View
Power Equipment Operators	Churn Drill & Earth Boring Machine(group 5)	$71.91	7B	4G	8U	View
Power Equipment Operators	Combination Heavy Duty Mechanic-welder, When Required To Do Both(group 4)	$73.15	7B	4G	8U	View
Power Equipment Operators	Compactor Self Propelled Without Blade(group 5)	$71.91	7B	4G	8U	View
Power Equipment Operators	Compactor With Blade Self Propelled(group 4)	$73.15	7B	4G	8U	View
Power Equipment Operators	Compactor, Multi-engine(group 4)	$73.15	7B	4G	8U	View
Power Equipment Operators	Compactor, Robotic(group 4)	$73.15	7B	4G	8U	View
Power Equipment Operators	Compressor (any Power) 1,250 Cu Ft And Over Total Capacity(group 5)	$71.91	7B	4G	8U	View
Power Equipment Operators	Compressor Operator (any Power) Under 1,250 Cu Ft Total Capacity(group 6)	$68.69	7B	4G	8U	View

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Power Equipment Operators	Concrete Batch Plant And/or Wet Mix (3 Units Or More) (group1)	$79.54	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Concrete Batch Plant And/or Wet Mix Operator (1 & 2 Drums) (group 2)	$77.63	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Concrete Batch Plant Quality Control(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Concrete Breaker (assistant To Engineer Required)(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Concrete Canal Line, Assistant To Engineer Required(group 2)	$77.63	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Concrete Curing Machine (riding Type) (group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Concrete Diamond Head Profiler(group 2)	$77.63	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Concrete Paving Road Mixer(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Concrete Planer(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Concrete Saw(group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Concrete, Automatic Slip Form Paver (asst To Engineer Required) (group 2)	$77.63	**7B**	**4G**	**8U**	**View**

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Power Equipment Operators	Concrete, Combination Mixer & Compressor Operator, Gunite Work(group 5)	$71.91	7B	4G	8U	View
Power Equipment Operators	Concrete, Curb Machine Mechanical Berm, Curb And/or Curb And Gutter(group 5)	$71.91	7B	4G	8U	View
Power Equipment Operators	Concrete, Finishing Machine(group 5)	$71.91	7B	4G	8U	View
Power Equipment Operators	Concrete, Grout Plant(group 4)	$73.15	7B	4G	8U	View
Power Equipment Operators	Concrete, Grouting Machine(group 5)	$71.91	7B	4G	8U	View
Power Equipment Operators	Concrete, Joint Machine(group 5)	$71.91	7B	4G	8U	View
Power Equipment Operators	Concrete, Mixer Mobile(group 4)	$73.15	7B	4G	8U	View
Power Equipment Operators	Concrete, Mixer Single Drum Any Capacity(group 5)	$71.91	7B	4G	8U	View
Power Equipment Operators	Concrete, Paving Machine 8' And Less (asst To Engineer Required)(group 5)	$71.91	7B	4G	8U	View
Power Equipment Operators	Concrete, Placing Boom(group 5)	$71.91	7B	4G	8U	View
Power Equipment Operators	Concrete, Pump Truck(group 5)	$71.91	7B	4G	8U	View

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Power Equipment Operators	Concrete, Pump(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Concrete, Pumpcrete Operator (any Type) (group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Concrete, Reinforced Tank Banding Machine (asst To Engineer Required)(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Concrete, Slip Form Pumps, Power Driven Hydraulic Lifting Device For Concrete Forms(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Concrete, Spreader(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Concrete, Telebelt(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Concrete, Treated Base Roller Operator, Oiling(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Conveyor Operator Or Assistant(group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Conveyored Material Hauler(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Crane, Bridge Locomotive, Gantry And Overhead(group 4)	$73.15	**7B**	**4G**	**8U**	**View**

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Power Equipment Operators	Crane, Carry Deck(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Crane, Chicago Boom & Similar Types(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Crane, Floating (derrick Barge) 30 Ton But Less Than 150 Ton (asst To Engineer Required)(group 2)	$77.63	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Crane, Floating 150 Ton But Less Than 250 Ton (asst To Engineer Required) (group 1)	$79.54	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Crane, Floating 250 Ton And Over (asst To Engineer And Deckhand Required) (group 1)	$81.70	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Crane, Floating Clamshell 3 Cu. Yds. & Over (fireman Or Diesel Electric Engineer Required(group 2)	$77.63	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Crane, Floating Clamshell, Dragline Etc. Operator Under 3 Cu. Yds. Or Less Than 30 Ton (diesel-electric Engineer Required) (group 4)	$73.15	**7B**	**4G**	**8U**	**View**

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Power Equipment Operators	Crane, Hydraulic 200 Ton Through 399 Ton (group 1)	$79.54	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Crane, Hydraulic 50 Ton Through 89 Ton With Luffing Or Tower Attachment(group 2)	$77.63	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Crane, Hydraulic 50 Ton Through 89 Tons(group 3)	$76.48	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Crane, Hydraulic 90 Ton Through 199 Ton With Luffing Or Tower Attachment (group 1)	$79.54	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Crane, Hydraulic 90 Ton Through 199 Ton(group 2)	$77.63	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Crane, Hydraulic Crane 200 Ton Through 300 Ton With Luffing Or Tower Attachment(group 1)	$81.70	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Crane, Hydraulic Crane 400 Ton And Over(group 1)	$83.86	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Crane, Hydraulic Crane Over 300 Ton Through 399 Ton With Luffer Or Tower Attachment(group 1)	$83.86	**7B**	**4G**	**8U**	**View**

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Power Equipment Operators	Crane, Hydraulic Under 50 Ton(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Crane, Lattice Boom 200 Ton Through 299 Ton, With Over 200' Boom(group 1)	$81.70	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Crane, Lattice Boom 300 Ton Through 399 Ton(group 1)	$81.70	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Crane, Lattice Boom 300 Ton Through 399 Ton, With Over 200' Boom(group 1)	$83.86	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Crane, Lattice Boom 50 Ton Through 89 Ton With 150' Boom Or Less(group 3)	$76.48	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Crane, Lattice Boom 50 Ton Through 89 Ton With Over 150' Boom	$77.63	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Crane, Lattice Boom 90 Ton Through 199 Ton With 150' - 200' Boom(group 2)	$77.63	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Crane, Lattice Boom Under 50 Ton(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Crane, Lattice Boom, 200 Ton Through 299 Ton With 200' Boom Or Less (group 1)	$79.54	**7B**	**4G**	**8U**	**View**

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Power Equipment Operators	Crane, Lattice Boom, 90 Ton Through 199 Ton With Over 200' Boom (group 1)	$79.54	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Crane, Shovel, Dragline Or Clamshell 3 Cu. Yds. But Less Than 5 Cu. Yds. (asst To Engineer Required)(group 3)	$76.48	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Crane, Tower Crane With 175' Tower Or Less And With Less Than 200' Jib(group 2)	$77.63	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Crane, Tower Crane With Over 175' Tower Or Over 200' Jib (group 1)	$79.54	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Crane, Tugger(group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Crane, Whirley 90 Ton And Over (group 1)	$79.54	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Crane, Whirley Under 90 Ton(group 2)	$77.63	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Crusher Feederman(group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Crusher Oiler(group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Crusher Plant(group 2)	$77.63	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Deckhand(group 6)	$68.69	**7B**	**4G**	**8U**	**View**

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Power Equipment Operators	Derrick Operator Under 100 Ton (two Operators Required When Swing Control Is Remote From Hoist) (group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Diesel-electric Engineer (plant Or Floating)(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Directional Drill Over 20,000 Lbs Pullback(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Drill Assistant(group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Drill Cat Operator(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Drill Directional Type Less Than 20,ooo Lbs Pullback(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Drill Doctor And/or (bit Grinder)(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Drill Mud Mixer(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Drill Oscillator(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Drill, Directinal Locator(group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Driller, Percussion, Diamond, Core, Cable, Rotary & Similar Type(group 4)	$73.15	**7B**	**4G**	**8U**	**View**

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Power Equipment Operators	Elevating Grader Operator, Tractor Towed Requiring Operator Or Grader(group 5)	$71.91	7B	4G	8U	View
Power Equipment Operators	Elevating Loader Operator (any Type) (group 5)	$71.91	7B	4G	8U	View
Power Equipment Operators	Elevator To Move Personnel Or Materials(group 5)	$71.91	7B	4G	8U	View
Power Equipment Operators	Excavator Over 80,000 Lbs Through 130,000 Lbs(group 3)	$76.48	7B	4G	8U	View
Power Equipment Operators	Excavator Operator, Over 20,000 Lbs Through 80,000 Lbs(group 4)	$73.15	7B	4G	8U	View
Power Equipment Operators	Excavator Operator, Over 130,000 Lbs(group 2)	$77.63	7B	4G	8U	View
Power Equipment Operators	Fireman(group 6)	$68.69	7B	4G	8U	View
Power Equipment Operators	Floating, Crane 350 Ton And Over (asst To Engineer And Deckhand Required) (group 1)	$83.86	7B	4G	8U	View
Power Equipment Operators	Fork Lift(group 6)	$68.69	7B	4G	8U	View
Power Equipment Operators	Fork Lift, Over 10 Ton Or Robotic(group 5)	$71.91	7B	4G	8U	View

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Power Equipment Operators	Generator Operator(group 4)	$73.15	7B	4G	8U	View
Power Equipment Operators	Grade Checker(group 6)	$68.69	7B	4G	8U	View
Power Equipment Operators	Grade Setter / Layout From Plans(group 4)	$73.15	7B	4G	8U	View
Power Equipment Operators	Grade-all(group 4)	$73.15	7B	4G	8U	View
Power Equipment Operators	Guardrail Machines, I.e. Punch, Auger, Etc. (group 4)	$73.15	7B	4G	8U	View
Power Equipment Operators	Guardrail Punch Oiler(group 6)	$68.69	7B	4G	8U	View
Power Equipment Operators	Hammer Operator (pile Driver)(group 4)	$73.15	7B	4G	8U	View
Power Equipment Operators	Heavy Duty Repairman Assistant(group 6)	$68.69	7B	4G	8U	View
Power Equipment Operators	Heavy Equipment Robotics Operator Or Mechanic(group 2)	$77.63	7B	4G	8U	View
Power Equipment Operators	Helicopter Hoist(group 5)	$71.91	7B	4G	8U	View
Power Equipment Operators	Helicopter Radioman (ground)(group 6)	$68.69	7B	4G	8U	View
Power Equipment Operators	Helicopter When Used In Erecting Workcrane(group 1)	$79.54	7B	4G	8U	View
Power Equipment Operators	Hoist Operator, Single Drum(group 5)	$71.91	7B	4G	8U	View

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Power Equipment Operators	Hoist, 2 Drums Or More(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Hoist, Stiff Leg, Guy Derrick Or Similar Type, 50 Ton And Over(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Hydraulic Backhoe Track Type Up To And Including 20,000 Lbs(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Hydraulic Backhoe Wheel Type (any Make) (group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Hydraulic Pipe Press(group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Hydro Axe (loader Mounted Or Similar Type)(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Hydrographic Seeder Machine Straw, Pulp Or Seed(group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Hydrostatic Pump Operator(group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Internal Full Slab Vibrator Operator(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Jack Operator, Elevating Barges, Barge Operator, Self-unloading (asst To	$73.15	**7B**	**4G**	**8U**	**View**

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

	Engineer Required) (group 4)					
Power Equipment Operators	Laser Screed(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Lattice Boom Crane 400 Ton And Over(group 1)	$83.86	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Lime Spreader, Construction Job Site(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Loaders Operator, Front End & Overhead, 25,000 Lbs And Less Than 60,000 Lbs(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Loaders, 120,000 Lbs And Above(group 2)	$77.63	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Loaders, 60,000 Lbs And Less Than 120,000 Lbs(group 3)	$76.48	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Loaders, Rubber-tire Type, Less Than 25,000 Lbs(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Log Skidders(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Master Environmental Maintenance Mechanic(group 2)	$77.63	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Material Handler(group 6)	$68.69	**7B**	**4G**	**8U**	**View**

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Power Equipment Operators	Mechanic, Heavy Duty(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Mixer Box (c.t.b., Dry Batch, Etc.)(group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Oiler(group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Parts Man (tool Room) (group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Pavement Grinder And Or Grooving Machine (riding Type)(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Pile Driver Operator (not Crane Type) (asst To Engineer Required) (group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Pipe Bending, Cleaning, Doping And Wrapping Machines(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Pipe, Cast In Place Pipe Laying Machine(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Plant Oiler(group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Pump (any Power) (group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Pump Operator, More Than 5 Pumps (any Size)(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Rail, Ballast Compactor, Regulator	$71.91	**7B**	**4G**	**8U**	**View**

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

	Or Tamper Machines(group 5)					
Power Equipment Operators	Rail, Ballast Tamper Multi-purpose(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Rail, Brakeman, Switchman, Motorman(group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Rail, Car Mover(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Rail, Clip Applicator(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Rail, High Rail Self Loader Truck(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Rail, Lo-railer(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Rail, Locomotive, 40 Ton And Over (asst To Engineer Required) (group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Rail, Shuttle Car Operator(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Rail, Speedswing(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Rail, Switchman(group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Rail, Tamping Machine, Mechanical, Self-propelled(group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Rail, Track Liner(group 5)	$71.91	**7B**	**4G**	**8U**	**View**

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Power Equipment Operators	Remote Controlled Earth Moving Equipment(group 2)	$77.63	7B	4G	8U	View
Power Equipment Operators	Rigger(group 6)	$68.69	7B	4G	8U	View
Power Equipment Operators	Roller Grading (not Asphalt)(group 6)	$68.69	7B	4G	8U	View
Power Equipment Operators	Rubber-tired Dozers And Pushers(group 4)	$73.15	7B	4G	8U	View
Power Equipment Operators	Scraper All Types(group 4)	$73.15	7B	4G	8U	View
Power Equipment Operators	Service Oiler (greaser) (group 5)	$71.91	7B	4G	8U	View
Power Equipment Operators	Shovel, Dragline, Clamshell, 5 Yards And Over(group 2)	$77.63	7B	4G	8U	View
Power Equipment Operators	Side-boom(group 4)	$73.15	7B	4G	8U	View
Power Equipment Operators	Skip Loader, Drag Box(group 4)	$73.15	7B	4G	8U	View
Power Equipment Operators	Stump Grinder (loader Mounted Or Similar Type)(group 4)	$73.15	7B	4G	8U	View
Power Equipment Operators	Surface Heater And Planer(group 4)	$73.15	7B	4G	8U	View
Power Equipment Operators	Sweeper Self-propelled, Construction Job Site(group 5)	$71.91	7B	4G	8U	View
Power Equipment Operators	Tar Pot Fireman (power Agitated) Or	$68.69	7B	4G	8U	View

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

	Not(group 6)					
Power Equipment Operators	Tractor Rubber-tired, 50 Hp Flywheel & Under(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Tractor, Rubber-tired Over 50 Hp Flywheel(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Trenching Machine 3 Ft Depth And Deeper (asst To The Operator If Required)(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Trenching Machine Operator, Maximum Digging Capacity 3 Ft Depth(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Truck Crane Oiler-driver(group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Truck, All Terrain Or Track Type(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Truck, Barrel Type(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Truck, Boom(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Truck, Off-road Trucks, Articulated And Non-articulated Trucks(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Truck, Offraod Trucks, Articulated And Non-articulated Trucks(group 5)	$71.91	**7B**	**4G**	**8U**	**View**

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Power Equipment Operators	Truck, Vacuum(group 5)	$71.91	7B	4G	8U	View
Power Equipment Operators	Truck, Water(group 5)	$71.91	7B	4G	8U	View
Power Equipment Operators	Tub Grinder(group 4)	$73.15	7B	4G	8U	View
Power Equipment Operators	Tunnel Boring Machine Mechanic(group 4)	$73.15	7B	4G	8U	View
Power Equipment Operators	Tunnel Boring Machine(group 1)	$79.54	7B	4G	8U	View
Power Equipment Operators	Tunnel Segment Plant(group 4)	$73.15	7B	4G	8U	View
Power Equipment Operators	Tunnel Separation Plant(group 4)	$73.15	7B	4G	8U	View
Power Equipment Operators	Tunnel Shaef Loader(group 4)	$73.15	7B	4G	8U	View
Power Equipment Operators	Tunnel, Locomotive, Dinkey(group 5)	$71.91	7B	4G	8U	View
Power Equipment Operators	Tunnel, Micro Boring Tunnel Machine(group 1)	$79.54	7B	4G	8U	View
Power Equipment Operators	Tunnel, Mucking Machine(group 4)	$73.15	7B	4G	8U	View
Power Equipment Operators	Tunnel, Power Jumbo Setting Slip Forms, Etc. (group 5)	$71.91	7B	4G	8U	View
Power Equipment Operators	Tunnel, Shield Operator(group 4)	$73.15	7B	4G	8U	View
Power Equipment Operators	Ultra High Pressure Water Jet Cutting Tool	$73.15	7B	4G	8U	View

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

	System Operator(group 4)					
Power Equipment Operators	Underwater Equipment, Remote Or Otherwise(group 2)	$77.63	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Vacuum Blasting Machine Operator(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Water Pulls, Water Wagon(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Welder's Assistant(group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Welder; Heavy Duty, Certified Or Not(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Welding Machine(group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Wheel Excavation Any Size (grade Oiler Required)(group 2)	$77.63	**7B**	**4G**	**8U**	**View**
Power Equipment Operators	Wire Mat Or Brooming Machine(group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Air Filtration Equipment(group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Asphalt Plant (any Type) (assistant Engineer Required) (group 2)	$77.63	**7B**	**4G**	**8U**	**View**

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Power Equipment Operators- Underground Sewer & Water	Asphalt, Burner & Reconditioner (any Type), (asst To Engineer If Required) (group 5)	$71.91	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Asphalt, Extrusion Machine Operator(group 5)	$71.91	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Asphalt, Paver (screed Man Required)(group 4)	$73.15	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Asphalt, Pugmill (any Type)(group 6)	$68.69	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Asphalt, Raker(group 6)	$68.69	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Asphalt, Roller (any Asphalt Mix)(group 5)	$71.91	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Asphalt, Roto-mill, Pavement Profiler Under 8 Ft Lateral Cut(group 4)	$73.15	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Asphalt, Roto-mill, Pavement Profiler, 8 Ft Lateral Cut & Over(group 2)	$77.63	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Asphalt, Roto-mill, Pavement Profiler, Groundman(group 5)	$71.91	7B	4G	8U	View

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Power Equipment Operators- Underground Sewer & Water	Asphalt, Screed(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Asphalt, Truck Mounted Spreader, With Screed(group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Auger Oiler(group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Auto Grader Or "trimmer" (grade Checker Required) (group 2)	$77.63	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Back Filling Machine (assistant To Engineer Required)(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Backhoe, Robotic, Track And Wheel Type Up To And Including 20,000 Lbs. With Any Attachments(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Band Wagons (in Conjuction With Whell Excavator)(group 2)	$77.63	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Bell Man (any Type Of Comunication)(group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Blade Any Type(group 4)	$73.15	**7B**	**4G**	**8U**	**View**

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Power Equipment Operators- Underground Sewer & Water	Blade, Robotic(group 2)	$77.63	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Boatman(group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Boatman, Licensed(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Bobcat, Skid Steer (< 1yd)(group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Boom Type Lifting Device, 5 Ton Capacity Or Less(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Boring Machine (asst To Engineer Required) (group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Broom Self-propelled, Construction Job Site(group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Bulldozer Operator, 20,000 Lbs Or Less, Or 100 Horse Or Less(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Bulldozer Operator, Over 20,000 Lbs And More Than 100 Horse Up To 70,000 Lbs(group 4)	$73.15	**7B**	**4G**	**8U**	**View**

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Power Equipment Operators- Underground Sewer & Water	Bulldozer Over 70,000 Lbs Up To And Including 120,000 Lbs(group 3)	$76.48	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Bulldozer Over 120,000 Lbs And Above(group 2)	$77.63	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Bulldozer Robotic Equipment(group 2)	$77.63	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Cable-plow (any Type) (group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Cableway 25 Ton & Over(group 2)	$77.63	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Cableway Up To 25 Ton(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Canal Trimmer (grade Oiler Required)(group 2)	$77.63	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Cat Drill (john Henry) (group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Cement Pump(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Challenger(group 4)	$73.15	**7B**	**4G**	**8U**	**View**

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Power Equipment Operators- Underground Sewer & Water	Chip Spreading Machine(group 5)	$71.91	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Chippers (asst To Engineer If Required) (group 4)	$73.15	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Churn Drill & Earth Boring Machine(group 5)	$71.91	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Combination Heavy Duty Mechanic-welder, When Required To Do Both(group 4)	$73.15	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Compactor Self Propelled Without Blade(group 5)	$71.91	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Compactor With Blade Self Propelled(group 4)	$73.15	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Compactor, Multi-engine(group 4)	$73.15	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Compactor, Robotic(group 4)	$73.15	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Compressor (any Power) 1,250 Cu Ft And Over Total Capacity(group 5)	$71.91	7B	4G	8U	View
Power Equipment Operators- Underground	Compressor Operator (any Power) Under	$68.69	7B	4G	8U	View

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Sewer & Water	1,250 Cu Ft Total Capacity(group 6)					
Power Equipment Operators- Underground Sewer & Water	Concrete Batch Plant And/or Wet Mix (3 Units Or More) (group1)	$79.54	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Concrete Batch Plant And/or Wet Mix Operator (1 & 2 Drums) (group 2)	$77.63	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Concrete Batch Plant Quality Control(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Concrete Breaker (assistant To Engineer Required)(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Concrete Canal Line, Assistant To Engineer Required(group 2)	$77.63	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Concrete Curing Machine (riding Type) (group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Concrete Diamond Head Profiler(group 2)	$77.63	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Concrete Paving Road Mixer(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Concrete Planer(group 5)	$71.91	**7B**	**4G**	**8U**	**View**

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Power Equipment Operators- Underground Sewer & Water	Concrete Saw(group 6)	$68.69	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Concrete, Automatic Slip Form Paver (asst To Engineer Required) (group 2)	$77.63	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Concrete, Combination Mixer & Compressor Operator, Gunite Work(group 5)	$71.91	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Concrete, Curb Machine Mechanical Berm, Curb And/or Curb And Gutter(group 5)	$71.91	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Concrete, Finishing Machine(group 5)	$71.91	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Concrete, Grout Plant(group 4)	$73.15	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Concrete, Grouting Machine(group 5)	$71.91	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Concrete, Joint Machine(group 5)	$71.91	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Concrete, Mixer Mobile(group 4)	$73.15	7B	4G	8U	View

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Power Equipment Operators- Underground Sewer & Water	Concrete, Mixer Single Drum Any Capacity(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Concrete, Paving Machine 8' And Less (asst To Engineer Required)(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Concrete, Placing Boom(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Concrete, Pump Truck(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Concrete, Pump(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Concrete, Pumpcrete Operator (any Type) (group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Concrete, Reinforced Tank Banding Machine (asst To Engineer Required)(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Concrete, Slip Form Pumps, Power Driven Hydraulic Lifting Device For Concrete Forms(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Concrete, Spreader(group 5)	$71.91	**7B**	**4G**	**8U**	**View**

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Power Equipment Operators- Underground Sewer & Water	Concrete, Telebelt(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Concrete, Treated Base Roller Operator, Oiling(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Conveyor Operator Or Assistant(group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Conveyored Material Hauler(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Crane, Bridge Locomotive, Gantry And Overhead(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Crane, Carry Deck(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Crane, Chicago Boom & Similar Types(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Crane, Floating (derrick Barge) 30 Ton But Less Than 150 Ton (asst To Engineer Required)(group 2)	$77.63	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Crane, Floating 150 Ton But Less Than 250 Ton (asst To Engineer Required) (group 1)	$79.54	**7B**	**4G**	**8U**	**View**

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Power Equipment Operators- Underground Sewer & Water	Crane, Floating 250 Ton And Over (asst To Engineer And Deckhand Required) (group 1)	$81.70	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Crane, Floating Clamshell 3 Cu. Yds. & Over (fireman Or Diesel Electric Engineer Required(group 2)	$77.63	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Crane, Floating Clamshell, Dragline Etc. Operator Under 3 Cu. Yds. Or Less Than 30 Ton (diesel-electric Engineer Required) (group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Crane, Hydraulic 200 Ton Through 399 Ton (group 1)	$79.54	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Crane, Hydraulic 50 Ton Through 89 Ton With Luffing Or Tower Attachment(group 2)	$77.63	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Crane, Hydraulic 50 Ton Through 89 Tons(group 3)	$76.48	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Crane, Hydraulic 90 Ton Through 199 Ton With Luffing Or Tower Attachment (group 1)	$79.54	**7B**	**4G**	**8U**	**View**

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Power Equipment Operators- Underground Sewer & Water	Crane, Hydraulic 90 Ton Through 199 Ton(group 2)	$77.63	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Crane, Hydraulic Crane 200 Ton Through 300 Ton With Luffing Or Tower Attachment(group 1)	$81.70	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Crane, Hydraulic Crane 400 Ton And Over(group 1)	$83.86	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Crane, Hydraulic Crane Over 300 Ton Through 399 Ton With Luffer Or Tower Attachment(group 1)	$83.86	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Crane, Hydraulic Under 50 Ton(group 4)	$73.15	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Crane, Lattice Boom 200 Ton Through 299 Ton, With Over 200' Boom(group 1)	$81.70	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Crane, Lattice Boom 300 Ton Through 399 Ton(group 1)	$81.70	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Crane, Lattice Boom 300 Ton Through 399 Ton, With Over 200' Boom(group 1)	$83.86	7B	4G	8U	View

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Power Equipment Operators- Underground Sewer & Water	Crane, Lattice Boom 50 Ton Through 89 Ton With 150' Boom Or Less(group 3)	$76.48	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Crane, Lattice Boom 50 Ton Through 89 Ton With Over 150' Boom	$77.63	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Crane, Lattice Boom 90 Ton Through 199 Ton With 150' - 200' Boom(group 2)	$77.63	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Crane, Lattice Boom Under 50 Ton(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Crane, Lattice Boom, 200 Ton Through 299 Ton With 200' Boom Or Less (group 1)	$79.54	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Crane, Lattice Boom, 90 Ton Through 199 Ton With Over 200' Boom (group 1)	$79.54	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Crane, Shovel, Dragline Or Clamshell 3 Cu. Yds. But Less Than 5 Cu. Yds. (asst To Engineer Required)(group 3)	$76.48	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Crane, Tower Crane With 175' Tower Or Less And With Less Than 200' Jib(group 2)	$77.63	**7B**	**4G**	**8U**	**View**

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Power Equipment Operators- Underground Sewer & Water	Crane, Tower Crane With Over 175' Tower Or Over 200' Jib (group 1)	$79.54	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Crane, Tugger(group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Crane, Whirley 90 Ton And Over (group 1)	$79.54	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Crane, Whirley Under 90 Ton(group 2)	$77.63	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Crusher Feederman(group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Crusher Oiler(group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Crusher Plant(group 2)	$77.63	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Deckhand(group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Derrick Operator Under 100 Ton (two Operators Required When Swing Control Is Remote From Hoist) (group 4)	$73.15	**7B**	**4G**	**8U**	**View**

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Power Equipment Operators- Underground Sewer & Water	Diesel-electric Engineer (plant Or Floating)(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Directional Drill Over 20,000 Lbs Pullback(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Drill Assistant(group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Drill Cat Operator(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Drill Directional Type Less Than 20,ooo Lbs Pullback(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Drill Doctor And/or (bit Grinder)(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Drill Mud Mixer(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Drill Oscillator(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Drill, Directinal Locator(group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Driller, Percussion, Diamond, Core, Cable, Rotary & Similar Type(group 4)	$73.15	**7B**	**4G**	**8U**	**View**

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Power Equipment Operators- Underground Sewer & Water	Elevating Grader Operator, Tractor Towed Requiring Operator Or Grader(group 5)	$71.91	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Elevating Loader Operator (any Type) (group 5)	$71.91	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Elevator To Move Personnel Or Materials(group 5)	$71.91	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Excavator Over 80,000 Lbs Through 130,000 Lbs(group 3)	$76.48	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Excavator Operator, Over 20,000 Lbs Through 80,000 Lbs(group 4)	$73.15	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Excavator Operator, Over 130,000 Lbs(group 2)	$77.63	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Fireman(group 6)	$68.69	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Floating, Crane 350 Ton And Over (asst To Engineer And Deckhand Required) (group 1)	$83.86	7B	4G	8U	View
Power Equipment Operators- Underground	Fork Lift(group 6)	$68.69	7B	4G	8U	View

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Sewer & Water						
Power Equipment Operators- Underground Sewer & Water	Fork Lift, Over 10 Ton Or Robotic(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Generator Operator(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Grade Checker(group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Grade Setter / Layout From Plans(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Grade-all(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Guardrail Machines, I.e. Punch, Auger, Etc. (group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Guardrail Punch Oiler(group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Hammer Operator (pile Driver)(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Heavy Duty Repairman Assistant(group 6)	$68.69	**7B**	**4G**	**8U**	**View**

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Power Equipment Operators- Underground Sewer & Water	Heavy Equipment Robotics Operator Or Mechanic(group 2)	$77.63	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Helicopter Hoist(group 5)	$71.91	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Helicopter Radioman (ground)(group 6)	$68.69	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Helicopter When Used In Erecting Workcrane(group 1)	$79.54	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Hoist Operator, Single Drum(group 5)	$71.91	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Hoist, 2 Drums Or More(group 4)	$73.15	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Hoist, Stiff Leg, Guy Derrick Or Similar Type, 50 Ton And Over(group 4)	$73.15	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Hydraulic Backhoe Track Type Up To And Including 20,000 Lbs(group 5)	$71.91	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Hydraulic Backhoe Wheel Type (any Make) (group 5)	$71.91	7B	4G	8U	View
Power Equipment Operators- Underground	Hydraulic Pipe Press(group 6)	$68.69	7B	4G	8U	View

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Sewer & Water						
Power Equipment Operators- Underground Sewer & Water	Hydro Axe (loader Mounted Or Similar Type)(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Hydrographic Seeder Machine Straw, Pulp Or Seed(group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Hydrostatic Pump Operator(group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Internal Full Slab Vibrator Operator(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Jack Operator, Elevating Barges, Barge Operator, Self-unloading (asst To Engineer Required) (group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Laser Screed(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Lattice Boom Crane 400 Ton And Over(group 1)	$83.86	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Lime Spreader, Construction Job Site(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Loaders Operator, Front End & Overhead, 25,000 Lbs And Less	$73.15	**7B**	**4G**	**8U**	**View**

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

	Than 60,000 Lbs(group 4)					
Power Equipment Operators- Underground Sewer & Water	Loaders, 120,000 Lbs And Above(group 2)	$77.63	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Loaders, 60,000 Lbs And Less Than 120,000 Lbs(group 3)	$76.48	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Loaders, Rubber-tire Type, Less Than 25,000 Lbs(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Log Skidders(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Master Environmental Maintenance Mechanic(group 2)	$77.63	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Material Handler(group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Mechanic, Heavy Duty(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Mixer Box (c.t.b., Dry Batch, Etc.)(group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Oiler(group 6)	$68.69	**7B**	**4G**	**8U**	**View**

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Power Equipment Operators- Underground Sewer & Water	Parts Man (tool Room) (group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Pavement Grinder And Or Grooving Machine (riding Type)(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Pile Driver Operator (not Crane Type) (asst To Engineer Required) (group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Pipe Bending, Cleaning, Doping And Wrapping Machines(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Pipe, Cast In Place Pipe Laying Machine(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Plant Oiler(group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Pump (any Power) (group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Pump Operator, More Than 5 Pumps (any Size)(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Rail, Ballast Compactor, Regulator Or Tamper Machines(group 5)	$71.91	**7B**	**4G**	**8U**	**View**

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Power Equipment Operators- Underground Sewer & Water	Rail, Ballast Tamper Multi-purpose(group 4)	$73.15	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Rail, Brakeman, Switchman, Motorman(group 6)	$68.69	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Rail, Car Mover(group 5)	$71.91	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Rail, Clip Applicator(group 5)	$71.91	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Rail, High Rail Self Loader Truck(group 5)	$71.91	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Rail, Lo-railer(group 5)	$71.91	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Rail, Locomotive, 40 Ton And Over (asst To Engineer Required) (group 5)	$71.91	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Rail, Shuttle Car Operator(group 5)	$71.91	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Rail, Speedswing(group 5)	$71.91	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Rail, Switchman(group 6)	$68.69	7B	4G	8U	View

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Power Equipment Operators- Underground Sewer & Water	Rail, Tamping Machine, Mechanical, Self-propelled(group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Rail, Track Liner(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Remote Controlled Earth Moving Equipment(group 2)	$77.63	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Rigger(group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Roller Grading (not Asphalt)(group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Rubber-tired Dozers And Pushers(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Scraper All Types(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Service Oiler (greaser) (group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Shovel, Dragline, Clamshell, 5 Yards And Over(group 2)	$77.63	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Side-boom(group 4)	$73.15	**7B**	**4G**	**8U**	**View**

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Power Equipment Operators- Underground Sewer & Water	Skip Loader, Drag Box(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Stump Grinder (loader Mounted Or Similar Type)(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Surface Heater And Planer(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Sweeper Self-propelled, Construction Job Site(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Tar Pot Fireman (power Agitated) Or Not(group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Tractor Rubber-tired, 50 Hp Flywheel & Under(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Tractor, Rubber-tired Over 50 Hp Flywheel(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Trenching Machine 3 Ft Depth And Deeper (asst To The Operator If Required)(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Trenching Machine Operator, Maximum Digging Capacity 3 Ft Depth(group 5)	$71.91	**7B**	**4G**	**8U**	**View**

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Power Equipment Operators- Underground Sewer & Water	Truck Crane Oiler-driver(group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Truck, All Terrain Or Track Type(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Truck, Barrel Type(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Truck, Boom(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Truck, Off-road Trucks, Articulated And Non-articulated Trucks(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Truck, Offraod Trucks, Articulated And Non-articulated Trucks(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Truck, Vacuum(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Truck, Water(group 5)	$71.91	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Tub Grinder(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground	Tunnel Boring Machine Mechanic(group 4)	$73.15	**7B**	**4G**	**8U**	**View**

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Sewer & Water						
Power Equipment Operators- Underground Sewer & Water	Tunnel Boring Machine(group 1)	$79.54	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Tunnel Segment Plant(group 4)	$73.15	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Tunnel Separation Plant(group 4)	$73.15	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Tunnel Shaef Loader(group 4)	$73.15	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Tunnel, Locomotive, Dinkey(group 5)	$71.91	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Tunnel, Micro Boring Tunnel Machine(group 1)	$79.54	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Tunnel, Mucking Machine(group 4)	$73.15	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Tunnel, Power Jumbo Setting Slip Forms, Etc. (group 5)	$71.91	7B	4G	8U	View
Power Equipment Operators- Underground Sewer & Water	Tunnel, Shield Operator(group 4)	$73.15	7B	4G	8U	View

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Power Equipment Operators- Underground Sewer & Water	Ultra High Pressure Water Jet Cutting Tool System Operator(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Underwater Equipment, Remote Or Otherwise(group 2)	$77.63	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Vacuum Blasting Machine Operator(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Water Pulls, Water Wagon(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Welder's Assistant(group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Welder; Heavy Duty, Certified Or Not(group 4)	$73.15	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Welding Machine(group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Wheel Excavation Any Size (grade Oiler Required)(group 2)	$77.63	**7B**	**4G**	**8U**	**View**
Power Equipment Operators- Underground Sewer & Water	Wire Mat Or Brooming Machine(group 6)	$68.69	**7B**	**4G**	**8U**	**View**
Power Line Clearance Tree Trimmers	Groundman	$33.83	**7E**	**4A**		**View**

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Power Line Clearance Tree Trimmers	Journey Level in Charge	$57.79	7E	4A	View
Power Line Clearance Tree Trimmers	Spray Person	$51.98	7E	4A	View
Power Line Clearance Tree Trimmers	Tree Equipment Operator	$57.79	7E	4A	View
Power Line Clearance Tree Trimmers	Tree Trimmer	$51.98	7E	4A	View
Refrigeration & Air Conditioning Mechanics	Journey Level	$99.52	5Z	10	View
Residential Brick Mason	Journey Level	$29.27		1	View
Residential Carpenters	Journey Level	$40.93		1	View
Residential Cement Masons	Journey Level	$71.52	7E	1H	View
Residential Drywall Applicators	Journey Level	$31.21		1	View
Residential Drywall Tapers	Journey Level	$31.48		1	View
Residential Electricians	Journey Level	$38.76		1	View
Residential Glaziers	Journey Level	$49.60		1	View
Residential Insulation Applicators	Journey Level	$29.82		1	View
Residential Laborers	Journey Level	$38.63		1	View
Residential Marble Setters	Journey Level	$22.73		1	View
Residential Painters	Journey Level	$30.66		1	View

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Residential Plumbers & Pipefitters	Journey Level	$41.84		1	View
Residential Refrigeration & Air Conditioning Mechanics	Journey Level	$27.13		1	View
Residential Sheet Metal Workers	Journey Level (Field or Shop)	$70.15	5A	1B	View
Residential Soft Floor Layers	Journey Level	$24.54		1	View
Residential Sprinkler Fitters (Fire Protection)	Journey Level	$55.64		1	View
Residential Stone Masons	Journey Level	$35.66		1	View
Residential Terrazzo Workers	Journey Level	$17.13		1	View
Residential Terrazzo/Tile Finishers	Journey Level	$17.13		1	View
Residential Tile Setters	Journey Level	$25.32		1	View
Roofers	Journey Level	$67.22	5I	1V	View
Roofers	Using Irritable Bituminous Materials	$68.45	5I	1V	View
Sheet Metal Workers	Journey Level (Field or Shop)	$95.17	5A	1B	View
Shipbuilding & Ship Repair	New Construction Boilermaker	$38.27	7W	4I	View
Shipbuilding & Ship Repair	New Construction Crane Operator	$35.82	7W	4I	View
Shipbuilding & Ship Repair	New Construction Electrician	$30.96	7W	4I	View

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Shipbuilding & Ship Repair	New Construction Fitter	$38.27	**7W**	**4I**	**View**
Shipbuilding & Ship Repair	New Construction Heat & Frost Insulator	$87.79	**5N**	**1F**	**View**
Shipbuilding & Ship Repair	New Construction Laborer	$26.32	**7W**	**4I**	**View**
Shipbuilding & Ship Repair	New Construction Loader/Rigger	$33.39	**7W**	**4I**	**View**
Shipbuilding & Ship Repair	New Construction Machinist	$45.75	**7W**	**4I**	**View**
Shipbuilding & Ship Repair	New Construction Mechanic	$43.50	**7W**	**4I**	**View**
Shipbuilding & Ship Repair	New Construction Painter	$35.82	**7W**	**4I**	**View**
Shipbuilding & Ship Repair	New Construction Sheet Metal	$38.27	**7W**	**4I**	**View**
Shipbuilding & Ship Repair	New Construction Warehouse / Yard Person	$30.96	**7W**	**4I**	**View**
Shipbuilding & Ship Repair	New Construction Welder / Burner	$38.27	**7W**	**4I**	**View**
Shipbuilding & Ship Repair	Ship Repair Boilermaker	$53.04	**7V**	**1B**	**View**
Shipbuilding & Ship Repair	Ship Repair Carpenter	$53.04	**7V**	**1B**	**View**
Shipbuilding & Ship Repair	Ship Repair Crane Operator	$53.04	**7V**	**1B**	**View**
Shipbuilding & Ship Repair	Ship Repair Electrician	$53.04	**7V**	**1B**	**View**

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Shipbuilding & Ship Repair	Ship Repair Heat & Frost Insulator	$87.79	**5N**	**1F**	**View**
Shipbuilding & Ship Repair	Ship Repair Laborer	$53.04	**7V**	**1B**	**View**
Shipbuilding & Ship Repair	Ship Repair Machinist	$53.04	**7V**	**1B**	**View**
Shipbuilding & Ship Repair	Ship Repair Operating Engineer	$53.04	**7V**	**1B**	**View**
Shipbuilding & Ship Repair	Ship Repair Painter	$53.04	**7V**	**1B**	**View**
Shipbuilding & Ship Repair	Ship Repair Pipefitter	$53.04	**7V**	**1B**	**View**
Shipbuilding & Ship Repair	Ship Repair Rigger	$53.04	**7V**	**1B**	**View**
Shipbuilding & Ship Repair	Ship Repair Sheet Metal	$53.04	**7V**	**1B**	**View**
Shipbuilding & Ship Repair	Ship Repair Shipwright	$53.04	**7V**	**1B**	**View**
Shipbuilding & Ship Repair	Ship Repair Warehouse/Teamster	$53.04	**7V**	**1B**	**View**
Sign Makers & Installers (Electrical)	Journey Level	$19.27		**1**	**View**
Sign Makers & Installers (Non-Electrical)	Journey Level	$22.40		**1**	**View**
Soft Floor Layers	Journey Level	$63.29	**15J**	**4C**	**View**
Solar Controls For Windows	Journey Level	$17.13		**1**	**View**
Sprinkler Fitters (Fire Protection)	Journey Level	$83.61	**7J**	**1R**	**View**
Stage Rigging Mechanics (Non Structural)	Journey Level	$17.13		**1**	**View**

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Stone Masons	Journey Level	$79.19	5A	1B		View
Street And Parking Lot Sweeper Workers	Journey Level	$17.13		1		View
Surveyors	Chain Person	$68.69	7B	1B	9H	View
Surveyors	Instrument Person	$71.91	7B	1B	9H	View
Surveyors	Party Chief	$77.63	7B	1B	9H	View
Telecommunication Technicians	Journey Level	$83.46	5A	1B		View
Telephone Line Construction - Outside	Cable Splicer	$42.62	5A	2B		View
Telephone Line Construction - Outside	Hole Digger/Ground Person	$27.97	5A	2B		View
Telephone Line Construction - Outside	Telephone Equipment Operator (Light)	$35.60	5A	2B		View
Telephone Line Construction - Outside	Telephone Lineperson	$40.28	5A	2B		View
Terrazzo Workers	Journey Level	$68.27	5A	1B		View
Tile Setters	Journey Level	$68.27	5A	1B		View
Tile, Marble & Terrazzo Finishers	Finishers	$51.00	5A	1B		View
Traffic Control Stripers	Journey Level	$94.37	15N	1K		View
Truck Drivers	Asphalt Mix Over 10 Yards	$49.39	5A	1B		View
Truck Drivers	Asphalt Mix To 10 Yards	$49.24	5A	1B		View

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Truck Drivers	Dump Truck	$49.24	**5A**	**1B**	**View**
Truck Drivers	Dump Truck And Trailer	$49.39	**5A**	**1B**	**View**
Truck Drivers	Other Trucks	$49.39	**5A**	**1B**	**View**
Truck Drivers - Ready Mix	Transit Mix 5 cubic yards and under	$49.24	**5A**	**1B**	**View**
Truck Drivers - Ready Mix	Transit Mix over 11 cubic yards up to 15 cubic yards	$49.85	**5A**	**1B**	**View**
Truck Drivers - Ready Mix	Transit Mix over 5 cubic yards up to 7 cubic yards	$49.39	**5A**	**1B**	**View**
Truck Drivers - Ready Mix	Transit Mix Over 7 cubic yards up to 11 cubic yards	$49.54	**5A**	**1B**	**View**
Well Drillers & Irrigation Pump Installers	Irrigation Pump Installer	$17.13		**1**	**View**
Well Drillers & Irrigation Pump Installers	Oiler	$17.13		**1**	**View**
Well Drillers & Irrigation Pump Installers	Well Driller	$17.13		**1**	**View**

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Washington State Department of Labor and Industries
Policy Statement
(Regarding the Production of "Standard" or "Non-standard" Items)

Below is the department's (State L&I's) list of criteria to be used in determining whether a prefabricated item is "standard" or "non-standard". For items not appearing on WSDOT's predetermined list, these criteria shall be used by the Contractor (and the Contractor's subcontractors, agents to subcontractors, suppliers, manufacturers, and fabricators) to determine coverage under RCW 39.12. The production, in the State of Washington, of non-standard items is covered by RCW 39.12, and the production of standard items is not. The production of any item outside the State of Washington is not covered by RCW 39.12.

1. Is the item fabricated for a public works project? If not, it is not subject to RCW 39.12. If it is, go to question 2.

2. Is the item fabricated on the public works jobsite? If it is, the work is covered under RCW 39.12. If not, go to question 3.

3. Is the item fabricated in an assembly/fabrication plant set up for, and dedicated primarily to, the public works project? If it is, the work is covered by RCW 39.12. If not, go to question 4.

4. Does the item require any assembly, cutting, modification or other fabrication by the supplier? If not, the work is not covered by RCW 39.12. If yes, go to question 5.

5. Is the prefabricated item intended for the public works project typically an inventory item which could reasonably be sold on the general market? If not, the work is covered by RCW 39.12. If yes, go to question 6.

6. Does the specific prefabricated item, generally defined as standard, have any unusual characteristics such as shape, type of material, strength requirements, finish, etc? If yes, the work is covered under RCW 39.12.

Any firm with questions regarding the policy, WSDOT's Predetermined List, or for determinations of covered and non-covered workers shall be directed to State L&I at (360) 902-5330.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

WSDOT's
Predetermined List for
Suppliers - Manufactures - Fabricator

Below is a list of potentially prefabricated items, originally furnished by WSDOT to Washington State Department of Labor and Industries, that may be considered non-standard and therefore covered by the prevailing wage law, RCW 39.12. Items marked with an X in the "YES" column should be considered to be non-standard and therefore covered by RCW 39.12. Items marked with an X in the "NO" column should be considered to be standard and therefore not covered. Of course, exceptions to this general list may occur, and in that case shall be evaluated according to the criteria described in State and L&I's policy statement.

	ITEM DESCRIPTION	YES	NO
1.	Metal rectangular frames, solid metal covers, herringbone grates, and bi-directional vaned grates for Catch Basin Types 1, 1L, 1P, and 2 and Concrete Inlets. See Std. Plans		X
2.	Metal circular frames (rings) and covers, circular grates, and prefabricated ladders for Manhole Types 1, 2, and 3, Drywell Types 1, 2, and 3 and Catch Basin Type 2. See Std. Plans		X
3.	Prefabricated steel grate supports and welded grates, metal frames and dual vaned grates, and Type 1, 2, and 3 structural tubing grates for Drop Inlets. See Std. Plans.		X
4.	Concrete Pipe - Plain Concrete pipe and reinforced concrete pipe Class 2 to 5 sizes smaller than 60 inch diameter.		X
5.	Concrete Pipe - Plain Concrete pipe and reinforced concrete pipe Class 2 to 5 sizes larger than 60 inch diameter.		X
6.	Corrugated Steel Pipe - Steel lock seam corrugated pipe for culverts and storm sewers, sizes 30 inch to 120 inches in diameter. May also be treated, 1 thru 5.		X
7.	Corrugated Aluminum Pipe - Aluminum lock seam corrugated pipe for culverts and storm sewers, sizes 30 inch to 120 inches in diameter. May also be treated, #5.		X

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

	ITEM DESCRIPTION	YES	NO
8.	Anchor Bolts & Nuts - Anchor Bolts and Nuts, for mounting sign structures, luminaries and other items, shall be made from commercial bolt stock. See Contract Plans and Std. Plans for size and material type.		X
9.	Aluminum Pedestrian Handrail - Pedestrian handrail conforming to the type and material specifications set forth in the contract plans. Welding of aluminum shall be in accordance with Section 9-28.14(3).	X	
10.	Major Structural Steel Fabrication - Fabrication of major steel items such as trusses, beams, girders, etc., for bridges.	X	
11.	Minor Structural Steel Fabrication - Fabrication of minor steel Items such as special hangers, brackets, access doors for structures, access ladders for irrigation boxes, bridge expansion joint systems, etc., involving welding, cutting, punching and/or boring of holes. See Contact Plans for item description and shop drawings.	X	
12.	Aluminum Bridge Railing Type BP - Metal bridge railing conforming to the type and material specifications set forth in the Contract Plans. Welding of aluminum shall be in accordance with Section 9-28.14(3).		X
13.	Concrete Piling--Precast-Prestressed concrete piling for use as 55 and 70 ton concrete piling. Concrete to conform to Section 9-19.1 of Std. Spec..	X	
14.	Precast Manhole Types 1, 2, and 3 with cones, adjustment sections and flat top slabs. See Std. Plans.		X
15.	Precast Drywell Types 1, 2, and with cones and adjustment Sections. See Std. Plans.		X
16.	Precast Catch Basin - Catch Basin type 1, 1L, 1P, and 2 With adjustment sections. See Std. Plans.		X

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

	ITEM DESCRIPTION	YES	NO
17.	Precast Concrete Inlet - with adjustment sections, See Std. Plans		X
18.	Precast Drop Inlet Type 1 and 2 with metal grate supports. See Std. Plans.		X
19.	Precast Grate Inlet Type 2 with extension and top units. See Std. Plans		X
20.	Metal frames, vaned grates, and hoods for Combination Inlets. See Std. Plans		X
21.	Precast Concrete Utility Vaults - Precast Concrete utility vaults of various sizes. Used for in ground storage of utility facilities and controls. See Contract Plans for size and construction requirements. Shop drawings are to be provided for approval prior to casting.		X
22.	Vault Risers - For use with Valve Vaults and Utilities Vaults.		X
23.	Valve Vault - For use with underground utilities. See Contract Plans for details.		X
24.	Precast Concrete Barrier - Precast Concrete Barrier for use as new barrier or may also be used as Temporary Concrete Barrier. Only new state approved barrier may be used as permanent barrier.		X
25.	Reinforced Earth Wall Panels – Reinforced Earth Wall Panels in size and shape as shown in the Plans. Fabrication plant has annual approval for methods and materials to be used. See Shop Drawing. Fabrication at other locations may be approved, after facilities inspection, contact HQ. Lab.	X	
26.	Precast Concrete Walls - Precast Concrete Walls - tilt-up wall panel in size and shape as shown in Plans. Fabrication plant has annual approval for methods and materials to be used	X	

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

	ITEM DESCRIPTION	YES	NO
27.	Precast Railroad Crossings - Concrete Crossing Structure Slabs.	X	
28.	12, 18 and 26 inch Standard Precast Prestressed Girder – Standard Precast Prestressed Girder for use in structures. Fabricator plant has annual approval of methods and materials To be used. Shop Drawing to be provided for approval prior to casting girders. See Std. Spec. Section 6-02.3(25)A	X	
29.	Prestressed Concrete Girder Series 4-14 - Prestressed Concrete Girders for use in structures. Fabricator plant has annual approval of methods and materials to be used. Shop Drawing to be provided for approval prior to casting girders. See Std. Spec. Section 6-02.3(25)A.	X	
30.	Prestressed Tri-Beam Girder - Prestressed Tri-Beam Girders for use in structures. Fabricator plant has annual approval of methods and materials to be used. Shop Drawing to be provided for approval prior to casting girders. See Std. Spec. Section 6-02.3(25)A	X	
31.	Prestressed Precast Hollow-Core Slab – Precast Prestressed Hollow-core slab for use in structures. Fabricator plant has Annual approval of methods and materials to be used. Shop Drawing to be provided for approval prior to casting girders. See Std. Spec. Section 6-02.3(25)A.	X	
32.	Prestressed-Bulb Tee Girder - Bulb Tee Prestressed Girder for use in structures. Fabricator plant has annual approval of methods and materials to be used. Shop Drawing to be provided for approval prior to casting girders. See Std. Spec. Section 6-02.3(25)A	X	
33.	Monument Case and Cover See Std. Plan.		X

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

	ITEM DESCRIPTION	YES	NO
34.	Cantilever Sign Structure - Cantilever Sign Structure fabricated from steel tubing meeting AASHTO-M-183. See Std. Plans, and Contract Plans for details. The steel structure shall be galvanized after fabrication in accordance with AASHTO-M-111.	X	
35.	Mono-tube Sign Structures - Mono-tube Sign Bridge fabricated to details shown in the Plans. Shop drawings for approval are required prior to fabrication.	X	
36.	Steel Sign Bridges - Steel Sign Bridges fabricated from steel tubing meeting AASHTO-M-138 for Aluminum Alloys. See Std. Plans, and Contract Plans for details. The steel Structure shall be galvanized after fabrication in accordance with AASHTO-M-111.	X	
37.	Steel Sign Post - Fabricated Steel Sign Posts as detailed in Std Plans. Shop drawings for approval are to be provided prior to fabrication		X
38.	Light Standard-Prestressed - Spun, prestressed, hollow concrete poles.	X	
39.	Light Standards - Lighting Standards for use on highway illumination systems, poles to be fabricated to conform with methods and materials as specified on Std. Plans. See Specia Provisions for pre-approved drawings.	X	
40.	Traffic Signal Standards - Traffic Signal Standards for use on highway and/or street signal systems. Standards to be fabricated to conform with methods and material as specified on Std. Plans. See Special Provisions for pre-approved drawings	X	
41.	Precast Concrete Sloped Mountable Curb (Single and Dual Faced) See Std. Plans.		X

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

	ITEM DESCRIPTION	YES	NO
42.	Traffic Signs - Prior to approval of a Fabricator of Traffic Signs, the sources of the following materials must be submitted and approved for reflective sheeting, legend material, and luminum sheeting. **NOTE:** *** Fabrication inspection required. Only signs tagged "Fabrication Approved" by WSDOT Sign Fabrication Inspector to be installed.	X	X
		Custom Message	Std Signing Message
43.	Cutting & bending reinforcing steel		X
44.	Guardrail components	X	X
		Custom End Sec	Standard Sec
45.	Aggregates/Concrete mixes	Covered by WAC 296-127-018	
46.	Asphalt	Covered by WAC 296-127-018	
47.	Fiber fabrics		X
48.	Electrical wiring/components		X
49.	treated or untreated timber pile		X
50.	Girder pads (elastomeric bearing)	X	
51.	Standard Dimension lumber		X
52.	Irrigation components		X

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

	ITEM DESCRIPTION	YES	NO
53.	Fencing materials		X
54.	Guide Posts		X
55.	Traffic Buttons		X
56.	Epoxy		X
57.	Cribbing		X
58.	Water distribution materials		X
59.	Steel "H" piles		X
60.	Steel pipe for concrete pile casings, standard		X
	Steel pipe for concrete pile casings, custom	X	
61.	Steel pile tips, standard		X
62.	Steel pile tips, custom	X	

Prefabricated items specifically produced for public works projects that are prefabricated in a county other than the county wherein the public works project is to be completed, the wage for the offsite prefabrication shall be the applicable prevailing wage for the county in which the actual prefabrication takes place.

It is the manufacturer of the prefabricated product to verify that the correct county wage rates are applied to work they perform.

See RCW 39.12.010
(The definition of "locality" in RCW 39.12.010(2) contains the phrase "wherein the physical work is being performed." The department interprets this phrase to mean the actual work site.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

WSDOT's List of State Occupations not applicable to Heavy and Highway Construction Projects

This project is subject to the state hourly minimum rates for wages and fringe benefits in the contract provisions, as provided by the state Department of Labor and Industries.
The following list of occupations, is comprised of those occupations that are not normally used in the construction of heavy and highway projects.
When considering job classifications for use and / or payment when bidding on, or building heavy and highway construction projects for, or administered by WSDOT, these Occupations will be excepted from the included "Washington State Prevailing Wage Rates For Public Work Contracts" documents.

- Building Service Employees
- Electrical Fixture Maintenance Workers
- Electricians - Motor Shop
- Heating Equipment Mechanics
- Industrial Engine and Machine Mechanics
- Industrial Power Vacuum Cleaners
- Inspection, Cleaning, Sealing of Water Systems by Remote Control
- Laborers - Underground Sewer & Water
- Machinists (Hydroelectric Site Work)
- Modular Buildings
- Playground & Park Equipment Installers
- Power Equipment Operators - Underground Sewer & Water
- Residential *** ALL ASSOCIATED RATES ***
- Sign Makers and Installers (Non-Electrical)
- Sign Makers and Installers (Electrical)
- Stage Rigging Mechanics (Non Structural)

The following occupations may be used only as outlined in the preceding text concerning "WSDOT's list for Suppliers - Manufacturers - Fabricators"

- Fabricated Precast Concrete Products
- Metal Fabrication (In Shop)

Definitions for the Scope of Work for prevailing wages may be found at the Washington State Department of Labor and Industries web site and in WAC Chapter 296-127.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

WAC 296-127-018 Agency filings affecting this section

Coverage and exemptions of workers involved in the production and delivery of gravel, concrete, asphalt, or similar materials.

(1) The materials covered under this section include but are not limited to: Sand, gravel, crushed rock, concrete, asphalt, or other similar materials.

(2) All workers, regardless of by whom employed, are subject to the provisions of chapter 39.12 RCW when they perform any or all of the following functions:

(a) They deliver or discharge any of the above-listed materials to a public works project site:

(i) At one or more point(s) directly upon the location where the material will be incorporated into the project; or

(ii) At multiple points at the project; or

(iii) Adjacent to the location and coordinated with the incorporation of those materials.

(b) They wait at or near a public works project site to perform any tasks subject to this section of the rule.

(c) They remove any materials from a public works construction site pursuant to contract requirements or specifications (e.g., excavated materials, materials from demolished structures, clean-up materials, etc.).

(d) They work in a materials production facility (e.g., batch plant, borrow pit, rock quarry, etc.,) which is established for a public works project for the specific, but not necessarily exclusive, purpose of supplying materials for the project.

(e) They deliver concrete to a public works site regardless of the method of incorporation.

(f) They assist or participate in the incorporation of any materials into the public works project.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

(3) All travel time that relates to the work covered under subsection (2) of this section requires the payment of prevailing wages. Travel time includes time spent waiting to load, loading, transporting, waiting to unload, and delivering materials. Travel time would include all time spent in travel in support of a public works project whether the vehicle is empty or full. For example, travel time spent returning to a supply source to obtain another load of material for use on a public works site or returning to the public works site to obtain another load of excavated material is time spent in travel that is subject to prevailing wage. Travel to a supply source, including travel from a public works site, to obtain materials for use on a private project would not be travel subject to the prevailing wage.

(4) Workers are not subject to the provisions of chapter 39.12 RCW when they deliver materials to a stockpile.

(a) A "stockpile" is defined as materials delivered to a pile located away from the site of incorporation such that the stockpiled materials must be physically moved from the stockpile and transported to another location on the project site in order to be incorporated into the project.

(b) A stockpile does not include any of the functions described in subsection (2)(a) through (f) of this section; nor does a stockpile include materials delivered or distributed to multiple locations upon the project site; nor does a stockpile include materials dumped at the place of incorporation, or adjacent to the location and coordinated with the incorporation.

(5) The applicable prevailing wage rate shall be determined by the locality in which the work is performed. Workers subject to subsection (2)(d) of this section, who produce such materials at an off-site facility shall be paid the applicable prevailing wage rates for the county in which the off-site facility is located. Workers subject to subsection (2) of this section, who deliver such materials to a public works project site shall be paid the applicable prevailing wage rates for the county in which the public works project is located.

[Statutory Authority: Chapter 39.12 RCW, RCW 43.22.051 and 43.22.270. 08-24-101, § 296-127-018, filed 12/2/08, effective 1/2/09. Statutory Authority: Chapters 39.04 and 39.12 RCW and RCW 43.22.270. 92-01-104 and 92-08-101, § 296-127-018, filed 12/18/91 and 4/1/92, effective 8/31/92.]

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

****

Overtime Codes

Overtime calculations are based on the hourly rate actually paid to the worker. On public works projects, the hourly rate must be not less than the prevailing rate of wage minus the hourly rate of the cost of fringe benefits actually provided for the worker.

1. ALL HOURS WORKED IN EXCESS OF EIGHT (8) HOURS PER DAY OR FORTY (40) HOURS PER WEEK SHALL BE PAID AT ONE AND ONE-HALF TIMES THE HOURLY RATE OF WAGE.

B. All hours worked on Saturdays shall be paid at one and one-half times the hourly rate of wage. All hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.

C. The first two (2) hours after eight (8) regular hours Monday through Friday and the first ten (10) hours on Saturday shall be paid at one and one-half times the hourly rate of wage. All other overtime hours and all hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.

D. The first two (2) hours before or after a five-eight (8) hour workweek day or a four-ten (10) hour workweek day and the first eight (8) hours worked the next day after either workweek shall be paid at one and one-half times the hourly rate of wage. All additional hours worked and all worked on Sundays and holidays shall be paid at double the hourly rate of wage.

E. The first two (2) hours after eight (8) regular hours Monday through Friday and the first eight (8) hours on Saturday shall be paid at one and one-half times the hourly rate of wage. All other hours worked Monday through Saturday, and all hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.

F. The first two (2) hours after eight (8) regular hours Monday through Friday and the first ten (10) hours on Saturday shall be paid at one and one-half times the hourly rate of wage. All other overtime hours worked, except Labor Day, shall be paid at double the hourly rate of wage. All hours worked on Labor Day shall be paid at three times the hourly rate of wage.

G. The first ten (10) hours worked on Saturdays and the first ten (10) hours worked on a fifth calendar weekday in a four-ten hour schedule, shall be paid at one and one-half times the hourly rate of wage. All hours worked in excess of ten (10) hours per day Monday through Saturday and all hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.

H. All hours worked on Saturdays (except makeup days if work is lost due to inclement weather conditions or equipment breakdown) shall be paid at one and one-half times the hourly rate of wage. All hours worked Monday through Saturday over twelve (12) hours and all hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.

I. All hours worked on Sundays and holidays shall also be paid at double the hourly rate of wage.

J. The first two (2) hours after eight (8) regular hours Monday through Friday and the first ten (10) hours on Saturday shall be paid at one and one-half times the hourly rate of wage. All hours worked over ten (10) hours Monday through Saturday, Sundays and holidays shall be paid at double the hourly rate of wage.

K. All hours worked on Saturdays and Sundays shall be paid at one and one-half times the hourly rate of wage. All hours worked on holidays shall be paid at double the hourly rate of wage.

M. All hours worked on Saturdays (except makeup days if work is lost due to inclement weather conditions) shall be paid at one and one-half times the hourly rate of wage. All hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Overtime Codes Continued

1. N. All hours worked on Saturdays (except makeup days) shall be paid at one and one-half times the hourly rate of wage. All hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.

O. The first ten (10) hours worked on Saturday shall be paid at one and one-half times the hourly rate of wage. All hours worked on Sundays, holidays and after twelve (12) hours, Monday through Friday and after ten (10) hours on Saturday shall be paid at double the hourly rate of wage.

P. All hours worked on Saturdays (except makeup days if circumstances warrant) and Sundays shall be paid at one and one-half times the hourly rate of wage. All hours worked on holidays shall be paid at double the hourly rate of wage.

Q. The first two (2) hours after eight (8) regular hours Monday through Friday and up to ten (10) hours worked on Saturdays shall be paid at one and one-half times the hourly rate of wage. All hours worked in excess of ten (10) hours per day Monday through Saturday and all hours worked on Sundays and holidays (except Christmas day) shall be paid at double the hourly rate of wage. All hours worked on Christmas day shall be paid at two and one-half times the hourly rate of wage.

R. All hours worked on Sundays and holidays shall be paid at two times the hourly rate of wage.

U. All hours worked on Saturdays shall be paid at one and one-half times the hourly rate of wage. All hours worked on Sundays and holidays (except Labor Day) shall be paid at two times the hourly rate of wage. All hours worked on Labor Day shall be paid at three times the hourly rate of wage.

V. All hours worked on Sundays and holidays (except Thanksgiving Day and Christmas day) shall be paid at one and one-half times the hourly rate of wage. All hours worked on Thanksgiving Day and Christmas day shall be paid at double the hourly rate of wage.

X. The first four (4) hours after eight (8) regular hours Monday through Friday and the first twelve (12) hours on Saturday shall be paid at one and one-half times the hourly rate of wage. All hours worked over twelve (12) hours Monday through Saturday, Sundays and holidays shall be paid at double the hourly rate of wage. When holiday falls on Saturday or Sunday, the day before Saturday, Friday, and the day after Sunday, Monday, shall be considered the holiday and all work performed shall be paid at double the hourly rate of wage.

Y. All hours worked outside the hours of 5:00 am and 5:00 pm (or such other hours as may be agreed upon by any employer and the employee) and all hours worked in excess of eight (8) hours per day (10 hours per day for a 4 x 10 workweek) and on Saturdays and holidays (except labor day) shall be paid at one and one-half times the hourly rate of wage. (except for employees who are absent from work without prior approval on a scheduled workday during the workweek shall be paid at the straight-time rate until they have worked 8 hours in a day (10 in a 4 x 10 workweek) or 40 hours during that workweek.) All hours worked Monday through Saturday over twelve (12) hours and all hours worked on Sundays and Labor Day shall be paid at double the hourly rate of wage.

Z. All hours worked on Saturdays and Sundays shall be paid at one and one-half times the hourly rate of wage. All hours worked on holidays shall be paid the straight time rate of pay in addition to holiday pay.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Overtime Codes Continued

2. ALL HOURS WORKED IN EXCESS OF EIGHT (8) HOURS PER DAY OR FORTY (40) HOURS PER WEEK SHALL BE PAID AT ONE AND ONE-HALF TIMES THE HOURLY RATE OF WAGE.

   B. All hours worked on holidays shall be paid at one and one-half times the hourly rate of wage.

   F. The first eight (8) hours worked on holidays shall be paid at the straight hourly rate of wage in addition to the holiday pay. All hours worked in excess of eight (8) hours on holidays shall be paid at double the hourly rate of wage.

   M. This code appears to be missing. All hours worked on Saturdays, Sundays and holidays shall be paid at double the hourly rate of wage.

   R. All hours worked on Sundays and holidays and all hours worked over sixty (60) in one week shall be paid at double the hourly rate of wage.

   U. All hours worked on Saturdays shall be paid at one and one-half times the hourly rate of wage. All hours worked over 12 hours in a day or on Sundays and holidays shall be paid at double the hourly rate of wage.

3. ALL HOURS WORKED IN EXCESS OF EIGHT (8) HOURS PER DAY OR FORTY (40) HOURS PER WEEK SHALL BE PAID AT ONE AND ONE-HALF TIMES THE HOURLY RATE OF WAGE.

   F. All hours worked on Saturday shall be paid at one and one-half times the hourly rate of wage. All hours worked on Sunday shall be paid at two times the hourly rate of wage. All hours worked on paid holidays shall be paid at two and one-half times the hourly rate of wage including holiday pay.

   H. All work performed on Sundays between March 16th and October 14th and all Holidays shall be compensated for at two (2) times the regular rate of pay. Work performed on Sundays between October 15th and March 15th shall be compensated at one and one half (1-1/2) times the regular rate of pay.

   J. All hours worked between the hours of 10:00 pm and 5:00 am, Monday through Friday, and all hours worked on Saturdays shall be paid at a one and one-half times the hourly rate of wage. All hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.

   K. Work performed in excess of eight (8) hours of straight time per day, or ten (10) hours of straight time per day when four ten (10) hour shifts are established, or forty (40) hours of straight time per week, Monday through Friday, or outside the normal 5 am to 6pm shift, and all work on Saturdays shall be paid at one and one-half times the hourly rate of wage. All work performed after 6:00 pm Saturday to 5:00 am Monday and Holidays, and all hours worked in excess of twelve (12) hours in a single shift shall be paid at double the hourly rate of wage.

   After an employee has worked eight (8) hours at an applicable overtime rate, all additional hours shall be at the applicable overtime rate until such time as the employee has had a break of eight (8) hours or more. When an employee returns to work without at least eight (8) hours time off since their previous shift, all such time shall be a continuation of shift and paid at the applicable overtime rate until he/she shall have the eight (8) hours rest period.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Overtime Codes Continued

4. ALL HOURS WORKED IN EXCESS OF EIGHT (8) HOURS PER DAY OR FORTY (40) HOURS PER WEEK SHALL BE PAID AT ONE AND ONE-HALF TIMES THE HOURLY RATE OF WAGE.

A. All hours worked in excess of eight (8) hours per day or forty (40) hours per week shall be paid at double the hourly rate of wage. All hours worked on Saturdays, Sundays and holidays shall be paid at double the hourly rate of wage

C. On Monday through Friday, the first four (4) hours of overtime after eight (8) hours of straight time work shall be paid at one and one half (1-1/2) times the straight time rate of pay, unless a four (4) day ten (10) hour workweek has been established. On a four (4) day ten (10) hour workweek scheduled Monday through Thursday, or Tuesday through Friday, the first two (2) hours of overtime after ten (10) hours of straight time work shall be paid at one and one half (1-1/2) times the straight time rate of pay. On Saturday, the first twelve (12) hours of work shall be paid at one and one half (1-1/2) times the straight time rate of pay, except that if the job is down on Monday through Friday due to weather conditions or other conditions outside the control of the employer, the first ten (10) hours on Saturday may be worked at the straight time rate of pay. All hours worked over twelve (12) hours in a day and all hours worked on Sunday and Holidays shall be paid at two (2) times the straight time rate of pay.

D. All hours worked in excess of eight (8) hours per day or forty (40) hours per week shall be paid at double the hourly rate of wage. All hours worked on Saturday, Sundays and holidays shall be paid at double the hourly rate of pay. Rates include all members of the assigned crew.

EXCEPTION:
On all multipole structures and steel transmission lines, switching stations, regulating, capacitor stations, generating plants, industrial plants, associated installations and substations, except those substations whose primary function is to feed a distribution system, will be paid overtime under the following rates:

The first two (2) hours after eight (8) regular hours Monday through Friday of overtime on a regular workday, shall be paid at one and one-half times the hourly rate of wage. All hours in excess of ten (10) hours will be at two (2) times the hourly rate of wage. The first eight (8) hours worked on Saturday will be paid at one and one-half (1-1/2) times the hourly rate of wage. All hours worked in excess of eight (8) hours on Saturday, and all hours worked on Sundays and holidays will be at the double the hourly rate of wage.

All overtime eligible hours performed on the above described work that is energized, shall be paid at the double the hourly rate of wage.

E. The first two (2) hours after eight (8) regular hours Monday through Friday and the first eight (8) hours on Saturday shall be paid at one and one-half times the hourly rate of wage. All other hours worked Monday through Saturday, and all hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.

On a four-day, ten-hour weekly schedule, either Monday thru Thursday or Tuesday thru Friday schedule, all hours worked after ten shall be paid at double the hourly rate of wage. The Monday or Friday not utilized in the normal four-day, ten hour work week, and Saturday shall be paid at one and one half (1½) times the regular shift rate for the first eight (8) hours. All other hours worked Monday through Saturday, and all hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.

G. All hours worked on Saturdays shall be paid at one and one-half times the hourly rate of wage. All hours worked Monday through Saturday over twelve (12) hours and all hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.

I. The First eight (8) hours worked on Saturdays shall be paid at one and one-half times the hourly rate of wage. All hours worked in excess of eight (8) per day on Saturdays shall be paid at double the hourly rate of wage. All hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Overtime Codes Continued

4. J. The first eight (8) hours worked on a Saturday shall be paid at one and one-half times the hourly rate of wage. All hours worked in excess of eight (8) hours on a Saturday shall be paid at double the hourly rate of wage. All hours worked over twelve (12) in a day, and all hours worked on Sundays and Holidays shall be paid at double the hourly rate of wage.

K. All hours worked on a Saturday shall be paid at one and one-half times the hourly rate of wage, so long as Saturday is the sixth consecutive day worked. All hours worked over twelve (12) in a day Monday through Saturday, and all hours worked on Sundays and Holidays shall be paid at double the hourly rate of wage.

L. The first twelve (12) hours worked on a Saturday shall be paid at one and one-half times the hourly rate of wage. All hours worked on a Saturday in excess of twelve (12) hours shall be paid at double the hourly rate of pay. All hours worked over twelve (12) in a day Monday through Friday, and all hours worked on Sundays shall be paid at double the hourly rate of wage. All hours worked on a holiday shall be paid at one and one-half times the hourly rate of wage, except that all hours worked on Labor Day shall be paid at double the hourly rate of pay.

S. On a four (4) day ten (10) hour workweek scheduled Monday through Thursday, or Tuesday through Friday, work performed in excess of (10) hours shall be paid at one and one half (1-1/2) times the hourly rate of pay. On Monday through Friday, work performed outside the normal work hours of 6:00 a.m. and 6:00 p.m. shall be paid at one and one-half (1-1/2) times the straight time rate, (except for special shifts or multiple shift operations).

All hours worked on Saturdays shall be paid at one and one-half times the hourly rate of wage. All work performed on Sundays and holidays shall be paid at double the hourly rate of wage. When an employee returns to work without at least eight (8) hours time off since their previous shift, all such time shall be a continuation of shift and paid at the applicable overtime rate until such time as the employee has had a break of eight (8) hours.

Multiple Shift Operations: When the first shift of a multiple shift (a two or three shift) operation is started at the basic straight time rate or at a specific overtime rate, all shifts of that day's operation shall be completed at that rate. Special Shifts: The Special Shift Premium is the basic hourly rate of pay plus $2.00 an hour. When due to conditions beyond the control of the employer or when an owner (not acting as the contractor), a government agency or the contract specifications require more than four (4) hours of a special shift can only be performed outside the normal 6am to 6pm shift then the special shift premium will be applied to the basic straight time for the entire shift. When an employee works on a special shift, they shall be paid the special shift premium for each hour worked unless they are in overtime or double-time status. (For example, the special shift premium does not waive the overtime requirements for work performed on Saturday or Sunday).

U. The first four (4) hours after eight (8) regular hours Monday through Friday and the first twelve (12) hours on Saturday shall be paid at one and one-half times the hourly rate of wage. (Except on makeup days if work is lost due to inclement weather, then the first eight (8) hours on Saturday may be paid the regular rate.) All hours worked over twelve (12) hours Monday through Saturday, and all hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Overtime Codes Continued

4. X. All hours worked on Saturdays shall be paid at one and one-half times the hourly rate of wage. All hours worked on Sundays and holidays shall be paid at double the hourly rate of wage. Work performed outside the normal shift of 6 am to 6pm shall be paid at one and one-half the straight time rate, (except for special shifts or three shift operations). All work performed on Sundays and holidays shall be paid at double the hourly rate of wage. Shifts may be established when considered necessary by the Employer.

The Employer may establish shifts consisting of eight (8) or ten (10) hours of work (subject to WAC 296-127-022), that shall constitute a normal forty (40) hour work week. The Employer can change from a 5-eight to a 4-ten hour schedule or back to the other. All hours of work on these shifts shall be paid for at the straight time hourly rate. Work performed in excess of eight hours (or ten hours per day (subject to WAC 296-127-022) shall be paid at one and one-half the straight time rate.

When due to conditions beyond the control of the Employer, or when contract specifications require that work can only be performed outside the regular day shift, then by mutual agreement a special shift may be worked at the straight time rate, eight (8) hours work for eight (8) hours pay. The starting time shall be arranged to fit such conditions of work.

When an employee returns to work without at a break of eight (8) hours since their previous shift, all such time shall be a continuation of shift and paid at the applicable overtime rate until such time as the employee has had a break of eight (8) hours.

Overtime Codes Continued

11. ALL HOURS WORKED IN EXCESS OF EIGHT (8) HOURS PER DAY OR FORTY (40) HOURS PER WEEK SHALL BE PAID AT ONE AND ONE-HALF TIMES THE HOURLY RATE OF WAGE.

B After an employee has worked eight (8) hours, all additional hours worked shall be paid at the applicable overtime rate until such time as the employee has had a break of eight (8) hours or more.

C The first two (2) hours after eight (8) regular hours Monday through Friday and the first eight (8) hours on Saturday shall be paid at one and one-half times the hourly rate of wage. All other overtime hours worked, except Labor Day, and all hours on Sunday shall be paid at double the hourly rate of wage. All hours worked on Labor Day shall be paid at three times the hourly rate of wage. All non-overtime and non-holiday hours worked between 4:00 pm and 5:00 am, Monday through Friday, shall be paid at a premium rate of 15% over the hourly rate of wage.

D. All hours worked on Saturdays and holidays shall be paid at one and one-half times the hourly rate of wage. All hours worked on Sundays shall be paid at double the hourly rate of wage.

After an employee has worked eight (8) hours, all additional hours worked shall be paid at the applicable overtime rate until such time as the employee has had a break of eight (8) hours or more.

E. The first two (2) hours after eight (8) regular hours Monday through Friday, the first ten (10) hours on Saturday, and the first ten (10) hours worked on Holidays shall be paid at one and one-half times the hourly rate of wage. All hours worked over ten (10) hours Monday through Saturday, and Sundays shall be paid at double the hourly rate of wage.

After an employee has worked eight (8) hours, all additional hours worked shall be paid at the applicable overtime rate until such time as the employee has had a break of eight (8) hours or more.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Overtime Codes Continued

11. F. The first two (2) hours after eight (8) regular hours Monday through Friday and the first eight (8) hours on Saturday shall be paid at one and one-half times the hourly rate of wage. All other hours worked Monday through Saturday, and all hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.

On a four-day, ten-hour weekly schedule, either Monday thru Thursday or Tuesday thru Friday schedule, all hours worked after ten shall be paid at double the hourly rate of wage. The Monday or Friday not utilized in the normal four-day, ten hour work week, and Saturday shall be paid at one-half times the hourly rate of wage for the first eight (8) hours. All other hours worked Monday through Saturday, and all hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.

G. Work performed in excess of eight (8) hours of straight time per day, or ten (10) hours of straight time per day when four ten (10) hour shifts are established, or forty (40) hours of straight time per week, Monday through Friday, or outside the normal 5 am to 6pm shift, and all work on Saturdays shall be paid at one and one-half times the hourly rate of wage.

All work performed after 6:00 pm Saturday to 5:00 am Monday and Holidays, and all hours worked in excess of twelve (12) hours in a single shift shall be paid at double the hourly rate of wage.

After an employee has worked eight (8) hours at an applicable overtime rate, all additional hours shall be at the applicable overtime rate until such time as the employee has had a break of nine (9) hours or more. When an employee returns to work without at least nine (9) hours time off since their previous shift, all such time shall be a continuation of shift and paid at the applicable overtime rate until he/she shall have the nine (9) hours rest period.

H. Work performed in excess of eight (8) hours of straight time per day, or ten (10) hours of straight time per day when four ten (10) hour shifts are established, or forty (40) hours of straight time per week, Monday through Friday, or outside the normal 5 am to 6pm shift, and all work on Saturdays shall be paid at one and one-half times the hourly rate of wage.

All work performed after 6:00 pm Saturday to 5:00 am Monday and Holidays, and all hours worked in excess of twelve (12) hours in a single shift shall be paid at double the hourly rate of wage.

After an employee has worked eight (8) hours at an applicable overtime rate, all additional hours shall be at the applicable overtime rate until such time as the employee has had a break of ten (10) hours or more. When an employee returns to work without at least ten (10) hours time off since their previous shift, all such time shall be a continuation of shift and paid at the applicable overtime rate until he/she shall have the ten (10) hours rest period.

J. All hours worked on holidays shall be paid at double the hourly rate of wage.

K. On Monday through Friday hours worked outside 4:00 am and 5:00 pm, and the first two (2) hours after eight (8) hours worked shall be paid at one and one-half times the hourly rate. All hours worked over 10 hours per day Monday through Friday, and all hours worked on Saturdays, Sundays, and Holidays worked shall be paid at double the hourly rate of wage.

L. An employee working outside 5:00 am and 5:00 pm shall receive an additional two dollar ($2.00) per hour for all hours worked that shift. All hours worked on holidays shall be paid at one and one-half times the hourly rate of wage. All hours worked on holidays shall be paid at one and one-half times the hourly rate of wage.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Overtime Codes Continued

11. M. On Monday through Friday, the first four (4) hours of overtime after eight (8) hours of straight time work shall be paid at one and one half (1-1/2) times the straight time rate of pay, unless a four (4) day ten (10) hour workweek has been established. On a four (4) day ten (10) hour workweek scheduled Monday through Thursday, or Tuesday through Friday, the first two (2) hours of overtime after ten (10) hours of straight time work shall be paid at one and one half (1-1/2) times the straight time rate of pay.

Work performed outside the normal work hours of 5:00 a.m. and 6:00 p.m. shall be paid at one and one-half (1-1/2) times the straight time rate, (except for special shifts or multiple shift operations). When the first shift of a multiple shift (a two or three shift) operation is started at the basic straight time rate or at a specific overtime rate, all shifts of that day's operation shall be completed at that rate. When due to conditions beyond the control of the Employer or when contract specifications require that work can only be performed outside the regular day shift of 5:00 am to 6:00 pm, then a special shift may be worked at the straight time rate, plus the shift pay premium when applicable. The starting time of work will be arranged to fit such conditions of work. Such shift shall consist of eight (8) hours work for eight (8) hours pay or ten (10) hours work for ten (10) hours pay for four ten shifts.

On Saturday, the first twelve (12) hours of work shall be paid at one and one half (1-1/2) times the straight time rate of pay. All work performed after 6:00 pm Saturday to 5:00 am Monday, all work performed over twelve (12) hours, and all work performed on holidays shall be paid at double the straight time rate of pay.

Shift Pay Premium: In an addition to any overtime already required, all hours worked between the hours of 6:00 pm and 5:00 am shall receive an additional two dollars ($2.00) per hour.

N. All work performed over twelve hours in a shift and all work performed on Sundays and Holidays shall be paid at double the straight time rate.

Any time worked over eight (8) hours on Saturday shall be paid double the straight time rate, except employees assigned to work six 10-hour shifts per week shall be paid double the straight time rate for any time worked on Saturday over 10 hours.

O. All work performed on Saturdays, Sundays, and Holidays shall be paid at one and one half (1-1/2) times the straight time rate of pay.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Overtime Codes Continued

11. P. Work performed in excess of ten (10) hours of straight time per day when four ten (10) hour shifts are established and all work on Saturdays, except for make-up days shall be paid at time and one-half (1 ½) the straight time rate.

Work performed outside the normal work hours of 5:00 a.m. and 6:00 p.m. shall be paid at one and one-half (1-1/2) times the straight time rate, (except for special shifts or multiple shift operations). When the first shift of multiple shift (a two or three shift) operation is started at the basic straight time rate or at a specific overtime rate, all shifts of that day's operation shall be completed at that rate. When due to conditions beyond the control of the Employer or when contract specifications require that work can only be performed outside the regular day shift of 5:00 a.m. to 6:00 p.m., then a special shift may be worked at the straight time rate, plus the shift pay premium when applicable. The starting time of work will be arranged to fit such conditions of work. Such shifts shall consist of eight (8) hours work for eight (8) hours pay or ten (10) hours work for ten (10) hours pay for four ten-hour shifts.

In the event the job is down due to weather conditions, then Saturday may, be worked as a voluntary make-up day at the straight time rate. However, Saturday shall not be utilized as a make-up day when a holiday falls on Friday. All work performed on Sundays and holidays and work in excess of twelve (12) hours per day shall be paid at double (2x) the straight time rate of pay.

After an employee has worked eight (8) hours at an applicable overtime rate, all additional hours shall be at the applicable overtime rate until such time as the employee has had a break of eight (8) hours.

When an employee returns to work without a break of eight (8) hours since their previous shift, all such time shall be a continuation of shift and paid at the applicable overtime rate until such time as the employee has had a break of eight (8) hours.

Q. All hours worked between the hours of 6:00 pm and 6:00 am, Monday through Saturday, shall be paid at a premium rate of 35% over the hourly rate of wage. Work performed on Sundays shall be paid at double time. All hours worked on holidays shall be paid at double the hourly rate of wage.

R On Monday through Saturday hours worked outside 6:00 am and 7:00 pm, and all hours after eight (8) hours worked shall be paid at one and one-half times the hourly rate. All hours worked on Sundays and Holidays shall be paid at double the hourly rate of wage.

When a holiday falls on a Saturday, the Friday before shall be the observed holiday. When a holiday falls on a Sunday, the following Monday shall be the observed holiday.

S. The first ten (10) hours worked on Saturdays shall be paid at one and one-half times the hourly rate of wage. In the event the job is down due to weather conditions, or other conditions beyond the control of the Employer, then Saturday may be worked at the straight time rate, for the first eight (8) hours, or the first ten (10) hours when a four day ten hour workweek has been established.

All hours worked Monday through Saturday over twelve (12) hours and all hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.

When an employee returns to work without a break of eight (8) hours since their previous shift, all such time shall be a continuation of shift and paid at the applicable overtime rate until such time as the employee has had a break of eight (8) hours.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Overtime Codes Continued

11. T. On Monday through Friday, the first four (4) hours of overtime after eight (8) hours of straight time work shall be paid at one and one half (1-1/2) times the straight time rate of pay, unless a four (4) day ten (10) hour workweek has been established. On a four (4) day ten (10) hour workweek scheduled Monday through Thursday, or Tuesday through Friday, the first two (2) hours of overtime after ten (10) hours of straight time work shall be paid at one and one half (1-1/2) times the straight time rate of pay.

On Saturday, the first twelve (12) hours of work shall be paid at one and one half (1-1/2) times the straight time rate of pay, except that if the job is down on Monday through Friday due to weather conditions or other conditions outside the control of the employer, the first ten (10) hours on Saturday may be worked at the straight time rate of pay.

All hours worked over twelve (12) hours in a day and all hours worked on Sunday and Holidays shall be paid at two (2) times the straight time rate of pay.

U. On Monday through Friday, the first four (4) hours of overtime after eight (8) hours of straight time work shall be paid at one and one half (1-1/2) times the straight time rate of pay, unless a four (4) day ten (10) hour workweek has been established. On a four (4) day ten (10) hour workweek scheduled Monday through Thursday, or Tuesday through Friday, the first two (2) hours of overtime after ten (10) hours of straight time work shall be paid at one and one half (1-1/2) times the straight time rate of pay.

On Saturday, the first twelve (12) hours of work shall be paid at one and one half (1-1/2) times the straight time rate of pay, except that if the job is down on Monday through Friday due to weather conditions or other conditions outside the control of the employer, the first ten (10) hours on Saturday may be worked at the straight time rate of pay.

All hours worked over twelve (12) hours in a day and all hours worked on Sunday and Holidays shall be paid at two (2) times the straight time rate of pay.

If, due to conditions beyond the control of the Employer or when contract specifications require that work can only be performed outside the regular day shift, then a Special Shift may be worked, Monday through Friday, at the straight-time rate. The starting time of work for the Special Shift will be arranged to fit such conditions of work. Such Special Shift shall consist of eight (8) hours of work for eight (8) hours of pay or ten (10) hours of work for ten(10) hours of pay on a four-ten workday schedule.

V. All hours worked on Saturdays and Sundays (except make-up days due to conditions beyond the control of the employer) shall be paid at one and one-half times the hourly rate of wage. All hours worked on holidays shall be paid at double the hourly rate of wage.

W. Work performed in excess of eight (8) hours of straight time per day, or ten (10) hours of straight time per day when four ten (10) hour shifts are established, or forty (40) hours of straight time per week, Monday through Friday, or outside the normal 6 am to 6pm shift, and all work on Saturdays shall be paid at one and one-half times the hourly rate of wage. All work performed on Sundays and Holidays shall be paid at double the hourly rate of wage.

After an employee has worked eight (8) hours at an applicable overtime rate, all additional hours shall be at the applicable overtime rate until such time as the employee has had a break of eight (8) hours or more.

When an employee returns to work without at least eight (8) hours time off since their previous shift, all such time shall be a continuation of shift and paid at the applicable overtime rate until he/she shall have the eight (8) hours rest period.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Holiday Codes

5. A. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, Friday after Thanksgiving Day, and Christmas Day (7).

B. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, Friday after Thanksgiving Day, the day before Christmas, and Christmas Day (8).

C. Holidays: New Year's Day, Presidents' Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday after Thanksgiving Day, And Christmas Day (8).

D. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday and Saturday after Thanksgiving Day, And Christmas Day (8).

H. Holidays: New Year's Day, Memorial Day, Independence Day, Thanksgiving Day, the Day after Thanksgiving Day, And Christmas (6).

I. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, and Christmas Day (6).

K. Holidays: New Year's Day, Presidents' Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, Friday After Thanksgiving Day, The Day Before Christmas, And Christmas Day (9).

L. Holidays: New Year's Day, Martin Luther King Jr. Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, Friday after Thanksgiving Day, And Christmas Day (8).

N. Holidays: New Year's Day, Presidents' Day, Memorial Day, Independence Day, Labor Day, Veterans' Day, Thanksgiving Day, The Friday After Thanksgiving Day, And Christmas Day (9).

P. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, Friday And Saturday After Thanksgiving Day, The Day Before Christmas, And Christmas Day (9). If A Holiday Falls On Sunday, The Following Monday Shall Be Considered As A Holiday.

Q. Paid Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, and Christmas Day (6).

R. Paid Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, Day After Thanksgiving Day, One-Half Day Before Christmas Day, And Christmas Day. (7 1/2).

S. Paid Holidays: New Year's Day, Presidents' Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, And Christmas Day (7).

Z. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Veterans Day, Thanksgiving Day, the Friday after Thanksgiving Day, And Christmas Day (8).

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Holiday Codes Continued

6. G. Paid Holidays: New Year's Day, Martin Luther King Jr. Day, Presidents' Day, Memorial Day, Independence Day, Labor Day, Veterans' Day, Thanksgiving Day, the Friday after Thanksgiving Day, Christmas Day, and Christmas Eve Day (11).

H. Paid Holidays: New Year's Day, New Year's Eve Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, Friday After Thanksgiving Day, Christmas Day, The Day After Christmas, And A Floating Holiday (10).

T. Paid Holidays: New Year's Day, Presidents' Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, The Friday After Thanksgiving Day, The Last Working Day Before Christmas Day, And Christmas Day (9).

Z. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, Friday after Thanksgiving Day, And Christmas Day (7). If a holiday falls on Saturday, the preceding Friday shall be considered as the holiday. If a holiday falls on Sunday, the following Monday shall be considered as the holiday.

Holiday Codes Continued

7. A. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday and Saturday after Thanksgiving Day, And Christmas Day (8). Any Holiday Which Falls On A Sunday Shall Be Observed As A Holiday On The Following Monday. If any of the listed holidays falls on a Saturday, the preceding Friday shall be a regular work day.

B. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday and Saturday after Thanksgiving Day, And Christmas Day (8). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. Any holiday which falls on a Saturday shall be observed as a holiday on the preceding Friday.

C. Holidays: New Year's Day, Martin Luther King Jr. Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday after Thanksgiving Day, And Christmas Day (8). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. Any holiday which falls on a Saturday shall be observed as a holiday on the preceding Friday.

D. Paid Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Veteran's Day, Thanksgiving Day, the Friday after Thanksgiving Day, And Christmas Day (8). Unpaid Holidays: President's Day. Any paid holiday which falls on a Sunday shall be observed as a holiday on the following Monday. Any paid holiday which falls on a Saturday shall be observed as a holiday on the preceding Friday.

E. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday after Thanksgiving Day, And Christmas Day (7). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. Any holiday which falls on a Saturday shall be observed as a holiday on the preceding Friday.

F. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday after Thanksgiving Day, the last working day before Christmas day and Christmas day (8). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. Any holiday which falls on a Saturday shall be observed as a holiday on the preceding Friday.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Holiday Codes Continued

7. G. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, and Christmas Day (6). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday.

H. Holidays: New Year's Day, Martin Luther King Jr. Day, Independence Day, Memorial Day, Labor Day, Thanksgiving Day, the Friday after Thanksgiving Day, the Last Working Day before Christmas Day and Christmas Day (9). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. Any holiday which falls on a Saturday shall be observed as a holiday on the preceding Friday.

I. Holidays: New Year's Day, President's Day, Independence Day, Memorial Day, Labor Day, Thanksgiving Day, The Friday After Thanksgiving Day, The Day Before Christmas Day And Christmas Day (9). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. Any holiday which falls on a Saturday shall be observed as a holiday on the preceding Friday.

J. Holidays: New Year's Day, Independence Day, Memorial Day, Labor Day, Thanksgiving Day and Christmas Day (6). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. Any holiday which falls on a Saturday shall be observed as a holiday on the preceding Friday.

K. Holidays: New Year's Day, Memorial Day, Independence Day, Thanksgiving Day, the Friday and Saturday after Thanksgiving Day, And Christmas Day (8). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. Any holiday which falls on a Saturday shall be observed as a holiday on the preceding Friday.

L. Holidays: New Year's Day, Memorial Day, Labor Day, Independence Day, Thanksgiving Day, the Last Work Day before Christmas Day, And Christmas Day (7). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. Any holiday which falls on a Saturday shall be observed as a holiday on the preceding Friday.

N. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday after Thanksgiving Day, And Christmas Day (7). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. When Christmas falls on a Saturday, the preceding Friday shall be observed as a holiday.

P. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, Friday after Thanksgiving Day, And Christmas Day (7). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday.

Q. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday after Thanksgiving Day, the Last Working Day before Christmas Day and Christmas Day (8). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. If any of the listed holidays falls on a Saturday, the preceding Friday shall be a regular work day.

S. Paid Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, Friday after Thanksgiving Day, Christmas Day, the Day after Christmas, and A Floating Holiday (9). If any of the listed holidays falls on a Sunday, the day observed by the Nation shall be considered a holiday and compensated accordingly.

V. Holidays: New Year's Day, President's Birthday, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday after Thanksgiving Day, Christmas Day, the day before or after Christmas, and the day before or after New Year's Day. If any of the above listed holidays falls on a Sunday, the day observed by the Nation shall be considered a holiday and compensated accordingly.

W. Holidays: New Year's Day, Day After New Year's, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday after Thanksgiving Day, Christmas Eve Day, Christmas Day, the day after Christmas, the day before New Year's Day, and a Floating Holiday.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Holiday Codes Continued

7. X. Holidays: New Year's Day, Day before or after New Year's Day, Presidents' Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday after Thanksgiving Day, Christmas Day, and the day before or after Christmas day. If a holiday falls on a Saturday or on a Friday that is the normal day off, then the holiday will be taken on the last normal workday. If the holiday falls on a Monday that is the normal day off or on a Sunday, then the holiday will be taken on the next normal workday.

Y. Holidays: New Year's Day, Presidents' Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday after Thanksgiving Day, and Christmas Day. (8) If the holiday falls on a Sunday, then the day observed by the federal government shall be considered a holiday and compensated accordingly.

Z. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday and Saturday after Thanksgiving Day, Christmas Eve, and Christmas Day (9). Any holiday which falls on a Saturday shall be observed as a holiday on the preceding Friday. Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday.

Holiday Codes Continued

15. G. New Year's Day, Washington's Birthday, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, The Friday After Thanksgiving Day, the last scheduled workday before Christmas, and Christmas Day (9). If any of the listed holidays falls on a Sunday, the day observed by the Nation shall be considered a holiday and compensated accordingly.

H. Holidays: New Year's Day, Martin Luther King Jr. Day, Independence Day, Memorial Day, Labor Day, Thanksgiving Day, the Friday after Thanksgiving Day, the Last Working Day before Christmas Day and Christmas Day (9). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. Any holiday which falls on a Saturday shall be observed as a holiday on the preceding Friday.

I. Holidays: New Year's Day, President's Day, Independence Day, Memorial Day, Labor Day, Thanksgiving Day, The Friday After Thanksgiving Day, The Day Before Christmas Day And Christmas Day (9). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. Any holiday which falls on a Saturday shall be observed as a holiday on the preceding Friday.

J. Holidays: New Year's Day, Martin Luther King Jr. Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday and Saturday after Thanksgiving Day, and Christmas Day (9). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. If any of the listed holidays falls on a Saturday, the preceding Friday shall be a regular work day.

K. Holidays: New Year's Day, Memorial Day, Independence Day, Thanksgiving Day, the Friday and Saturday after Thanksgiving Day, And Christmas Day (8). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. Any holiday which falls on a Saturday shall be observed as a holiday on the preceding Friday.

L. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Veteran's Day, Thanksgiving Day, the Friday after Thanksgiving Day, and Christmas Day (8). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. If any of the listed holidays falls on a Saturday, the preceding Friday shall be a regular work day.

M. Holidays: New Year's Day, Martin Luther King Jr. Day, Independence Day, Memorial Day, Labor Day, Thanksgiving Day, the Friday after Thanksgiving Day, Christmas Eve Day and Christmas Day (9). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. If any of the listed holidays falls on a Saturday, the preceding Friday shall be a regular work day.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Holiday Codes Continued

15. N. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Veteran's Day, Thanksgiving Day, the Friday after Thanksgiving Day, and Christmas Day (8). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday.

O. Holidays: New Year's Day, Martin Luther King Jr. Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday and Saturday after Thanksgiving Day, the day before Christmas day, and Christmas Day (10). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday.

P. Holidays: New Year's Day, Memorial Day, Labor Day, Independence Day, Thanksgiving Day, the Friday after Thanksgiving Day, Christmas Eve Day, And Christmas Day (8). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. Any holiday which falls on a Saturday shall be observed as a holiday on the preceding Friday.

Note Codes

8. D. Workers working with supplied air on hazmat projects receive an additional $1.00 per hour.

L. Workers on hazmat projects receive additional hourly premiums as follows -Level A: $0.75, Level B: $0.50, And Level C: $0.25.

M. Workers on hazmat projects receive additional hourly premiums as follows: Levels A & B: $1.00, Levels C & D: $0.50.

N. Workers on hazmat projects receive additional hourly premiums as follows -Level A: $1.00, Level B: $0.75, Level C: $0.50, And Level D: $0.25.

S. Effective August 31, 2012 – A Traffic Control Supervisor shall be present on the project whenever flagging or spotting or other traffic control labor is being utilized. Flaggers and Spotters shall be posted where shown on approved Traffic Control Plans or where directed by the Engineer. All flaggers and spotters shall possess a current flagging card issued by the State of Washington, Oregon, Montana, or Idaho. This classification is only effective on or after August 31, 2012.

T. Effective August 31, 2012 – A Traffic Control Laborer performs the setup, maintenance and removal of all temporary traffic control devices and construction signs necessary to control vehicular, bicycle, and pedestrian traffic during construction operations. Flaggers and Spotters shall be posted where shown on approved Traffic Control Plans or where directed by the Engineer. All flaggers and spotters shall possess a current flagging card issued by the State of Washington, Oregon, Montana, or Idaho. This classification is only effective on or after August 31, 2012.

U. Workers on hazmat projects receive additional hourly premiums as follows – Class A Suit: $2.00, Class B Suit: $1.50, And Class C Suit: $1.00. Workers performing underground work receive an additional $0.40 per hour for any and all work performed underground, including operating, servicing and repairing of equipment. The premium for underground work shall be paid for the entire shift worked. Workers who work suspended by a rope or cable receive an additional $0.50 per hour. The premium for work suspended shall be paid for the entire shift worked. Workers who do "pioneer" work (break open a cut, build road, etc.) more than one hundred fifty (150) feet above grade elevation receive an additional $0.50 per hour.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Note Codes Continued

8. V. In addition to the hourly wage and fringe benefits, the following depth and enclosure premiums shall be paid. The premiums are to be calculated for the maximum depth and distance into an enclosure that a diver reaches in a day. The premiums are to be paid one time for the day and are not used in calculating overtime pay.

Depth premiums apply to depths of fifty feet or more. Over 50' to 100' - $2.00 per foot for each foot over 50 feet. Over 101' to 150' - $3.00 per foot for each foot over 101 feet. Over 151' to 220' - $4.00 per foot for each foot over 220 feet. Over 221' - $5.00 per foot for each foot over 221 feet.

Enclosure premiums apply when divers enter enclosures (such as pipes or tunnels) where there is no vertical ascent and is measured by the distance travelled from the entrance. 25' to 300' - $1.00 per foot from entrance. 300' to 600' - $1.50 per foot beginning at 300'. Over 600' - $2.00 per foot beginning at 600'.

W. Meter Installers work on single phase 120/240V self-contained residential meters. The Lineman/Groundmen rates would apply to meters not fitting this description.

X. Workers on hazmat projects receive additional hourly premiums as follows - Class A Suit: $2.00, Class B Suit: $1.50, Class C Suit: $1.00, and Class D Suit: $0.50. Special Shift Premium: Basic hourly rate plus $2.00 per hour.

When due to conditions beyond the control of the Employer or when an owner (not acting as the contractor), a government agency or the contract specifications requires that work can only be performed outside the normal 5 am to 6pm shift, then the special shift premium will be applied to the basic hourly rate. When an employee works on a special shift, they shall be paid a special shift premium for each hour worked unless they are in OT or Double-time status. (For example, the special shift premium does not waive the overtime requirements for work performed on Saturday or Sunday.)

Y. Tide Work: When employees are called out between the hours of 6:00 p.m. and 6:00 a.m. to work on tide work (work located in the tide plane) all time worked shall be at one and one-half times the hourly rate of pay.

Swinging Stage/Boatswains Chair: Employees working on a swinging state or boatswains chair or under conditions that require them to be tied off to allow their hands to be free shall receive seventy-five cents ($0.75) per hour above the classification rate.

Z. Workers working with supplied air on hazmat projects receive an additional $1.00 per hour.

Special Shift Premium: Basic hourly rate plus $2.00 per hour. When due to conditions beyond the control of the Employer or when an owner (not acting as a contractor), a government agency or the contract specifications require that more than (4) hours of a special shift can only be performed outside the normal 6 am to 6pm shift, then the special shift premium will be applied to the basic straight time for the entire shift. When an employee works on a special shift, they will be paid a special shift premium for each hour worked unless they are in overtime or double-time status. (For example, the special shift premium does not waive the overtime requirements for work performed on Saturday or Sunday.)

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Note Codes Continued

9. A. Workers working with supplied air on hazmat projects receive an additional $1.00 per hour.

Special Shift Premium: Basic hourly rate plus $2.00 per hour. When due to conditions beyond the control of the Employer or when an owner (not acting as the contractor), a government agency or the contract specifications require that more than four (4) hours of a special shift can only be performed outside the normal 6 am to 6pm shift, then the special shift premium will be applied to the basic straight time for the entire shift. When an employee works on a special shift, they shall be paid a special shift premium for each hour worked unless they are in overtime or double-time status. (For example, the special shift premium does not waive the overtime requirements for work performed on Saturday or Sunday.)

Certified Crane Operator Premium: Crane operators requiring certifications shall be paid $0.50 per hour above their classification rate.

Boom Pay Premium: All cranes including tower shall be paid as follows based on boom length:

(A) – 130' to 199' – $0.50 per hour over their classification rate.
(B) – 200' to 299' – $0.80 per hour over their classification rate.
(C) – 300' and over – $1.00 per hour over their classification rate.

B. The highest pressure registered on the gauge for an accumulated time of more than fifteen (15) minutes during the shift shall be used in determining the scale paid.

Tide Work: When employees are called out between the hours of 6:00 p.m. and 6:00 a.m. to work on tide work (work located in the tide plane) all time worked shall be at one and one-half times the hourly rate of pay. Swinging Stage/Boatswains Chair: Employees working on a swinging stage or boatswains chair or under conditions that require them to be tied off to allow their hands to be free shall receive seventy-five cents ($0.75) per hour above the classification rate.

C. Tide Work: When employees are called out between the hours of 6:00 p.m. and 6:00 a.m. to work on tide work (work located in the tide plane) all time worked shall be at one and one-half times the hourly rate of pay. Swinging Stage/Boatswains Chair: Employees working on a swinging stage or boatswains chair or under conditions that require them to be tied off to allow their hands to be free shall receive seventy-five cents ($0.75) per hour above the classification rate.

Effective August 31, 2012 – A Traffic Control Supervisor shall be present on the project whenever flagging or spotting or other traffic control labor is being utilized. A Traffic Control Laborer performs the setup, maintenance and removal of all temporary traffic control devices and construction signs necessary to control vehicular, bicycle, and pedestrian traffic during construction operations. Flaggers and Spotters shall be posted where shown on approved Traffic Control Plans or where directed by the Engineer. All flaggers and spotters shall possess a current flagging card issued by the State of Washington, Oregon, Montana, or Idaho. These classifications are only effective on or after August 31, 2012.

D. Industrial Painter wages are required for painting within industrial facilities such as treatment plants, pipelines, towers, dams, bridges, power generation facilities and manufacturing facilities such as chemical plants, etc., or anywhere abrasive blasting is necessary to prepare surfaces, or hazardous materials encapsulation is required.

E. Heavy Construction includes construction, repair, alteration or additions to the production, fabrication or manufacturing portions of industrial or manufacturing plants, hydroelectric or nuclear power plants and atomic reactor construction. Workers on hazmat projects receive additional hourly premiums as follows -Level A: $1.00, Level B: $0.75, Level C: $0.50, And Level D: $0.25.

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal

Note Codes Continued

9. F. Industrial Painter wages are required for painting within industrial facilities such as treatment plants, pipelines, towers, dams, power generation facilities and manufacturing facilities such as chemical plants, etc., or anywhere abrasive blasting is necessary to prepare surfaces, or hazardous materials encapsulation is required.

H. One (1) person crew shall consist of a Party Chief. (Total Station or similar one (1) person survey system). Two (2) person survey party shall consist of a least a Party Chief and a Chain Person. Three (3) person survey party shall consist of at least a Party Chief, an Instrument Person, and a Chain Person.

I. In addition to the hourly wage and fringe benefits, the following depth and enclosure premiums shall be paid. The premiums are to be calculated for the maximum depth and distance into an enclosure that a diver reaches in a day. The premiums are to be paid one time for the day and are not used in calculating overtime pay.

Depth premiums apply to depths of fifty feet or more. Over 50' to 100' - $2.00 per foot for each foot over 50 feet. Over 101' to 150' - $3.00 per foot for each foot over 101 feet. Over 151' to 220' - $4.00 per foot for each foot over 220 feet. Over 221' - $5.00 per foot for each foot over 221 feet.

Enclosure premiums apply when divers enter enclosures (such as pipes or tunnels) where there is no vertical ascent and is measured by the distance travelled from the entrance. 25’ to 300’ - $1.00 per foot from entrance. 300’ to 600’ - $1.50 per foot beginning at 300’. Over 600’ - $2.00 per foot beginning at 600’.

Employees may be required to perform any combination of work within the Diving team/crew, (with the exception of dive Supervisor) provided they are paid at the highest rate at which he/she has worked for the shift.

L. Workers on hazmat projects receive additional hourly premiums as follows -Level A: $0.75, Level B: $0.50, And Level C: $0.25.

Tide Work: When employees are called out between the hours of 6:00 p.m. and 6:00 a.m. to work on tide work (work located in the tide plane) all time worked shall be at one and one-half times the hourly rate of pay.

Swinging Stage/Boatswains Chair: Employees working on a swinging stage or boatswains chair or under conditions that require them to be tied off to allow their hands to be free shall receive seventy-five cents ($0.75) per hour above the classification rate.

M. Certified Crane Operator Premium: Crane operators requiring certifications shall be paid $1.50 per hour above their classification rate.

Workers on hazmat projects receive additional hourly premiums as follows - Class A Suit: $2.00, Class B Suit: $1.50, Class C Suit: $1.00, and Class D Suit: $0.50.

Special Shift Premium: Basic hourly rate plus $2.00 per hour. When due to conditions beyond the control of the Employer or when an owner (not acting as the contractor), a government agency or the contract specifications requires that work can only be performed outside the normal 6 am to 6pm shift, then the special shift premium will be applied to the basic hourly rate. When an employee works on a special shift, they shall be paid a special shift premium for each hour worked unless they are in OT or Double-time status. (For example, the special shift premium does not waive the overtime requirements for work performed on Saturday or Sunday.)

Provided to Builders Exchange of WA, Inc. For usage Conditions Agreement see www.bxwa.com - Always Verify Scal