



Addendum #6

October 21, 2026

CIP Project T-57 – SR 169 Pedestrian Bridge

This Addendum, including all attachments and referenced documents, amends the bid documents for the aforementioned project.

1. Interpretation

- a) This Addendum forms part of and will be read together with the bid documents.
- b) In the event of any inconsistency between the terms of this Addendum and the other bid documents, this Addendum will prevail. Where the conflict is between this Addendum and the terms of a later Addendum, the later Addendum will prevail.

2. Bid Document Revisions

2.19 The following deletion is made to Schedule A of the bid form as follows:

SCHEDULE A						
Item No.	Spec Sec. #	Description	Unit	Estimated Quantity	Unit Price	Amount
SITE PREPARATION AND GRADING						
A-30	~~8-01~~	~~TREE PROTECTION FENCE~~	~~LS~~	~~1~~	~~\$~~	~~\$~~

2.20 The following schedule for optional items is added to the bid form as follows:

SCHEDULE C – OPTIONAL ITEMS						
Item No.	Spec Sec. #	Description	Unit	Estimated Quantity	Unit Price	Amount
LIGHTING AND ELECTRICAL						
C-1	8-36	GRAZER LIGHTING	LS	1	\$	\$

Schedule C shall not be included in the Total Bid Price.

The revised Bid Schedule is provided as a part of this Addendum.

2.21 The following revisions are made to the Special Provisions (edits in red):

Section	Revision Description
1-09.2(1) General Requirements for Weighing Equipment	<i>Special Provision 1-09.2(1) General Requirements for Weighing Equipment will be deleted. Refer to WSDOT Standard Specifications for requirements of Section 1-09.2(1).</i>

Section	Revision Description
8-01.4 Measurement	<i>The following deletion is made to this section:</i> Supplement this section with the following: (*****) No specific unit of measure will apply to erosion control and water pollution prevention which shall be measured per lump sum. ~~“Temporary Chain Link Fence” and “Tree Protection Fence”~~ shall be measured per linear foot of fencing installed as shown on the plans.
8-35.1 Description	<i>The following modification is made to this section:</i> Bridge and walkway lighting in the base bid shall include but is not limited to all poles, luminaires, poles, anchor bolts, foundations (refer to the structural Plans for luminaire foundations on the bridge), conduit, boxes, work in building, breakers, surge protection and wiring as shown on the Plans. Work includes PSE transformer relocation, ~~utility vault installation and trench work for the primary line to the relocated transformer~~, conduit relocation around Pier P6 to power existing street light pole, and related work noted on the drawings.
8-35.3(2) Submittals	<i>The following modifications are made to this section:</i> Product Data: Provide manufacturer's standard catalog data for specified products demonstrating compliance with referenced standards. Provide list of fittings being provided with descriptions, load capabilities, and either photographs or drawings for each type. Shop Drawings shall be provided for review and acceptance by the Engineer for the following items at a minimum: • Poles and anchor bolts • Luminaires and mounting brackets • Down lights • All conduit and related fittings • Junction Boxes • Cabling and conductors • Fuses and breakers Work Plan: Provide a detailed work plan for the PSE transformer relocation, ~~vault installation, and trenching for the primary line to the relocated transformer~~. Contractor shall provide a new concrete pad for the relocated transformer. ~~PSE will provide a new utility vault (approximately 4' x 4' in size) to be installed underneath the relocated transformer; the Contractor shall be responsible for the installation of the new utility vault.~~ Supply the materials and labor required to conduct the trenching work to extend the underground power conduit to the new transformer pad location. The work plan shall include details of materials, equipment, and sequencing required for the relocation, along with any coordination hold points required for the Work. ~~It is anticipated that PSE will complete their design for the transformer relocation by Fall 2027. The Contractor shall be responsible for protecting the transformer in its existing location until the relocation commences.~~

Section	Revision Description
	The Contractor shall coordinate with PSE on the timing of the power shutdowns and power ons, and relocation of the transformer, including re-running the conductor through the lengthened duct runs. At minimum, the Contractor shall have coordination meetings with PSE for the following: • Kick-off meeting with PSE to review requirements • Coordination with PSE on construction work plan at least two (2) weeks prior to relocation work for transformer • Coordination with PSE on timing of power switchovers at least two (2) weeks prior to relocation work for the transformer
8-36 Grazer Lighting	<i>Section 8-36 will be made optional and paid under item C-1 of the bid form.</i> <i>The following edits are made to this section:</i> 8-36.1 Description Grazer lighting is an optional bid item for the Work. Grazer lighting shall include LED RGBW grazer lights, drivers and DCU's connectors, in curb and structure mounted boxes specifically for grazer lighting and lighting controls for grazer lighting as noted on the Plans. Any joint use conduit and boxes which are required to feed the cameras shall be included under Section 8-35. The work shall include all labor, material, tools, and equipment, supplies, incidental work, with all appurtenances, to satisfactorily complete the work defined in the Standard Specifications, Special Provisions and the particular items called for in the Plans. 8-36.4 Measurement Measurement of grazer lighting optional item as described in this Section and the Contract Plans will be measured as lump sum. 8-36.5 Payment Payment will be made for the following optional bid item: "Grazer Lighting", lump sum. Payment for the optional item will be made at the lump sum price bid and shall be full compensation for all labor, material, tools, and equipment, supplies, incidental work, with all appurtenances, to satisfactorily complete the work defined in the Standard Specifications, Special Provisions and the particular items called for in the Plans.

3. Bid Opening Date Extension

- The bid opening date will be extended by two (2) days. Sealed bids will be received by the City of Maple Valley, Washington until 1:00 p.m., October 28th, 2026.

4. Questions & Answers

Q24: 8-34.1 states “all equipment within the main play area, as procured and installed by others.”

Is the playground contractor provided by the owner or does the contractor need to bring on their own playground sub?

A24: Playground equipment will be installed under a separate contract and will not be a part of this scope of work. The successful bidder will be responsible for coordinating with the playground equipment contractor and for installing the grading underneath the rubberized play surfacing.

Q25: Does spec section 1-09.2(1) apply to this project or is this just a boiler plate spec that didn't get omitted from this project's specs? If not, and it is required, please provide a pay avenue for it or which BI is it incidental too?

A25: Special Provision 1-09.2(1) shall be deleted.

Q26: We request a two-day delay to the bid date for the City of Maple Valley T-57 SR 169 Pedestrian Bridge from Monday, October 26 to Wednesday, October 28. Due to the complexity of this project and the number of highly specialized subs and suppliers involved, putting the bid together on a Monday will be very difficult as many of these subs and suppliers typically do not work on the weekends. A Monday bid will likely result in more errors and less complete proposals whereas a bid opening on Wednesday afternoon will allow contractors to provide more complete and accurate bids to the City of Maple Valley.

A26: The bid opening date will be extended by two (2) days to October 28th, 2026.

Q27: Are bid items 18 and 30 a double up on bid items or are both of them needed?

A27: Tree protection fencing is included in bid item A-18. Bid item A-30 shall be deleted.

End of Addendum No. 6

BID SCHEDULE: T-57 SR 169 Pedestrian Bridge

Note: Unit prices for all items, all extensions, and the total amount of bid must be shown. Show unit prices in figures only (ink or typed). Enter dollars and cents to two decimal points. Where conflict occurs between the unit price and the total amount named for any item the unit price shall prevail, and totals shall be corrected to conform thereto.

Schedule A

Item No.	Spec. Sec. #	Item Description	Unit	Estimated Quantity	Unit Price	Amount
General						
A-1	1-04	MINOR CHANGE	EST	200,000		
A-2	1-05	SURVEYING	LS	1		
A-3	1-05	RECORD DRAWINGS (MINIMUM BID \$5,000)	LS	1		
A-4	1-07	APPRENTICESHIP INCENTIVE	CAL C	10,000		
A-5	1-07	APPRENTICESHIP PENALTY	CAL C	(10,000)		
A-6	1-07	SPCC PLAN	LS	1		
A-7	1-09	MOBILIZATION	LS	1		
Site Preparation and Grading						
A-8	2-04	PROJECT TEMPORARY TRAFFIC CONTROL	LS	1		
A-9	2-04	TRAFFIC CONTROL SUPERVISOR	HR	520		
A-10	2-04	PEDESTRIAN TRAFFIC CONTROL	LS	1		
A-11	2-04	FLAGGERS	HR	920		
A-12	2-04	SEQUENTIAL ARROW SIGN	HR	2,400		
A-13	2-04	PORTABLE CHANGEABLE MESSAGE SIGN	HR	19,000		
A-14	2-04	UNIFORM POLICE OFFICERS	HR	160		
A-15	2-04	TEMPORARY CHAIN LINK FENCE	LF	750		

Item No.	Spec. Sec. #	Item Description	Unit	Estimated Quantity	Unit Price	Amount
A-16	2-04	WORKZONE SAFETY CONTINGENCY	FA	50,000		
A-17	3-01	CLEARING AND GRUBBING	LS	1		
A-18	3-01	TREE PROTECTION	LS	1		
A-19	3-02	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	LS	1		
A-20	3-02	CEMENT CONC. PAVEMENT REMOVAL INCL. HAUL	SY	210		
A-21	3-02	ASPHALT PAVEMENT REMOVAL INCL. HAUL	SY	720		
A-22	3-03	SITE EXCAVATION INCL. HAUL	CY	380		
A-23	3-03	UNSUITABLE FOUNDATION EXCAVATION INCL. HAUL	CY	10		
A-24	3-07	STRUCTURE EXCAVATION CLASS B, INCL. HAUL	CY	445		
A-25	3-07	SHORING OR EXTRA EXCAVATION CLASS B, INCL. HAUL	LS	1		
A-26	4-04	CRUSHED SURFACING TOP COURSE	TON	470		
A-27	4-04	CRUSHED SURFACING BASE COURSE	TON	670		
A-28	5-04	HMA CL. 1/2" PG 58H-22	TON	100		
A-29	8-01	EROSION CONTROL AND WATER POLLUTION PREVENTION	LS	1		
A-30	DELETED					
A-31	8-01	INLET PROTECTION	EA	10		
A-32	8-01	STABILIZED CONSTRUCTION ENTRANCE	LS	1		
A-33	8-05	ADJUST UTILITY STRUCTURE TO GRADE	EA	6		
Approach Structures						
A-34	6-02	CAST-IN-PLACE SLAB - CLIMBING WALL	SF	650		

Item No.	Spec. Sec. #	Item Description	Unit	Estimated Quantity	Unit Price	Amount
A-35	6-02	CONCRETE RUNNING SURFACE	SF	1,700		
A-36	3-03	GRAVEL BORROW STRUCTURAL FILL	CY	400		
Substructure						
A-37	6-02	STRUCTURE EXCAVATION CLASS A INCL. HAUL	CY	280		
A-38	6-02	CONC. CLASS 4000 FOR BRIDGE (SPREAD FOOTINGS)	CY	65		
A-39	6-02	STEEL REINFORCING BAR FOR BRIDGE (SPREAD FOOTINGS)	LB	15,000		
A-40	6-02	CONC. CLASS 4000 FOR BRIDGE (ABUTMENTS AND PIERS)	CY	115		
A-41	6-02	STEEL REINFORCING BAR FOR BRIDGE (ABUTMENT AND PIERS)	LB	51,000		
A-42	6-03	STRUCTURAL CARBON STEEL - SUBSTR.	LS	1		
A-43	6-19	CONSTRUCTING 4.92 FT. DIAM SHAFT (TYPE 1)	LF	440		
A-44	6-19	CONSTRUCTING 7 FT. DIAM SHAFT (TYPE 2)	LF	110		
A-45	6-19	CONSTRUCTING 3.94 FT. DIAM SHAFT (TYPE 3)	LF	90		
A-46	6-19	QA SHAFT TEST	EA	12		
A-47	6-19	REMOVING SHAFT OBSTRUCTIONS	EST	50,000		
A-48	6-01	STRUCTURE SURVEYING	LS	1		
Superstructure						
A-49	6-02	CONC. CLASS 4000D FOR BRIDGE (BRIDGE DECK AND STAIRS)	CY	239		
A-50	6-02	CONC. CLASS 4000 FOR BRIDGE (GIRDERS)	CY	163		
A-51	6-02	STEEL REINFORCING BAR FOR BRIDGE - UNCOATED	LB	32,500		
A-52	6-02	STEEL REINFORCING BAR FOR BRIDGE - EPOXY (DECK)	LB	79,000		

Item No.	Spec. Sec. #	Item Description	Unit	Estimated Quantity	Unit Price	Amount
A-53	6-03	STRUCTURAL LOW ALLOY STEEL - SUPERSTR.	LS	1		
A-54	6-03	STRUCTURAL CARBON STEEL - SUPERSTR.	LS	1		
A-55	6-03	BRIDGE DECK (CORRUGATED STEEL DECKING)	SF	966		
A-56	6-02	ELASTOMERIC BEARINGS - SUPERSTR.	EA	4		
A-57	6-02	ISOLATION BEARINGS - SUPERSTR.	EA	4		
A-58	6-02	EXPANSION JOINT SYSTEM COMPRESSION SEAL - SUPERSTR.	LF	23		
A-59	6-02	DECK JOINT - COVER PLATE	EA	6		
A-60	6-02	DECK DRAINS	EA	6		
A-61	6-04	BRIDGE ROOF - TIMBER ELEMENTS, PLYWOOD SUBSTRATE, WATERPROOFING, METAL ROOFING	LS	1		
A-62	6-12	BRIDGE RAILING	LF	1,186		
A-63	6-12	BRIDGE THROW BARRIER - ARCH SUPERSTRUCTURE	LF	184		
A-64	6-12	FREESTANDING HANDRAIL	LF	344		
A-65	6-02	APPROACH SLAB	SY	31		
A-66	6-12	BURIED CURB	LF	205		
Civil and Utilities						
A-67	7-00	UTILITY POTHOLING	FA	10,000		
A-68	7-00	UTILITY COORDINATION	LS	1		
A-69	7-01	DRAIN PIPE 12 IN. DIAM.	LF	74		
A-70	7-01	DUCTILE IRON STORM SEWER PIPE 12 IN. DIAM.	LF	140		
A-71	7-01	DECK DRAIN	EA	2		

Item No.	Spec. Sec. #	Item Description	Unit	Estimated Quantity	Unit Price	Amount
A-72	7-05	ADJUST CATCH BASIN TO GRADE	EA	1		
A-73	7-05	CATCH BASIN TYPE 1	EA	7		
A-74	7-05	AREA DRAIN	EA	2		
A-75	7-05	CATCH BASIN TYPE 2, 48 IN. DIAM.	EA	2		
A-76	7-05	CONNECT EXISTING PIPE TO PROPOSED DRAINAGE STRUCTURE	EA	2		
A-77	7-05	CONNECT PROPOSED PIPE TO EXISTING DRAINAGE STRUCTURE	EA	1		
A-78	7-06	INFILTRATION FACILITY	CY	65		
A-79	7-15	PVC SANITARY SEWER PIPE, 6 IN. DIAM.	LF	170		
A-80	7-19	SEWER CLEANOUT	EA	2		
A-81	8-04	CEMENT CONC. TRAFFIC CURB AND GUTTER	LF	340		
A-82	8-04	CEMENT CONC. PEDESTRIAN CURB	LF	110		
A-83	8-04	CEMENT CONC. VERTICAL CURB	LF	50		
A-84	8-14	CEMENT CONC SIDEWALK	SY	830		
A-85	8-14	CEMENT CONC. RAMP	SY	99		
A-86	8-14	CEMENT CONC. BIKE RAMP	SY	62		
A-87	8-14	GREEN DETECTABLE WARNING STRIP	LF	60		
A-88	8-21	PERMANENT SIGNING	LS	1		
Landscaping						
A-89	8-02	TOPSOIL TYPE A	CY	475		
A-90	8-02	ARBORIST WOOD CHIP MULCH	SY	1610		
A-91	8-02	FINE COMPOST	CY	25		

Item No.	Spec. Sec. #	Item Description	Unit	Estimated Quantity	Unit Price	Amount
A-92	8-02	PSIPE Cercis canadensis 'Pink Pom Poms' / Pink Pom Poms Eastern Redbud; 1.5" Cal., 8'-10' Ht.	EA	5		
A-93	8-02	PSIPE Acer truncatum x platanoides 'JFS-KW187' / Urban Sunset Maple; 2" Cal., 10'-12' Ht.	EA	4		
A-94	8-02	PSIPE Cercidiphyllum japonicum 'Biringer' / Hanna's Heart Katsura; 1.5" Cal., 8'-10' Ht.	EA	4		
A-95	8-02	PSIPE Prunus x Yedoensis 'Akebono' / Akebono Yoshino Cherry; 2" Cal., 10'-12' Ht.	EA	3		
A-96	8-02	PSIPE Acer palmatum 'Wolf' / Emperor I Japanese Maple; 1.5" Cal., 10'-12' Ht.	EA	3		
A-97	8-02	PSIPE Pinus flexilis 'Vanderwolf's Pyramid' / Vanderwolf's Pyramid Limber Pine; 8'-10' Ht.	EA	1		
A-98	8-02	PSIPE Pinus contorta / Shore Pine; 8'-10' Ht.	EA	1		
A-99	8-02	PSIPE Pinus mugo 'Pumilio' / Dwarf Mugo Pine; 15 Gal. Cont.	EA	11		
A-100	8-02	PSIPE Acer palmatum 'Kihachijo' / Kihachijo Japanese Maple; 15 Gal. Cont.	EA	2		
A-101	8-02	PSIPE Berberis thunbergii 'Concorde' / Concorde Japanese Barberry; 1 Gal. Cont.	EA	91		
A-102	8-02	PSIPE Cornus sericea 'Flaviramea' / Yellow Twig Dogwood; 2 Gal. Cont.	EA	44		
A-103	8-02	PSIPE Cornus sericea 'Kelseyii' / Kelsey's Dwarf Red Twig Dogwood; 2 Gal. Cont.	EA	40		
A-104	8-02	PSIPE Calluna vulgaris 'Wynanda' / Wynanda Heather; 1 Gal. Cont.	EA	26		
A-105	8-02	PSIPE Epimedium x perralchicum 'Frohnleiten' / Frohnleiten Epimedium; 1 Gal. Cont.	EA	143		
A-106	8-02	PSIPE Hakonechloa macra 'Aureola' / Golden Variegated Forest Grass; 1 Gal. Cont.	EA	250		
A-107	8-02	PSIPE Hydrangea quercifolia 'Munchkin' / Munchkin Oakleaf Hydrangea; 2 Gal. Cont.	EA	66		
A-108	8-02	PSIPE Nandina domestica 'Murasaki' / Flirt Heavenly Bamboo; 2 Gal. Cont.	EA	40		

Item No.	Spec. Sec. #	Item Description	Unit	Estimated Quantity	Unit Price	Amount
A-109	8-02	PSIPE Polystichum munitum / Sword Fern; 1 Gal. Cont.	EA	252		
A-110	8-02	PSIPE Rhododendron x 'Christmas Cheer' / Christmas Cheer Rhododendron 2 Gal. Cont.	EA	83		
A-111	8-02	PSIPE Rhododendron x 'Elviira' / Elviira Rhododendron; 2 Gal. Cont.	EA	47		
A-112	8-02	PSIPE Rosa x 'NOAMEL' / Flower Carpet Appleblossom Rose; 2 Gal. Cont.	EA	59		
A-113	8-02	PSIPE Rosa gymnocarpa / Baldhip Rose; 2 Gal. Cont.	EA	29		
A-114	8-02	PSIPE Sarcococca hookeriana var. humilis / Dwarf Himalayan Sweetbox; 2 Gal. Cont.	EA	70		
A-115	8-02	PSIPE Spiraea betulifolia 'Tor' / Birchleaf Spirea; 2 Gal. Cont.	EA	96		
A-116	8-02	PSIPE Vaccinium ovatum / Evergreen Huckleberry; 2 Gal. Cont.	EA	5		
A-117	8-02	PSIPE Narcissus x 'Dutch Master' / Dutch Master Daffodil; Bulb	EA	200		
A-118	8-02	PSIPE Aster x frikartii 'Monch' / Monch Frikart's Aster; 1 Gal. Cont.	EA	25		
A-119	8-02	PSIPE Coreopsis lanceolata / Lanceleaf Tickseed; 1 Gal. Cont.	EA	49		
A-120	8-02	PSIPE Geum x 'TNGEUTR' / Tempo Rose Geum; 1 Gal. Cont.	EA	78		
A-121	8-02	PSIPE Hemerocallis x 'Purple D'Oro' / Purple D'Oro Daylily; 1 Gal. Cont.	EA	40		
A-122	8-02	PSIPE Lavandula angustifolia 'Hidcote' / Hidcote English Lavender; 1 Gal. Cont.	EA	128		
A-123	8-02	PSIPE Leucanthemum x superbum 'Mount Hood' / Mount Hood Shasta Daisy; 1 Gal. Cont.	EA	68		
A-124	8-02	PSIPE Pennisetum alopecuroides 'Hameln' / Hameln Fountain Grass; 1 Gal. Cont.	EA	128		
A-125	8-02	PSIPE Rudbeckia fulgida sullivantii 'Goldsturm' / Goldsturm Coneflower; 1 Gal. Cont.	EA	52		

Item No.	Spec. Sec. #	Item Description	Unit	Estimated Quantity	Unit Price	Amount
A-126	8-02	PSIPE Verbena bonariensis 'Lollipop' / Lollipop Tall Verbena; 1 Gal. Cont.	EA	28		
A-127	8-02	ROOT BARRIER	LF	544		
A-128	8-02	LANDSCAPE BOULDER	EA	63		
A-129	8-02	LANDSCAPE LOG	EA	22		
A-130	8-02	TREE PLANTERS - MAIN SPAN	EA	2		
A-131	8-02	PROPERTY RESTORATION	FA	20,000		
A-132	8-03	IRRIGATION SYSTEM, COMPLETE	LS	1		
Site Furnishings						
A-133	8-12	WOOD POST & RAIL FENCE	LF	18		
A-134	8-12	PORTABLE RESTROOM ENCLOSURE FENCE	LF	32		
A-135	8-14	DECORATIVE SURFACE TREATMENT	SY	13		
A-136	8-14	METAL INLAY	LS	1		
A-137	8-19	REMOVABLE BOLLARD	EA	5		
A-138	8-26	WOOD BENCH	EA	2		
A-139	8-26	EXISTING BENCH REINSTALLATION	EA	1		
A-140	8-26	STACKED WOOD BENCH STRUCTURE	EA	1		
A-141	8-27	PICNIC TABLE	EA	3		
A-142	8-28	EXISTING BIKE RACK REINSTALLATION	EA	7		
A-143	8-32	PET WASTE BAG DISPENSER	EA	1		
A-144	8-33	GRAVEL AREA	SY	75		
A-145	8-34	COORDINATION - PLAY EQUIPMENT AREA	LS	1		

Item No.	Spec. Sec. #	Item Description	Unit	Estimated Quantity	Unit Price	Amount
Misc. Non-Structural Items						
A-146	8-35	BRIDGE AND WALKWAY LIGHTING	LS	1		
A-147	8-35	UNDERGROUND POWER RELOCATIONS	LS	1		
A-148	2-04	PROJECT INFORMATIONAL SIGNS	LS	1		

TOTAL PRICE – SCHEDULE A \$ _____

Schedule B – Water Improvements

Item No.	Spec. Sec. #	Item Description	Unit	Estimated Quantity	Unit Price	Amount
General						
B-1	1-04	MINOR CHANGE	EST	10,000		
B-2	1-05	SURVEYING	LS	1		
B-3	1-05	RECORD DRAWINGS (MINIMUM BID \$2,000)	LS	1		
B-4	1-09	MOBILIZATION	LS	1		
Site Preparation and Grading						
B-5	2-04	PROJECT TEMPORARY TRAFFIC CONTROL	LS	1		
B-6	2-04	TRAFFIC CONTROL SUPERVISOR	HR	16		
B-7	2-04	PEDESTRIAN TRAFFIC CONTROL	LS	1		
B-8	3-02	TREE REMOVAL	EA	2		
B-9	3-02	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	LS	1		
B-10	3-07	SHORING OR EXTRA EXCAVATION CLASS B, INCL. HAUL	LS	1		

Item No.	Spec. Sec. #	Item Description	Unit	Estimated Quantity	Unit Price	Amount
Civil and Utilities						
B-11	7-00	UTILITY POTHOLING	FA	2000		
B-12	7-09	REMOVAL OF EXISTING WATER MAIN	LF	45		
B-13	7-09	STEEL CASING PIPE, 18 IN. DIAM	LF	30		
B-14	7-09	CL 52 DUCTILE IRON PIPE FOR WATER MAIN, 8 IN. DIAM.	LF	72		
B-15	7-09	CONNECTION TO EXISTING MAIN	EA	2		
B-16	7-12	GATE VALVE, 8 IN.	EA	1		

TOTAL PRICE – SCHEDULE B (PRE-TAX) \$ _____
 SALES TAX (9.1%) \$ _____
 TOTAL PRICE – SCHEDULE B (WITH TAX) \$ _____

TOTAL BID PRICE (SCHEDULE A + B) \$ _____

Schedule C – Optional Items

Item No.	Spec. Sec. #	Item Description	Unit	Estimated Quantity	Unit Price	Amount
C-1	8-36	GRAZER LIGHTING	LS	1		

TOTAL PRICE – SCHEDULE C – OPTIONAL ITEMS \$ _____