Oregon
Tina Kotek, Governor

Department of Transportation
Statewide Project Delivery Branch
Project Development Section
Project Controls Office
555 13th St NE
Salem, OR 97301

DATE: October 26, 2026

Addendum No. 6

TO: **PLAN HOLDERS**

PREPARED BY: Sean R. Triana 2026.10.26 10:36:53 -07'00'
Sean Triana

APPROVED BY: BORNSTEDT George F 2026.10.26 11:01:58-07'00' P.E.
George Bornstedt

FINAL ELECTRONIC DOCUMENT AVAILABLE UPON REQUEST

SUBJECT: I-84 (Westbound): Union Pacific Railroad Bridge (Hood River) Project
Columbia River Highway
Hood River County
Grading, Drainage, Structures, Paving, Signing, and Roadside Development
(Bids Closing November 19, 2026)

The following changes are made to the Project Special Provisions:

1. Subsection 00253.00 Scope - The paragraph that begins with the words "On Structure No. 02443…" is replaced with the following:

   On Structure No. 02443, provide temporary work access, containment system(s) for Bridge Removal of the entire existing bridge on spans 1 through 9.

2. Subsection 00253.00 Scope - The paragraph that begins with the words "On Structure No. 24318…" is replaced with the following:

   On Structure No. 24318, provide temporary work access, containment system(s) for bridge construction on spans 1 through 4 not already included under Falsework in Section 00540.

3. Subsection 00235.05 Containment Requirements - This subsection is added after subsection 00253.04:

   00253.05 Containment Requirements – Replace this subsection, except for the subsection number and title, with the following:

   Provide containment for Bridge Removal on Agency and UPRR right of way as shown, specified, or directed.

4. Subsection 00501.40 Removal and Disposal - This subsection is added after subsection 000501.03:

   00501.40 Removal and Disposal – Add the following sentence to this subsection:

   Provide containment for Bridge Removal Work according to Section 00253 and 00290.

5. Subsection 00540.01 Abbreviations and Definitions - This subsection is added after the paragraph that begins “Comply with Section 00540…”:

   00540.01 Abbreviations and Definitions – Replace the paragraph that begins “**Falsework - …”** with the following paragraph:

   Falsework - Structural system to support the vertical and horizontal loads from forms, reinforcing steel, plastic concrete, structural steel, work access systems, loads from formwork construction and placement operations and other related loads.

These changes will be included in the Contract for this Project. It is understood that your Bid must and shall be submitted accordingly.

st:GB