ADDENDUM NO. 2

November 5, 2026

Attention All Bidders and Plan Holders:

Davison RD MP 0.01 Bridge Rehabilitation Project
Federal Aide Project No. BHOS-2021(075)
Federal Aid Contract No. TA7620
County Road Project No. 2198

Plans

Delete note 2 on Sheet S8 (12 of 18) and replace it with the following:

2. REMOVE EXISTING TOP AND BOTTOM BATTEN PLATES PRIOR TO HEAT STRAIGHTENING. DO NOT REMOVE MORE THAN TWO SETS OF BATTEN PLATES (4 TOTAL) AT ONE TIME. REMOVE BATTEN PLATES ONLY WITHIN CHORD REPAIR AREA AND WHILE CHORD IS BEING REPAIRED.

Add the following to the end of the notes on sheet S10 (14 of 18):

4. LATERAL BRACING SHALL BE CONNECTED BY EITHER WELDING OR BOLTING. BOLT HOLES MAY BE UTILIZED ONLY WHEN DETERMINED BY THE ENGINEER TO BE ACCEPTABLE. ELONGATED, DISTORTED, OR OTHERWISE DEFICIENT HOLES SHALL NOT BE REUSED. EACH CONNECTION SHALL CONSIST OF A SINGLE CONNECTION METHOD; COMBINED WELDED AND BOLTED CONNECTIONS SHALL NOT BE PERMITTED.

Add the following to the end of the notes on sheet S13 (17 of 18):

4. TRAFFIC WILL TEMPORARILY BE ALLOWED ON THE NEW TIMBER DECK PRIOR TO INSTALLING WATERPROOF MEMBRANE AND PAVING

All Bidders will be required to furnish evidence of the receipt of this addendum. This addendum will be incorporated into and made part of the contract when awarded and formally executed.

END OF
ADDENDUM NO. 2

M VINCENT HALL
STATE OF WASHINGTON
40730
REGISTERED
PROFESSIONAL ENGINEER
11/5/2026

M. Vincent Hall
Assistant County Engineer